MaiAgent User Guide

Table of Contents

1. Getting Started

1.1 Apply for an Account

1.2 Invitation: Join an Organization

1.3 Log In to the Platform

1.4 Forgot Password

1.5 Personal Account Settings

1.6 Notification Center

1.7 System Notifications and Email

1.8 Top Bar Tools: Ask AI, Support Center, and Interface Language

2. MaiAgent Work | Employee Productivity

2.1 MaiAgent Work Overview

2.2 MaiGPT

2.3 Create Documents and Spreadsheets from Templates

2.4 AI Chat

2.5 Conversation Handoff

2.6 AI Memory

2.7 Canvas

2.8 Deep Research

2.9 AI Image Generation

2.10 AI Video Generation

2.11 AI Presentations

2.12 Connectors

2.13 Manage Connectors (Administrators)

2.14 Use on Different Devices

2.15 Web Version

2.16 iOS App

2.17 Use on LINE
2.18 Use on Microsoft Teams
2.19 Frequently Asked Questions
2.20 Usage and Quotas
2.21 Choose the Right Model
2.22 Security and Privacy
2.23 File Library
2.24 Create Workspaces and Import Files
2.25 Search, Filters, and File Details
2.26 Use Workspaces in MaiGPT
2.27 Let AI Edit and Organize Files
2.28 Version History and Restore
2.29 Shared Spaces
2.30 Online Editing
2.31 Knowledge Base vs. File Library: Differences and When to Use Each
2.32 Chat with Agents (Agent Marketplace)
2.33 Official Built-in Agents
2.34 Use Official Built-in Agents
2.35 Enable and Manage
2.36 AI Meeting Records
2.37 Create Meeting Records
2.38 Live Meeting Transcription
2.39 Quick Access to Meeting Records
2.40 Backup Audio for Meeting Records
2.41 Offline Meeting Transcription
2.42 Meeting Record Details
2.43 Meeting Access Permissions
2.44 AI Meeting Summaries and Q&A
2.45 Download and Knowledge Base Integration
2.46 Use Cases: Internal Knowledge Management
2.47 Professional Knowledge Management
2.48 Meeting Requirements Management
2.49 Financial Analysis Assistant
2.50 Billing Assistant
2.51 Credit Analysis Assistant

2.52 Use Cases: Image Vision

2.53 Invoice Recognition

2.54 Business Card Scanning

2.55 ID Document Recognition

2.56 Use Cases: Writing and Content Creation

2.57 Official Document Writing Assistant

2.58 Draft Legal Notice Letters

2.59 AI Translation

2.60 Ad Copywriting and Idea Generation

3. MaiAgent Serve｜Customer Service

3.1 MaiAgent Serve Overview

3.2 Text Customer Service: From Setup to Launch

3.3 Voice Customer Service: From Setup to Launch

3.4 Customer Service Copilot

3.5 Daily Customer Service Operations

3.6 Customer Service Agent Handbook

3.7 Customer Service Supervisor Guide

3.8 All Conversations

3.9 Conversation Viewer

3.10 Inbox Search

3.11 Conversation Platform Analytics

3.12 Human Agent Handoff and Replies

3.13 Contacts

3.14 AI Customer Service Quality Management

3.15 Use Cases: Text Customer Service

3.16 Regulatory Search Assistant

3.17 Product Search Assistant

3.18 Use Cases: Voice Customer Service

3.19 IVR Customer Intent Recognition

3.20 Voice Call Summaries

3.21 Voice Call Quality Assurance

4. MaiAgent Build｜Agent Development

4.1 MaiAgent Build Overview

4.2 Agent Builder
4.3 I Want to Do X. What Should I Use?
4.4 Agent
4.5 Agent Features
4.6 Create an Agent
4.7 Create an Agent from the Agent Template Library
4.8 Role Instruction Design Guide
4.9 Add Role Instructions to an Agent
4.10 Multilingual Support
4.11 Cross-Conversation Search
4.12 Persistent Memory
4.13 Knowledge Base Label Filtering
4.14 Response Length and Agent Execution Limits
4.15 Agent Scheduling
4.16 Set Up Agent Schedules
4.17 Code Interpreter (Code Execution)
4.18 Browser Tool (Browser Operations)
4.19 Voice Agent
4.20 Agent Usage Analytics
4.21 Knowledge Base
4.22 Knowledge Base Overview
4.23 Create a Knowledge Base: Basic Settings
4.24 Crawler
4.25 Use the Web Crawling Feature
4.26 Create FAQs
4.27 Document Management: Tags and Metadata
4.28 Move Knowledge Base Files
4.29 PDF Document Translation
4.30 Search Testing
4.31 Database
4.32 Text to SQL Features
4.33 Create and Configure a Database
4.34 Text to SQL with a MaiAgent Database
4.35 Text to SQL with Supabase
4.36 Link Agents and Group Permissions

4.37 Tools

4.38 Tool Features Overview

4.39 Create MCP Tools

4.40 MCP Interactive Cards (MCP Apps)

4.41 Create API Tools

4.42 Configure Tools for an Agent

4.43 Customize Tool Message Display

4.44 Configure Contact MCP Credentials

4.45 Built-in AI Image Generation Tool

4.46 Gemini 3 Image Generation Tool

4.47 Quick Menu

4.48 Agent UI

4.49 Quick Reply

4.50 Skills

4.51 Skill Management

4.52 Agent Teams

4.53 Create and Orchestrate Teams

4.54 Team Execution Records

4.55 Hook Message Interception

4.56 Add and Configure Hooks

4.57 Hook Execution Logs

4.58 Publish to Conversation Platforms

4.59 Web Chat Overview

4.60 Connect a Conversation Platform: Website

4.61 Chat Without Logging In Using a Contact Source ID

4.62 Connected Services

4.63 Citation Display

4.64 Markdown Rendering

4.65 Embed MaiGPT in Window Mode

4.66 Connect a Conversation Platform: LINE

4.67 Connect a Conversation Platform: FB Messenger

4.68 Connect a Conversation Platform: Instagram

4.69 Connect a Conversation Platform: Telegram

4.70 Connect a Conversation Platform: Microsoft Teams

4.71 Connect a Conversation Platform: WhatsApp

4.72 Connect a Conversation Platform: Email
4.73 Connect a Conversation Platform: Slack
4.74 Connect a Conversation Platform: LINE WORKS
4.75 Connect a Conversation Platform: Team+
4.76 Connect a Conversation Platform: Viber
4.77 Migrate from Another Customer Service System to MaiAgent
4.78 Phone Customer Service (Call Center)
4.79 Conversation and Human Handoff Settings
4.80 Conversation Platform Settings Overview
4.81 Basic Settings
4.82 Appearance Settings
4.83 Response Loading Style
4.84 Feature Settings
4.85 Interaction Settings
4.86 Customer Service Human Handoff Settings
4.87 Human Agent Handoff Notifications
4.88 Conversation Tag Management
4.89 Conversation Analytics
4.90 Webhook
4.91 AgentOps
4.92 Test Dataset Management
4.93 Automated Evaluation and Agent Monitoring
4.94 Conversation Details and Execution Timeline
4.95 Voice Conversation Records and Latency Analysis
4.96 Evaluation Insights Reports
4.97 Tool Execution Records
4.98 Add Conversation Records to FAQs
4.99 AI Gateway
4.100 Use Cases: External Data Integration
4.101 Agricultural Data Queries
4.102 Google Workspace Connector
4.103 Use Cases: Agent Optimization Consultant

5. Organization Management and Governance

5.1 Organization and Member Management

5.2 Organization Overview
5.3 Organization Management
5.4 Member Management
5.5 Profiles: Custom Attributes
5.6 Announcement Management
5.7 Delete an Organization
5.8 Roles and Permissions
5.9 Role Permission Management
5.10 Transfer Others' Conversations Permission
5.11 MaiGPT Role Usage Permissions
5.12 Role Resource Access Permissions
5.13 Role Resource Visibility Controls
5.14 Role Member Filtering
5.15 Differences Between Roles and Contacts
5.16 Role Permission Planning Guide
5.17 Model Access Permissions
5.18 Third-Party Login (SSO)
5.19 SAML Integration
5.20 ADFS Integration
5.21 EIP Integration
5.22 Keycloak Integration
5.23 Cloudflare Access Integration
5.24 Identity Synchronization (LDAP/SCIM)
5.25 Knowledge Management Permissions: Query Metadata
5.26 Get Started with the Query Builder
5.27 Activity Logs
5.28 Developer Tools
5.29 API Key Management
5.30 API Call Logs
5.31 OAuth Applications
5.32 Security and Privacy (2)

6. Plans, Usage, and Billing

6.1 Trial and Subscription Plans
6.2 Credits Billing System

6.3 Member Credits Quota Management
6.4 Conversation Platform Credits Quota Management
6.5 How the Three Quotas Work: Scenarios and FAQs
6.6 Usage Calculation
6.7 Usage Statistics

Getting Started

Apply for an Account

If your company is using MaiAgent for the first time, you can choose to:

Self-register and apply for a trial: Register an account on the login page, create your company's organization, and fill in the application details. After approval, a 14-day trial is activated.

Contact Sales: Discuss an enterprise plan directly with the sales team.

> Is your company already using MaiAgent? Please don't create another organization yourself. Ask your company's organization administrator to invite you. For the steps after receiving an invitation, see Received an Invitation: Join an Organization.

Choose How to Apply

Your situation	Recommended approach	Result
You want to try it out first and evaluate whether it fits	Self-register and apply for a trial	A 14-day trial is activated after approval
You've decided to adopt it and need an enterprise plan or dedicated planning	Contact Sales	The sales team helps with evaluation and activation
Your company already has an organization and an administrator is inviting you	Received an Invitation: Join an Organization	You join your company's existing organization

Self-Register and Apply for a Trial

Register an Account

Go to the login page https://admin.maiagent.ai/login, click Sign up next to "Don't have an account?" below, and fill in the following fields:

Field	Description
Full name	Required. Shown in the organization member list
Company name	Required
Company email	Required. You will use this email to log in later

Field	Description
Password／Confirm password	We recommend at least 9 characters, including uppercase letters, lowercase letters, numbers, and special characters. If the password is not strong enough, "Please enter a valid password" is shown
Invitation code	Optional. Leave it blank if you don't have one. See Invitation Code Field below for its purpose

The Sign up button becomes clickable only after you check "I have read and agree to the Privacy Policy and Terms of Service". If a human verification challenge appears, complete it first. After the Registration successful message appears, clicking the button in the dialog takes you back to the login page.

Log In

On the login page, enter the Company email you just used, click Continue, then enter your password and click Log in (see How to Log In to the Platform for details).

An account that hasn't joined any organization yet sees a welcome screen after logging in, followed by two cards:

Join an organization: Use this if your company already has an organization. Click Copy to get a message template (including your name, email, and a quick-action link for the administrator) and send it to your company's organization administrator, asking them to add you.

Create a new organization: Use this when applying on behalf of your company for the first time. Continue to the next step.

Create an Organization and Fill in the Application Details

On the Create a new organization card, click Try Enterprise Plan free for 14 days. After you confirm "Create a brand-new organization?", the Add organization dialog opens:

Field	Description
Name	Required. The organization name, shown in the organization switcher at the top of the left menu
Invitation code	Optional. The field hint reads "Optional: paste your trial invitation code". Leave it blank if you don't have a trial invitation code from Sales
Company name	Required. Used for review
Tax ID	Optional. Must be 8 digits
Contact phone	Required. Used by the reviewers to contact you

Field	Description
Hide Chinese models	Checked by default. When checked, Chinese models provided by the platform do not appear in the organization's model menu. After creation, the organization owner can change this in the organization overview; see Model Access Permissions: Chinese Models

The bottom of the dialog shows "After submission, your organization will enter review; once approved, a 14-day trial will be activated". Click Confirm, and when you see "Organization created successfully", the application is complete.

> The company name, tax ID, and contact phone can only be entered when creating the organization and cannot be changed afterward. Please double-check before submitting.

Wait for Review

During review, the top of the page always shows "Your organization is under review. A 14-day trial will be activated once approved, and you will be notified by email." This notice cannot be dismissed.

Approved: The system sends a notification email and activates the trial. The trial is counted from the day of approval. For plan details and what happens after it ends, see Trial and Subscription Plans.

Not approved: The top of the page changes to "Your organization did not pass review, and the trial cannot be activated for now." If you have questions, email sales@maiagent.ai.

The person who creates the organization becomes its owner. To invite colleagues later, see Member Management.

What the "Invitation Code" Field Is For

Both the registration screen and the Add organization dialog have an Invitation code field, and you can leave either blank. The effect depends on which code you have:

The code you have	Where to enter it	Effect
A personal invitation code shared by a colleague or friend	Registration screen	Only records the referrer. It does **not** add you to any organization; the description below the field on the registration screen refers to this kind of code
An invitation link generated by an organization administrator	Filled in automatically when you open the registration screen from the link	After registering, you join that organization directly without creating one. See Received an Invitation: Join an Organization

The code you have	Where to enter it	Effect
A trial invitation code provided by Sales	Registration screen, or the Invitation code field when creating an organization	Company information is filled in automatically when the organization is created, so you skip the application fields and can use the organization right after creation

When using a trial invitation code:

If you entered it during registration, the Add organization dialog opens directly after login and shows "Trial invitation detected (company name). Company information will be filled in automatically, and you can use it right after creation." You only need to fill in the organization name before submitting.

If you paste it in the Add organization dialog, application fields such as the company name are hidden. If the code is invalid or expired, an error appears below the field; after you clear the code, the application fields reappear and you can go through the regular review process instead.

If the trial invitation becomes invalid before you submit, the screen shows "The trial invitation is no longer valid. Please create the organization through the regular process and fill in the application details." Fill in the application details as prompted.

> If you enter an unrecognized invitation code during registration, "Invalid referral code." appears and registration cannot be completed. Check the invitation code, or clear the field and register again.

Contact Sales

If you need an enterprise plan, a formal procurement process, or dedicated help planning your adoption, email sales@maiagent.ai with the following information so the sales team can get in touch with you:

```
Company name:
Company tax ID:
Name:
Contact phone:
LINE ID (optional):
```

To upgrade your plan during the trial, the sales team also assists; see Trial and Subscription Plans: Upgrade Plan.

FAQ

I've registered, but after logging in I only see "Join an organization" and "Create a new organization"?

This means your account hasn't joined any organization yet. If your company already has an organization, click Copy on the Join an organization card and send the message to your organization administrator; after the administrator adds you, refresh the page to get in. Choose Create a new organization only when applying on behalf of your company for the first time.

Can I use the platform while the application is under review?

The trial is not activated before approval, and trial days do not start counting. You will be notified of the result by email; if you need help, email sales@maiagent.ai.

The Tax ID keeps showing a format error?

The Tax ID field accepts only 8 digits. If you don't have a tax ID, you can leave it blank.

Further Reading

How to Log In to the Platform

Received an Invitation: Join an Organization

Trial and Subscription Plans

Member Management

Invitation: Join an Organization

When your company administrator adds you to a MaiAgent organization, you may receive an invitation email, an invitation link, or an activation email asking you to set a password. This page is for **invited employees**: complete registration or login based on what you have in hand, and once logged in you can use the Agents and MaiGPT that the organization has opened to you. For how administrators send invitations, see Member Management.

> If you already have a MaiAgent account and the administrator invites you by email, the system adds you to the organization directly and does not send an email. After refreshing the page or logging in again, you will see the new organization in the organization switcher (see Switching When You Belong to Multiple Organizations).

First, Identify Which Kind of Invitation You Received

What you received	What it means	What to do
An email whose subject contains "invites you to join"	The administrator invited you by email, and you don't have an account yet	Click the link in the email to register; see Register with an Invitation Email or Invitation Link
An organization invitation link forwarded by a colleague or in an announcement	A shared link generated by the administrator that many people can use	Click the link to register; the steps are the same as above
An email whose subject contains "Welcome, please set your password"	The administrator has already created an account for you from a list	Click the link in the email to set your password; see Log In After Setting Your Password
No email, but the organization already appears in your organization list	You already had an account and were added directly	Switch to that organization and start using it

Register with an Invitation Email or Invitation Link

Open the Invitation Link

Click the link in the invitation email, or open the invitation link shared by the administrator directly. Your browser opens the MaiAgent registration screen, with the Invitation Code field already filled in.

Fill In the Registration Details

Field	Description
Full Name	Your name, shown in the organization member list
Company Name	Your company name
Company Email	If you received an invitation email, you **must enter the email address that received it**; the system adds you to the organization based on this email
Password／Confirm Password	We recommend at least 9 characters mixing uppercase letters, lowercase letters, numbers, and special symbols (for example `!@#$`); if the strength is insufficient, "Please enter a valid password" is shown
Invitation Code	Keep the auto-filled content; do not modify or delete it

> The explanatory text below the Invitation Code field (recommended use, does not automatically join an organization) applies to personal referral codes. An invitation code filled in from an organization invitation link adds you to that organization after registration; when you open the page from an invitation email, you are added based on the company email you enter.

Agree to the Terms and Submit

The Register button can be clicked only after you check "I have read and agree to the Privacy Policy and Terms of Service". If a human verification appears on screen, complete it first. After the Registration successful message appears, clicking the button in the message window takes you back to the login page.

Log In

On the login page, enter the Company Email you just used, click Continue, then enter your password and click Log In. You go straight into the organization with the role permissions the administrator specified in the invitation.

Log In After Setting Your Password

When an administrator adds members in bulk from an Excel list, the system creates accounts directly for people who don't have one yet and sends an email whose subject contains "Welcome, please set your password".

Click the link in the email to open the password-setting screen.

Enter a new Password and Confirm Password (same rules as above), then click Reset.

Return to the login page and log in with that email and the new password.

The password-setting link has a validity period. If the link has expired, click Forgot password? on the login page and reset it with the same email; see Forgot Password.

Invitation Validity Period

Invitation method	When it expires
Invitation email	No expiration date. It is complete once you register and join with that email; it becomes invalid after the administrator revokes it
Organization invitation link	The expiration date is set by the administrator when creating it (default 7 days). It cannot be used after it expires or is disabled by the administrator; before it becomes invalid, multiple people can register with it

If you didn't receive the invitation email, the administrator can click Resend on that invitation under Invitation Status. A single invitation can be sent **at most 3 times including the first send**, and at least **5 minutes** must have passed since the last send. If fewer than 5 minutes have passed or it has already been sent 3 times, Resend does not appear.

When Your Company Uses Single Sign-On (SSO)

When your company has set up single sign-on, you usually **don't need to set a password on the registration page**:

Go to the login page, enter your company email, and click Continue.

If your company email's domain is bound to single sign-on, the screen indicates that you will be verified through single sign-on, and the button changes to Go to Acme SSO Login (Acme is your organization's name). After you click it, log in on your company's identity verification page.

On your first SSO login, the system creates your account automatically. If the administrator has already sent an email invitation to the **same email address**, you also join that organization and receive the specified role.

If your company uses another login method (for example EIP or Keycloak), use the login URL provided by your company instead; for the process, see Third-Party Login (SSO).

> Organization invitation links are used only on the registration page. If your company uses SSO, ask the administrator to invite your company email by email instead, so that you are automatically added on your first SSO login.

When the screen shows "Single sign-on for this organization is suspended. Please contact your system administrator.", single sign-on is temporarily unavailable, and only accounts that have set a platform password can log in with a password; contact your company IT or organization administrator.

Switching When You Belong to Multiple Organizations

Each organization's roles, Agents, Credits quota, and API keys are independent, so confirm which organization you are in before taking any action.

Switch organizations: The drop-down at the top of the left menu shows the current organization. Open it and choose the organization to go to (you can type a name to search); the page reloads to that organization's home page. When the left menu is collapsed, click the building icon at the top instead.

Keep frequently used organizations at the top: Click your avatar in the top right → Account → My Organizations, then click Pin on an organization. Pinned organizations appear at the top of the switcher with a pin icon; pinning is stored only in the browser on the current device.

For more account settings, see Personal Account Settings.

FAQ

I never received the invitation email?

First check your spam folder, then ask the administrator to look at the invitation under Invitation Status: when it shows Email failed to send or is still Pending, it can be resent (subject to the 3-send and 5-minute limits above). When the status is Pending, you can also go to the login page and click Register, then complete registration with the **invited email address**; the system adds you to the organization all the same.

"Invalid referral code." appears when registering?

The invitation code is no longer valid: the invitation link has expired or been disabled, or the invitation email has been revoked or already used. Ask the administrator to invite you again or provide a new invitation link.

I finished registering but can't see my company's organization?

When registering from an invitation email, the most common cause is entering a different email address from the one that received the email. Tell the administrator the email address you actually registered with so they can invite you again; because you already have an account, the system adds you to the organization directly.

I already have an account, but the invitation link won't let me register?

Invitation links can only be used to register new accounts. If you already have an account, ask the administrator to invite the email address you currently log in with by email, and you will be added to the organization directly.

I received a Credits quota right after joining. Is that normal?

Yes. If the organization has set a "default quota for new members", or the administrator who invited you set a separate quota in the invitation, you automatically receive a personal quota the moment you join, and its validity period starts from the time you joined. To check it, see Members Checking Their Own Quota. If the organization has enabled "block consumption until quota is distributed" and you haven't received a quota, using AI is blocked; contact the administrator to distribute one, see Member Credits Quota Management.

I log in after joining the organization but see "No Access"?

You are already in the organization, but the administrator hasn't enabled any features for your role yet. For what you can do on this page and what to ask the administrator to do, see How to Log In to the Platform: Seeing the "No Access" page after logging in?.

Further Reading

How to Log In to the Platform

Forgot Password

Personal Account Settings

Member Management (Administrators)

Log In to the Platform

MaiAgent platform login page: https://admin.maiagent.ai/login

The login page initially shows only one field: Work email. After you enter your email and click Continue (or press Enter), the system checks the email domain: if your company has set up single sign-on (SSO), it takes you to the company's login page; otherwise, it expands the password field so you can enter your password.

Don't have an account yet? If your company is using MaiAgent for the first time, see Apply for an Account. If you received an invitation from your company administrator, see Received an Invitation: Join an Organization.

Choose a Login Method

Your account	Login method
Registered with an email and have a platform password	Email and password
Want to log in with a Google account	Log in with Google
Your company has set up SAML single sign-on	Enter your work email to be taken to the company login page automatically
Your company uses EIP, Keycloak, or Cloudflare Access to log in	Use the login URL provided by your company; see Third-Party Login (SSO)

Log In with Email and Password

Enter your Work email and click Continue.

When the email is identified as a platform account, the screen shows "Local account — enter your password to log in" and expands the Password field.

Enter your password. If a human verification challenge appears, complete it first.

Click Log in. On success, a Login successful notification appears and you enter the platform.

> You can also paste "email password" (separated by a single half-width space) into the Work email field all at once. The system automatically splits it into the two fields; then just click Log in.

For what to do when you enter the wrong credentials, see What should I do if I see "Incorrect email or password"?. If you forgot your password, click Forgot password? at the bottom of the login page; for the steps, see Forgot Password.

Log In with Google

Enter your Google account email and click Continue.

After the password field expands, a Log in with Google button appears below the "Other login methods" divider. Click it.

On the Google screen, select your account and complete verification. You will be returned to MaiAgent and logged in automatically.

If the email of your Google account matches an existing MaiAgent account, you will log in to that same account.

If you don't have a MaiAgent account yet, logging in with Google for the first time creates one automatically. After logging in, join or create an organization by following Apply for an Account.

If login is not completed, the screen shows Login failed, and you can click Retry or Back to login. The explanatory text below the failure screen means the following:

Text on screen	What it means	What to do
Login was not completed. Please log in again.	Verification data was missing when returning from Google, commonly caused by opening a bookmark directly or closing the Google window midway	Click Back to login and go through the process again
Login failed. Please log in again.	Google verified you, but MaiAgent could not complete login with this account (for example, the account has been disabled)	Click Retry; if it still fails, log in with your password instead or contact your organization administrator
Other English messages	The error reason returned by MaiAgent, displayed as is	Take a screenshot and give it to your administrator

> If the email domain has company single sign-on set up, clicking Continue takes you directly to the company's login page, and Log in with Google does not appear. Please log in with your company account instead.

Company Single Sign-On (SSO)

After your company administrator sets up SAML single sign-on and binds the company email domain, employees don't need to enter a password when logging in:

Enter your Work email. The screen indicates that this email will be verified through single sign-on (for example, "Acme account — will be verified with Entra ID single sign-on.", where Acme is your organization's name), and the button changes to Go to Acme SSO login (if the system cannot identify the organization name, the button stays as Continue).

Click the button and complete login on your company's authentication page.

After successful verification, you are returned to MaiAgent and enter the platform. The first time you log in with SSO, the system creates your account automatically.

Message on screen	What it means	What to do
Single sign-on is temporarily disabled for this organization. Please contact your system administrator.	The company's single sign-on is temporarily disabled	The password field also expands; accounts with a platform password can log in with it. Others should contact company IT or the organization administrator
Unable to determine the login method right now. You can log in with your password directly or try again.	The system temporarily cannot determine which login method applies to this email	Enter your password to log in directly, or click Continue again to re-check
Unable to complete single sign-on. Please try again; if it keeps failing, contact your system administrator.	Verification failed on the company login page	Click Retry; accounts with a platform password can click Use password instead to return to the login page and enter the password
Login timed out. Please log in again.	Verification succeeded on the company login page, but the one-time login code was already used or expired when returning to MaiAgent, commonly because the "Logging in" page was refreshed or an old bookmark was used	Click Retry to go through single sign-on again

If your company uses Keycloak, EIP, or Cloudflare Access, see the respective pages for failure messages: Keycloak, EIP, Cloudflare Access.

> Only SAML-type single sign-on redirects automatically after you enter your email. If your company uses EIP, Keycloak, or Cloudflare Access, use the login link provided by your company. For how administrators set up single sign-on, see Third-Party Login (SSO).

After Logging In

You haven't joined any organization yet: You first see a welcome screen. You can send your information to your company administrator and ask them to invite you, or create a new organization and apply for a trial; see Apply for an Account.

You belong to multiple organizations: Switch organizations from the dropdown at the top of the left menu. Each organization's roles, Agents, and quotas are independent. For how to switch and pin frequently used organizations, see Received an Invitation: Join an Organization.

Update your profile or change your password: See Personal Account Settings.

Top Toolbar

After logging in, the top-right corner of the screen shows a fixed row of tools, unaffected by the left menu and role permissions:

Item	Description
Ask AI	Appears only when the organization has enabled the back-office AI assistant. Click once to expand a chat window on the right side of the screen where you can ask how to use the back office; click again to collapse it. If you haven't joined any organization, you are prompted to create or join one first
Cookbook	Opens the MaiAgent Cookbook in a new tab, with approaches and examples for various use cases
Docs	Opens this manual (docs.maiagent.ai) in a new tab
Support Center	Opens the MaiAgent Helpdesk support center in a new tab to report issues or check tickets, logging you in automatically with your current account
Bell icon	Notification center: system announcements and organization announcements; see Notification Center
Language icon	Switches the back-office interface language; the page reloads after switching
Avatar	User menu: Account (personal account settings), Switch organization, Create organization, Log out

> The Cookbook and Support Center links are provided by the site configuration. For self-hosted or on-premises deployments where they are not configured, these two items do not appear.

For what you can ask Ask AI, how to open a ticket in the Support Center, and which interface languages are available, see Top Bar Tools: Ask AI, Support Center, and Interface Language.

FAQ

What should I do if I see "Incorrect email or password"?

When you enter your email and password and one of them is wrong, an "Incorrect email or password" message and a Forgot password? button appear below the password field. You can handle it as follows:

Re-check your details: Confirm that your Work email and Password are entered correctly. The message collapses automatically once you update either field, and you can click Log in again.

Quickly reset your password: If you forgot your password, click Forgot password? next to the message. The system opens the reset form and fills in the email you just entered; for the following steps, see Forgot Password.



When credentials are wrong, go straight to the password reset form from the message

> This in-form message is used only for incorrect credentials. If another error dialog appears, handle it according to the reason shown on screen; for example, resetting your password cannot fix an incomplete human verification. The original Forgot password? entry at the bottom of the login page remains available, but it does not fill in your email automatically.

I see a "No access" page after logging in. What does it mean?

This means your account has no role granting you feature permissions in the **organization you are currently in**. It is common the first time you come in through company single sign-on, or right after being added to an organization before the administrator has assigned a role. This is a normal security design, not a login failure. The page lists the name of your current organization and several things you can do:

Button	Purpose
Switch to another organization to test	Appears only when you belong to multiple organizations. Click any organization to switch to it; if the problem is only with this organization, you can use the others as usual
Email request template, Copy template	A request message pre-filled with your name and email; copy it and paste it to your organization administrator

Button	Purpose
Send email request	Opens a request email addressed to the site support mailbox in your computer's mail app, with the template above as its content
Re-check permissions	Click this after the administrator assigns a role. If you have permissions, it shows "Permissions updated, redirecting..." and takes you into the back office; if not, it shows "Permissions not yet granted. Please contact your administrator." The system also checks automatically once when you enter this page
Log out	Log in with a different account

Ask your administrator to go to Organization Settings → Organization Overview → Manage Actions → Edit Members, find your account, and assign a role using Edit member role; see Member Management.

I clicked "Continue" but was taken to the company's login page?

Your email domain has company single sign-on set up. Please log in with your company account on that page. If the company's login page is malfunctioning and you have set a platform password, you can click Use password instead on the failure screen.

I can't find the "Log in with Google" button?

This button appears only after you enter your email, click Continue, and the password field expands. If the email domain has company single sign-on set up, this button does not appear.

Which email should I use the first time I log in?

Use the Work email you entered when registering. If you registered from an invitation email, use the email address that received the invitation; see Received an Invitation: Join an Organization.

Further Reading

Apply for an Account

Received an Invitation: Join an Organization

Forgot Password

Third-Party Login (SSO)

Forgot Password

If you forget your MaiAgent login password, you can request a reset email on the login page and set a new password yourself. All you need is access to the inbox of your registered email.

> For accounts that log in through company single sign-on (SSO), the password is managed by your company's identity system. See Accounts Using Company Single Sign-On.

1. Click Forgot Password

Go to the login page https://admin.maiagent.ai/login and click Forgot password? at the bottom right.

2. Enter Your Registered Email

The screen title changes to Reset password. Enter the email you used to register in Company email; if a human verification challenge appears, complete it first, then click Reset.

When you see the message "A password reset email has been sent to your inbox", the reset email has been sent. Click Back to return to the login screen.



If the email you enter is not an account on the platform, the system does not send an email and the screen shows an error. Make sure it is the company email you used to register.

3. Open the Reset Password Email in Your Inbox and Click the "Reset Password" Button

Find the password reset email sent by MaiAgent in your inbox and click the button in the email to open the screen for setting a new password.

The link has an expiration time, so finish setting your password within the time stated in the email.

Each request invalidates the link in the previous email; if you request more than once, use the link in the **latest** email.



4. Reset Your New Password

On the Reset password screen, enter a new Password and Confirm password, then click Reset.

We recommend at least 9 characters, including uppercase letters, lowercase letters, numbers, and special characters (for example `!@#$%^&*`). If the password is not strong enough, "Please enter a valid password" is shown.

If the two fields don't match, "The passwords entered do not match" is shown.

After the "Password changed successfully" message appears, you are returned to the login screen when it closes. Log in with your new password (see How to Log In to the Platform).



Accounts Using Company Single Sign-On

When you log in with company single sign-on (SSO), you enter your company account password, which is managed by your company's identity system. MaiAgent's "Forgot password" only sets the MaiAgent platform password and does not change your company account password. If you forget your company account password, reset it in the identity system according to your company's policy, or contact your company's IT.

FAQ

I never received the reset email?

First check your spam folder and make sure you entered the company email you registered with. If you still haven't received it, go back to the login page, request again, and use the latest email.

After opening the link, "Verification code has expired" or "Invalid verification code" appears?

The link has passed its expiration time, has already been used, or you requested a newer reset email afterward. Go back to the login page, click Forgot password? to request again, and use the link in the latest email.

I'm logged in and want to change my password, not recover a forgotten one?

Click your avatar or name at the top right of the console, choose Account, and change the password in the Account Security tab. See Personal Account Settings: Change Password.

Personal Account Settings

Every user has their own Account page, where you can update your name and avatar, change your password, see which organizations you belong to, and manage your Credit quota, API keys, and AI memory in the current organization. This page requires no role permissions; all logged-in members can see it.

How to Access

Click your avatar or name in the top-right of the back office and select Account. The tabs on the left side of the page are divided into two groups:

Group	Tab	What it manages
Personal Account (shared across all organizations)	Profile	Avatar, name, company name; personal preferences and custom attributes; delete account
	My Organizations	The organizations you belong to, and pinning
	Invitation Management	Your personal invitation code, invitation link, and invitation emails
	Account Security	Change password
Current organization name (applies only to the current organization)	Credit Quota	Your personal quota in this organization; appears only when the organization uses Credits billing
	API Keys	Personal API keys you issued yourself
	AI Memory	Preferences and facts remembered by Agents; appears only when the organization has AI memory enabled

The heading of the second group is the name of the current organization. To view the quota or keys of another organization, switch organizations first; see Switching When You Belong to Multiple Organizations.

Profile

Avatar

Click the avatar to open Upload Avatar, then click Choose Image or drag an image in (JPG/PNG supported, up to 5 MB per file). You can rotate, flip, and zoom to adjust the crop area. When you are done, click Confirm and Upload, and the avatar in the top-right updates immediately.

Name and Company Name

Click Edit to change your Full Name and Company Name, then click Save. The Company Email is your login account and cannot be changed here. Your name belongs to the account itself, so every organization you are in sees the same name.

Personal Preferences and Custom Attributes

Personal Preferences: Describe your habits and common scenarios in a piece of text (up to 1,000 characters), and the AI refers to it when interacting with you. For example: "I prefer bulleted replies and Traditional Chinese."

Custom Attributes: Additional information such as department, job title, and extension. You can add them manually, or click Download Template to get an Excel template, fill it in, and use Import Excel to fill them in bulk. For details, see Profile: Custom Attributes.

These two items are stored on your member record in the **current organization**, so you need to fill them in separately when you switch to another organization. After making changes, click Save in that section.

Delete Account

At the bottom of Profile is Delete Account, which permanently deletes your account and personal data and cannot be undone.

Click Delete Account. The system first checks whether the account can be deleted.

If you are the **only member and the only owner** of an organization, the dialog lists "The following organizations solely owned by you will also be deleted:".

Enter your email as prompted to confirm, then click Confirm Delete. When finished, Account deleted is displayed and you are logged out.

When Unable to delete the account at this time: appears, the dialog states the reason. Common reasons include:

You are the **only owner** of an organization that still has other members: first make sure the organization has another owner.

You created data that must be kept in an organization that is still in use: follow the message to handle it first, or contact the organization administrator for help.

My Organizations

Lists all the organizations you have joined; the organization you are currently in is marked Currently in use. Click Pin to move frequently used organizations to the top of the organization switcher menu in the top-left, and click Unpin to restore. Pinning is stored only in the browser on this device.

Invitation Management

Your Invitation Information at the top shows your personal Invitation Code (click Edit to change it to something memorable using uppercase letters and numbers) and the corresponding Invitation Link. The three toggles below:

Toggle	Content
Invitation Code	People who registered with your invitation code
Invitation Link	The organization invitation link for the current organization, where you can see the description, expiration time, usage count, and status, and copy the link
Invitation Emails	Platform invitations sent with Invite via Email, which you can Resend or Revoke

> Personal invitation codes and Invitation Emails are for referring others to register on the platform; after registering, the person will not join your organization. To add colleagues to an organization, have an organization administrator invite them from Member Management.

Account Security: Change Password

In Account Security, enter your Current Password, New Password, and Confirm New Password, then click Change Password. You are done when you see "Password changed successfully." The new password must be at least 9 characters and include uppercase and lowercase letters, numbers, and special characters.

If you forgot your current password, log out and use Forgot Password instead. Accounts created through your company's single sign-on (SSO) have no platform password; change it in your identity system according to company policy.

Credit Quota

This appears only when the organization uses Credits billing. The page header reads "Your personal quota in *organization name*." and My Credit Quota below shows one of the following depending on your situation:

What is shown	What it means
Quota card (see the fields in the table below)	An administrator has allocated a personal quota to you
You currently have no personal quota limit	Spending uses the organization wallet directly
You need a quota to use AI services	No quota has been allocated yet or it has expired; contact an administrator to allocate one
Quota expired (Your quota expired on …)	The quota has expired; contact an administrator to allocate a new quota

Fields on the quota card:

Field	Description
Used progress bar	The proportion of the quota limit that has been consumed
Quota Limit, Remaining	The total quota for this period and the Credits you can still use
Effective Time, Expiration Time	An expiration time of "Permanent" means it never expires; if there is a deadline, "N days remaining" is also shown
Next Reset	The next time a recurring quota (for example, monthly) resets "Used" to zero, with the cycle in parentheses; a one-time quota shows "No reset"
Allocated By, Notes	The administrator who allocated this quota and their comments

My Role Quota below shows the quota of the roles you belong to, with the same fields, plus a status label in the top-right: Active, Low Balance (85% used), Exhausted, Not Allocated. If you see "This role requires a quota but currently has no valid quota," spending for the entire role (including you) is paused; ask an administrator to allocate a new quota or remove the restriction. "You currently have no role quota limit" means none of your roles has quota control enabled.

People with organization Credit management permission also see an Organization Total Usage link in the page header. For how quotas are allocated and reset, see Member Credits Quota Management.

API Keys

A personal access key calls the MaiAgent API as you, with exactly the same permissions as you, and can only be used in the **organization where it was created**. Any member can issue one on their own.

Click Create Key (or Create Your First Key if you have no keys yet).

Enter a Name, and optionally choose an Expiration Time (leave blank for never expires).

Copy the full key immediately. After you close the dialog you can no longer see the full key; if you lose it, revoke it and create a new one.

The list shows only the keys you issued yourself; click Revoke when you no longer use one. Keys issued to you by an administrator are managed by organization administrators, and people with API Key management permission see an Organization Key Management link in the page header. To connect AI tools using a key, see MaiAgent MCP.

AI Memory

This appears only when the organization has AI memory enabled. It lists the preferences and facts Agents have remembered from conversations, and you can add, edit, and delete them. For details, see AI Memory.

FAQ

I can't see the "Credit Quota" or "AI Memory" tab?

These two tabs appear according to the current organization's settings: if the organization does not use Credits billing, there is no Credit Quota; if the organization has not enabled AI memory, there is no AI Memory. First confirm that the organization in the top-left is the one you want to check.

I filled in personal preferences, but they disappeared after I switched to another organization?

Personal preferences and custom attributes are stored on your member record in each organization separately. Fill them in again under Profile in that organization.

My API key doesn't work in another organization?

A personal API key is bound to the organization where it was created. Switch to the organization you want to use first, then create a new key under API Keys.

Further Reading

Receiving an Invitation: Joining an Organization

Notification Center

Profile: Custom Attributes

Member Credits Quota Management

AI Memory

Notification Center

The Notification Center is the bell in the top-right corner of the console. It brings together announcements from the MaiAgent platform, announcements for your organization, and system notifications, such as human handoff notifications when a conversation is assigned to you or reminders that your personal quota is running low. All signed-in members can see the bell; the notifications it contains depend on your **current organization** and role.

Open the Notification Center

Click the bell icon in the top-right corner of the console. The red number on the bell is the **unread** notification count (shown as 99+ above 99), covering system announcements and notifications for the current organization. While the page is open, the unread count updates automatically about once a minute. It also refreshes when you return from another browser tab.

The Notification Center has two tabs. The number after each tab name is the total number of notifications currently visible in that tab:

Tab	Contents
System Announcements	Announcements from the MaiAgent platform for all users, such as system maintenance, feature updates, and real-time status reports on model service delays or issues
Organization Announcements	Announcements for the current organization, including announcements published by its owner and notifications automatically sent by the system based on your work

Types of notifications

Common notifications in the Organization Announcements tab are listed below. Each notification has a display period and disappears from the list automatically when it expires.

Notification	Recipients	Display period
Announcements published by the organization owner in Announcement Management	All members, or the groups (roles) and members specified when publishing	The period set when publishing
Human Handoff Notification	The support specialist assigned to the conversation and the configured copy recipients	7 days

Notification	Recipients	Display period
Personal Quota Running Low, Personal Quota Expiring Soon	The member whose quota meets the reminder conditions	7 days
Low Credits Balance, Credits Expiring Soon, Payment Failed, Auto Top-Up Failed	Organization owner	7 days
Data Retention Warning	Organization owner	Until the scheduled deletion date
Connector Activated	The member who previously requested activation of the connector	7 days

For configuring human handoff notification recipients, see Human Handoff Support Notifications. For quota reminder conditions, see Member Credits Quota Management. For notifications that also send Email and other occasions when the system sends mail, see System Notifications and Email.

View notifications and mark them as read

Read the list

Unread notifications have bold titles and a small dot on the left.

Higher-priority notifications have a label: Important (such as human handoff notifications and quota reminders) or Urgent (such as data retention warnings).

Each entry shows a content summary and how long ago it was published. If the publisher chooses to disclose their identity, the Publisher's name and Email are shown.

The list loads 10 entries at a time and automatically loads more as you scroll down. At the end, it shows “No more data.” If there are no notifications, it shows No announcements.

Mark as read

Click a notification to open a detail dialog showing its full content and display period. If the notification includes a link, link text appears at the bottom of the dialog, defaulting to Learn More. For human handoff notifications, it is Take Over; clicking it opens the conversation.

Click Got It or the close button in the top-right corner to mark the notification as read and reduce the red count. Read notifications remain in the list and can be reopened at any time during their display period.

Mark all as read

When you have unread notifications, Mark All as Read appears in the top-right corner of the Notification Center. Clicking it marks all notifications visible to you in **System Announcements and the current**

organization as read, and displays All marked as read. Notifications in other organizations are unaffected; handle them separately after switching organizations.

System announcements that appear automatically

Two types of system announcements appear proactively if you have not read them, without opening the bell:

Type	How it appears	How to dismiss it
System maintenance	A banner at the top of the page content, showing one announcement at a time	Click the close button on the right of the banner; this also marks it as read
Feature update	A dialog that appears automatically when you sign in (or reload the console) or navigate to another page	Click Got It or close it; this also marks it as read

When there are multiple system maintenance announcements: The banner shows only the highest-priority announcement (Urgent before Important, followed by Normal; newer announcements come first within the same priority). Long content is truncated; hover over it to see the full title and content. The others are grouped under "N more announcements" on the right of the banner. Click it to expand a list below the banner, with each row showing a title and start time. You can also close announcements individually in this list. Closing the current announcement brings up the next one.

When feature update dialogs appear: The system checks only when you sign in or reload the console, or navigate to another page. A dialog will not suddenly appear while you are working on the same page. At most one dialog appears at a time, with the rest saved for the next page navigation. If an organization announcement dialog is also due, the organization announcement appears first.

Proactive reminders for organization announcements

By default, organization announcements appear only in the bell's Organization Announcements tab. If the organization owner sets the Reminder Method to Toast or Dialog when publishing, you will see it proactively the next time you sign in (or reload the console) or navigate to another page. Each toast appears only once. A dialog reappears on refresh or page navigation until you dismiss it. Both types of reminder have Organization Announcement at the top.

Dialog

The full announcement appears in the center of the screen. Clicking Got It, the close button in the top-right corner, or the area outside the dialog, or pressing Esc, dismisses it and marks it as read so it will not appear again.



Organization announcement dialog

Toast

A toast appears in the top-right corner of the screen with the announcement title. A countdown in the bottom-right corner says “Disappears in N seconds,” and the progress bar at the bottom shrinks accordingly. The duration is set by the publisher.



Organization announcement toast

Pause the countdown: Hover over the toast or give it keyboard focus to pause the countdown and display “Paused (N seconds total).” The countdown also pauses when you switch to another browser tab.

Read the full content: Click View to open the full announcement. It is marked as read only after you close it. If the announcement has been deleted or disabled, you will see “Unable to open announcement: This announcement has been deleted or disabled.”

Does not count as read: Clicking the close button in the top-right corner or letting the countdown finish dismisses the toast, but the announcement remains unread in the Organization Announcements tab. You can open it from the bell later.

Appears only once: Once a toast has appeared in one tab or on one device, it will not appear again in other tabs or on other devices.

> At most one dialog and one toast appear per page navigation; the rest wait until the next navigation. If both are due, the toast waits until you close the dialog before appearing and starting its countdown from the beginning.

Announcements visible to new members

To avoid overwhelming new members with old announcements as soon as they join:

When an account is registered, system announcements still within their display period are automatically considered read.

When a member joins an organization, that organization's announcements still within their display period are automatically considered read.

These announcements remain in the Notification Center list and new members can open them, but they do not count toward the red number or interrupt members with banners, dialogs, or toasts. Only announcements published **after** joining appear as unread.

Frequently asked questions

A colleague mentioned an announcement, but it is missing from my Notification Center. Why?

Check the following in order: Are you in the same organization, as shown in the top-left corner? (Organization announcements show only those for the current organization.) Was the announcement sent only to specific roles or members? Has its display period expired?

Why did the red number change after I switched organizations?

This is expected. The unread count covers only system announcements and notifications for the **current organization**, with a separate count for each organization.

How do I publish an organization announcement?

Organization owners can go to Organization Settings → Organization Overview and click Announcement Management under Management Actions to create an announcement. They can configure its Reminder Method, display period, Priority, multilingual content, and Target Audience. Other roles with Organization Overview permission can only view announcements. For all fields and procedures, see Announcement Management.

Further reading

System Notifications and Email

Human Handoff Support Notifications

Member Credits Quota Management

Manage Connectors (Admin)

Personal Account Settings

System Notifications and Email

MaiAgent proactively sends emails to the relevant people when events occur around accounts, members, customer support, connectors, plans, and quotas. This page lists **all** system emails in one place: when they are sent, who receives them, whether they can be turned off, and where to configure them. Many events also trigger an in-app notification in the Notification Center in the top-right of the back office; for a comparison, see In-App Notifications vs. Emails.

> System emails are sent by the MaiAgent platform (for private cloud and on-premises deployments, they are sent from the sender mailbox configured by your company). The email language does not change with the recipient's interface language. Emails that support agents send to customers as replies through Connect a Messaging Platform: Email are sent from the mail account configured on that messaging platform. They are not system emails and are outside the scope of this page.

Use Case: Telling In-App Notifications and Emails Apart

An organization administrator wants to confirm whether a notification she received is also sent by email. She first opens the Notification Center in the top-right of the back office to check the notification type, then compares it against In-App Notifications vs. Emails on this page. For example, "Connector enabled" is sent only as an in-app notification and no email follows; knowing this rule, she no longer has to keep waiting for an email that will never be sent.



The Notification Center is organized into System Announcements and Organization Announcements; to see whether an email is also sent, check the notification table on this page

Accounts and Members

Email	When it is sent	Who receives it	Can it be turned off, and where to configure
Password reset email	On the login page, click Forgot Password and submit an email; see Forgot Password	The account owner	Cannot be turned off
Invitation email	An administrator invites someone who **does not yet have a MaiAgent account** to join the organization by email; see Member Management	The invited email address	Cannot be turned off. If it was not received, click Resend under Invitation Status, up to 3 sends including the first, at least 5 minutes apart; see Receiving an Invitation: Joining an Organization
Set-password email (bulk	When an administrator bulk-adds members with Excel, for	The owner of the new	Cannot be turned off

Email	When it is sent	Who receives it	Can it be turned off, and where to configure
member import)	**accounts newly created this time** in the list; see Bulk Member and Permission Management	account	
Organization approved rejected	When the review of an organization that self-registered and applied for a trial is completed; see Apply for an Account	The organization owner	Cannot be turned off

Handoff to Human Support

Email	When it is sent	Who receives it	Can it be turned off, and where to configure
Handoff to human notification email	When a conversation handed off to a human is **assigned to a support agent** (including transfer to another agent)	The assigned agent, with a CC to the configured members and groups	Yes. On the messaging platform, go to Handoff to Human Support Settings → Notifications → Email Notification; see Handoff to Human Support Notifications

A handoff notification email is sent only when **all three conditions are met at the same time**; for details, see Email Rules That Are Easy to Misunderstand.

MaiGPT Connectors and Tools

Email	When it is sent	Who receives it	Can it be turned off, and where to configure
Connector request email	A member clicks Request Activation in MaiGPT for a connector that is not enabled for the organization, or requests adding an enabled connector to their own role. Sent only once per request	The organization owner, and members with connector management permission	Cannot be turned off. For how to handle requests, see Manage Connectors (Administrators)

Email	When it is sent	Who receives it	Can it be turned off, and where to configure
MCP tool needs re-authorization	The authorization of an organization-shared MCP tool becomes invalid and is rejected by the external service at run time. Notified only once per invalidation; sent again only if it becomes invalid again after recovery	Members who can manage the tool and can see the tool	Cannot be turned off in the organization back office. For re-authorization, see Create an MCP Tool
Schedule skipped a tool with invalid authorization	When an Agent Schedule runs, a tool is skipped because its authorization is invalid. Sent only once per tool per schedule within 7 days	The schedule's creator; if the creator is no longer in the organization, members who can re-authorize the tool	Cannot be turned off. No more emails are sent once you re-authorize the tool, or disable the schedule or remove the tool from the Agent

Plans, Credits, and Quotas

Email	When it is sent	Who receives it	Can it be turned off, and where to configure
Low credit balance reminder	The organization's Credits balance falls below the reminder threshold. Not repeated within 24 hours	The organization owner, and the notification recipients set in the balance reminder	Yes. Enable Balance Reminder under Balance Reminder (on by default); see Low Balance Reminder. **Only organizations on a paid plan receive the email**; see the note below
Personal quota almost used up	A member's personal quota reaches the reminder threshold (80% by default). Sent only once per quota period	The member	Yes, **off by default**. Member Quota → Reminder Settings → Enable Personal Quota Reminder; see Personal Quota Reminder Settings
Personal quota expiring soon	Checked daily at 9 AM; a personal quota expires within the configured number of days (7 by default)	The member	Same as above; shares one switch with "almost used up"
Plan scheduled	MaiAgent schedules a plan for the organization that takes effect in the future	The organization owner	No switch in the organization back office; whether it is sent is configured centrally by the MaiAgent platform

Email	When it is sent	Who receives it	Can it be turned off, and where to configure
Plan activated	A plan takes effect, for example a scheduled plan reaches its effective date, a trial converts to a paid plan, or a renewal. If Credits are granted at the same time, the email includes the credited amount	The organization owner	Same as above
Monthly Credits granted	The plan's monthly Credits are credited on the grant date	The organization owner	Same as above
Credits top-up credited	Credits from a top-up are credited, including Credits that MaiAgent reissues to the organization	The organization owner	Same as above

Data Retention

Email	When it is sent	Who receives it	Can it be turned off, and where to configure
Data about to be permanently purged	After an organization has no valid paid plan and enters the data retention period, one email is sent when **89, 60, 30, 14, 7, and 1 days** remain before the purge	The organization owner	Cannot be turned off. For the retention period and how to prevent data from being purged, see Data Retention Policy

Email Rules That Are Easy to Misunderstand

Low Credit Balance Reminders Are Emailed Only on Paid Plans

When the balance falls below the threshold, all organizations receive a Low credit balance reminder in the Notification Center, but the **email is sent only to organizations with a paid plan**. Organizations on a free plan or with no plan see only the in-app notification, even if Enable Balance Reminder is on and notification recipients are filled in. Organizations subscribed through AWS Marketplace are billed by Marketplace and do not receive this reminder.

People Who Already Have an Account Receive No Email When Added to an Organization

When the person's email is already registered with MaiAgent, all of the following methods **add them to the organization directly without sending any email**, and no in-app notification is sent either:

Inviting a member by email

Bulk-adding members with Excel (only newly created accounts in the list receive a set-password email)

Syncing members through LDAP or SCIM

After logging in, the person can switch to the new organization in the top-left. If you need to notify them, tell them separately.

A Handoff Notification Email Requires Three Conditions at the Same Time

Condition	Default	Where to configure
Enable Human Agent Handoff is on for the messaging platform	Off	Handoff to Human Support Settings of the messaging platform
Email Notification is on for that messaging platform	On	Handoff to Human Support Settings → Notifications
The organization can use handoff notifications	On	Configured by the MaiAgent platform; there is no switch in the organization back office

In addition, the email is sent only when the conversation is **assigned to a support agent**; no email is sent when the AI decides to hand off but no one has taken over yet, when the conversation is returned to the AI, or when the queue times out (these events can be sent to external systems through Webhook notifications). If the first two are on and the conversation is assigned but you still receive no email, contact MaiAgent.

These Events Do Not Send Email

The following events appear only in the Notification Center and are not emailed: Credits expiring soon, payment failed, auto top-up failed, connector enabled (notifies the member who originally requested it), and a member being removed from an organization.

In-App Notifications vs. Emails

Notification in the Notification Center	Also sent by email?
Handoff to human notification	Follows the Email Notification switch; the in-app notification is controlled separately by the Notification Center Announcements switch

Notification in the Notification Center	Also sent by email?
Personal quota almost used up, Personal quota expiring soon	Yes
Low credit balance reminder	Only for organizations on a paid plan
Data retention warning	Emailed only when 89, 60, 30, 14, 7, or 1 days remain; on other days only the in-app notification is sent
MCP tool needs re-authorization	Yes
Credits expiring soon, Payment failed, Auto top-up failed, Connector enabled	No

FAQ

I should have received an email but didn't?

Check in this order: first check your spam folder; compare against this page to confirm that the email's switch and conditions are all satisfied; for invitation emails, check Invitation Status to see whether Email delivery failed is shown. For private cloud and on-premises deployments, a system administrator must first configure email sending; see Invitation and Notification Email Sending Settings in the technical manual.

Can a member opt out of receiving emails?

There is currently no per-user unsubscribe setting. Emails that can be turned off are all controlled per organization or per messaging platform; see the "Can it be turned off" column in the tables above. The CC recipients of handoff notifications and the notification recipients of balance reminders can be adjusted in their respective settings.

Further Reading

Notification Center

Handoff to Human Support Notifications

Credits Billing System

Member Credits Quota Management

Manage Connectors (Administrators)

Top Bar Tools: Ask AI, Support Center, and Interface Language

For an overview of every button in the top-right bar of the console, see How to Log In to the Platform: Top Toolbar. This page covers only the three that need a closer look: Ask AI, Support Center, and the interface language.

> On-premises or white-label environments may not have Ask AI or Support Center. If you don't see these two buttons, use your company's internal support channel.

Ask AI: Ask How to Use the Platform

Click Ask AI and a chat window slides out on the right side of the screen. It contains an AI assistant provided by MaiAgent that knows the platform well. It is good for questions such as:

"Where do I set up tag filtering for a knowledge base?"

"How do I connect an Agent to LINE?"

"What happens when a member's quota runs out?"

It specializes in **platform operations and feature explanations**, not in handling your business questions. To ask about your company's knowledge base or your own Agents, use MaiGPT or the Agent Marketplace. The window pushes the console content to the left, so you can look at the screen while you ask. Click Ask AI again or the close button on the window to collapse it.

Screen	Meaning
A "Unable to use Ask AI" popup appears: "You have not joined any organization yet⋯"	Your account has not joined any organization. Follow Apply for an Account to join or create an organization, then use it
Ask AI is missing from the top bar	Ask AI is not enabled in this environment

> The preview window of the Agent Template Library also has an Ask AI button. It is the same assistant, and clicking it first sends a question about that template for you.

Support Center: Report Issues and View Tickets

If you run into a malfunction, want to request a feature, or have a contract or billing question, click Support Center in the top bar (hovering shows "Go to Support Center to report an issue"). The system opens a new tab and automatically signs you in to the MaiAgent Helpdesk ticket system with the account you are currently logged in with. If automatic sign-in fails, you will land on the MaiAgent Helpdesk login page with your email pre-filled; just sign in with an email verification code.

Once in MaiAgent Helpdesk, you can:

Create a new ticket: describe the problem and attach screenshots and the time it occurred

Check the progress of tickets you have opened and discuss back and forth with support staff inside the ticket

> When reporting a Web Chat, conversation, or knowledge base issue, please also provide the name of the chat platform, the time the conversation took place, the Agent used, and any error text shown on screen (for example, the stage and error category listed on the connection failure screen) so support staff can pinpoint the problem directly.

If your browser blocks the new tab, the system opens MaiAgent Helpdesk in the current tab instead. To return to the console, use your browser's "Back" button.

Switching the Console Interface Language

Click the language icon in the top bar to choose 繁體中文, 简体中文, English, 日本語, or 한국어. After you choose, the whole page reloads, and this browser keeps using the setting from then on.

This setting affects only **the text of the console interface** (menus, buttons, prompts):

The language of AI replies is determined by the language you ask in and the Agent's role instructions; see Multi-Language Support

The language website visitors see in Web Chat is determined by the visitors' own settings; see Web Chat: Multi-Language Support

Content created by the organization, such as MaiGPT templates and Agent names, is not translated

Further Reading

Notification Center

Personal Account Settings

How to Log In to the Platform: Seeing the "No Access" page after logging in?

MaiAgent Work | Employee Productivity

MaiAgent Work Overview

Help everyone focus on more valuable work.

MaiAgent Work is an AI workspace for employees. Search company knowledge, organize meetings, and use Agents from the marketplace for everyday tasks, all in one place. Start using it as soon as your account is activated, without building your own Agents. Administrators grant access to features and models by job role, while the enterprise centrally manages usage and conversation records.

Products

MaiGPT	Enterprise AI chat connected to company knowledge. Choose from multiple models, get answers with knowledge base citations, and generate Word documents, Excel spreadsheets, and presentations directly. Supports Canvas, Deep Research, image and video generation, connectors, and AI memory.	MaiGPT
File Library	A central location for your organization's files. Organize project documents in file workspaces, let MaiGPT read and edit files directly, and automatically save AI-generated files. Every change is versioned and can be restored.	File Library
Agent Marketplace	Choose official built-in Agents by task without building your own. Once the organization enables them, members can use them directly in conversations.	Agent Marketplace
AI Meeting	Transcribe in real time or upload audio recordings to automatically generate summaries, decisions, and action items. You can also ask questions about meeting content.	AI Meeting

Get Started by Role

Your role	Suggested starting point
Employee	MaiGPT: Start with AI Chat, then try Creating Documents and Spreadsheets with Templates
Anyone handling many documents	File Library: Create a file workspace, then Use Workspaces in MaiGPT to let AI read and edit files
Frequent meeting participant	Create Meeting Records, then use AI Meeting Summaries and Q&A to organize key points after the meeting

Your role	Suggested starting point
Organization administrator	Set up MaiGPT Role Permissions and Member Credits Quota Management, then enable official Agents in the Agent Marketplace
Department knowledge owner	Create a Knowledge Base first so colleagues can look up department information through MaiGPT or the Agent Marketplace

A Common Starting Point: Internal Knowledge Q&A

Most enterprises start with one department's manuals and SOPs:

Organize One Department's Documents

Select the manuals, SOPs, and frequently asked questions most relevant to the work, then upload them to a Knowledge Base.

Let Colleagues Ask Questions Directly

Colleagues ask questions in MaiGPT or the internal Q&A service. MaiGPT includes citations to knowledge base sources in its answers; click a citation to view the original document.

Expand to the Next Department

After verifying answer quality, apply the same approach to other departments. Control access through Roles and Permissions.

Use Cases

Internal Knowledge Management: Professional knowledge, meeting needs, financial analysis, billing expenses, and credit analysis

Computer Vision: Invoice, official document, business card, and ID document recognition


Writing and Content Creation: Translation, official documents, legal notice letters, marketing copy, instructional material design, and conversation practice

> To design your own Agents and integrate enterprise systems, see the MaiAgent Build Overview. To bring AI to customer touchpoints, see the MaiAgent Serve Overview.

MaiGPT

MaiGPT is your company's dedicated AI chat assistant. You can talk to it just like ChatGPT, but it can also query your company's internal data, connect to your work tools, and all conversations stay within the company — nothing leaks out.

Overview: MaiGPT Feature Modules



MaiGPT six major feature modules overview

AI chat is the core experience — choose a model, upload files, and ask questions directly. Other features extend the chat capabilities: Canvas lets you edit AI-generated documents in real time, Deep Research has AI automatically search the web to produce comprehensive reports, AI Image Generation lets you describe visuals with text, and Connectors let AI access your work tools like Notion and Slack.

Six Features at a Glance

Feature	What It Does	Typical Use Cases
AI Chat	Multi-model conversation with file uploads, knowledge base Q&A, and web search	Daily Q&A, document analysis, translation
Canvas	Edit AI-generated long-form content in real time	Writing reports, emails, proposals, creating charts
Deep Research	AI automatically searches the web to produce structured research reports	Market research, competitive analysis, topic research
AI Image Generation	Generate images from text descriptions with iterative editing	Marketing materials, presentation illustrations, concept visualization
Connectors	Connect external work tools so AI can query them directly	Search Notion notes, find Slack messages, locate Google Drive files
Multi-Device Access	Web, iOS App, LINE, Microsoft Teams	Use MaiGPT anytime, anywhere

How Is It Different from Agent Builder?



MaiGPT vs Agent Builder: positioning, audience, use cases, and operation at a glance

	MaiGPT	Agent Builder
Audience	All company employees	IT admins Developers
Purpose	Chat directly with AI to get daily work done	Build AI assistants for customers or internal use
How to Use	Just type, like ChatGPT	Configure role instructions, knowledge bases, tools, and other modules

Quick rule of thumb: Want to use AI yourself → MaiGPT; Want to build AI assistants for others → Agent Builder.

Recommended Getting Started Order

If this is your first time using MaiGPT, follow this order to get started:

```
Step 1 → Start a conversation — pick an AI model and ask a question
Step 2 → Try uploading a file — let AI analyze the document for you
Step 3 → Use Canvas — ask AI to write a report or email for you
Step 4 → Expand as needed: connect Notion
 Slack, use Deep Research
```


You don't need to learn everything at once. Start with chat + file uploads, then gradually explore advanced features.

Still Have Questions?

FAQ — Answers about usage limits, model selection, security, and privacy

Create Documents and Spreadsheets from Templates

The Document and Spreadsheet shortcuts on the MaiGPT home page let you select a template and data sources before returning to the conversation and asking AI to generate content. Documents work well for reports, summaries, and proposals, while spreadsheets are ideal for organizing data into fields and rows.



Filter document templates by source and category, then add a knowledge base, skill, or database below



The spreadsheet shortcut provides built-in templates such as Gantt charts, dashboards, registers, and spreadsheets

Use Case

Project manager Mai needs to prepare a weekly progress report. She selects the weekly report template under Document, adds the project knowledge base, and applies the template. MaiGPT brings the template and selected data sources into the conversation, where she can specify the scope for the week and generate a draft.

Create a Document or Spreadsheet

Choose a Document or Spreadsheet

In the Productivity section of the MaiGPT home page, select Document or Spreadsheet.

Find a Template

Use search, or filter by All
Built-in
Organization
Favorites to find a suitable template. Click the star on a card to add it to Favorites, then switch to Favorites to find it quickly later. Click Preview to enlarge the template content (you can zoom and flip through pages). Organization template cards also have Delete Organization Template (shown based on permissions); deletion cannot be undone.

> Organization templates are provided by your company, while Built-in templates are included with MaiGPT. The templates displayed depend on your organization's settings.

Add Data Sources

At the bottom of the panel, select the knowledge bases, skills, or databases to reference. Add only the sources needed for the content to keep the subsequent conversation focused.

Apply the Template and Describe Your Request

Select a template, then click Apply. The selected template appears above the input box, which is also prefilled with prompt text. Close the template panel, add the time period, audience, output tone, or required fields to your message, and submit the generation request.

When generation is complete, MaiGPT lists a summary of the results and the generated files in its response. Review the content, then click Download to get the document or spreadsheet.



MaiGPT displays the weekly report summary, generated file name, and download button

The workflow is the same for spreadsheets. The following example uses the Project Schedule Gantt Chart template to generate an Excel file from three fictitious work items. When it is ready, review the item summary, file name, and file size in the response, then download the `.xlsx` file.



The spreadsheet result lists three work items and provides an Excel file for download

Manage Your Own Templates

Select Import Document Template or Import Spreadsheet Template in the upper-right corner of the panel to add custom templates permitted by your organization. Imported templates appear in the template list and can be reused later.

> If the data source list is empty, first confirm that you have access to the relevant knowledge base, skill, or database, then contact your organization administrator for assistance.

AI Chat

AI chat is the core MaiGPT experience. Choose an AI model, enter a question, and get an answer. You can also upload files for AI to analyze, query your company's knowledge base, search the web for the latest information, and adjust the AI's reasoning effort to match the complexity of your question.

On this page: Chat capabilities | Quick start | Choose an AI model | The “+” menu: files, skills, tools, and connectors | Upload files and images | Knowledge base Q&A | Web search | Reasoning effort | Conversation memory | Message actions | Organize conversations: pin frequently used conversations | Organize conversations: rename and delete | Organize conversations: search | Share conversations | Review earlier messages while a reply is being generated | Navigation bar for long conversations | Next steps

Chat capabilities

Capability	What it does	When to use it
Choose an AI model	Choose a model before starting a conversation	Select the best AI for your task
Reasoning effort	Control how deeply AI reasons before answering	Analysis with multiple steps, logical reasoning, decision support
Upload files and images	Upload documents for AI to read, summarize, and analyze	Contract reviews, report analysis, image recognition
Knowledge base Q&A	Query your company's internal knowledge base	Look up company policies, product manuals, and SOPs
Web search	Search the web for the latest information	News, market developments, competitor information
Skills, tools, and connectors	Specify skills, tools, or external services for this question from the “+” menu	Repeatable workflows, querying external systems
Conversation memory	Remember conversation context and your preferences	Ongoing discussions, long-term collaboration
Message actions	Edit sent messages and switch versions, like or dislike replies, and branch from a reply	Rephrase a question, give feedback on reply quality, explore different approaches to the same question
Organize conversations	Rename, delete, and pin conversations	Manage a growing conversation history

Capability	What it does	When to use it
Search conversations	Find past conversations by title or message content	Manage a growing conversation history
Share conversations	Share a whole conversation with organization members so they can browse it or copy it and continue asking questions	Share results, continue someone else's work
Conversation handoff	Create a handoff summary when a conversation gets too long, then continue in a new conversation	Long discussions, high context usage

---

Quick start

After signing in to the MaiAgent admin console, click MaiGPT at the top of the left menu to open the chat screen (see Web version: where to open it), then:

Choose a model — Before sending your first message, click the model name at the bottom right of the input box to select an AI

Type a question — Enter your question in the input box and press Enter to send

Upload a file — Click Add (+) at the bottom left of the input box → Upload file, or drag a file directly into the conversation area

Not sure where to start? Just type a question. AI automatically responds based on your question, with no setup required.

While AI is replying, the send button becomes a square Stop button. If you notice a mistake in your question, click it to stop the reply. Your sent message and earlier conversation remain, so you can ask again or use Edit message.

When you start a new conversation, the Office apps row below the input box provides shortcuts to Slides, Documents, and Spreadsheets (plus Meeting records if your organization has enabled meeting records). You can choose a template before starting. See AI Slides, Create documents and spreadsheets from templates, and Meeting records shortcut. This row disappears after you send your first message.

Choose an AI model

MaiGPT includes a range of AI models you can choose from based on your task. Each model has different strengths, and choosing the right one can improve your answers.

How to choose a model

Start a new conversation.

Click the model name next to the send button at the bottom right of the input box. The menu opens upward.

Enter a name in Search models··· to filter the list, then click the model you want to use.

You may see these labels next to model names in the menu:

Label	Meaning
Default	The model used when you do not explicitly choose one
Custom	A model connected by your organization, such as a self-hosted model or one in your company's own cloud account, configured by an administrator
Multimodal	Can understand images; suitable for questions about uploaded images
Reasoning	Supports reasoning effort adjustment; suitable for questions that require reasoning

> You cannot change models after sending the first message Once a conversation starts, the model name is locked. Hovering over it displays “You cannot change models after the conversation starts.” To ask the same question using a different model, start a new conversation and select it there.

When a model is locked or no longer available

After an administrator changes the models available to your role, you may see the following notices in older conversations:

What you see	Meaning and action
The model name is grayed out, with the tooltip “Your role can no longer use this model”	Access to this conversation's model has been revoked. You can still read its contents, but sending a message opens the dialog in the next row
A dialog saying “The model used in this conversation is no longer available” with Create new conversation	Click Create new conversation to use a currently available model. Attached files do not carry over to the new conversation; upload them again
A tooltip saying “Your role currently has no available models. Please contact your organization administrator”	No models are available to your role. Ask your administrator to adjust MaiGPT role permissions

What you see	Meaning and action
A tooltip saying “Conversation messages are loading. You can select a model shortly” or “Failed to load conversation messages…”	For the former, wait a moment; for the latter, refresh the page

Which model should I use?

My task	Suggested model	Why
Write reports, analyze documents	Claude	Strong Chinese comprehension and long-form writing
Code, technical questions	Claude GPT	Both perform well; try both and compare
Quick Q&A, translation	Gemini	Fast responses
Creative ideas, brainstorming	Claude GPT	Better creative output
Get the latest information	Enable web search	Works with any model

> Not sure which to choose? Start with the default model. If you are not satisfied with its answer, start a new conversation and ask another model the same question. Compare which answer better meets your needs.

Frequently asked questions

Can I change models during a conversation?

No. Once you send the first message, the model for that conversation is fixed. Your original conversation history stays intact. To use a different model, start a new conversation.

Why can't I see some models?

Your organization administrator configures available models by role (see MaiGPT role permissions). If your role currently has no available models, the model menu displays “Your role currently has no available models. Please contact your organization administrator.”

Do all models cost the same?

Usage is calculated differently for different models, but your company typically manages this centrally, so you do not need to worry about costs.

The “+” menu: files, skills, tools, and connectors

Add (+) at the bottom left of the input box contains resources to use with your question. Open it and hover over an item with an arrow to expand its submenu.

Item	What it does
Upload file	Select files to attach to this message; see Upload files and images. Hidden if the Agent does not allow uploads
Skills	Specify skills to use for this question, grouped into Built-in and Organization custom
Tools	Specify tools to use for this question, such as web search; also grouped into Built-in and Organization custom
Connectors	Toggle external services available to this conversation, or click Authorize for services that require authorization
Deep Research	Have AI break down a question and run multiple searches to produce a research report; see Deep Research

Specify skills and tools

Click Add (+) and hover over Skills or Tools.

Enter keywords in Search skills
Search tools at the top of the submenu, or click items directly in the list. You can select multiple items; click an item again to deselect it.

Selected items appear as tags in the input box. When you send a message, AI uses your specified skills or tools to answer.

Selected tags stay in this conversation and are included with subsequent messages. Click × on a tag to remove it when no longer needed. Tags clear automatically when you switch to another conversation. At the bottom of the submenu, Add skill
Manage my skills and Add tool
Manage my tools open the Skills and Tools management pages.

Connectors

The Connected services section in the Connectors submenu lists services enabled by your organization. Use the switch on the right to decide whether to use a service in this conversation. Services that require sign-in authorization display Authorize and become usable once authorization is complete. If your organization has not enabled any connectors, the menu displays “No connectors enabled for this organization.” For connection instructions and service usage, see Connectors.

Deep Research

Select Deep Research to add a tag of the same name to the input box. Your next message is processed in research mode. Each conversation supports only one Deep Research session. If research has already been performed in the conversation, this item is disabled; start a new conversation to use it again. If your role does not have access to this feature, the item is also disabled, with the tooltip "This feature is not enabled for your role. Please contact your organization administrator if you need access."

> Can't find the item you want? Skills, Tools, and Connectors only list items available to your role. Your organization administrator controls their scope; see MaiGPT role permissions.

Upload files and images

You can give MaiGPT files or images for AI to read, summarize, analyze, or translate.

How to upload

There are two ways:

Upload from the "+" menu — Click Add (+) at the bottom left of the input box → Upload file, then select your files

Drag and drop — Drag files from your desktop into the conversation area

After uploading, files appear above the input box. Enter your question, then press Enter to send.

> You do not need to upload frequently used project files each time. Place them in a file workspace in the File Library, then select Start conversation here from the workspace. MaiGPT finds the files relevant to your question and reads them in full before answering. See Use workspaces in MaiGPT.

Supported formats

Type	Formats
Documents	PDF, Word (.docx), Excel (.xlsx), PowerPoint (.pptx), TXT
Images	PNG, JPG, GIF
Other	CSV, JSON, Markdown
Email	Outlook messages (.msg), EML (.eml)

When you upload a `.msg` or `.eml` email file, AI can read its subject, sender, recipients, date, body, and attachment list. It also reads the contents of document attachments embedded in the email (up to 20, each no larger than 10 MB; image and audio attachments, as well as nested email attachments, are not read). Encrypted emails cannot be read.



After uploading an email, you can ask about both the message and its document attachments

What you can do

Uploaded content	What you can ask AI
A contract PDF	“Which clauses in this contract are unfavorable to us?”
An Excel report	“Summarize the key trends in this report”
A product image	“What are the specifications of the product in this image?”
A meeting presentation	“Summarize the three main points of this presentation”
An English document	“Translate this into Traditional Chinese”

Tips

> Upload multiple files at once You can select multiple files to upload together, and AI analyzes them together. For example, upload three quotations and ask “Compare the differences between these three quotations.”

> File size limits Document and audio file limits in conversations depend on your company's settings; the current default is 10 MB. Images have a separate limit. If a file exceeds the limit, MaiGPT shows the next steps instead of uploading it directly.

When file contents cannot be read

For example, a project manager wants to summarize a PDF sent by a partner, but the file was corrupted during transfer. She clicks Add → Upload file, selects the file, and enters a request for a summary. If the system cannot read its contents, the reply may explain that a summary cannot be provided and ask her to upload it again. When she sees this message, she can first check that the original file opens normally, then obtain a complete copy and upload it again.




In this verification, MaiGPT explained that it could not summarize the file and requested another upload.

> If parsing fails, first open the original file on your computer to confirm that it is intact and complete, then download it again or ask the sender to resend it. Do not use the filename as the basis for a summary. After uploading again, verify that the answer actually comes from the file contents.

What to do when a file exceeds the limit

For example, project manager Mai wants MaiGPT to summarize an 11 MB report from a fictional company. After selecting the file, the screen indicates that it exceeds 10 MB. Mai can upload it to a

knowledge base and link it, then return to the conversation to continue asking questions.



When a file exceeds the conversation limit, follow the on-screen instructions to handle it through a knowledge base

Check the filename and current size limit in the dialog.

If you have knowledge base permissions, click Go to knowledge base. Create or open a knowledge base, upload the file, and wait for processing to finish.

In the knowledge base's Linked AI Assistant (linked Agent) settings, link the knowledge base to the Agent used by MaiGPT. Return to AI Chat, click Select knowledge base, choose that knowledge base, and enter the question you want MaiGPT to handle.

> These steps apply to the MaiGPT admin web interface. Web Chat end users do not have a knowledge base entry point. If you do not see Go to knowledge base, ask your organization administrator to add the file to the Agent's knowledge base. You can also paste the passages you need analyzed, or split the file into smaller files and upload them again. Audio files tend to reach the limit more easily; try compressing them first.

Knowledge base Q&A

MaiGPT can connect to your company's knowledge base so you can query internal information through conversation. AI answers include sources that you can click to view the original documents.

How to use it

Just ask. If your MaiGPT is connected to your company's knowledge base, AI automatically searches for relevant information to answer your questions.

“What is the company's leave request process?”

“What are the differences between product A and product B?”

“What should new hires do on their first day?”

To limit the search scope for your question, click Select knowledge base at the top right of the conversation page, then select knowledge bases or individual documents and FAQs in the right panel. Once selected, the button displays “N documents selected.” If you cannot see this button, knowledge base RAG is not enabled for your role; contact your organization administrator.

Right panel: reference documents and Output

The Expand/collapse side panel button on the far right of the conversation page opens a panel with two sections:

Section	Contents
Reference documents	Knowledge base documents cited in this conversation. Select the scope to retrieve from here (the same setting as Select knowledge base)
Output	Files, images, and videos generated in this conversation. Each item has a Download option. If nothing has been generated, it displays “No output yet”

If “This feature is not enabled for your role” appears below a section heading, your administrator has not enabled that capability for your role. See MaiGPT role permissions.

Answers include sources

AI replies identify their sources, usually as citation markers or links. Click them to view the relevant passages in the original document.

This lets you:
- **Verify the answer** — See which document AI based its answer on
- **Learn more** — Open the full original text if the summary is not enough

Can't find an answer?

If AI replies “I couldn't find relevant information in the knowledge base,” possible reasons include:

Situation	What to do
The information has not been uploaded to the knowledge base	Ask an administrator to upload the relevant documents
The question is too vague	Try asking with more specific keywords
Knowledge base permissions restrict access	You may not have permission to access that information; contact an administrator

> AI not finding something does not mean your company lacks the information Administrators upload and maintain knowledge base content. If you know a document exists but AI cannot find it, notify your administrator to check whether it has been imported into the knowledge base.

Web search

MaiGPT can search the web for the latest information to answer your questions. This is useful for news, market developments, competitor information, and other situations that require current data.

How to use web search

Mention that you need the latest information in your question, and MaiGPT decides whether to search the web:

"Search for today's Taiwan stock market closing level"

"What recent regulatory updates relate to AI?"

"Find out what new products competitor X has recently launched"

To ensure a web search is performed for this question, select the web search tool from the "+" menu:

Click Add (+) at the bottom left of the input box and hover over Tools.
Enter "search" in Search tools, then select the web search tool under Built-in.
Enter and send your question.

While AI searches, the reply displays "Searching the web" along with the search keywords. When finished, it changes to "Searched the web," then provides a complete answer with links to its sources.

> The tool list only shows tools available to your role. If you cannot find the web search tool, ask your organization administrator to check the Tools scope in MaiGPT role permissions.

When to use web search

Use it for	Not needed for
Latest news and current events	Internal company information (use the knowledge base)
Product prices and specifications	Writing reports or translating (without external information)
Regulatory and policy updates	Analyzing uploaded files
Researching market trends	Everyday conversation and brainstorming

> Web search vs Deep Research Web search is useful for quickly looking up a question, with answers in seconds. If you need to research a topic in depth and produce a complete report, use Deep Research.

Reasoning effort

Reasoning effort controls how deeply AI reasons before answering. Higher effort is better suited to complex questions involving reasoning, analysis, or decisions with multiple steps, but replies take longer and consume more usage.

How to adjust it

At the bottom right of the input box, to the left of the model name, click the Reasoning effort button (it displays the current level, such as Default).

Choose a level from the menu. This setting applies only to this conversation. You can change it at any time during the conversation; subsequent replies use the new level.

Level	Description
Default	No explicit level is specified; the Agent settings or the model itself determines it. Based on the model's actual behavior, the menu labels it Default (no reasoning · fastest) or Default (model decides how to reason); see below
Off	No reasoning. Labeled Off (same as default) if the model does not reason by default, or Off (fastest) if the model reasons by default
Minimal–Maximum	Enable reasoning. Higher levels mean deeper reasoning, slower replies, and more credits. Enabling reasoning adds roughly 1–3 seconds per model call, depending on the model

Does "Default" actually enable reasoning? It depends on the model:

Default (no reasoning · fastest): This model does not think when no level is specified, making this the fastest option. Selecting any thinking level (including Minimal) will be slower than the default.

Default (model decides how to reason): When no level is specified, this model decides whether to think and how deeply. For the fastest replies, select Off (fastest) (shown only when the model supports disabling thinking).

If Default and Off have no labels in parentheses, "Default" follows the level configured by the Agent administrator in the Agent settings. The menu does not label its speed.

> Available levels depend on the model The menu lists only the levels supported by the current model. Off appears only when thinking can be disabled. If the model does not support adjusting thinking effort, this button does not appear in the input box. The menu button displays only a short name (such as Default or High); labels in parentheses appear only when you open the menu.

While the AI is thinking, a "Thinking" section usually appears above its reply and expands automatically. When thinking finishes, it collapses to "Thought for N seconds." Click it to expand and view the thinking content.

When to increase the level

Increase the level for	Use the default or a lower level for
Complex analysis and comparisons	Simple questions ("What's the weather like today?")
Tasks requiring logical reasoning	Translation
Mathematical calculations and data analysis	Casual conversation
Decisions that need multiple perspectives	Polishing or rewriting text

---

Conversation memory

MaiGPT remembers your conversations so you can continue earlier discussions without explaining the background every time.

Two types of memory

Conversation memory (short-term)

Within the same conversation, the AI remembers what you said earlier. You can continue the discussion:

You: “Summarize the key points of Q1 sales performance.”

AI: (Provides a summary.)

You: “Add a comparison with Q2.” ← The AI knows you mean sales performance.

Starting a new conversation clears short-term memory, and the AI starts from scratch.

Long-term memory

MaiGPT can remember important information across conversations, such as your role, preferences, and frequently used formats.

You: “Remember that I work in marketing and always use bullet points in reports.”

AI: Got it. I'll remember that.

The AI will remember these preferences even in new conversations.

Tips

> Make the most of a single conversation When working on one topic (such as writing a report), try to finish it in the same conversation. This lets the AI remember all the context and provide better answers.

> Need a fresh start? If you want to switch to a completely different topic, start a new conversation to keep the previous topic from affecting answers about the new one.

Message actions

Hover over any message to see a row of small icons below it. Your own messages have Copy and Edit message; AI replies have Copy, Like, Dislike, and Branch conversation from here. These actions work the same way in MaiGPT, the Agent Marketplace, and Web Chat. See the comparison table at the end of this section for differences.

Edit sent messages and switch versions

If you asked the wrong question or left out a condition, you don't need to start a new conversation.

Hover over your own message and click Edit message (the pencil icon). The message becomes an editable text box.

Edit the content. A notice below the text box says: “Editing this message will delete all subsequent conversation content. The Bot will generate a new reply based on the updated content.”

Click Confirm (or Cancel to discard the edit). The AI generates a new reply based on the updated content.

A version selector, ‹ 2
2 ›, appears below edited messages. Use the left and right arrows to switch versions; the numbers indicate “current version
total versions.” Switching versions also switches the AI replies that follow that version. The original replies are not actually lost.

> Editing changes the course of the conversation after this message. If you still need the later replies, copy them first or use a conversation branch to preserve the original path.

Like, dislike, and give feedback on replies

If a reply is helpful, click Like; click again to remove it.

If a reply has a problem, click Dislike to open the Provide feedback dialog. Select a reason (irrelevant to the question
inaccurate or factually incorrect
incomplete or too brief
did not follow instructions or requirements
inappropriate or unprofessional tone), add details under Other feedback if needed, and click Submit. Click an existing dislike again to remove it.

Your likes and dislikes are recorded on each reply. The Agent's administrators can view feedback for each reply in the Conversation Viewer. The “User satisfaction” metric in Usage Analytics is also calculated from these likes and dislikes, so give feedback based on your actual experience.

Branch a conversation from a reply

To try a different question in the same context while preserving the current conversation, hover over an AI reply and click Branch conversation from here (the branching icon). The system copies the content **up to and including that reply** into a new conversation, displays “Conversation branch created!”, and switches to it automatically. The original conversation is unaffected, and each can continue independently.

Unlike editing a message, which changes what follows in the same conversation, branching creates a separate conversation.

Answer an Agent's question cards

Some Agents (such as Deep Research or Conversation Handoff) use question cards to clarify your needs before proceeding. Question cards appear in place of the input box. Here's how to use them:

Action	How to do it
Single or multiple choice	Click an option. Questions labeled “You can select multiple options” allow multiple selections; click an option again to deselect it.
Ranking	Drag options to reorder them, or use `Shift + ↑` `↓`.
Other answers	When a question allows a custom response, an Enter another answer⋯ field appears.
Navigate multiple questions	Use Previous Next. “Question N M” appears at the top.
Submit	Click Confirm and submit. A Skip option is also available for questions you can skip.
Keyboard	`Enter` submits or advances to the next question, `Space` toggles selection, `↑` `↓` switches options, `←` `→` moves to the previous/next question, and `Esc` skips.

If a card displays “Estimated usage: about N Credits,” the work that follows submission is expected to consume approximately that many Credits. In Web Chat, administrators can display question cards as a floating row of buttons above the input box. See Function Settings: Question option display mode.

Another type of card comes from the tools themselves. When an Agent calls an MCP tool or connector with an interactive interface, a card appears below the reply for you to query, fill in, or submit directly. See MCP interactive cards (MCP Apps).

Comparison across three interfaces

Action	MaiGPT	Agent Marketplace	Web Chat (website visitors)
Copy	✅	✅	✅
Like/dislike and provide feedback	✅	✅	✅ All visitors
Edit messages and switch versions	✅	✅	Only logged-in visitors
Branch conversations	✅ “Branch conversation from here”	✅ Same as MaiGPT	Only logged-in visitors; the button is named Branch conversation
Question cards	Options panel	Options panel	Options panel or floating buttons, configured by the administrator

Organize conversations: Pin frequently used conversations

As your conversations accumulate, important or frequently used ones can be pushed down by newer conversations and become hard to find. Pin them to keep them at the top of the conversation list on the left, just a click away.

How to pin

In the conversation list on the left, hover over the conversation you want to pin.
Click the ⋮ menu that appears on the right.
Select Pin.

The conversation moves to the Pinned section at the top of the list, with a 📌 icon beside its title.

How to unpin

Click the ⋮ menu on a pinned conversation and select Unpin. It returns to Recent conversations below.

Sorting and rules

Item	Description
Sort order	Both the pinned section and the regular list are sorted by the time of the last message, newest first, regardless of when you pinned a conversation.
Number of pins	There is no limit; you can pin multiple conversations at once.
Persistence	Pins are saved and remain after refreshing the page or logging in again.
Collapse the section	Click the “Pinned” heading to expand or collapse the section.
Scope	You can pin only your own conversations.

When pinning is useful

Finance
banking: Reconciliation or financial plan comparison conversations you regularly follow up on.

Technology
electronics manufacturing: Frequently used product specification or technical troubleshooting conversations.

Educational institutions: Recurring admissions questions or course planning discussions.

Services
retail: Ongoing event planning or membership benefit inquiries.

Or any workflow you return to every day.

> Pinning affects only your own view Pinning is a personal organizational tool. It changes only the order you see in your conversation list; it does not affect other members or the conversation content.

Organize conversations: Rename and delete

In the conversation list on the left, hover over a conversation and click the ⋮ on the right to see these options: Pin
Unpin (see the previous section), Rename, and Delete conversation.

Rename a conversation

The title is generated automatically from the first message. Click ⋮ → Rename, enter a new title, and press `Enter` or click Confirm. This changes only the title, leaving the content intact.

Delete a conversation

Click ⋮ → Delete conversation and confirm “Are you sure you want to delete this conversation?” The deletion cannot be undone. Shared versions remain available; see Sharing rules.

Delete multiple conversations at once

To clean up several of your own conversations at once, open All conversations on the left side of MaiGPT. You can also delete conversations in bulk from the left sidebar on the Agent Marketplace conversation page. See Chat with an Agent: Delete multiple conversations at once.

For example, after a round of proposal testing, a project manager wants to remove two test conversations. She searches for the test topic in All conversations, clicks Edit, selects the two conversations, and confirms deletion. They then disappear from the list and from recent conversations on the left.

Open All conversations. Search conversation titles or messages first if needed.

Click Edit to the right of the search box and select the conversations to delete. You can also click Select all to select conversations in the currently loaded list. You can select up to 100 at a time; conversations that have not loaded are excluded.



Check “2 selected” and the selected items, then click “Delete” at the bottom right.

Click Delete at the bottom right, check the count in the confirmation dialog, and click Delete again. If all deletions succeed, “Deleted N conversations” appears and edit mode closes.



The confirmation dialog shows how many conversations you are about to delete.

> Messages in these conversations are also deleted, and the interface offers no undo. Deleting the original conversation does not revoke existing shares; manage them separately according to the Sharing rules.

To cancel, click Cancel in the confirmation dialog, or return to the list and click Done to exit edit mode. Changing the search keyword clears your selections. Check the conversations you want to delete again. If some deletions fail, successfully deleted conversations are removed first, while failed items remain in the list. If the entire batch fails, try again later.

> Pinning is exclusive to MaiGPT. The Agent Marketplace conversation sidebar supports renaming, deleting, and deleting multiple conversations at once, but not pinning. The Web Chat history sidebar automatically groups conversations by today, yesterday, and the past 7 days. See Web Chat: Conversation history sidebar.

Organize conversations: Search conversations

If you remember discussing something but can't recall which conversation it was in, search by keyword. Search covers your own MaiGPT conversations and matches **conversation titles and message content**.

Open the search panel with a keyboard shortcut

On the MaiGPT page, press `Cmd + K` (`Ctrl + K` on Windows) to open the search panel in the center of the screen.

Before you type, the panel lists Recent conversations. Enter keywords in Search conversation titles or messages⋯, and results update in real time. Title matches highlight the keyword in the title; message matches display a message excerpt containing the keyword below the title.

Use `↑` `↓` to select a result and press `Enter` to open the conversation, or click the result directly. Press `Cmd + K` (`Ctrl + K`) again or `Esc` to close the panel.

Browse and search on the All conversations page

Click All conversations above the conversation list on the left (or the arrow beside the Recent conversations heading) to open the full-page conversation list. Scroll down to load more conversations automatically. Enter keywords in the search box at the top; matching works the same way as in the search panel.

> When no conversations match, the search panel displays “No results found,” while the All conversations page suggests trying other keywords. If the search panel displays “Search failed. Please try again later,” wait a moment and search again.

Share conversations

You can share an entire conversation with members of your organization. They can open the link to view the full content. If you allow copying, they can also copy it to their own conversation list with one click and continue asking questions.

Use case

A knowledge base administrator uses MaiGPT to compile an FAQ for new employees and wants the entire organization to use it directly. At the top of the conversation, he clicks Share and selects Quick share with the organization. The link is immediately copied to the clipboard, ready to paste into an announcement. Members can open it to browse the entire FAQ. To ask follow-up questions about their own situation, they click Continue conversation to copy it to their own conversation list. The original conversation is unaffected.

How to share

The sharing button is at the top of the conversation page and appears only when the current conversation contains messages.

1. Click “Share”

Click Share at the top of the conversation page to open two options:

Quick share with the organization: Generates a link and copies it to the clipboard immediately. All organization members can view and copy the conversation, with no additional settings required.

Customize sharing scope: Choose who to share with and their permissions. See the next step.



The Share button offers Quick share with the organization and Customize sharing scope

2. Set the sharing scope and permissions

After selecting Customize sharing scope, configure the following in the dialog:

Field	Description
Sharing scope	Everyone in the organization, Specific groups, or Specific members. For groups or members, click the selection row below and check the recipients. You can select several at once.
Share title	Optional. The title shown on the shared page and in the Browse organization shares list. Leave blank to use the conversation title.
Description	Optional. Briefly describe the conversation's key points or purpose.
Sharing permissions	Allow copying (default): Recipients can copy the conversation to their own list and continue asking questions. Read only: Recipients can only view it.

分享

分享範圍

組織內全員
一鍵複製分享連結（預設全員可見）

特定群組
選擇特定群組成員可查看

特定成員
僅限指定成員查看

分享標題

新進人員常見問題

描述

報到、設備、報帳、會議室、通訊工具五題問答，可複製後依自己的情況追問。

35 / 500

分享權限

可複製

只讀



Set the sharing scope, title, description, and permissions in the same dialog

3. Generate and send the link

Click Generate share link. The link is copied to the clipboard automatically. You can also click Copy link on the screen to copy it again. Send the link to the recipient, who must log in to MaiAgent to open it.



The generated link is copied automatically; you can also click Copy link again

What recipients see

After logging in and opening the link, the recipient sees the shared page. The top shows the title, sharer, sharing time, and message count; below is the entire conversation. This page is for viewing only and has no input box.

With Allow copying permission, Continue conversation appears at the bottom. Clicking it copies the conversation into a new conversation owned by the recipient, displays “Copied to your conversation list!”, and switches to it automatically so they can ask follow-up questions immediately.

With Read only permission, the page displays “This conversation is shared as read only,” with no copy button.

Members outside the sharing scope, or accounts from other organizations, see “Unable to load this shared conversation. The link may no longer be valid.”



Pages that allow copying have a Continue conversation button at the bottom; click it to copy the conversation to your own list

> The copy is a new conversation After clicking Continue conversation, the recipient continues in a new conversation under their own account. Your original conversation is unchanged, and you cannot see their subsequent content. The two conversations are independent.

Browse organization shares and manage your shares

Click Browse organization shares at the top of the conversation page to list all shares in the organization that you have permission to view. Search by title or description, then click View to open a shared page.

On this page, click My shares to manage every conversation you have shared:

Action	Description
Edit	Change the share title, description, and sharing permissions. You cannot change the sharing scope or recipients after creation. To share with different people, revoke the share and create a new one.
Copy link	Copy the same sharing link again.

Action	Description
Revoke share	After revocation, others opening the link see a loading error. Conversations already copied to their own lists are unaffected.



Use My shares to edit, copy links, or revoke shares

Sharing rules

Item	Description
Shared content	The share contains the content as it was when you clicked Share. Messages you add to the original conversation afterward do not appear on the shared page. Create a new share to share updated content.
Excluded content	AI thinking and tool execution logs do not appear on the shared page. Only the conversation text, code, and Canvas content are included.
Who can open it	Only logged-in members of the same organization. If the scope is limited to groups or members, people outside that list cannot open it.
Expiration	There is no expiration date. The share remains valid until you revoke it.
After the original is deleted	The shared page can still be viewed and copied, retaining the version from the moment it was shared.
Who can manage it	Only the person who created the share can edit or revoke it.

Review earlier content while a reply is being generated

While MaiGPT generates a long reply, you can scroll up to review earlier content. The screen stays where you scroll instead of jumping back to the latest output as new text appears. When you scroll **above the most recent question**, a white Back to latest pill appears above the input box. Click it to return to the last question and resume automatic following.

Use case

A customer service manager asks MaiGPT to put together a long training checklist. While the AI is still writing, she wants to check the requirements she provided in the previous exchange, so she scrolls up. The screen stays at the passage she wants to read, without being pushed away by newly generated text, and Back to latest appears above the input box. After checking, she clicks the pill button to return to her current question and continues watching MaiGPT finish the remaining content.

How to use it

1. Scroll up

While MaiGPT is generating a response, scroll up using the mouse wheel, a touch gesture, or the scroll bar.

2. Read in place

The screen stays where you scrolled to, and newly generated content does not change your current position. When you scroll above the last question, Back to latest appears above the input box.



After you scroll above the last question, Back to latest appears above the input box. Click it to return to that question.

3. Return to the latest content

Click Back to latest to return to the last question and resume automatically following the latest content. You can also scroll back down to the bottom to resume following.

> Back to latest only appears when you are above the last question. If you scroll down within the same long response to read content already generated, the screen also stays in place, but the pill button does not appear. Scroll to the bottom to catch up with the latest content.

Navigation for long conversations

After asking many questions in a conversation, finding a particular one can take effort. When the conversation contains at least 3 of your questions and the browser window is at least 768 pixels wide, a column of small dots appears on the right side of the conversation area. Each dot represents one of your questions, and the question currently in view is highlighted.

Hover over the column of dots to expand a text list showing the beginning of each question (up to 50 characters). Questions with only attachments appear as "[Attachment]".

Click any question to scroll to it. A brief highlight helps you locate it.

Move the pointer away to collapse the list back into a column of dots.

Next steps

Write documents with Canvas

Create AI presentations

Quick access to meeting records

Back to the MaiGPT overview

Conversation Handoff

The longer you chat in the same conversation, the more the assistant needs to remember. When the content approaches its limit, the assistant starts to lose track of what you discussed at the beginning.

With “Conversation Handoff,” you can ask the assistant to organize your current progress into a **handoff summary**, then start a new conversation with one click to continue your work. The assistant in the new conversation reads this summary first, so you do not need to explain the background again. The original conversation is also preserved for you to revisit at any time.

> Conversation handoff is available only after MaiAgent enables the system's global conversation handoff feature. This global switch is not available in the admin console, and customer administrators cannot configure it themselves. Contact MaiAgent to enable it. Once enabled globally, conversation handoff is available in MaiGPT and Web Chat. For Web Chat, an administrator must also turn on “Enable Conversation Handoff” for the conversation platform (see Enable in Web Chat). Other conversation platforms, such as LINE, Facebook Messenger, and Microsoft Teams, are not supported.

Use Case

A marketing specialist is planning an autumn product launch in MaiGPT. She has spent the afternoon discussing the venue, guest count, budget allocation, and introduction scripts for two featured products with the assistant. She notices that “Context Usage” below the input box has reached 82%, and a prompt bar above the input box suggests preparing a handoff.

She clicks “Prepare Handoff.” The assistant creates a handoff summary listing the event goals, the confirmed venue and budget, the introduction scripts in progress, and the remaining tasks. After reviewing the summary, she clicks “Continue in New Conversation.” The screen switches to a new conversation, and the assistant first says, “We've picked up where you left off. The current tasks are…” She then asks the assistant to write the invitation without pasting the earlier discussion again.

Where You Can Use It

Entry Point	Users	Description
MaiGPT	Organization members	The MaiGPT conversation page works the same way in every layout. Once the global conversation handoff feature is enabled, you can use it without configuring a separate platform switch
Web Chat	Website visitors, organization members	The Web Chat conversation window embedded on a website is also available to visitors who are not logged in. After the global conversation handoff feature is enabled, an administrator must also turn on “Enable Conversation Handoff” for that conversation platform (off by default)

> The Web Chat assistant must use Agent mode The assistant prepares the handoff summary. If the assistant connected to Web Chat does not use “Agent mode” (or Agent Teams), it cannot generate a handoff summary. MaiGPT is not affected.

Enable in Web Chat

Conversation handoff and context usage in Web Chat have **two independent switches**, configured separately for each conversation platform and off by default. Visitors to a customer's embedded Web Chat see neither handoff prompts nor context usage until an administrator enables them. “Show Context Usage” takes effect as soon as it is enabled. “Enable Conversation Handoff” takes effect only after MaiAgent enables the global conversation handoff feature.

The customer service manager at an online retailer notices that website visitors often ask about several orders in a single conversation. As the conversation gets longer, the assistant loses track of order numbers mentioned at the start. She wants visitors to first see how much conversation space they have used, so she opens Feature Settings for the official website's Web Chat conversation platform, enables only Show Context Usage, and saves. When visitors reopen the conversation window and receive the assistant's first reply, “Context Usage” and a percentage appear below the input box.

1. Open the Conversation Platform's Feature Settings

In the admin console, go to Customer Service Conversations → Conversation Platforms. Edit the Web Chat platform you want to enable, then click Feature Settings in the left menu.

2. Enable the Switches You Need and Save

The “Basic Features” section has two switches. You can enable either one or both:

Switch	Effect in Web Chat When Enabled
Enable Conversation	When the global conversation handoff feature is enabled, a handoff prompt bar appears starting at 80% context usage, the assistant can generate a handoff summary card, and visitors

Switch	Effect in Web Chat When Enabled
Handoff	can continue in a new conversation. If the global feature is disabled, turning on this switch produces no visible change
Show Context Usage	Displays the context usage percentage below the input box

After configuring the switches, click Save.



“Enable Conversation Handoff” and “Show Context Usage” under “Feature Settings” → “Basic Features”

> The two switches are independent: If you enable only “Show Context Usage,” only the percentage appears, without a handoff prompt bar. If you enable only “Enable Conversation Handoff,” usage is not displayed below the input box, but the handoff prompt bar still appears at the 80%, 90%, and 100% usage thresholds (the global conversation handoff feature must be enabled). Conversation handoff also requires the global switch: MaiAgent controls the global conversation handoff switch. It is not available in the admin console, so customer administrators must contact MaiAgent to enable it. When the global switch is off, handoff is unavailable on all platforms, including MaiGPT, and enabling “Enable Conversation Handoff” produces no visible change. “Show Context Usage” is unaffected by the global switch. The settings page for internal platforms does not display these two switches. For their locations on the settings page, see Feature Settings.

View Context Usage

A “Context Usage” row below the conversation input box contains a short progress bar and a percentage. It shows how much of the assistant's available memory space this conversation has used.

MaiGPT: Always displayed; no configuration is needed.

Web Chat: Displayed only after an administrator enables Show Context Usage for that conversation platform (see Enable in Web Chat). This switch is independent of “Enable Conversation Handoff.”

Display rules:

In a new conversation, the row appears only after the assistant's first reply.

It updates after each completed assistant reply.

The maximum displayed value is 100%.

The closer usage gets to 100%, the more advisable it is to continue in a new conversation. Once it reaches 100%, the assistant starts losing access to the earliest conversation content.



“Context Usage” below the input box updates after each assistant reply



After “Show Context Usage” is enabled in Web Chat, “Context Usage” and a percentage appear below the input box

Three Ways to Start a Handoff

1. Ask the Assistant Directly

At any time, you can enter and send a message like this:

Hand off this conversation to a new conversation

The assistant prepares a handoff summary (see “Handoff Summary” below). You do not need to wait for usage to increase before handing off.

2. Use the Prompt Bar

When context usage reaches **80%**, a prompt appears above the input box:

This conversation is approaching its context limit. We recommend preparing a summary and handing off to a new conversation to continue

The prompt bar has two buttons on the right:

Prepare Handoff: Automatically sends “Hand off this conversation to a new conversation” for you, and the assistant prepares the handoff summary.

Close: Hides the prompt bar so you can continue in the original conversation.

After you close it, the prompt bar appears again when usage crosses the next threshold (**90%**, **100%**). At 100%, the prompt changes to:

This conversation has reached its context limit. To preserve the completeness of the conversation content, we recommend preparing a summary and handing off to a new conversation to continue

> Closing the prompt bar applies only to the currently open page. After refreshing the page, the prompt bar appears again if usage is still above the threshold.

3. Respond to the Assistant's Proactive Question

When context usage reaches 80%, the assistant adds a question at the end of that reply, such as:

This conversation is getting quite long. Would you like me to summarize the key points and hand off to a new conversation to continue?

If you agree with a response such as “Yes” or “Sure,” the assistant prepares a handoff summary.

If you say “No” or ignore the question, the assistant continues as usual without repeating the question every time.

The assistant reminds you once more at each of the 90% and 100% thresholds.

The assistant's question and the prompt bar appear at the same time. You can use either method to start the handoff.

Handoff Summary

The assistant's summary remains in the original conversation as a "Handoff Summary" card with five sections:

Section	Content
Goals	What this conversation aims to accomplish
Decided	Confirmed decisions and conclusions
In Progress	Items still being worked on and their current status
To Do	What needs to be done next
Key References	Important numbers, names, and names of previously uploaded files

The summary uses the language of your conversation. Sections with no content are hidden.

At the bottom of the card is a "Continue in New Conversation" button, with a note beside it indicating which new conversation will be created.



After you enter a handoff request, the assistant leaves a handoff summary card in the original conversation

> The system does not switch conversations automatically After the handoff summary is generated, you remain in the original conversation. Review the summary and confirm it is correct before clicking “Continue in New Conversation.” If important information is missing, ask the assistant to add it in the original conversation, or request another handoff.

You can hand off the same conversation more than once. Each handoff creates a new summary, and only the **latest summary** displays the button.

Continue in a New Conversation

Click “Continue in New Conversation”

Click Continue in New Conversation at the bottom of the handoff summary card. While the conversation is being created, the button displays “Creating New Conversation…”.

Enter the New Conversation

The screen switches to a new conversation whose title is the original title followed by “(Continued)”. The system sends the first message on your behalf, with the text “Continuing from the handoff for 〈original conversation title〉”. The message is labeled “Sent by System”.

The Assistant Confirms the Continuation Status

After reading the handoff summary, the assistant first confirms the continuation status in one sentence, such as “We've picked up where you left off. The current tasks are…”. You can then chat as usual.



The system sends a continuation message in the new conversation, and the assistant reads the summary and confirms the continuation status

After the handoff, the conversation list shows the relationship between the two conversations. The original is labeled “Handed Off To,” and the new one is labeled “Continued from Original Conversation.” The button in the original conversation changes to “Go to New Conversation”. Clicking it again returns to the same new conversation without creating another one.



The conversation list shows the handoff relationship between the two conversations

If creating the new conversation fails, the screen displays “Failed to create a new conversation. Please try again,” and the button becomes available to click again.

What You Can Do After Continuing in a New Conversation

Continue your work directly: The assistant already knows the goals, decisions, and tasks in the handoff summary, so you can give it the next instruction immediately.

Use the same assistant: The new conversation uses the same assistant as the original, with the same model, knowledge base, and tool settings.

Revisit the original conversation: The complete original conversation remains in the conversation list for you to open and review whenever needed.

Hand off again: When the new conversation gets long, you can hand off to another new conversation. Usage is calculated afresh in each new conversation.

The assistant in the new conversation can see only the handoff summary, not the other messages in the original conversation. The following content is not carried over:

Files and images uploaded in the original conversation (the summary lists only their filenames)

Files generated in the original conversation and Canvas content

Conversation details outside the summary

If the new conversation needs this content, upload the files again or paste the relevant passages into the new conversation.

> If the original conversation or handoff summary was deleted before continuing, the assistant says, “I couldn't find the handoff summary from the original conversation. Please tell me directly what you'd like to continue.” Simply explain what you want to continue.

Notes for Web Chat Visitors

Web Chat visitors who are not logged in can also hand off conversations using the steps above. Keep in mind:

The new and original conversations are saved only in the visitor's current browser. They are not available in another browser or on another device.

After the visitor's conversation history expires, the original conversation can no longer be opened, but an already created new conversation remains usable.

Unsupported Scenarios

Scenario	Description
Other conversation platforms such as LINE, Facebook Messenger, Microsoft Teams, and Slack	Usage and prompt bars are not displayed, and the assistant does not proactively ask about handoff
Automatically switching to a new conversation	Not supported. You must click “Continue in New Conversation” yourself
Handing off to a different assistant	Not supported. The new conversation always uses the original assistant
Carrying the original conversation's attachments and generated files into the new conversation	Not supported. Upload them again in the new conversation
Compressing content and continuing within the same conversation	Not supported. A handoff always opens a new conversation

---

Frequently Asked Questions

Can I hand off while usage is still low?

Yes. Enter “Hand off this conversation to a new conversation” directly. You do not need to wait for the prompt bar.

Can I still hand off if I accidentally closed the prompt bar?

Yes. Ask the assistant to hand off directly in the input box.

How is context usage calculated?

The percentage represents how much of the assistant's available memory space the conversation currently occupies, estimated from the conversation content and the assistant's model. Different models can remember different amounts, so conversations of the same length may have different usage percentages.

Can I keep chatting in the original conversation after a handoff?

Yes. The original conversation is not locked, but its usage is already high, so we recommend continuing in the new conversation.

Related Features

AI Chat

Feature Settings: The “Enable Conversation Handoff” and “Show Context Usage” switches for Web Chat

Conversation Handoff and Continuation API (Technical Manual): How to create a continuation conversation from a handoff summary when building your own frontend or integrating through the API

AI Memory

The AI Memory page lets you view and manage the preferences and facts currently saved in your account. You can add, edit, delete, or reactivate your memories here.

> AI Memory is enabled by default in the cloud version, with no additional request required. Availability in on-premises deployments depends on organization settings. You can turn off your own AI Memory on this page at any time; see Turn AI Memory On or Off.

When to Use It

For example, a project manager wants to organize the communication preferences saved in her account. She can open AI Memory to review the existing content and manually add a preference to "reply in English." As her needs change, she can edit or delete it at any time.

Open the Memory List

Click the account menu in the upper right and select Account. In the organization section of your profile page, click AI Memory. The page lists your memories; if none exist yet, it shows "No memories yet."



Empty state of the AI Memory list

Turn AI Memory On or Off

At the top of the AI Memory page is a Let the Assistant Remember Me toggle, which is on by default. Decide whether you want the Agent to remember you based on your needs. This toggle only affects your own memories in the current organization. It does not affect other members of the same organization or your settings in other organizations.

Click the account menu in the upper right and select Account. On your profile page, click AI Memory.

Switch the Let the Assistant Remember Me toggle at the top of the page. After the change succeeds, “AI Memory enabled” or “AI Memory disabled” appears.

When turned off:

The Agent does not remember new content from your conversations, and the “remember this” feature is unavailable.

The Agent does not refer to your saved memories during conversations.

A message above the list says “AI Memory is disabled. The assistant will not read or add your memories.”

> Turning off the toggle does not delete memories. Saved memories remain, and you can still view, edit, delete, or manually add them on this page. Once you turn it back on, the Agent can use these memories again. Conversations held while it was off are not added to memory retroactively.

> If the toggle is off and cannot be clicked, and “Your organization has not enabled AI Memory” appears, your organization currently has this feature disabled. The Agent will not remember any members. Contact your organization administrator or MaiAgent support if you have questions.

Add a Memory Manually

On the AI Memory page, click Add in the upper right.

Select a type and enter a topic, summary, and details. Use English `snake_case` for the topic, such as `communication_style`. Enter each detail on a separate line if needed.



Fields to fill in when adding a memory manually

Click Save. The new memory appears in the list.

Ask the Agent to Remember Something in Chat

In addition to adding memories manually on the AI Memory page, you can tell the Agent "Please remember…" directly in a conversation. The Agent organizes the content into a memory and saves it to your memory list for reference in future conversations.

The Agent may also proactively record facts it considers useful over the long term, such as your job role, preferred response language, or frequently used skills.

Requirements

The Agent can write memories during a conversation only when all of the following conditions are met:

The organization has enabled AI Memory.
Your Let the Assistant Remember Me toggle is on (the default).
Vector Memory is enabled in the Agent's settings.

The person chatting is a member of the organization the Agent belongs to. Conversations with anonymous visitors are not saved to memory.

The same conditions apply when using an Agent from the Agent Marketplace: as long as you are a member of the Agent’ s organization, the Agent can use your AI Memory.

> The Agent does not save sensitive personal information, such as credit card numbers, national ID numbers, passport numbers, bank account numbers, mobile phone numbers, Email addresses, passwords, or API keys. Content containing this information is not saved to memory, and the Agent tells you it cannot save it.

Use Case

For example, a marketing planner is preparing a new product presentation in MaiGPT and wants to avoid repeating the product code name in every future conversation. She types “Please remember: our demo product code name is Aurora. Use this code name when writing product introductions from now on.” The Agent runs Save Memory and confirms that it has remembered the information. On the AI Memory page, she can see this memory tagged as User Request. When she opens a new conversation and asks the Agent to write a product introduction, it uses the code name Aurora.



Ask the Agent to remember something in chat; the steps area shows that Save Memory was used

> If a memory written by the Agent has the same topic as an existing memory, it updates that memory instead of creating a duplicate.

Memory Source Tags

Each memory in the list has a source tag. Memories written by the Agent during conversations display one of these two tags:

Tag	Meaning
User Request (green)	Content you explicitly asked the Agent to remember in a conversation
Assistant Recorded (purple)	Content the Agent proactively identified and saved during a conversation

Other source tags may also appear, such as Manually Added for memories you add on this page, or AI Extracted for memories the system automatically organizes from conversations. If a memory is not something you want to keep, edit or delete it as described below.



Source tags in the memory list: AI Extracted and User Request

Manage Existing Memories

In the memory list, you can:

Edit the topic, summary, and details.

Delete memories that are no longer accurate or that you do not want AI to use. Deletion cannot be undone.

Reactivate expired items in the “Expired Memories” section.

Click the refresh button to update the list.

> Memories may affect answers in future conversations. If content is outdated, inaccurate, or unsuitable for long-term retention, correct or delete it promptly.

Usage and Billing

AI Memory uses your organization’s Credits in two ways:

Usage	How It Is Billed	How It Appears in Consumption Records
Organizing memories	When AI Memory organizes and saves memories from conversations, the platform's system model performs the work. Credits are deducted at that model's rate, with a separate record for each operation. Charges are attributed to the member being remembered. If member quotas or role quotas are configured, usage is also deducted from that member's personal quota and their role's quota.	Service category AI Memory, with AI Memory (Input) and AI Memory (Output) in the details
Referencing memories in answers	Memories included when the Agent answers count toward that reply's input usage and are billed according to the model the Agent uses.	A note next to the reply's input row says "This input includes approximately N tokens of AI Memory, already included in input usage"

Memories are not organized, and no AI Memory consumption is incurred, in the following cases:

You have turned off Let the Assistant Remember Me, the organization has not enabled AI Memory, the conversation is with an anonymous visitor, or the Agent does not have Vector Memory enabled.

A message contains sensitive personal information (these messages are not sent for memory organization).

The organization has insufficient Credits, or the remembered member's personal quota or their role's role quota is exhausted.

The organization process fails.


If the process succeeds but finds nothing worth remembering, it is still billed.

For how organization administrators can view this consumption, see Credits Billing: View AI Memory Consumption. If you do not want your conversations to generate AI Memory usage, turn off AI Memory. The Agent will then stop organizing memories from your new conversations and will not include your memories when answering.

Canvas

Canvas is the area MaiGPT uses to display documents and charts. When AI generates content in Canvas, you can view the result alongside the conversation and use preview, source code, and download features depending on the content type. Markdown documents currently support previewing. To edit text manually, download the file first, then open it in a text editor.

> Web Chat embedded on a website has the same Canvas, plus a map canvas that displays places and itineraries. For the visitor-side toolbar and controls, see Web Chat: Canvas and Browser.



Markdown Canvas displays the document content, with source code, full-screen, and download controls in the upper-right corner

When to use Canvas

Scenario	Example prompt
Write a report	"Write a Q1 performance summary for me"
Write an email	"Help me reply to this customer's inquiry"
Organize meeting notes	"Format the following content as meeting notes"
Draw a flowchart	"Draw a leave request flowchart"
Create a table	"Create a table comparing Plan A and Plan B"

How to use it

Open Canvas

AI automatically opens Canvas when generating longer documents. You can also ask it directly:

"Use Canvas to write a..."

Edit content

After Canvas opens, you can:

View the document — Read the content in Markdown Canvas. Switch to source code mode to view the Markdown text; this mode is not a text-editing field.

Download and edit — Download the Markdown file, then edit it in a text editor. Changes to the local file are not automatically written back to Canvas.

Request changes — Clearly specify the paragraph you want to adjust in the conversation, such as "Make the second paragraph more concise."

Export

The upper-right corner of Markdown Canvas provides a Download menu:

Original format (.md) — Save the Markdown file so you can edit it in a text editor

PDF document — Download a PDF for reading and sharing

To copy the Markdown text, switch to code mode, then use the copy button in the content area.

What Canvas can create

Type	Suitable for	Example
Documents	Reports, emails, proposals, announcements	"Write a new product launch announcement"
Tables	Comparative analysis, data organization	"Compare quotes from three vendors"
Charts	Flowcharts, organization charts, sequence diagrams	"Draw the customer complaint handling process"

Tips

> Let AI help you iterate You do not need to get it right the first time. Have AI produce a first draft, then refine it step by step: 1. "Write a first draft" 2. "Make the tone more formal" 3. "Add supporting data" 4. "Change the last paragraph into a call to action"

> Keep the versions you need If you need to keep the current content, download the file first. The preview and source code modes of Markdown Canvas do not let you edit text directly; edit the downloaded local file instead.

Write documents

You can ask AI to write reports, emails, proposals, announcements, or meeting notes, and view the result in Canvas. Markdown documents can be downloaded and then edited manually.

Quick start

Just tell AI what you want to write:

"Write a quote reply email to a customer"

"Use Canvas to organize today's meeting notes"

"Write an internal announcement for a new feature launch"

After AI generates a document in Canvas, you can open the preview and download the result.

Edit and revise


Download and edit manually

Markdown Canvas does not let you click on text to edit it the way Word does. Use the Download menu in the upper-right corner to save the Markdown file, then open it in a text editor. Source code mode is for viewing and copying only.

Ask AI to revise it

Enter clear revision instructions in the conversation, for example:

You say	AI does
"Make the tone more formal"	Adjusts the tone of the whole document
"The second paragraph is too long, shorten it"	Shortens a specific paragraph
"Add a paragraph about the schedule"	Adds a paragraph
"Change it to a bulleted list"	Reformats the layout
"Translate it into English"	Translates the whole document



The download menu offers the original Markdown format and PDF

Common document templates

Try these prompts to quickly produce common documents:

Document type	Example prompt
Weekly report	"Write this week's report. Highlights: finished Project A, started Requirement B, will do C next week"
Email	"Write an email politely but clearly declining a vendor's quote"
Meeting notes	"Format the following content as meeting notes: (paste your notes)"
Proposal	"Write a proposal outline for adopting AI customer service, including a benefit analysis"
Announcement	"Write a system maintenance announcement. The time is Saturday 2–6 AM"

Export documents

For how to download and copy Markdown documents, see Export above. You can edit the downloaded local file with the appropriate tool.

Create charts

Describe what you want in natural language, and AI can draw flowcharts, organization charts, sequence diagrams, and other charts for you in Canvas. You do not need to learn any syntax; just say what you want to draw.

Quick start

Just tell AI what kind of chart you want:

"Draw a leave request flowchart"

"Draw our department's organization chart"

"Draw the process from a user placing an order to shipment"

Supported chart types

Chart type	Example prompt	Purpose
Flowchart	"Draw the expense reimbursement process"	Steps and decision branches

Chart type	Example prompt	Purpose
Organization chart	"Draw the department structure"	Reporting relationships
Sequence diagram	"Draw a sequence diagram of an API call"	Order of system interactions
Gantt chart	"Draw a Gantt chart of the project schedule"	Project scheduling
Mind map	"Use a mind map to organize our marketing strategy"	Brainstorming and categorizing

Edit charts

Want to adjust the result? Just say:

You say	AI does
"Add a review step after step two"	Adds a node
"Change the flowchart to run left to right"	Changes the direction
"Remove the last step"	Deletes a node
"Change the colors to blue tones"	Adjusts the style

Export charts

When you are done, you can:

Copy — Paste it into a presentation or document
Take a screenshot — Capture the chart directly from Canvas

Next steps

Deep Research
Back to the MaiGPT overview

Deep Research

Deep Research is MaiGPT's in-depth research feature. Enter a research topic, and AI proposes a research plan. It then searches for and organizes information based on the direction you confirm and produces a report. It is suitable for market research, competitive analysis, and technical research.

How It Differs from Regular Chat

	Regular Chat	Deep Research
Best suited for	Quick questions and everyday tasks	Research that requires searching and organizing multiple sources
How it works	Enter a question and receive a response	Review the research plan and cost estimate first, then choose an output format
Research results	Chat response	Canvas document, chat response, or downloadable files
Waiting time	Usually shorter	Varies with the topic's scope and search conditions

When to Use It

A corporate planning manager is preparing to evaluate how to adopt generative AI. He enables Deep Research in MaiGPT and enters "Research the current state, challenges, and success stories of generative AI adoption among Taiwanese businesses." He first reviews the research plan and estimated Credits, then selects Reply directly in the chat. Once the research is complete, he can read the organized findings and cited sources in the original conversation as a basis for further discussion.

Start a Research Task

The following example covers topic research without attached files.

1. Enable Deep Research

Open a New Chat in MaiGPT, click Add (＋) next to the input box, and select Deep Research. Once enabled, a label with the same name appears below the input box.



Select "Deep Research" in the Add menu

> If you cannot see Deep Research, contact your organization administrator to check your MaiGPT role permissions.

2. Enter a Research Topic

Describe the topic, scope, and purpose of the report, then click the send button at the bottom right of the input box. If you want to confirm the direction first, explicitly request, "Please propose a research plan first and wait for my confirmation before proceeding."

More general	More specific
"Research AI"	"Research the current state, challenges, and success stories of generative AI adoption among Taiwanese businesses"
"Analyze competitors"	"Compare the enterprise knowledge base features of three specified products and summarize their use cases"



Confirm that "Deep Research" is enabled before submitting your research topic

3. Review the Plan and Cost Estimate

Read the research direction proposed by AI and the estimated Credits. If the scope is unsuitable, request adjustments in the same conversation first. Proceed to the next step once both the direction and the estimate are acceptable.

1. **整體概況與導入現況**：分析台灣企業導入生成式 AI 的普及程度、主要應用領域、企業規模與產業差異，以及近年的政策、投資與市場趨勢。
2. **主要應用場景與效益**：整理企業在客服、製造、研發、行銷、知識管理、軟體開發與行政流程等場景的導入方式，並評估生產力、成本、營收、品質或決策效率等成效。
3. **關鍵企業與成功案例**：盤點具代表性的台灣企業及其生成式 AI 專案，說明導入動機、技術架構、治理方式、執行成果與可複製的成功因素。
4. **技術與組織挑戰**：探討資料品質與安全、模型準確性、幻覺、系統整合、算力與成本、人才短缺，以及員工採用和流程改造等問題。
5. **法規、資安與 AI 治理**：研究個資、機密資料、智慧財產權、著作權、供應商風險與台灣及國際 AI 法規對企業導入的影響，並整理常見治理做法。
6. **導入策略與衡量方法**：比較自建、採購與混合式方案，歸納從試點、概念驗證到規模化部署的實務路徑，以及 ROI、使用率、品質與風險等評估指標。
7. **未來展望與建議**：研判代理型 AI、多模態模型、主權 / 企業級 AI、產業專用模型等趨勢，並提出台灣企業未來 1 至 3 年的優先行動建議。

預估一次完整研究的成本約為 18,905 credits；實際消耗將依實際搜尋與 token 使用量計費，可能高於或低於此估算。

The research plan includes a cost estimate; the amount shown is only an estimate for this demonstration

4. Choose an Output Format and Confirm the Start

Select a format in the Choose the research report's output format before confirming the start card:

Option	How results appear after research is complete
Canvas document	Preview the report in Canvas, view its source, read it in full screen, or download it
Reply directly in the chat	Display the report in the original conversation for convenient reading within the chat
Download files (docx／PDF)	Generate downloadable Word and PDF files for saving or sharing



Choose Canvas, a chat response, or downloadable files based on the report's purpose

> Selecting a format also sends a confirmation message. The system then checks the available quota and starts the research if the check passes. Review the plan and cost estimate before selecting a format. Once selected, the card retains your chosen format, and you cannot select another format on the card.



After selection, the card retains only the output format used for this research

5. Wait for the Research Results

Once research starts, the conversation displays Research progress. AI searches for and organizes information, then generates a report. The time required varies with the research scope, sources, and generation conditions. Refer to the actual progress shown.

Credits Usage Estimates and Quota Prechecks

Deep Research may perform multiple searches and analyses. The cost estimate in the plan helps you decide whether to proceed. When you confirm execution, the system checks the available quota against the estimate.

How the Estimate Is Calculated

The estimate first uses the median actual usage from up to 20 of your organization's most recent research tasks.

If your organization has no research history, it uses the median of recent research tasks across the platform. If there is still no history, it uses the default estimate configured in the system.

This is a reference based on historical usage, rather than a fixed price quoted for the current topic. Actual charges depend on usage such as searches and Tokens, and may be higher or lower than the estimate.

> The estimate is not a spending limit and does not guarantee that you will have sufficient quota throughout the research. The check before confirmation uses the estimate and balance at that time. Subsequent actual usage may still exceed the estimate.

The Research Plan Includes a Cost Estimate

When AI proposes a plan, it includes estimated Credits and a note that actual usage may be higher or lower than the estimate. AI generates this text, so the wording and amount may vary. Read the notice in your current conversation.

Quota Check Before Execution

After you confirm execution, the system checks the organization wallet and the quotas applicable to this task. If any applicable quota is insufficient, the research will not start:

Check	What is checked	Details
Organization wallet	Whether available Credits can cover the estimated usage	About Credits
Individual quota	The member's available quota, if configured	Member Credits quotas
Shared role quota	The available shared quota of the member's role, if configured	Role quotas
Conversation platform quota	The available quota for the platform used by this conversation, if configured	Conversation platform Credits quotas

What Happens If the Check Blocks Research

AI displays a notice about insufficient quota. Follow the notice and contact your organization administrator for assistance.

Research does not start. The original conversation and research plan remain at the stage awaiting confirmation.

Once the quota has been replenished, ask AI to proceed in the same conversation. For example, "The quota has been replenished. Please start the research according to the plan you just proposed." You do not need to enter the topic again.

What to Do When Quota Is Insufficient

Your role	What to do
Regular member	Share the insufficient quota notice with your organization administrator and explain the research purpose and estimated usage
Organization administrator	Follow the notice to check the organization wallet, individual quota, role quota, or conversation platform quota, then take action according to the organization's budget

Frequently Asked Questions

Q: Does seeing a cost estimate mean that amount has already been deducted?

The estimated amount is not deducted directly. **The estimate and quota check themselves are free, but AI responses such as generating the research plan and confirming details in the conversation may still consume Credits.** Therefore, research that has not started or is blocked by the quota check does not mean the entire conversation is free.

Q: Why is actual usage higher or lower than the estimate?

The estimate uses historical research costs. Differences in the number of searches, source lengths, and Token usage for this task lead to differences in actual usage.

Q: Do I need to start a new research task after replenishing the quota?

No. Return to the original conversation and ask AI to proceed according to the confirmed plan.


Q: Why do I not see a cost estimate?

Deployments without Credits billing enabled do not provide cost estimates. If an estimate is temporarily unavailable, the system still checks the existing available quota rules. The absence of an estimate does not mean the task is free.

Read and Export the Report

Read the Report

Once research is complete, open the results in the format you selected earlier. As you read the conclusions, also check the cited sources and the scope of applicability provided in the report.



台灣企業導入生成式 AI 的現況、挑戰與成功案例

執行摘要

台灣企業對人工智慧的認知與試用已快速增加，但從個人使用、部門試驗走向制度化、可規模化的生成式 AI 導入，仍處於早期階段。公開調查顯示，企業導入率會因定義、樣本與成熟度門檻而有顯著差異：PwC Taiwan / 數位產業署 2024 年調查中，僅約 8% 企業有「明確應用 AI」；KPMG Taiwan 2025 年調查則顯示 46% 受訪企業內部使用過 AI，其中 26% 使用生成式 AI。這些數字並不矛盾，而是反映「曾經使用」「正在評估」與「制度化導入」之間的差距。

產業差異明顯。ICT、電腦電子與半導體相關企業在 AI 成熟度、資料基礎與人才資源上領先；傳統製造、營建及農林漁牧礦業則相對落後。製造業的 ERP、MES、產線機聯網、API 整合與資料治理，是生成式 AI 能否從辦公室知識工作延伸到研發、生產與品質管理的關鍵。企業規模方面，大型企業較能負擔專責團隊、算力、資料治理與自建平台；中小企業則較依賴雲端服務、現成大型語言模型與外部服務商。

When a chat response is selected, the completed report can be read in the original conversation; the image shows an excerpt from the beginning

When you select Canvas document, the report appears in the Canvas panel. Click Full screen view at the top right to enlarge it for reading. Switch to code mode displays the Markdown source. Click Switch to preview mode to return to the formatted view.



Canvas full screen preview preserves the report title, body, and action buttons at the top

Edit the Report

The Markdown Canvas used for research output on this page provides preview, source viewing, and download features. **It does not support editing by typing directly.** To edit the report manually, download the original Markdown file, or select Download files (docx／PDF) before starting the research and edit the downloaded Word file with an appropriate editor.

For additional searches or analysis, ask follow-up questions in the conversation. New AI responses are still charged based on actual usage.

Export

If you select Download files (docx／PDF), Generating downloadable files⋯ appears after the report is complete. Wait until the files have been generated, then click Download for the corresponding file. If you select Canvas, click Download at the top right of the panel and choose Original format (.md) or PDF document.



Once the files have been generated, click "Download" next to the Word or PDF file



The Canvas download menu offers the original Markdown and a PDF document

Next Steps

Learn about Canvas

View Credits and usage history

Return to the MaiGPT overview

AI Image Generation

MaiGPT has built-in AI image generation. Describe the image you want in words, and the AI creates it for you. Descriptions in Chinese are supported, so you don't need to write in English. After an image is generated, you can keep refining it until you are satisfied.

Generate Images from a Text Description

Describe the image you want directly in the conversation:

"Draw an illustration of a modern office with bright colors"

"Generate a marketing product image with a blue gradient background"

"Draw a cute mascot: a cat in a suit"

Prompt Tips

The more specific your description, the closer the image will be to what you expect:

Generic description	Better description
"Draw a cat"	"An orange cat sitting on a windowsill, sunset in the background, watercolor style"
"Make a poster"	"A vertical A4 poster titled 'Annual Conference 2025', tech style, blue-purple tones"
"Product image"	"A cup of coffee on a white background, top-down angle, a few coffee beans beside it, commercial photography style"

You can specify:
- **Style** — watercolor, flat design, realistic, cartoon, commercial photography
- **Color tone** — bright, warm, cool, monochrome
- **Composition** — top-down, front view, close-up, wide shot
- **Purpose** — social media post, presentation illustration, marketing material

Download an Image

After an image is generated, click it to view it enlarged. To save it to your device:

Computer: while viewing the image, right-click

Phone
tablet: while viewing the image, long-press it

Edit and Iterate on Images

Not happy with the generated image? You don't need to start over. You can keep revising it in the same conversation until you are satisfied.

How to Edit

After an image is generated, simply tell the AI what to change in the conversation:

"Change the background to white"

"Make the person's expression a smile"

"Add the company logo in the bottom-right corner"

"Make the overall color tone a bit warmer"

The AI generates a new version based on your instructions.

Generate from an Existing Image

You can also upload an image and have the AI use it as a reference to generate a new one:

(Upload a product photo)

"Use the style of this image as a reference and generate similar marketing material"

"Turn this image into a cartoon style"

Tips

> Edit step by step Don't ask for too many changes at once. Changing one thing at a time works best: 1. First make sure the composition and subject are right 2. Then adjust the color tone and style 3. Finally add details (text, logo, etc.)

> Start over if you're not satisfied If the edits keep drifting in the wrong direction, it's better to describe the image again from scratch. The AI generates independently each time, so starting over is sometimes faster than continuing to revise.

Next Steps

Connectors

Back to MaiGPT Overview

AI Video Generation

MaiGPT can generate videos from text descriptions. The conversation guides you through selecting the video quality and aspect ratio, then displays a summary of your settings and the estimated Credits before submission. You do not need to remember the technical names of video models.

> Video generation consumes Credits. Before submitting, review the estimated usage on the confirmation screen, then decide whether to generate the video.

Use Case

A marketer wants to create a short social media video for a new product. In MaiGPT, they describe the appearance, setting, and camera movement for a fictional smart speaker, select the video quality and a landscape aspect ratio based on the campaign requirements, then review the duration, settings, and estimated Credits on the confirmation card. Generation starts only after they confirm.

Generate a Video from Text

1. Describe the Video

In a new MaiGPT conversation, describe the subject, setting, action, and camera effects. For example:

Generate a 4-second product showcase video: a white smart speaker slowly rotates on a table in a bright living room as the camera smoothly moves closer. Do not show any people or text.

2. Choose Generation Settings

Use the options in the conversation to select the video quality, then choose the aspect ratio. Available options may vary; refer to the options displayed at the time.



After selecting the quality and aspect ratio, the confirmation card displays the duration, aspect ratio, quality, content, and estimated Credits

3. Confirm and Generate

Review the content description, duration, aspect ratio, quality, and estimated Credits on the confirmation card. If the settings are correct, click Generate. To stop, click Cancel.

4. Preview the Result

After submitting, wait for the generated result in the same conversation.

Video Length and Model Limits

MaiGPT currently uses the following video models. Each generation produces one video, with a maximum length of 15 seconds:

Video model	Available quality	Length per video
HappyHorse 1.0	720p, 1080p	3–15 seconds
SeedDance 2.0 Standard	480p, 720p, 1080p	4–15 seconds

Video model	Available quality	Length per video
SeedDance 2.0 Fast	480p, 720p	4–15 seconds

15 seconds is the maximum for a single generation by the video models and cannot be changed in the settings. If you need a longer video, split the content into multiple segments of 15 seconds or less, generate each one separately, and join them together in video editing software.

> Credits are calculated by video duration: the longer the video, the more Credits it uses. The available quality options and lengths are as shown on the confirmation card.

Next Steps

AI Image Generation

Usage and Credits

Back to MaiGPT Overview

AI Presentations

After you ask AI to create a presentation in a MaiGPT chat, the presentation panel opens on the right. You can preview slides, edit content with AI, restore earlier versions, present, export PDF or PPTX files, or generate a share link. If the panel is collapsed, click the Open presentation card in the chat to reopen it.

Who can use it

Feature	Requirement
Create, preview, present, and export presentations	Access to MaiGPT (your role has MaiGPT permission)
Generate, copy, or disable share links	Presentation creator or organization owner; other members do not see sharing options in the View & Export menu
AI editing (Edit entire slide, click elements to edit, and Fact-check content) and Version history	These buttons appear only if your role has Agent Marketplace permission; you must be the presentation creator or organization owner to submit AI edits

---

Create a presentation

Start from the “Presentation” shortcut

Select a template, data sources, and slide count before sending your request so AI does not need to ask about each presentation style setting.

1. Open the presentation template panel

Start a new MaiGPT chat. In the Office apps row below the input box, click Presentation to expand the Presentation templates panel. This row appears only in new chats where no messages have been sent.

2. Choose a template

Find a template using Search presentation templates and favorites..., the source tabs (All, Favorites, Organization, and Built-in), or categories, then click a card to select it. To see each slide first, click Preview on the card. You can click Use this template in the preview window.

3. Add data sources and set the slide count

If needed, select the Knowledge bases, Skills, or Databases to reference at the bottom of the panel (optional; multiple selections allowed), then set the Slide count (1–50 slides; default: 10).

4. Apply and send

Click Apply (you must select a template first). A preview card for the template appears above the input box, and the selected data sources appear as tags in the input box. The input box is filled with "Help me generate a new presentation using this template, with N slides." If you have already entered a request, only "with N slides" is appended. Add your topic, audience, and key points, then send. These settings apply only to this submission.

Chats started from the shortcut always produce an AI presentation that you can preview and edit in the presentation panel, rather than directly delivering a .pptx file. Even if your request says "Please give me a .pptx file," MaiGPT first creates an AI presentation and reminds you to download the PowerPoint file from View & Export → Export PPTX in the presentation panel.

Ask directly in chat

You can also type "Create a 10-slide presentation for a new product launch." If you do not specify a format, MaiGPT usually first asks whether you want an AI presentation with live previews and sharing, or a PPTX file. If you choose an AI presentation, it asks you to confirm the template or style before creating it.

Generation progress and automatic images

When creation starts, the presentation panel automatically opens on the right. Progress messages appear at the top in sequence, such as "Analyzing your requirements...," "Planning the presentation outline (N slides)...," and "Drawing slide X
N...." Completed slides appear one by one, followed by "Presentation generated! N slides in total."

When a cover image, key visual, or contextual illustration is needed, AI automatically generates images and places them in the slides. Generated images count toward AI image generation usage; failed generations are not charged. If credits are insufficient or generation fails, AI completes the presentation using layout elements such as color blocks and icons, and explains the reason in its reply.

Presentation panel

Location	Content
Tabs at the top left	Presentation shows the slides individually; Files lists the HTML and CSS files that make up the presentation
View & Export at the top right	Presentation mode, Share link (replaced by Copy share link and Disable sharing when shared), Version history, Export PDF, and Export PPTX
Toolbar above each slide	Preview Code toggle, Edit entire slide, Fact-check content, and slide number

Close and reopen the panel

Click Close (×) at the top right of the panel to restore the chat area to its full width. The collapsed state is saved per conversation in the current browser: the panel stays collapsed when you send a new message, refresh, or switch away from the conversation and return. It returns to the default state if you change devices or browsers, or clear browser data. To reopen it, click Open presentation below the message that generated the presentation. When you generate a new presentation in the same conversation, the panel opens automatically.

Edit a presentation with AI

Perform the following actions in the slide's Preview mode. Only one edit can run at a time.

Rewrite an entire slide

On the slide you want to edit, click Edit entire slide and enter an instruction under “How would you like to change this slide?”, such as “Use a three-column comparison with more concise wording.” You can also click Rewrite, Shorten, Expand, Formal tone, or Translate under Favorites to insert a preset instruction and then adjust it.

Click Send →. When AI finishes, a “Before/After” comparison appears. Drag the divider to compare the changes.

Click Keep changes if you are satisfied, or Revert to return to the version before the edit.

Edit one or more elements

Hover over a text block or image on a slide to display its outline and Edit element. Click to select it, then click other blocks to add them to the selection (hold `Ctrl` or `Cmd` while clicking to toggle an individual block).

After selection, the floating toolbar shows “N selected.” You can click Select all, Clear, or Edit selected.

Enter an instruction and click Send →. When multiple elements are selected, the same instruction applies to all of them.

Review the comparison and click Keep changes to save a new version, or Revert to discard this edit.

Fact-check

Click Fact-check content on a slide. The input box is filled with a fact-checking instruction and a text summary of that slide. Review the content and send it; MaiGPT verifies the data, facts, and claims in the chat.

> AI edits count toward usage. If you see "Insufficient Credits balance. Please purchase more," contact your organization administrator. "The presentation has been updated. Please refresh and try again" means a new version was created while you were editing. Refresh and try again.

Version history and restoration

Rewriting an entire slide, keeping element edits, and restoring a version all create a new version.

Click View & Export → Version history. The list shows each Version N, labeled AI edit or Manual edit.

Click Restore on the version you want to return to, and confirm "Restore to version N? The current content will be replaced with this version."

Restoring creates a new version using that version's content. The original versions remain in the list, so you can restore them again later.

Present, export, and share

Action	Description
Presentation mode	Present in full screen. Use `→`, `↓`, or the space bar for the next slide, `←` or `↑` for the previous slide, and `Esc` to exit
Export PDF	Displays "Generating PDF, please wait..." and opens the download in a new tab when complete
Export PPTX	Generates and downloads a PPTX in the browser. If some images cannot be retrieved, a message says "PPTX export complete, but N images could not be retrieved and were skipped"
Share link	Generates and automatically copies a share link (displays "Share link copied")
Copy share link	Appears when shared; copies the same currently active link again

Action	Description
Disable sharing	Appears when shared; previously distributed links stop working immediately after confirmation. See Disable sharing

Share link

Recipients **do not need to log in** to open a share link. They can see the total slide count and each slide's content, and click Play presentation to view it in full screen. The share page shows the latest presentation content: subsequent AI edits or restorations appear when the same link is opened.

> Anyone with the link can open it. Links currently have no expiration date and remain valid until you disable sharing. Share only content that can be made public. When a link is no longer valid, recipients see “Presentation not found or link expired.”

Only the presentation creator and organization owner can generate, copy, or disable share links. Other members see no sharing options in the View & Export menu and cannot generate or disable public links for someone else's presentation.

Disable sharing

After a presentation is shared, Share link in the View & Export menu is replaced by Copy share link and Disable sharing in red.



When shared, the menu shows “Copy share link” and “Disable sharing” in red

At the top right of the presentation panel, click View & Export → Disable sharing.

A confirmation dialog asks “Disable public share link?” and warns that previously distributed links will stop working immediately. Click Disable sharing to confirm, or Cancel to leave everything unchanged and keep the link active.

“Sharing disabled” appears, and the menu returns to Share link.



A confirmation dialog appears before sharing is disabled

After sharing is disabled, anyone opening the old link sees “Presentation not found or link expired.” The presentation itself is unaffected. Clicking Share link again generates a completely new link; the old link remains invalid. If disabling fails, “Failed to disable sharing” appears and the sharing state stays unchanged.

Example scenario: A store operations specialist sends a vendor the share link for the “Acme Coffee Spring 2026 New Product Launch” presentation, then realizes she sent it to the wrong recipient. She opens the presentation panel, clicks View & Export → Disable sharing, and confirms. The old link immediately stops working. She then clicks Share link to get a new link and sends it only to the correct vendor.

> Organization owners can also disable share links for presentations created by other members, for example to revoke public links when a member leaves or is on leave.

Manage presentation templates

Action	Description
Add to favorites	Click the star at the top right of a template card (shows Add to favorites on hover) to find it later under the Favorites tab; click again to remove it. Favorites are personal
Import a template	Click Import presentation template in the panel. Imported templates appear under the Organization tab for everyone in the organization to use
Delete an organization template	The template uploader or organization owner can click Delete organization template on the card and confirm to permanently delete it. Built-in templates cannot be deleted

Import a template

In the Presentation templates panel, click Import presentation template.

Choose a source:

Upload file: drag or select a .pptx, .pdf, or .html template file, up to 20 MB.

Import from link: paste a Google Slides, Drive, OneDrive, or file link. The link must be publicly accessible over the internet.

Enter a Template name (automatically filled with the file name when uploading), then click Import.

Importing requires file conversion and thumbnail generation, which may take a few minutes. When complete, "Template imported successfully" appears and the panel switches to the Organization tab. If it fails, "Template import failed. Please check the file or link and try again" appears.

FAQ

Why can't I see the "Presentation" shortcut?

The Office apps row appears only in new MaiGPT chats where no messages have been sent. If a conversation has already started, open a new chat or ask MaiGPT to create a presentation directly in the chat.

Why can't I see AI editing buttons such as "Edit entire slide"?

Check that the slide is in Preview mode, no other edit is in progress, and your role has Agent Marketplace permission. If the buttons are visible but submission fails, you may not be the presentation creator. Ask the creator or organization owner to edit it.

Connectors

Connectors let MaiGPT access your third-party tools such as Notion, Slack, Google Drive, and GitHub. Once connected, you can query and interact with data in these tools directly from the conversation.

Available Tools

Tool	What You Can Do After Connecting
Notion	Search pages, query databases, create new pages
Slack	Search messages, view channel content
Google Drive	Search and read documents
GitHub	View repositories, issues, pull requests

> The table above lists common examples. The connectors actually available are enabled by your organization admin and made available according to your role. Refer to the list shown under + → Connectors in the chat input box. If the tool you need is not listed, you can submit a request in Manage My Connectors. For admin-side operations, see Manage Connectors (Admin).

How to Connect

1. Open the Connectors Menu

Click + on the left side of the chat input box and select Connectors. Connected Services in the submenu lists the connectors available for this conversation: authorized connectors show a toggle on the right that controls whether this conversation uses them, and OAuth connectors that are not yet authorized show an Authorize button on the right. At the bottom are Add Connector and Manage My Connectors.

2. Authorize Your Account

In the submenu, click Authorize for the connector (or select the connector in Manage My Connectors and click Authorize Connection). A new window opens to that service's authorization page; sign in and grant consent as prompted. Some connectors first ask you to select the authorization scope. If your browser blocks the pop-up window, allow it and try again.

3. Start Using It

After connecting successfully, just ask in the conversation:

"Search Notion for pages about the Q1 plan"

"Look up the quotation in Google Drive"

If the connected service provides an interactive interface, cards you can operate directly appear below the AI's reply. See MCP Interactive Cards (MCP Apps).

Manage Connected Tools

Click + → Connectors → Manage My Connectors to open "My Connectors". You can filter by status on the left:

Status	What You Can Do
Authorized	Disconnect
Authorization required	Authorize Connection; Reauthorize when authorization has expired
Admin setup required	Wait for the admin to finish setup
Role not enabled	Request access from your admin
Not enabled by organization	Request Activation

After you submit a request, "Request submitted" is displayed. Once the admin enables it, you receive a "Connector enabled" notification in the Notification Center.

Click any connector to see its details on the right:

Section	Content
Status description	For example, "Not yet authorized", "Authorization has expired", "{Service} is not available to your role", "{Service} has not been enabled by your organization", or "{Service} requires admin setup"; the corresponding button appears below
Authorization Info	Authorized At (when you completed authorization) and Credential Validity (when the credential issued by the service expires; if it expires and cannot be renewed, the status changes to "Authorization has expired" — click Reauthorize)
Requested Permission Scopes	The list of permissions requested from the service during authorization; used only for the Agent to act on this service on your behalf. Admins can view it when enabling the connector

Seeing "{Service} is repeatedly unavailable: {reason}. Please check the connection settings"?

When calls to the same connector fail several times in a row during a conversation, this message appears on screen, and the tool card is also marked "Currently unavailable". First go to Manage My Connectors and check the service's status: if it shows that reauthorization is needed, click Reauthorize. If the status is normal but calls still fail, the cause is usually a problem with the service itself or the connection settings of an organization-defined MCP server. Give the reason shown in the message to your organization admin (for where to configure it, see Manage Connectors (Admin)). To stop seeing this message, click Don't Show Again.

Notion

After connecting Notion, you can search Notion pages, query databases, and even create new pages directly in MaiGPT.

Connection Steps

Click + → Connectors in the input box and find Notion

Click Authorize to go to the Notion authorization page

Select the pages or workspace you want to authorize MaiGPT to access

Click "Allow" to complete authorization

What You Can Do

After connecting, say the following directly in the conversation:

You Say	MaiGPT Does
"Search Notion for pages about product specifications"	Searches and lists related pages
"Check the unfinished tasks in the Notion project database"	Queries the database and filters
"Create a new page in Notion titled Meeting Notes"	Creates a new page
"Save this summary to Notion"	Writes the content to Notion

Notes

> Authorization Scope When authorizing Notion, you can choose which pages to share with MaiGPT. Only the pages you authorize can be searched. If you cannot find a page, check whether it has been authorized.

Slack

After connecting Slack, you can search Slack messages and channel content in MaiGPT and quickly find earlier discussions.

Connection Steps

Click + → Connectors in the input box and find Slack
Click Authorize to go to the Slack authorization page
Confirm the authorization scope, then click "Allow"

What You Can Do

You Say	MaiGPT Does
"Search Slack for discussions about the server migration"	Searches related messages
"Check what's been discussed recently in the #general channel"	Summarizes channel content
"Find the link John mentioned last week"	Searches a specific person's messages

---

Google Drive

After connecting Google Drive, you can search and read your Google Drive documents in MaiGPT.

Connection Steps

Click + → Connectors in the input box and find Google Drive
Click Authorize to go to the Google authorization page
Select your Google account and allow access

What You Can Do

You Say	MaiGPT Does
"Search Google Drive for the quotation"	Searches and lists related documents
"Open the last meeting notes"	Finds the document and reads its content
"Summarize the market analysis report in Drive for me"	Reads the document and produces a summary

Notes

> Only Google-native formats are supported Currently, only Google-native formats such as Google Docs, Sheets, and Slides can be read. Office formats such as .pptx, .docx, and .xlsx cannot be read directly. Please first "convert to Google format" in Google Drive before referencing them.

> Shared Drive and external sharing limitations Files stored in a Shared Drive or existing as shortcuts may still fail to be read after authorization. Make sure the authorized account has access to that Shared Drive, and use the original file link instead of a shortcut.

GitHub

After connecting GitHub, you can query development-related information such as repositories, issues, and pull requests in MaiGPT.

Connection Steps

Click + → Connectors in the input box and find GitHub

Click Authorize to go to the GitHub authorization page

Select the repositories to authorize and confirm

What You Can Do

You Say	MaiGPT Does
"Check which issues are currently open in main-repo"	Lists the issues
"Show me a summary of the changes in PR #123"	Reads the PR and summarizes it
"Search the repo for code related to authentication"	Searches code

---

Next Steps

Manage Connectors (Admin)

MaiGPT Role Permissions

Back to MaiGPT Overview

Manage Connectors (Administrators)

Before members can use connectors such as Notion and Google Drive in MaiGPT, the organization must first **enable** them, and then each member can authorize their own use (for member-side steps, see Connectors). This page is for organization admins: on the MaiGPT Connectors page, decide which connectors the organization makes available, handle requests from members, and connect your company's own MCP servers.

Who Can Use This

Your role needs the MaiGPT Connector Management permission for MaiGPT Connectors to appear in the left menu. Organization owners have it by default.

Members only need the MaiGPT permission to **use** connectors, not the management permission.

Only the **organization owner** can revoke a member's authorization.

For how to set permissions, see Role Permission Management.

How to Access

Click MaiGPT Connectors in the left menu. The list shows all connectors provided by the platform and defined by your organization:

Column	Description
Connector Name	When members have submitted requests, an "N members requested" tag appears next to the name; hover over it to see the requesters' emails
Source	Built-in (provided by the platform) or Organization Custom (private MCP servers you added)
Authentication Type	OAuth 2.0 (each member authorizes individually), Service Account (one credential shared across the organization), or No Auth
Tool Category	The category under which tool cards are displayed in conversations; can be set only after the connector is enabled, and the selection is saved immediately
Enabled	Whether the connector is made available to the organization
Authorized Members	The number of members who have completed authorization; the edit icon next to it shows the list
Actions	Credential settings for Service Account connectors; edit and delete for organization-custom connectors

Access from the Tools Page

Organization-custom connectors have another entry point: AI Features → Tools, then switch to Manage Connectors in the second column on the page. The page header reads "Manage the organization's custom MCP connectors. Connectors are synced to MaiGPT Connectors, where you can choose whether to enable them." The list shows only organization-custom connectors (built-in ones are excluded), with the columns Connector, MCP Server URL, Authentication Method, Tool Category, Created At, and Actions (edit, delete), and Add Connector and Refresh in the upper right. This list and the list on this page edit the same data; enabling/disabling and member authorizations are still managed on this page.

Enable a Connector for the Organization

Turn on the Enabled toggle in that row, and you are done when you see Connector enabled successfully. After enabling, what members see depends on the authentication type:

Authentication Type	When Enabled	Member Side
OAuth 2.0	Enabled directly	Each member clicks Authorize and signs in to the service with their own account
Service Account	The Service Account Authentication window appears first; enter the authentication headers and create them. If you click Cancel, the toggle reverts	No authorization needed; everyone shares the credentials the admin entered. When the authentication headers are empty, Admin setup required is shown
No Auth	Enabled directly	Can be used without authorization

After you turn the toggle off (Connector disabled successfully), members can no longer use it in conversations; existing member authorizations are kept, and re-enabling restores them.

Make Available to Roles

Once a **built-in** connector is enabled, it is also limited by the role's MaiGPT usage permissions: a member's role must have "All" checked in the Connectors card or have this connector checked for the member to see the authorize button; otherwise the member side shows Role not enabled. **Organization-custom** connectors are not restricted by role. For how to set this, see MaiGPT Role Permissions.

Handle Member Requests

When members see an unavailable connector in Manage My Connectors, they can submit a request. The system emails the organization owner and people with the MaiGPT connector management permission,

and shows "N connectors have pending member enablement requests" at the top of this page.

Status the Member Sees	Button the Member Clicks	What You Need to Do
Not enabled by organization	Request Activation	On this page, turn on the connector's Enabled toggle
Role not enabled	Request from Admin	The connector is already enabled. Go to the MaiGPT usage permissions of the requester's role and check this connector, or add the requester to a role that already has access

Once done, the request is resolved automatically, and the requester receives Connector enabled in the Notification Center. This page has no button to reject individual requests; if you do not plan to make the connector available, tell the requester directly.

View and Revoke Member Authorizations

Click the edit icon in the Authorized Members column to open the list. Each member shows Authorized At, Token Expires At, and a status (Valid, Expired, Permanent).

When a member leaves or should no longer have access, the organization owner can click Revoke Authorization; after revocation, the member must authorize again to use it. Revocation applies only to OAuth 2.0 connectors. A connector that has never been enabled has no list and shows the message "This connector has not been created yet. Please enable it first."

Configure Service Account Credentials

After a Service Account connector is enabled, a settings icon (Connector Credential Settings) appears in the Actions column.

Authentication Headers: A JSON object, for example `{"Authorization": "Bearer your-token"}`. Headers that are already set show only masked values; leaving the field blank keeps the existing headers, and entering a value **overwrites the entire set**.

Header values can use the available context variables, which are filled in automatically for each conversation: `{{contact_id}}` (contact ID), `{{source_id}}` (source ID), `{{contact_name}}` (contact name), `{{conversation_id}}` (conversation ID), `{{inbox_id}}` (inbox ID), `{{organization_id}}` (organization ID).

contextData Allowlist

When an Agent is embedded in your website, the website can pass in its own data (such as a member number) through contextData and then write it into the authentication headers:

In the website's chat window embed settings, put the data into contextData (for how, see the technical manual Inject Page Context).

Enter the names in Allowed contextData Keys as a JSON string array, for example `["patientToken"]`; up to 20 names, and each name is limited to English letters, digits, and underscores, 1 to 64 characters.

In the value of the authentication header, write `{{context_data.patientToken}}`.

Rules: the name must be identical in all three places, including case; any name not on the allowlist always returns no value; when there is no value for that conversation, that header is not sent; only single-level names are supported, not `a.b`.

Add a Private MCP Server

When a company-built or third-party MCP server is not in the list, you can add it as an organization-private connector that only your organization can see. Servers added on this page use **OAuth 2.0** authentication.

Click Add Connector in the upper right.

Fill in Name (English letters, digits, underscores, hyphens) and Server URL (must be `https://`); Display Name, Description, Tool Category, and Logo (PNG, JPG, GIF, WebP, SVG, up to 2 MB) are optional.

If the authorization server cannot be detected automatically, also fill in OAuth Server URL, Resource Identifier, OAuth Client ID, and OAuth Client Secret. For descriptions of each field, see MCP Tool Setup.

Click Confirm. The system first tests whether it can connect to the server. If that fails, it shows the error reason (or Connection test failed) and nothing is created; on success, it shows Server added successfully, the connector is enabled automatically, and the source is marked Organization Custom.

The same organization-custom connectors also appear under Manage Connectors on the Tools page, and both places edit the same data.

Edit and Delete

Edit: Affects all tools that use the same MCP server URL. Changing the Server URL makes those tools no longer match and lose their authorization, so edit with caution.

Delete: Member and contact authorizations for this connector are removed as well. If any tools use this connector, the confirmation window lists the affected tools and the number of authorizations that will be revoked; clicking Delete All deletes the connector together with those tools.

FAQ

The connector is enabled, but members still don't see the authorize button?

Ask the member to open Manage My Connectors and check the status. If it shows Role not enabled, go to the member's role MaiGPT usage permissions and make this connector available; see Make Available to Roles.

The member side shows "Admin setup required"?

This means the Service Account connector does not have authentication headers yet. Click the settings icon in that row, fill in the Authentication Headers, and save; members can then use it.

An error appears when revoking authorization?

"Only the organization owner can revoke member authorizations" means you are not the organization owner; "Only authorizations for OAuth-type connectors can be revoked" means this connector is not of the type that members authorize individually.

The request notice at the top of the page never goes away?

If the connector has long been enabled, the requester is hitting a role restriction. Turning on the toggle cannot resolve this kind of request; instead, make the connector available in the requester's role.

Further Reading

Connectors (Member Side)

MaiGPT Role Permissions

MCP Tool Setup

Notification Center

Use on Different Devices

MaiGPT offers multiple ways to chat with AI on any device. Conversation history syncs automatically, so you can continue a discussion from whichever device you log in on.

Supported Devices and Platforms

Platform	Description	Best For
Web Version	Use directly in your browser with no installation	Office computers and laptops
iOS App	Native iPhone iPad app	Travel, commuting, and mobile work
LINE	Chat through the LINE official account	Users who regularly use LINE
Microsoft Teams	Use directly in Teams	Teams whose company already uses Teams

---

Which Should You Choose?

The most complete experience → Web version (supports all features)

The most convenient access on the go → iOS App or LINE

Integration with your workflow → Microsoft Teams

Conversation history is shared across all platforms. You can start a conversation on your computer and continue on your phone when you're out.

Using One Account on Multiple Devices

Sign in to the web version and the iOS App with the same MaiAgent account, and you can stay signed in on multiple devices at once. Signing in on a new device does not sign you out of your other devices.

Signing out affects only the current device. Your other devices stay signed in.

Your sign-in session is extended automatically as you use it. If a device goes unused for more than 30 days, you need to sign in again the next time you open it.

Conversation history is stored on the server, not on your device. When you switch to another device, refresh or reopen the conversation list to see the latest content.

LINE and Microsoft Teams use identity binding on their own platforms and are not affected by the sign-in behavior above.

Next Steps

Web Version

iOS App

Use on LINE

Use on Microsoft Teams

Back to MaiGPT Overview

Web Version

The MaiGPT web version works in any browser with no software installation required. It lives inside the MaiAgent admin console, not on a separate website.

Where to Open It

Open your browser and go to the MaiAgent admin login page https://admin.maiagent.ai/login. If your company self-hosts (on-premises) or uses a custom domain, use the admin URL provided by your company instead

Log in with your account and password (or use SSO). For login methods, see How to Log In to the Platform

Click MaiGPT at the top of the left menu to open the chat screen and start asking questions

> If MaiGPT does not appear in the left menu, your role does not have "MaiGPT permission". Ask your organization administrator to enable it in Role Permission Management. If your company uses a custom brand name, the menu shows the company's custom name instead of "MaiGPT". You can bookmark this page in your browser so that opening it takes you straight to MaiGPT.

To use it in LINE or Microsoft Teams, see Using on LINE and Using on Microsoft Teams.

Recommended Browsers

Browser	Support
Google Chrome	Recommended
Microsoft Edge	Supported
Safari	Supported
Firefox	Supported

> Use the latest version of your browser for the best experience.

Next Steps

iOS App

Using on LINE

Back to MaiGPT Overview

iOS App

MaiGPT offers an iOS App so you can use it anytime on iPhone and iPad.

Installation

Open the App Store

Search for "MaiGPT" or scan the QR code provided by your company

Download and install

Login

After opening the app, log in with the same account and password as the web version. Conversation history syncs across devices.

Features

The app supports the same core features as the web version:

AI Chat

Upload photos (take a photo directly or select from your photo library)

Knowledge Base Q&A

Web Search

> Some advanced features (Canvas, Deep Research) are recommended to be used on the web version for a better experience.

Next Steps

Using on LINE

Using on Microsoft Teams

Back to MaiGPT Overview

Use on LINE

If your company has connected MaiGPT to a LINE official account, you can chat with AI directly in LINE without opening a separate web page.

How to Get Started

Scan the LINE QR code provided by your company, or search for the official account name

Add the account as a friend

Send a message to start chatting

What You Can Do on LINE

Feature	Supported
Text conversation	Yes
Send images for AI recognition	Yes
Knowledge base Q&A	Yes
Upload files	Depends on configuration
Canvas	Not supported (use the web version)
Deep Research	Not supported (use the web version)

> LINE is suited for quick Q&A and simple tasks. If you need advanced features such as Canvas or Deep Research, we recommend switching to the web version.

Next Steps

Using MaiGPT on Microsoft Teams

Web version

Back to MaiGPT Overview

Use on Microsoft Teams

If your company has integrated MaiGPT into Microsoft Teams, you can chat with AI directly within Teams.

Getting Started

Find the MaiGPT app in the left sidebar of Teams (or have your IT admin install it)

Click to open it

Send a message to start chatting

What You Can Do on Teams

Feature	Supported
Text conversation	Yes
Send images	Yes
Knowledge Base Q&A	Yes
Upload files	Depends on configuration
Canvas	Not supported (use the web version)
Deep Research	Not supported (use the web version)

> The Teams integration lets you use AI without leaving your work environment. It's ideal for quick Q&A and daily work assistance.

Next Steps

Web

Using on LINE

Back to MaiGPT Overview

Frequently Asked Questions

The questions people ask most often when using MaiGPT.

Question Categories

Category	What it answers
Usage and Quotas	Which actions consume usage and how to save it
Choosing Between Models	Which scenarios suit Claude, GPT, and Gemini
Security and Privacy	How your data is protected and whether conversations can leak

---

Quick Answers

How is MaiGPT different from ChatGPT?

MaiGPT is your company's dedicated Agent. Your data stays inside the company, it can query the company knowledge base, it supports multiple AI models, and it is managed centrally by your company's IT team.

Do I need to pay?

No. Usage is managed and paid for centrally by your company.

Are my conversations secure?

All conversations are processed within the company environment and are never used to train AI models. See Security and Privacy for details.

How much text can I enter at once?

The input box has no fixed character limit. How much content can actually be processed depends on the context length of the selected model: the text you enter is sent to the model together with the earlier content of the conversation, attachments, and any retrieved data. The "Context usage" indicator below the input box shows how much of the context this conversation has already used.

For very long content (such as an entire report or a document with tens of thousands of characters), save it as a file and upload it as an attachment; see Uploading Files and Images. When context usage is high,

use Conversation Handoff to summarize the conversation and continue in a new one. For the exact length each model can handle, contact your organization administrator or your MaiAgent representative.

Next Steps

Usage and Quotas

Choosing Between Models

Security and Privacy

Back to MaiGPT Overview

Usage and Quotas

MaiGPT uses pay-as-you-go billing — you pay for what you use. Below is an overview of usage basics.

What Is Usage

Every time you chat with AI, the system calculates usage based on the length and complexity of your messages. Usage is usually managed and paid for centrally by your company, so you don't need to pay yourself.

Which Actions Consume Usage

Action	Usage
Regular conversation	Low
Uploading files for analysis	Medium (depends on file size)
Knowledge Base Q&A	Medium
Deep Research	High (performs multiple searches and analyses)
AI image generation	Medium
Raising thinking effort (e.g., Extra High, Max)	Higher (the higher the effort, the more usage it consumes)

How to Check Usage

> How you can view usage depends on your company's settings. If your interface shows usage, you can check it directly. Otherwise, contact your administrator to find out about usage.

If your company uses Credits billing, you can check your quota and remaining balance by going to the avatar in the top right → Account → Credit Quota. See Account Page: Credit Quota.

What Do These Messages Mean When My Message Is Blocked?

Message on screen	What it means	What to do
Credit quota has been used up. Please top up, change your plan, or contact support to continue using the related features	Your company's Credits wallet balance is insufficient	Ask your administrator to purchase more Credits. See Credits Billing System
Your personal Credit quota has been used up or has not been configured. Please contact your organization administrator	Your administrator requires a personal (or role) quota to use the service, and yours is used up, expired, or not yet assigned	Ask your administrator to distribute a new quota. See Member Credits Quota Management
"No Active Plan" window	Your company currently has no active paid plan	Ask your administrator to upgrade or renew. See Trial and Subscription Plans
Estimated consumption: approx. N Credits	An estimate shown before running high-consumption features such as Deep Research or video generation	Confirm before running; the actual charge is based on the completed result

---

Tips to Save Usage

The more precise your question, the less usage — Specific questions get shorter replies than vague ones, which uses less

Make good use of a single conversation — Continuing a conversation is cheaper than starting a new one, since you don't need to provide the background again

Choose the right feature — Simple questions don't need Deep Research; keep thinking effort at Default or lower it

---

Next Steps

How to Choose Between Models

Security and Privacy

Back to MaiGPT Overview

Choose the Right Model

MaiGPT offers a variety of AI models. Use this guide to quickly understand their differences.

Quick comparison

Model	Strengths	Speed	Suitable use cases
Claude	Chinese comprehension, long-form writing, analytical reasoning	Medium	Writing reports, analyzing documents, complex reasoning
GPT	Balanced general capabilities, coding	Medium	Coding, translation, general questions and answers
Gemini	Fast responses, multimodal capabilities	Fast	Quick questions and answers, image understanding
DeepSeek	Strong reasoning capabilities	Medium	Mathematics, logical reasoning
Gemma	Open source from Google, lightweight and efficient	Fast	Lightweight deployments, edge computing
Grok	Humorous style, creative ideas	Medium	Creative writing, brainstorming

The table lists only common model families. For the full list of model families available on MaiAgent, see Technical Guide - Large Language Models (LLM). Your organization owner manages which models your organization can use under Model access permissions.

> When you need up-to-date information, use web search with any model. Models do not automatically retrieve real-time information on their own. See How to choose a model.

Select a Qwen model

The MaiGPT model menu also offers the Qwen family, including Qwen3.8 Max and Qwen3.6 Plus. If you work in planning and need Qwen, open the model menu in the input area before submitting a question, search for "Qwen", and select a model enabled by your organization. Once selected, the input area displays the current model name.



Search for Qwen in the model menu, then select the model you want to use.

> If you cannot find a model, first check your organization's Model access permissions and your MaiGPT role permissions. Available models may change with platform availability and organization settings. Refer to the models actually listed in the menu.

Not sure which to choose?

Use this decision process:

Everyday work (writing documents, looking up information, translation) → Use the default model
Not satisfied with the quality → Try Claude or GPT
Need the fastest speed → Use Gemini
Complex reasoning or calculations → Use Claude or DeepSeek

> There is no "best" model Every model has strengths and weaknesses. The most practical approach is to try the same question with different models and find the one you prefer.

Next steps

Select an AI model (instructions)
Security and privacy
Back to the MaiGPT overview

Security and Privacy

MaiGPT is designed from the ground up to protect enterprise data security. Below are answers to the security questions people ask most often.

FAQ

Can my conversation content be seen by external parties?

No. Your conversation data stays within your company's environment and cannot be accessed by other companies or external parties.

Will AI use my conversations to train models?

No. The AI models used by MaiGPT do not use your conversation data for training.

Can company administrators see my conversations?

Yes, depending on role permissions. The following two groups can go to AgentOps → AI Assistant Monitoring → Conversation Records in the back office and use the member filter to see your MaiGPT questions and AI replies:

Organization owners

Members whose role has the AI Assistant Monitoring permission

To find out which roles in your company have these permissions, or what your company's policy is on viewing conversations, ask your IT administrator. For the administrator-side steps, see View MaiGPT Conversations.

Are uploaded files secure?

Uploaded files are stored in your company's secure environment. They are encrypted in transit and at rest. If administrators need a full description of the security mechanisms, see Security and Privacy.

Are connectors (Notion, Slack, etc.) secure?

Connectors use standard OAuth authorization, and MaiGPT does not store your account passwords. You can revoke authorization at any time.

Usage Recommendations

Avoid entering highly confidential information Although MaiGPT has comprehensive security protections, avoid entering passwords, credit card numbers, national ID numbers, or other highly sensitive information directly in conversations.

Next Steps


Usage and Quotas

Back to MaiGPT Overview

File Library

Keep your files together and let AI use them directly.

The file library is your organization's central file repository. Put a project's specifications, quotes, FAQ, and meeting notes in the same **file workspace**, then start a MaiGPT conversation directly from that workspace. AI finds the files it needs and reads them in full before answering. It can also edit files directly after you confirm. Documents and images generated by AI are automatically saved to the file library. Every upload, edit, move, and deletion is recorded in the version history and can be restored with one click.



Select a workspace on the left to view file names, sizes, update times, and sources on the right. You can also start a conversation here. All content shown is fictional demo data.

Use Case

A sales representative is preparing a new product launch proposal. In My Files, she creates an "A1 Launch Proposal" workspace and imports specifications, quotes, an FAQ, and customer interview notes all at once. She then clicks Start a Conversation Here in the workspace and asks MaiGPT to "summarize the differences between the plans in the Q3 quote." AI finds the quote, reads the entire file, and creates a comparison table with citations identifying the source document. Next, she asks AI to change the

warranty in the third FAQ entry to two years. After she confirms, AI writes the change directly to the file, and the version history records that she confirmed it in the conversation. If she later discovers a mistake, she can open the version list and restore the file.

File Library Spaces

The space tree on the left has four sections:

Space	Who can access it	Purpose
Personal Space › My Files	Only you	Your personal work files; AI-generated files are automatically saved to the Staging Area within it
Organization Space › Organization Shared Files	Members with organization space viewing permission	Materials shared across the organization, such as product documents and brand assets
Shared Spaces	Access is granted by authorized role	Folders used across departments; see Shared Spaces
System › Conversation Attachments	You (organization owners can view attachments across the organization)	Lists attachments from conversations you have participated in that have not been filed in a workspace and are still incurring charges; you can download them or delete them early



The space tree is divided into Personal Space, Organization Space, Shared Spaces, and System.

At the top level of a space, you can only create **file workspaces**. You cannot upload files directly there. All files go in a workspace or a folder within a workspace.

What Is a File Workspace?

A file workspace is a folder containing related files. You typically create one for each project, customer, or topic. Workspaces have three key features:

AI's working scope: Click Start a Conversation Here in a workspace to attach it to MaiGPT, allowing AI to read and edit its files.

Workspace instructions: The system automatically prepares a guide describing what the workspace contains and how to use it. AI refers to this guide when answering.

Version history: Every change in the workspace is recorded and can be restored with one click.

How Does the File Library Differ from the Knowledge Base?

The knowledge base is like a cheat sheet for an exam: content is split into chunks so an Agent can quickly find answers for users. It is suited to customer support and FAQs. The file library is like having a complete textbook beside you while doing homework: AI reads the entire original file to help you write, consolidate, and revise content. It can also edit files and preserve their versions.

Use the knowledge base to "find answers" and the file library to "work with files." For use cases, common mistakes, a decision table, and ways to use both together, see Knowledge Base vs. File Library: Differences and When to Use Each.

Availability and Permissions

By default, **only owners can use the file library**. To grant access to members, an owner or someone with role management permission must create a custom role, select the required file library permissions, and add members to that role. Default roles cannot grant file library permissions. The file library permissions in a member's custom roles determine which spaces they can use:

Permission	What it controls
File library permission	Whether File Library appears in the left menu
Personal space permission	Whether you can use your own My Files
Organization space viewing permission	Whether you can browse, search, and download Organization Shared Files

Permission	What it controls
Organization space editing permission	Whether you can upload, move, rename, and delete files in Organization Shared Files
Create shared spaces permission	Whether you can create and delete shared spaces, and change their names and authorized roles
Permission to be invited to shared spaces	Whether authorized roles can grant you access to shared spaces



Select file library permissions on the role permissions page.

For setup instructions, see Role and Permission Management. MaiGPT can still read files for members with viewing permission only, but it will not edit files for them.

Members without any file library permissions will not see File Library in the left menu. Opening the file library URL directly displays "You currently do not have file library permission. Please contact your organization administrator." In MaiGPT conversations, the controls for mounting and attaching the file library are disabled.

Limits

Item	Limit
File size	10 MB per file
Supported formats	PDF, DOC, DOCX, PPT, PPTX, XLS, XLSX, CSV, TXT, MD, JSON, HTML, PNG, JPG, JPEG, GIF, WebP, MP3, WAV, M4A, MP4
Folder depth	Up to 10 levels
Batch move/delete	Up to 200 files at a time
File versions	The latest 20 versions of each file are retained

For storage charges, see Credits Billing: File Library Storage.

Next Steps

Create a Workspace and Import Files

Search, Filters, and File Details

Use a Workspace in MaiGPT

Let AI Edit and Organize Files

Version History and Restore

Shared Spaces

Online Editing

Knowledge Base vs. File Library: Differences and When to Use Each

Create Workspaces and Import Files

Files are stored in **file workspaces**. After creating a workspace, you can import multiple files at once and create folders within it to organize them.

Use Case

A marketing specialist takes over a new product campaign whose files are scattered across email attachments, cloud drives, and colleagues' computers. She creates a "New Product Campaign" workspace in My Files and imports the specifications, quotation, and asset list in one go. After import, each file shows its size, timestamp, and source. This workspace becomes her starting point whenever she needs to find information or ask AI to organize it.

Create a File Workspace

1. Select a Space

Click File Library in the left menu, then select the destination in the space tree: choose My Files for personal content, Organization Shared Files for organization-wide use (requires permission to edit the organization space), or the appropriate shared space for use across departments.

2. Add a File Workspace

Click Add File Workspace above the space tree, confirm the Location, enter a File Workspace Name, and click Create. The new workspace appears immediately in the space tree and list.



The dialog shows where the workspace will be created

> You can only create workspaces at the top level of a space; you cannot upload files directly there. The Upload Files button is disabled at the space root. Open or create a workspace first.

3. Add Folders (Optional)

Inside the workspace, click Add Folder to organize your files further. Folders can be nested up to 10 levels deep, counting from the space root.

Import Files

1. Open the Import Dialog

Open a workspace or folder and click Upload Files (the upload icon) in the toolbar to open the Import Documents dialog.

2. Choose Files

Click Choose Files to select multiple files at once. The dialog lists the selected files and their sizes. Click Remove for any files you do not need.



Review the list and remove any unwanted files before importing

3. Start Importing

Review the list, then click Start Import. Imported files appear in the list with their size, update time, and source.

Supported Formats and File Size

Type	Formats
Documents	PDF, DOC, DOCX, PPT, PPTX, XLS, XLSX, CSV, TXT, MD, JSON, HTML
Images	PNG, JPG, JPEG, GIF, WebP
Audio and Video	MP3, WAV, M4A, MP4

The limit is **10 MB** per file. Files that exceed this limit or use an unsupported format are marked with an error during import and are not imported.

Delete a Workspace or Folder

Right-click a workspace card or folder (or click ⋯) and select Delete.

> You can only delete empty workspaces or folders: delete or move their files first. Deleting a workspace also removes its empty folders, workspace instructions, and version history. You cannot delete space roots or system folders such as Temporary Storage.

Related Pages

Search, Filters, and File Details

Use Workspaces in MaiGPT

Version History and Restore

Search, Filters, and File Details

As your file collection grows, you do not need to remember where each file is stored. The search bar at the top searches all spaces you can access, shows each result's location, and lets you open it with a click.

Use Case

A customer calls to ask about last quarter's quote. The sales representative only remembers that the filename contains “Quote.” She searches for “Quote” at the top of the file library, and the results show “Q3 Quote.xlsx” with “My Files › A1 Launch Proposal” below it. Clicking the file opens its details on the right, where she clicks Download to attach it for the customer.

Search Across Spaces

Enter a keyword in Search all visible files at the top right of the file library, then click the search button. The results list matching files from all spaces you have permission to view. Each result shows its location (space › workspace › folder). Click a filename to open its details.



Search results indicate “Across all visible spaces” and show each file's location

> To find workspaces in the current space only, use Search file workspaces in this space above the list.

Filter by Type and Switch Views

In a workspace, click Type: All to select one or more file types to display (for example, only Excel files or presentations). All types are shown when none are selected. Use the controls at the top right of the list to

switch between List view and Thumbnail view.



Select multiple types; leave all unchecked to show every type

---

File Details

Click a filename to open its details on the right, including:

Actions at the top: Download, Move, Delete

Edit and Upload new version: See Online Editing. After the file has been changed, Versions also appears; see Version History and Restore

Basic information: Size, file location, creation time, creator, update time, updater, and source (such as Upload or Agent output). AI-generated files also show the source workspace and the conversation that generated them

File preview

Start conversation: Bring this file into a new MaiGPT conversation



File details sidebar

Bulk Actions

Select the checkboxes on the left of the list (or select all using the header checkbox) to display actions such as Move and Delete at the top. You can process up to **200** files at a time. For a single file, you can also use the row's ⋯ menu to Download, Rename, Move to⋯, or Delete it.

> You can restore deleted files from the workspace's Version history. See Version History and Restore for details.

Related Pages

Create Workspaces and Import Files

Use Workspaces in MaiGPT

Use Workspaces in MaiGPT

Once you attach a workspace to MaiGPT, you no longer need to upload files one by one. AI finds the files relevant to your question, reads them in full, and answers with source citations. Attachments you upload in the conversation and files AI generates are also saved automatically to the file library.

Use Case

A sales representative clicks Start a conversation here in the "A1 Launch Proposal" workspace. She first asks, "What files are in this workspace?" to check what AI can access, then asks, "Summarize the differences between the plans in the Q3 quotation." AI reads the quotation and presents a comparison table. When the customer sends a new requirements document, she drags it directly into the conversation, and the system displays "Filed in 'A1 Launch Proposal'." She then asks AI to write a proposal outline as a Word file based on the specifications and the new requirements. The file is saved automatically to her temporary storage, with details identifying the source workspace and conversation.

Start a Conversation from a Workspace

1. Start a Conversation Here

Open the workspace you want to use in the file library, then click Start a conversation here.



Start a conversation here appears above the workspace list

2. Confirm the Workspace Is Attached

When MaiGPT opens, a workspace tag (such as "A1 Launch Proposal") appears below the input box, indicating that the workspace is attached to this conversation. Click × next to the tag to detach it.



The workspace tag below the input box

> You can attach one workspace to a conversation at a time. You can also click Start a conversation in the file details, or select multiple files and click Start a conversation, to bring only the selected files into the conversation.

Let AI Read Files and Answer

With a workspace attached, you can ask questions using file names or descriptions of their contents:

Try asking	What AI does
“What files are in this workspace?”	Lists folders and files so you can check what it can access
“Summarize the differences between the plans in the Q3 quotation”	Finds the quotation, reads it in full, and answers with source citations
“Compare the specifications with the competitor presentation”	Reads multiple files as needed and summarizes the differences



AI shows which files it has read; files it has read appear as attachments labeled “From workspace”

File reading rules:

AI can read up to 5 files at a time. If you need more files, split your questions across several requests.

Files that are still being parsed or failed to parse cannot be read. Wait for parsing to finish before asking.

If the file name is ambiguous, AI asks you to confirm which file you mean.

If the workspace has more than 300 items, AI first sees a folder-level overview, then searches deeper based on your question.

For members with view-only access, AI can still read files but will not modify them.

Workspace Guide

Each workspace has a Workspace guide describing its contents and what each file is for. AI refers to this guide when answering. Click Workspace guide at the top of the workspace to view and edit it.



The automatically organized workspace guide, labeled “Automatic” at the bottom

Automatic updates: After files are imported, moved, or deleted, or attachments are filed, the system automatically rewrites the guide. Multiple changes made within a short period are combined into one update. An entry labeled Workspace guide automatically updated is added to the version history and can be restored.

Manual edits: Once you edit the guide yourself and click Save, subsequent file changes will no longer overwrite your content. Instead, the system generates update suggestions and displays “File changes detected. Workspace guide update suggestions generated.” Click Apply suggestions to accept them and resume automatic updates.

You can also click Regenerate to have the system rewrite the guide based on the current files.

Automatically File Conversation Attachments

When you upload a file in a conversation with a workspace attached, the file is automatically added to that workspace. The message “Filed in ‘Workspace name’” appears in the upper-right corner. If it was filed in the wrong place, click Undo in the notification to undo the filing.



The filing notification remains until you act on it

To put the file in another workspace, say so directly in your message, for example, “Put this in the Client Project workspace.” If that workspace cannot be found or you do not have write access, the file stays in the current workspace and the system explains why.

Automatically Save AI Outputs

Documents, images, and videos that AI generates in a conversation are automatically saved to Temporary storage under My files, so you do not need to download and organize them separately.

Output list on the right: Output in the panel on the right lists this conversation’s outputs chronologically. You can preview and download them. Clicking Open in file library takes you to the folder containing the file and opens its details.

File details: Open a generated file in temporary storage to see its Source, labeled Agent output, along with the Source workspace and Output conversation. Click the output conversation to return to the

original conversation.



The Output list in the right panel



Generated file details identify the source workspace and output conversation

> You can move outputs you want to keep long term from temporary storage to a permanent workspace.

Related Pages

Let AI Edit and Organize Files

Version History and Restoration

AI Conversations

Let AI Edit and Organize Files

AI can read files and directly edit, rename, move, or delete files in a workspace. For every change, **AI first lists what will change and waits for your confirmation before proceeding**. Writing a file creates a new version, and deleted files can be restored within 30 days.

Use Case

The day before a product announcement, the warranty policy changes from one year to two years. In a conversation with the product workspace attached, a marketing specialist says, “Change the warranty in the third question of FAQ.md to two years for the main unit and three years for the motor.” AI displays the content before and after the edit and asks whether to write it back. After she confirms, AI updates FAQ.md directly. She then asks AI to rename three interview notes to “2026Q3_original filename” and move them to the “Interview Materials” folder. AI first lists the proposed changes in a table and completes them together after confirmation. Version history records that she confirmed each step in the conversation.

Edit File Contents

1. Describe What to Change

In a conversation with a workspace attached, describe the file and the content you want to change. For example:

“Change the warranty in the third question of FAQ.md to: two years for the main unit and three years for the motor.”

2. Confirm the Change

AI reads the file first, shows the content before and after the edit, and asks whether to write the change. Check the content, then reply to confirm or select the confirmation option AI provides. Only then will AI write the change to the file.



AI shows the content before and after the edit, then writes it only after confirmation

3. View the New Version

After the write completes, the file has a new version, with its name and location unchanged. The version list shows Agent, the person who confirmed the change, and the source conversation. See Version History and Restore.

Editable Formats

Type	Formats	Description
Text and data	MD, TXT, SQL, JSON, CSV	Edit contents directly
Office documents	XLSX, DOCX, PPTX	Requires Code Interpreter to be enabled in the conversation; complex charts or formatting may not be fully preserved, so check the result after editing

You need editing permission for the workspace. If you only have viewing permission, AI explains that it cannot edit the file and generates a new file instead. If a colleague saves a new version before you confirm, AI will not overwrite it. It tells you the file has been updated and asks you to confirm again to avoid overwriting someone else's content.

Rename and Move Files

You can ask AI to handle several files at once. For example, “Rename the three interview notes to ‘2026Q3_original filename’ and move them to the ‘Interview Materials’ folder.” AI first lists the Current Location, Current Filename, Filename After Operation, and Destination in a comparison table, then proceeds after confirmation.



Comparison table before renaming and moving files

Up to **20** files can be processed per operation.

Renaming cannot change the file extension.

If the destination folder does not exist, AI includes “Create Folder” in the comparison table and completes everything together after confirmation.

Renaming and moving the same file are performed together. If either step cannot be completed, neither step runs, and AI explains why.

Delete Files

Say “Delete the old Q2 quotation,” and AI lists the files to delete and their locations. **Deletion always requires your confirmation.**

Deleted files are retained for **30 days**. During that period, you can restore them to their original locations from the workspace's Version History.

If you are not a workspace owner (organization owner, space owner, or workspace creator), AI submits a deletion request instead. An owner can select Approve Deletion or Reject under Pending Deletions in the workspace. Requests expire after 7 days.

Related Pages

Use Workspaces in MaiGPT

Version History and Restore

Code Interpreter (Code Execution)

Version History and Restore

The file library keeps two levels of history. **Workspace version history** records everything that happens in a workspace, while **a file's version list** retains the previous contents of that file. Both support restoration, and restoring an item also creates a history entry.

Use Case

A manager notices that the warranty information in the FAQ was changed incorrectly. She opens the version list for FAQ.md and sees that the latest version is labeled Agent, with a note that a colleague confirmed it in a conversation and a link to that conversation. She previews the previous version, confirms that the content is correct, and clicks Restore to this version. The file immediately returns to its previous contents, and a new entry labeled "Restored from v1" appears in the version list.

Workspace Version History

Click Version history (the clock icon) in the upper-right corner of the file library. The sidebar lists changes chronologically. Use Scope at the top to choose which space or workspace to view. Changes you can undo have a restore icon on the right.



Changes you can undo have a restore icon on the right

Recorded events include:

Type	Events
Files	Upload, Rename, Move, Delete, Restore, Content updated, Content restored
Conversation-related	Session attachment (filing a conversation attachment), Session generation (AI output), Applied to conversation, Detached from conversation
Workspace guide	Workspace guide automatically updated, Guide saved manually, Guide suggestions

Session generation, Applied to conversation, and Detached from conversation are recorded for reference only and cannot be undone.

Actions performed by AI are labeled Agent and include “Confirmed by [name] in conversation” and the output conversation, so you can trace who approved the action and in which conversation.

> Restoring an item adds another “Restore” event to the history. If the original location no longer exists (for example, the folder has been deleted), the entry displays “The original location no longer exists. Unable to restore.”

File Version List

1. Open the Version List

Click the file name to open its details, then click Versions. This button appears only after the file has been modified (by AI, through online editing, or by uploading a new version). Newly uploaded files that have not been changed have no version list. The sidebar lists the file’s previous versions, including who saved each version and when, and whether Agent modified it. The version currently in use is labeled Current version.



Each version records who made and confirmed the changes

2. Preview an Older Version

Click any older version to see a preview of its contents below.



Preview an older version before deciding whether to restore it

3. Restore to This Version

Click Restore to this version and confirm. The system **creates a new version** using the older contents without deleting the versions in between. The new version is labeled Restored and “Restored from v◯.”



Restoring also creates a new version

> Each file retains its 20 most recent versions. Older versions are removed automatically. Restoring a file version requires edit access to the workspace.

Related Pages

Let AI Edit and Organize Files

Online Editing

Shared Spaces

Shared spaces are suitable for files that multiple departments need, but the entire organization does not, such as launch materials used by sales and marketing. Access to shared spaces is granted by **role**: members can see a space when their roles qualify. When their roles change, the spaces they can see update automatically, without configuring access for each person.

Use Case

The sales and product departments need to prepare materials together for a new product launch. The marketing manager creates a shared space named "A1 Launch | Sales and Marketing" in the file library and selects Sales Department and Product Department as authorized roles. The bottom of the dialog immediately lists the members who will gain access. Later, when a colleague transfers to the sales department, the manager does not need to configure anything else: the colleague sees this space when they log in to the file library.

Create a Shared Space

1. Open the Creation Dialog

In the space tree on the left of the file library, click ＋ (Create shared space) next to Shared spaces.

2. Enter a Name and Authorized Roles

Enter a Space name and select the custom roles to grant access to under Authorized roles (default roles cannot be selected). You can also leave the roles unselected and add them later. Only the creator and organization owner can see a space with no authorized roles. If the organization has no custom roles, the list displays "No custom roles yet. Create a custom role first." Anyone with role management permission can click Go to role settings. The Members who will gain access section below lists members in these roles in real time. It also indicates if any member lacks the "Can be invited to shared spaces" permission.



Preview which members will gain access before creating the space

3. Confirm Creation

Click Confirm to add the shared space to the space tree. As with other spaces, only file workspaces can be created at the top level of a shared space. Workspaces also support Start conversation from here, workspace instructions, and version history.

Who Can See a Shared Space

Members can see a shared space when they meet both conditions:

Their role is included in the space's Authorized roles
Their role has the Can be invited to shared spaces permission

The creator can always see the space. Organization owners do not need permission to be invited, but their role must still be among the authorized roles. They can also see the space if all authorized roles

have been deleted. Shared space access can only be granted to roles, not to individual people. To grant access to a specific member, add them to the appropriate role.

> Creating or deleting shared spaces, or changing a space's name or authorized roles, requires the Create shared spaces permission. For permission settings, see Role and Permission Management.

Edit and Delete

Edit: Open Edit shared space for the space to change its name or authorized roles. You can also clear all authorized roles. Changes are recorded in the space's version history.

Delete: A space cannot be deleted while it still contains content. Empty it first.

When there are no authorized roles (because the selection was cleared or all authorized roles were deleted): Only the creator and organization owner retain access. Add authorized roles again when needed.

Related Pages

File Library

Role and Permission Management

Online Editing

For small changes, you do not need to download and re-upload a file. Edit text-based files directly in the File Library and save to create a new version. You can restore earlier versions at any time.

> Your organization must enable online editing separately. If the file details do not show an Edit button, contact your organization administrator.


Use Case

A customer service supervisor notices a typo in an FAQ. She opens FAQ.md in the File Library, clicks Edit to fix the line, switches to Preview to check the formatting, and clicks Save. “Saved v4” appears in the upper-right corner, and the version list gains an entry for her change.

Edit a Text File

1. Open the Editor


Click the file name to open its details, then click Edit to open the full-page editor. The editor provides line numbers and syntax highlighting. CSV files use a table editor where you can add or delete rows.



The Save button in the upper-right corner becomes available after you make changes

2. Switch to Preview


For Markdown files, switch between Edit and Preview at the top. You cannot make changes in preview mode; return to Edit to continue editing.



Preview the formatted content

3. Save as a New Version

Click Save to save the content as a new version. “Saved v◯” appears in the upper-right corner. Use the version menu to view previous versions or switch back to an earlier version's content. The editor does not save automatically. If you have unsaved changes when leaving, the system prompts you.



Each save creates a new version

Supported Formats and Limits

Formats	Limits
MD, TXT, SQL, JSON, CSV	5 MB per file; up to 50,000 rows for CSV and JSON

Files that exceed these limits can only be previewed and downloaded.

Concurrent Editing

If a colleague saves a new version while you are editing, clicking Save displays “◯◯ saved a new version at ◯◯. You are editing the content of v◯” and offers two options:

Save My Content as a New Version Anyway: Keep your changes and save them as the latest version (your colleague's version remains in the version list).

Load Latest Version: Discard your current changes and continue editing from your colleague's latest version.

Upload a New Version

For a file you have edited locally, use Upload New Version in the file details to add it as a new version of the same file, keeping the file name and location. The uploaded file must use the **same format** as the original, with a limit of 10 MB per file. This supports text-based files as well as XLSX, DOCX, and PPTX. Like online editing, this feature must be enabled by your organization.

Related Pages

Version History and Restore

Let AI Edit and Organize Files

Knowledge Base vs. File Library: Differences and When to Use Each

A knowledge base is a cheat sheet for an exam; the file library is the full textbook beside you when doing homework.

Both can store documents, but AI uses them differently: a knowledge base helps an Agent **find answers quickly** to respond to users, while the file library lets AI **work with complete original files**. Putting data in the wrong place often leads to inaccurate answers, slower responses, or higher Credits usage. This page helps you decide where your data belongs.

At a Glance

	Knowledge Base (RAG)	**File Library**
Analogy	A cheat sheet for an exam	The full textbook beside you when doing homework
What it is	An Agent's "memory": content is split into chunks and indexed in advance	A central place for your organization's files: original files are stored in file workspaces
How AI uses it	Retrieves the few chunks most relevant to the question, then answers based on them	Reads complete files when needed before answering; can also edit, rename, and move files after your confirmation
Goal	Answer users' questions as quickly and accurately as possible	Help you write, consolidate, and revise content based on complete source material

You cannot bring a whole stack of textbooks into an exam, so you prepare a cheat sheet. For homework, you need to open the textbook and consult it in full. Answering external users' questions is like taking an exam: you need a cheat sheet that gets you to the answer quickly. Writing internal documents is like doing homework: you need the complete original files.

Use Case Comparison

	Knowledge Base	File Library
Typical scenarios	External customer support, FAQ responses, and queries about internal policies and SOPs	Writing, consolidating, and revising internal documents, such as drafting proposals, comparing multiple quotes, or updating FAQs to match new specifications
What you need	Speed and accuracy	Complete content that can be edited
Where it is used	Agents on any conversation platform (web Widget, LINE, API integrations, internal chat), and Knowledge Base Q&A in MaiGPT	MaiGPT (attach a workspace), and Internal Chat for Agents with a file workspace configured
How to prepare data	Requires preparation: write FAQs, clean the data, and remove outdated or duplicate content to ensure consistent answer quality	Add the original files and organize workspaces by project or topic
Does the content change?	Relatively stable; upload it again when updated	Frequently edited; every change has a version that you can restore

Conversation platforms such as web Widget, LINE, and API integrations never read from or write to the file library. Only MaiGPT and an Agent's Internal Chat use it. Put content that an external customer support Agent should answer from in a knowledge base.

Common Mistakes

Common practice	What happens	Recommendation
Putting product manuals in the file library and expecting an external customer support Agent to answer from them	Conversation platforms such as web Widget and LINE cannot access the file library, so the Agent cannot answer	Put them in a knowledge base and turn frequently asked questions into FAQs
Using the file library to answer large volumes of repeated common questions	Reading many complete documents can increase processing time and Credits usage; up to 5 files can be read at a time, with additional files read in batches	Organize the questions into knowledge base FAQs for fast, consistent answers
Dropping a large batch of unorganized original files into a	Knowledge bases primarily retrieve relevant chunks; if the task requires	Put them in a file library workspace so AI can read each file in full before

Common practice	What happens	Recommendation
knowledge base and asking an Agent to write a report or compare entire documents	comparing complete original files one by one, specify the documents and scope to reference	consolidating the content
Putting a draft that is still being revised in a knowledge base	Every change requires another upload and parsing wait, with no version history; outdated content may still be used in answers	Keep drafts in the file library, then add the final version to the knowledge base when the Agent needs to use it for external responses
Putting all documents in a knowledge base without organizing them	Irrelevant or conflicting chunks are used as sources, making answers inaccurate	Include only cleaned content relevant to the Agent's task, and use Search Testing before launch to confirm that the correct chunks can be retrieved

---

What Do I Want to Do → Where Should It Go?

What I want to do	Where to put it
Have a customer support Agent on the official website or LINE answer questions about products, plans, returns, and exchanges	Knowledge Base
Have an Agent use standard answers for common questions	Knowledge Base (FAQ)
Let colleagues look up company policies and SOPs in MaiGPT	Knowledge Base
Ask AI to write a proposal based on specifications and customer requirements	File Library
Compare the full differences between several quotes or contracts	File Library
Ask AI to edit document content directly and keep a record of changes	File Library
Save documents and images that AI generates in a conversation	File Library (automatically saved to the Temporary Area in My Files)
Use the same data for external answers and internal revisions	Both: maintain original files in the file library, and put organized final versions or FAQs in a knowledge base

Still unsure? Ask yourself: **Do I need to “find an answer” or “work with an entire file”?** Use a knowledge base to find answers and the file library to work with files.

Can I Use Both in the Same Agent or Conversation?

Yes. The two do not conflict. AI decides whether to retrieve knowledge base chunks or read workspace files based on the question.

Using Both in a MaiGPT Conversation

In the same MaiGPT conversation, you can attach a workspace and use Select Knowledge Base to specify which knowledge base to query.

For example, a customer support training manager wants to consult both original workspace files and a knowledge base. In a workspace containing sample warranty FAQs, she clicks Start a Conversation Here, selects the sample library knowledge base, and asks, “How long are the main unit and motor warranties in the workspace documents? What are the borrowing periods for undergraduate and graduate students in the knowledge base?” MaiGPT cites both the original workspace files and the knowledge base in a single response, helping her check the two data sources.



The same MaiGPT conversation cites original workspace files and the selected knowledge base to answer questions; all content shown is fictional sample data.

Using Both in Agent Settings

Once the file library is enabled for your organization, File Workspace appears in the Knowledge and Data group on the left side of Agent settings. You can configure it alongside Knowledge Base Settings. The file workspace determines how this Agent uses the file library in Internal Chat:

Option	Description
Do Not Use	Does not read from or write to workspaces (default)
Bind Workspace	Always works in one workspace, reading and saving outputs there; users cannot switch workspaces
Let Users Attach Their Own	Users can choose which file workspace to attach in the conversation

When the same Agent has both a knowledge base and a file workspace configured:

Conversation platforms such as web Widget, LINE, and API integrations: use only the knowledge base to answer.
Internal Chat: can query the knowledge base and read and write workspace files.

A common setup is: "**Use the knowledge base as the source for Q&A, and keep original working files in the file library.**" If you also need AI to generate or edit files, follow the steps in Let AI Edit and Organize Files. Simply asking a question or requesting an outline does not necessarily generate a file.



An Agent's file workspace can be disabled, bound to a fixed workspace, or left for users to attach. The built-in guidance also explains that external channels do not read from or write to the file library.

To bind a workspace, the person configuring the Agent needs edit permission for that workspace. After a workspace is bound, each user's ability to read from or write to it in a conversation still depends on their own file library permissions: for users with view-only permission, AI only reads files; it does not edit files or save outputs there. For permission settings, see Availability and Permissions.

Related Pages

Knowledge Base: what a knowledge base is and what content it can contain

How to Create FAQs

File Library: storage, file workspaces, and permissions

Using Workspaces in MaiGPT

Let AI Edit and Organize Files

Technical Guide: Knowledge Base vs. File Library: How They Work and How to Choose: how they work, permissions, capacity, and billing differences for SI, presales, and implementation engineers

Chat with Agents (Agent Marketplace)

Agent Marketplace in the left sidebar lets organization members chat directly with Agents in the management console. It has two tabs:

Official Built-in: Agents prepared by MaiAgent and enabled by your organization. See Official Built-in Agents.

Organization-built: Agents you create with Agent Builder. This page explains how to use them.

The marketplace remembers the tab you last used in this browser. The next time you open it from the left sidebar, refresh the page, or close and reopen the browser, it returns to that tab. On your first visit, or after clearing browser cookies, Official Built-in is the default. For example, if a customer service manager uses a company-built Agent every day to handle complaints, switching to Organization-built once means Agent Marketplace will open directly to Organization-built on future visits, saving an extra click.



After your last visit to Organization-built, Agent Marketplace opens to Organization-built again.

> This preference is stored only in the current browser and does not sync to your account. A different browser or device starts with Official Built-in. If your organization does not have an Official Built-in tab, the marketplace continues to show only organization-built Agents, regardless of this preference.

Introduction to Agent Marketplace Conversations

Conversations with organization-built Agents in Agent Marketplace use the **built-in conversation platform**, "Internal," which is automatically created when you create an Agent. No integration setup is required. In "All Conversations," these conversations are labeled with the source "Internal." Conversations stay within the platform and do not appear on external channels such as LINE or Web Chat.

💬 Chat Area

Interact with an Agent through real-time questions and answers

📋 Conversation History

View and manage all previous conversations

🤖 Agent Selection

Switch between Agents to chat with

⚙️ Agent Settings

Adjust the Agent settings for the current conversation in real time, including permissions and tool configuration

Visible only when you have permission to edit that Agent

📚 Knowledge Base Document Management

Precisely control which documents the Agent can reference in each conversation



How Do I Chat with an Agent in Agent Marketplace?

1. Choose an Agent from Agent Marketplace

Click "Agent Marketplace" in the left sidebar, switch to the Organization-built tab, and select the Agent you want to chat with to open its conversation page.

This tab also provides a few useful controls:

Location	Function
Toolbar: Search Agent name or description…	Filter by name or description
Toolbar: View Favorites	List only Agents you have added to your favorites
Toolbar: Agent Management Create Assistant	Open the Agent Builder management page or create a new Agent directly; visible only if you have Agent management permissions
Star on the card	Add to Favorites Remove from Favorites. Favorites sync to your account across devices
Tool icon on the card	Hover to see "N tools attached," indicating how many tools are configured for this Agent
Settings on the card	Open the Agent's settings page; visible only if you have permission to edit it

> If you cannot find an Agent on the Organization-built tab in Agent Marketplace, your role usually has not been assigned access to its "Internal" conversation platform. See Which Agents Appear on the Organization-built Tab for the listing criteria.

2. Select the Agent You Want to Chat With

Select the Agent you want to chat with from the blue dropdown menu (Select AI Assistant) at the upper left. When expanded, Search AI Assistants at the top lets you filter by name. The list shows Recently Used first, followed by All AI Assistants.



3. Start a Conversation

Continue a previous conversation: Select a topic from the previous Q&A topics on the left to resume the conversation.

Start a new conversation: Click "New Q&A" in the left panel to start a fresh conversation.

> All conversations appear in the Q&A history at the upper left.

After selecting a conversation, enter your question in the text box below to start chatting.



Continue a previous conversation (select a conversation)



Start a new conversation (create a conversation)

4. Customize the Document Reference Scope (Optional)

Use knowledge base management on the right to select the specific documents the Agent can reference in this conversation.



Select reference documents and FAQs separately for each message

Adjust the selection before sending each question

Document Access Scope

When sending the first message, allow access to all documents, including "氣氛燈-系列.md"

The Agent references the document and replies: "Document content: The official website has closed and no longer sells any products to the public."



When sending the second message, deselect "氣氛燈-系列.md"

The Agent cannot reference it and replies: "I cannot find the specific content of the **'氣氛燈-系列.md' file.**"



FAQ Access Scope

When sending the first message, allow access to all FAQs, including "How do LLMs work?"

The Agent references the FAQ and provides the relevant answer.



When sending the second message, deselect "How do LLMs work?"

The Agent cannot reference "How do LLMs work?" and replies: "I cannot find information about how LLMs work in the FAQs."



Tag Filtering

Use the tags configured in the knowledge base to filter which document content the Agent can reference:

> For tag settings, see Document Management: Tags and Metadata.

a. Click "Show Tag Filter" at the upper right



b. Choose the matching rule: Click "Include All Tags (AND)" or "Include Any Tag (OR)" to switch (the image below shows the older AND/OR buttons in the same location)



c. Add tags

Filter using "Include All Tags (AND)"

Documents: Only "進階露營.pdf" meets all the criteria and is available for the Agent to reference

FAQs: No FAQs meet all the criteria, so none are displayed

> Tag filtering applies to both documents and FAQs. These settings affect only this conversation. To apply the same default criteria across all conversation platforms for an Agent, configure Knowledge Base Tag Filtering on the Agent settings page.






5. Adjust Agent Settings in Real Time (Optional)

Use "AI Assistant Settings" at the upper right to change permissions, tools, and other configuration in real time.



Click it to open a pop-up panel on the right, where you can edit the permissions, tools, and other settings you need.



Who Can See the AI Assistant Settings Button?

This button appears based on your permission to edit **the currently selected Agent**. If you do not have edit permission, the button is hidden, but you can still chat with the Agent as usual.

Your Role or Permissions	Button Visibility
Organization owner	✅ Always visible
Your role has "Allow Editing" for this Agent	✅ Visible
Your role can only view this Agent	❌ Hidden; Q&A only
You do not have access to the "AI Assistant" feature	❌ Hidden

> Permissions are evaluated for each Agent individually. When the same person switches between Agents on the same page, the button may appear or disappear. This is normal.

> The button appears only after permissions have been checked. A brief delay when switching Agents is normal.

Organization administrators grant edit permission by selecting "Allow Editing" for each Agent on the "Assign AI Assistants" tab under "Role Permissions". See Role Resource Access Permissions for setup instructions. After an administrator changes the settings, members can refresh the page for them to take effect.

If you need to edit an Agent but cannot see this button, contact your organization administrator and ask them to enable "Allow Editing" for that Agent for your role.

Message and Conversation Actions

The Agent Marketplace conversation page shares the same message and conversation actions as MaiGPT. For full details, see MaiGPT: Message Actions and Organize Conversations. In Agent Marketplace:

Your messages: Hover to Copy or Edit Message. Editing deletes the subsequent conversation and generates a new reply. Use ‹ N
M › to switch between versions of an edited message.

Agent replies: Hover to Copy, Like, Dislike (opens the "Provide Feedback" window), or Branch Conversation from Here.

Conversation list on the left: Click ⋮ on a conversation to Rename or Delete Conversation. The search box below New Q&A finds conversations by title or message. To remove several at once, see Delete Multiple Conversations at Once below. Pinning is exclusive to MaiGPT and is not available here.

Official built-in Agent conversation pages: An additional Connected Services button at the top manages authorizations for external services the Agent accesses on your behalf. See Connected Services.

Voice: When the Agent has its voice assistant enabled, a Voice Interaction Mode button appears in the input bar. See Voice Assistant: How Users Interact.

Delete Multiple Conversations at Once

After a round of testing with an Agent, several test conversations often remain in the list on the left. You can select multiple conversations of your own directly in this list and delete them at once.

For example, a customer service manager finishes testing a newly launched help desk Agent and has three test conversations in the list. She wants to delete two and keep one for reference, so she clicks Edit, clicks Select All, and then clicks the conversation she wants to keep to deselect it. After she confirms deletion, only that conversation remains. One of the deleted conversations was open, so the screen automatically switches to a new conversation.

On the Agent conversation page, click the pencil icon, Edit, below New Q&A and to the right of the search box. In edit mode, the button becomes a checkmark icon, Done. You can search first, then click Edit if needed.

Click a conversation row or the checkbox at its start to select conversations to delete. In edit mode, clicking a row only selects it and does not open the conversation. You can also click Select All above the list to select the conversations currently loaded, up to 100 at a time. The upper right shows "N selected."


新建問答

搜尋對話標題...

全選 已選 2 則

- [x] 示範清理 A
- [x] 示範清理 B
- [ ] 示範清理 C

所有問答話題載入完畢 🎉



After you select two conversations, the button at the bottom of the list shows "Delete (2)."

Click Delete at the bottom of the list. A confirmation window asks "Delete N conversations?" Check the count and click Delete. When all deletions succeed, "N conversations deleted" appears and edit mode closes.

> Messages within the conversations are deleted as well, and the interface provides no undo option. The selection scope, selection clearing when the search term changes, and handling of partial failures follow the same behavior as MaiGPT's "All Conversations" page. See MaiGPT: Delete Multiple Conversations at Once.

If the deleted conversations include the one currently open, the screen automatically switches to a new conversation.

Edit does not appear when the list has no conversations.

If you decide not to delete anything, click Done to leave edit mode and clear the selection.

💡 Usage Tips

Conversation Management

Use conversation history to quickly return to previous discussions

Start a new Q&A for a fresh topic

Rename conversations as they accumulate so their titles clearly describe the topic

Precise Document Control

Limit reference documents for specific questions to get more precise answers

Prevent unrelated documents from interfering with the Agent's judgment

Flexible Settings

Adjust the Agent's capabilities in real time for different conversation scenarios

Test how different settings affect answer quality

Official Built-in Agents

Official built-in Agents are Agents that MaiAgent designs, tests, and publishes in advance. Their role instructions, models, and tools are already configured. Once an organization administrator activates them, members can start chatting right away—without building an Agent, adjusting role instructions, or preparing a knowledge base first.

In the Agent Marketplace, official built-in Agents and the Agents you build are organized into two tabs: Official Built-in and Organization-built.

How They Differ from Organization-built Agents

	Official Built-in Agents	**Organization-built Agents**
Creator	Designed, tested, and maintained by MaiAgent	Created through Agent Builder
Setup required	Ready to use	Must be built manually from scratch
Role instructions tools models	**Cannot be modified**	Fully customizable
Knowledge base	You can import your own documents	Fully customizable
Version updates	Automatically follows the latest official version	Maintained by you
Quantity limits	**Limit on simultaneous activations** depends on your plan	Depends on your plan (see Trials and Subscription Plans)
Who can use them	Administrators specify the Audience	Determined by role permissions

Simply put: **use official built-in Agents to get started quickly, or build your own for customization.** Both can coexist. Many organizations use official built-in Agents for general tasks and build their own Agents for company-specific workflows.

Organization-built Agents: Using Existing Assistants and Finding the Testing Entry Point

To use an existing AI assistant or open its test interface, start from the Organization-built tab in the Agent Marketplace. For full instructions, see Chat with an Agent. This tab lists the "Internal" conversation platforms available to the member. Each Agent automatically comes with three conversation platforms when it is created: Web, Internal, and API. The Internal platform is the channel members use to chat with the Agent in the Agent Marketplace. An Agent must meet all of the following conditions to appear in this tab:

It is an Agent created by the organization: This includes the entry Agent of an Agent Teams team. Official built-in Agents appear in the Official Built-in tab, while MaiGPT does not appear in the Agent Marketplace.

Its "Internal" conversation platform is enabled: It is not listed when Enabled is turned off in that platform's Function Settings.

The member's role is assigned this "Internal" conversation platform with Read selected: Default roles also count. Organization owners are exempt from this restriction and can see all organization-built Agents.

The member has Agent Marketplace permission: Without it, the Agent Marketplace does not appear in the left menu.

If condition 3 is met but the Agent is not assigned within the same role that has Agent Marketplace permission, the member can still start conversations but cannot rename or delete them. For step-by-step troubleshooting, see Members Still Cannot See an Agent After Permissions Are Set.

What You Can and Cannot Change After Activation

When you activate an official built-in Agent, the system creates a **locked Agent** in your organization based on the official blueprint.

You can:

Import your own documents into this Agent's dedicated knowledge base

Set which roles
groups can use it

Complete the connector authorizations it requires

You cannot:

Modify role instructions (System Prompt)

Add or remove tools or skills

Change the language model

It is normal to find no edit button in the AI Assistants list. Official built-in Agent settings are maintained centrally to ensure consistent quality across organizations and automatic updates when a new official version is released. If you need custom role instructions or a different combination of tools, build your own with Agent Builder, or apply an official template from the Agent Template Library to get an Agent you can freely modify.

Versions Update Automatically

Each official built-in Agent card displays its Version. When MaiAgent releases a new version—with improved prompts, behavior fixes, or expanded capabilities—**organizations that have activated it automatically receive the latest version**. There is no need or option to upgrade manually or pin a version.

If an Agent's response style or output format differs from before, it usually means a new official version has been released. The knowledge base content you imported is unaffected.

Simultaneous Activation Limits Depend on Your Plan

Official built-in Agents have a **limit on simultaneous activations** and a **cooldown period** after activation. Allowances vary by plan; see Trials and Subscription Plans ・ Feature Differences.

If your organization's plan does not include official built-in Agents, the Official Built-in tab does not appear in the Agent Marketplace. Contact the sales team to upgrade your plan.

For detailed rules on activation, cooldown calculations, and what to do when you reach the limit, see Activation and Management.

Currently Available Scenarios

Official built-in Agents are grouped into two main categories, **Job Functions** and **Industries**, with 14 scenario categories in total:

Job Functions

Scenario Category	Example Agents
Human resources	Interview question generation, resume evaluation, job description writing
Legal	Contract risk review, nondisclosure agreement review, regulatory compliance checks
General affairs	Administrative announcement writing, procurement price comparison, document classification and filing
Accounting	Expense receipt organization, financial report summary analysis, business tax Form 401 analysis
Project management	PRD writing, requirements organization and analysis, competitor analysis
Personal productivity	Meeting summaries, presentation design, email reply writing

Industries

Scenario Category	Example Agents
Healthcare	ICD-10 code suggestions, discharge summaries, nursing handover reports
Manufacturing	Quality issue 8D reports, SPC process control analysis, equipment knowledge Q&A
Banking	Credit assessment report writing, KYC due diligence summaries, financial regulatory interpretation lookup
Securities	Individual stock research analyst, internal compliance policy Q&A assistant, financial advisor meeting preparation assistant
Retail	Daily sales summaries, product listing copy, customer complaint and review analysis
General administration	Petition classification and task assignment, press release drafting, preliminary subsidy application review
Government budgeting and accounting	Budget and final accounts execution analysis
Legal affairs and procurement	Regulatory interpretation summaries, tender procurement document checks

> The table lists representative examples for each category. Official built-in Agents continue to be added; refer to the Agent Marketplace → Official Built-in tab for the actual available list. For each Agent's purpose, required documents, and output, read the marketplace card or click Preview to see its example scenario and what each step does.

Next Steps

Ready to get started → Use Official Built-in Agents

Organization administrators enabling access for a team → Activation and Management

Use Official Built-in Agents

This page is for **all members**. It explains how to find the right official built-in Agent in the Agent Marketplace, how to work with it, and who to contact if you run into an issue.

If you are an organization administrator deciding which Agents to make available to your team, see Enable and Manage.

How Official Built-in Agents Work

Every official built-in Agent follows the same workflow: **you provide source material and requirements, it asks follow-up questions until the details are clear, and then it produces the result.**



The four-step workflow for official built-in Agents

1. Follow the Greeting to Enter Your Task or Upload Files

When you start a conversation, the Agent first sends a **greeting** explaining what it can help with and what you need to provide. Follow its instructions: type a description of your request or upload files, such as contracts, résumés, reports, or meeting recordings, depending on the Agent.

2. The Agent Offers Options and Recommendations to Clarify the Output

The Agent does not immediately start working as soon as it receives your material. It asks about key decisions—for example, “How many years of experience should these interview questions target?” or

“Should the report use bullets or prose?” —and **provides options directly**, so you can click one or add a short response.

At this stage, some Agents also **retrieve external information through connectors**, such as data from your calendar, cloud drive, or a third-party system. The first time a connector is used, an authorization card appears in the conversation for you to approve access. For the authorization process and for viewing or disconnecting services later, see Connected Services.

> Do not skip this step. The extra 30 seconds you spend answering clarification questions directly improves the accuracy of the output.

3. Generate a Draft

Once the details are confirmed, the Agent generates the result. You can continue asking for changes in the conversation—adjust the tone, add sections, or change the structure—without starting over.

4. Choose Whether to Export to a Specific File Format

When you are satisfied with the draft, ask the Agent to export it as a file. Supported formats vary by Agent and commonly include Word, Excel, PDF, and presentation files. The generated file appears in the conversation for you to download.

Choose an Agent from the Agent Marketplace

Open the Agent Marketplace

After signing in, select Agent Marketplace from the left sidebar.

Switch to the “Official Built-in” Tab

At the top of the marketplace, switch from the Organization-built tab to Official Built-in.

Search or Filter by Scenario Category

Search: Use the search bar at the top to search by Agent name, description, or scenario keyword

Scenario categories: Narrow the list using category tags such as Human Resources, Legal, Healthcare, or Manufacturing, or select All Scenarios to see everything



Agent Marketplace → Official Built-in: tabs and scenario categories appear at the top, with the enabled count in the upper-right corner; each card shows the model it uses beneath the name

Cards are divided into two sections:

Section	Meaning	Available on the Card
Enabled	Your organization has enabled the Agent, so you can use it immediately	Preview and Start Conversation
Not Enabled	Your organization has not enabled the Agent	Preview only; no Start Conversation option

The upper-right corner of the page shows the number of Agents currently Enabled by your organization and its limit. This allowance is managed by the organization administrator.

Understand the Model Shown on Each Card

Beneath each Agent's name, the card shows the language model the Agent uses, as a brand icon plus the model name (for example, `Claude 4.8 Opus`). An enabled Agent shows the model it is currently using; an Agent that is not enabled shows the model it will use once enabled. If the system cannot find an available model, this line displays Model Not Set.

Usage Scenario

A compliance manager wants the organization administrator to enable AML Suspicious Transaction Report Drafting, but company policy allows data to be shared only with internally approved models. She opens Agent Marketplace → Official Built-in and finds the card in the Not Enabled section, where the model it uses is shown beneath the name. After checking it against the approved list, she asks the administrator to enable it, without having to enable a trial first to find out.

When the Model Is Not Yet Available to Your Organization

If the model used by an Agent is not currently available to your organization, the card shows the following indicators:

An orange lock labeled Not Available appears in the upper-right corner of the card. Hover over it to see This model is not yet available to your organization. Please contact your organization administrator

The scenario category tag shrinks to a colored dot plus the category name

The model name beneath the Agent name turns gray



When the model is not available, the card shows “Not Available” in the upper-right corner and the model name turns gray

If a model is turned off after an Agent has been enabled, the card is likewise labeled Not Available.

Model availability is managed by the organization owner in Model Access Permissions. Until the model is available, organization administrators cannot enable this Agent in Built-in Agent Management.

Preview Before You Decide

Not sure what an Agent actually does? Select Preview (the eye icon) in the upper-right corner of its card. **You can preview it without enabling it.**

The window is titled Conversation × Guide Sync and plays two synchronized columns:

Left column: Replays one Example Scenario, from the greeting and the user's request through each step completed by the Agent

Right column—Guide • What This Step Does: As the conversation advances, the corresponding STEP 01, STEP 02, and so on is highlighted, explaining what happens and which capabilities are used

After playback finishes, the right column changes to Guide • Select Each Step for Details. Select any step to expand it, or choose Replay to watch again.

Two more details appear at the bottom of the window:

Connectors: The third-party services used by this Agent, such as Microsoft 365 or Google Workspace

Enablement status: Agents that are not enabled display Must Be Enabled by an Organization Administrator; enabled Agents offer Start Conversation



Preview window: the left column replays an example conversation while the right column highlights the corresponding guide step

Start a Conversation

Select Start Conversation on a card in the Enabled section to open a new conversation, then follow the four steps under How Official Built-in Agents Work.



Step 1: The greeting tells you exactly what to provide; use the paper clip in the lower-left corner to upload files



Step 2: The Agent asks follow-up questions using option cards; the upper-right corner shows how many questions remain



Step 3: After confirming the details, the Agent generates a structured draft

Scroll Back While a Response Is Generating

While an Agent is generating a long response, you can scroll up to review earlier content. The view stays where you scrolled and is not pulled along by newly generated text. When you scroll to a point **above the most recent question**, Back to Latest appears above the input box.

Usage Scenario

An HR specialist asks the Job Description Writing Agent to produce a complete job description. While the response is still generating, she wants to check whether the job title and department she provided earlier are correct, so she scrolls up. The view stays in place and does not jump when new text appears. After checking, she selects Back to Latest, the view returns to the position of the most recent question, and she keeps reading as the Agent finishes the rest.

How to Use It

1. Scroll Up

While the Agent is generating a response, scroll up with the mouse wheel, a touch gesture, or by dragging the scrollbar.

2. Read in Place

The view stays where you scrolled, and new content being generated does not change your position. When you scroll to a point above the most recent question, Back to Latest appears above the input box. If you are only scrolling down to read within the same long response, the pill does not appear.



The response is still generating (“Thinking about the reply” in the upper-right corner and “Stop Response” in the lower-right corner); after scrolling up, “Back to Latest” appears above the input box

3. Back to Latest

Select Back to Latest. The view returns to the position of the most recent question and resumes automatically following the latest content.

Return to Recently Used Agents

After you have **had a conversation with at least one official built-in Agent**, a Recently Used row appears at the top of the marketplace, ordered from most to least recent conversation. Select Continue Conversation to resume your previous work without browsing through the categories again.

> This row includes only Agents that are enabled and that you have personally used. It is normal for the row not to appear when you have just joined an organization and have not started using any Agents.

When an Official Built-in Agent Is Unavailable

These situations look similar but have different causes:

What You See	What It Means	What to Do
The Agent is in the Not Enabled section and has Preview but no Start Conversation option	Your organization has not enabled this Agent	Ask your organization administrator to enable it
The Agent is in the Enabled section but displays No Permission to Use	Your organization enabled it, but you are not in this Agent's Authorized Users list	Ask your organization administrator to add your role/group to the authorized users
Not Available appears in the upper-right corner of the card	The model used by this Agent is not currently available to your organization	Contact your organization administrator and ask the organization owner to turn on the model in Model Access Permissions (if MaiAgent has not yet enabled the model, contact MaiAgent)
The Official Built-in tab does not appear in the marketplace	Your plan does not include official built-in Agents	Contact the sales team to upgrade your plan. See Trial and Subscription Plans

> If a search returns no results, select Clear Search to view every Agent in the category, or select Clear Selected to remove the category filter.

If a category has no enabled Agents, it displays No Enabled Agents in This Category and a Request Enablement button. This button takes you to Built-in Agent Management, but an organization administrator with the required permission must still enable the Agent.

Enable and Manage

This page is for organization administrators. For instructions for general members, see Use Official Built-in Agents.

Open Built-in Agent Management

Go to Organization Settings → Built-in Agent Management.

You can also select Go to Built-in Agent Management in the Agent Marketplace to open it directly.

If Built-in Agent Management is not in the menu, your plan does not include official built-in Agents. The screen will display Built-in Agents cannot be enabled under the current plan. Please upgrade your plan. Contact the sales team to upgrade. If you can view the page but the switches are locked, you do not have permission to manage enablement. Contact your organization administrator.



Built-in Agent Management: enablement count and filters appear at the top; the capsule after each version shows the model in use, and enabled Agents display action icons and an enablement switch on the right

Each row shows the Agent's name, scenario category, version, the model in use (the capsule after the version; see Agents Cannot Be Enabled When Their Model Is Not Available), and current Authorized: {Role Name} setting. Deactivated Agents display Deactivated, Knowledge Base Retained, while Agents in cooldown display Cooldown: N Days Remaining.

Depending on the Agent's status, the right side of each row shows the following action icons and the enablement switch:

Icon	Purpose
Configure Authorized Users	Specify which roles/groups can use the Agent
Clear Knowledge Base	Delete all imported documents and FAQs (cannot be undone)
Import to Knowledge Base	Open the Agent's dedicated knowledge base to upload documents

Use the search box at the top to search by keyword. You can also filter by status—All
Enabled
Not Enabled
Knowledge Base Retained—or by scenario category.

> Select the row itself, rather than an icon, to open the Agent's Preview window. You can see how it works before deciding whether to enable it.

Enable or Deactivate: Select “Apply Changes” to Take Effect

> Changing a switch does not take effect immediately. All changes remain pending until you select Apply Changes at the bottom to submit them together.

Switch the Agents You Want to Enable or Deactivate

In the list, set the switch to Enabled or Deactivated. The row is then labeled Pending Enablement or Pending Deactivation.


Review the Change Summary at the Bottom

A fixed action bar appears at the bottom of the screen. When changes are pending, it shows the number Pending Enablement, the number Pending Deactivation, and the resulting number of Enabled Agents

versus the limit. It also reminds you that an Agent cannot be deactivated within 7 days of enablement. The Apply Changes button becomes available at this point.

Select “Apply Changes”

Select Apply Changes to submit everything at once. To discard the changes, select Cancel to restore all switches.



After a switch is turned off, the row is labeled “Pending Deactivation,” and the counts and cooldown reminder update in the action bar below

If an individual item fails after the changes are applied, the screen identifies the reason for each failure, such as reaching the limit, an active cooldown period, or insufficient permissions. Successful changes are unaffected.

Agents Cannot Be Enabled When Their Model Is Not Available

Every official built-in Agent runs on a language model. The capsule after the version on each row shows the model it uses: for an enabled Agent, the model currently in use; for an Agent that is not enabled, the

model it will use once enabled. This model must be available to your organization so that members can chat normally after the Agent is enabled, so check the model on the capsule before you enable an Agent.


Use Case

An organization administrator is preparing to enable AML Suspicious Transaction Report Drafting for the compliance team. In Organization Settings → Built-in Agent Management, the administrator finds the row and sees a white capsule after the version that reads `Claude 4.8 Opus`, which means the model is available to the organization. The administrator switches it to enabled, selects Apply Changes, and then configures authorized users. The compliance team can start chatting in the marketplace without discovering only during a conversation that the model is unavailable.

What the Screen Shows When the Model Is Not Available

If the model used by an Agent is not currently available to your organization, the management page shows the following:

Location	What You See
The model capsule on the row	It turns orange and the brand icon is replaced by a lock. Hover over it to see This model is not available to this organization. Enable it in Model Settings first.
The enablement switch of an Agent that is not enabled	The switch is locked and cannot be toggled. Hover over it to see the same message, This model is not available to this organization. Enable it in Model Settings first.
Top of the page	An orange banner appears: “The models used by **N Agents** are not available to this organization. Enable them before enabling these Agents:” followed by the names of the models to enable, with Go to Model Settings on the right



When the model is not available, the model capsule turns orange with a lock in place of the brand icon, and the enablement switch cannot be toggled

Select Go to Model Settings to open Model Access Permissions. After the organization owner enables the model, return to Built-in Agent Management and the switch can be turned on normally.

> The banner at the top counts only Agents in the current list that are not enabled and whose model is not available. The number changes when you search by keyword or filter by scenario category, but it is not affected when you change the status filter (Enabled
> Not Enabled
> Knowledge Base Retained). If a model shows Not Activated on the Model Access Permissions page, MaiAgent has not yet activated it for your organization. Your organization cannot enable it on its own; contact MaiAgent. When a switch is locked for more than one reason, only one is shown, in this order of priority: no enablement management permission → in cooldown → enablement limit reached → model not available.

When the Model of an Enabled Agent Is Turned Off

If the model used by an Agent is turned off after the Agent has been enabled, the model capsule on its row turns into an orange lock, but **the enablement switch is not locked**. You can still deactivate it under the normal rules, including the 7-day cooldown period. These Agents are not counted in the banner at the top of the page.

To restore it, ask the organization owner to enable the model again in Model Access Permissions.

Enablement Limit and Cooldown Period

Concurrent Enablement Limit

The Enabled Count at the top of the page shows how many slots are currently used and the maximum allowed. The limit depends on your plan. See Trial and Subscription Plans ・ Feature Differences.

When the limit is reached, switches for Agents that are not enabled are locked and display Enablement limit reached. Deactivate an Agent or upgrade your plan.

7-day Cooldown Period

Each time an Agent is enabled, it cannot be deactivated for 7 days. During this period, the list displays Cooldown: N Days Remaining, and the switch is locked with the message In cooldown. Can be deactivated in N days.

> The cooldown period restarts each time the Agent is enabled. If you deactivate and then re-enable it, you must wait another 7 days before deactivating it again. We recommend using Preview to confirm that an Agent is suitable before enabling it, because you cannot swap it out during the cooldown period.

When You Want to Downgrade Your Plan

> If the number of Agents currently enabled exceeds the new plan's limit, the system blocks the plan change. You must first deactivate enough Agents to meet the new plan's limit. Because deactivation is also subject to the 7-day cooldown period, allow time for the cooldown when planning a downgrade.

What Happens When You Deactivate an Agent

> Deactivation does more than hide the Agent. The system removes the Agent along with its conversation channels: The Agent disappears from the AI Assistants list, and members can no longer chat with it Its conversation channels, such as Web Chat, and group permissions are removed Its Agent schedules stop running Your imported knowledge base is retained, with the status Deactivated, Knowledge Base Retained

If you re-enable it later, the system creates **a new Agent** based on the latest official blueprint and **automatically reconnects the original knowledge base**, so you do not need to upload the documents again. However, conversations from before deactivation do not appear under the new Agent.

Configure Authorized Users

Enabling an Agent does not make it available to the entire organization. You must also specify which roles/groups can use it.

Select Configure Authorized Users on the Agent's row. In the drawer, select the roles/groups that can use it, then select Save.

Configured Agents display Authorized: {Role Name} in the list
Agents without authorized users display Not Yet Available



Select the roles/groups allowed to use this Agent in the drawer

If a member sees No Permission to Use on an enabled Agent in the Agent Marketplace, they have not been added to its authorized users. Return here and add them.

Import to the Dedicated Knowledge Base

You cannot change the role instructions or tools of an official built-in Agent, but **you can give it your organization's documents**. Every enabled Agent has a dedicated knowledge base.

Select Import to Knowledge Base on the Agent's row to open its knowledge base settings. From there, use it like any other knowledge base: upload documents, create FAQs, and configure tags. See Knowledge Base Overview.

For example, you could import your company's contract templates and review guidelines into a “Contract Risk Review” Agent, or internal administrative policies into an “Administrative Process Q&A” Agent, so its answers reflect your organization's actual rules.

Clear the Knowledge Base

Select Clear Knowledge Base on the Agent's row to delete its imported documents and FAQs.

This permanently deletes all imported documents and FAQs and cannot be undone. Before proceeding, make sure the documents and FAQs are backed up elsewhere. A confirmation window reminds you of the scope of deletion. If your backup is not complete, select Cancel to keep the existing content.



Before clearing, confirm that your documents and FAQs are backed up; select “Cancel” if you are not ready.

The outcome depends on the Agent's current status:

Agent Status	After Clearing
Enabled	Only the knowledge base **content** is deleted. The knowledge base itself remains connected to the Agent, and you can continue importing new documents
Deactivated, Knowledge Base Retained	**The entire knowledge base is deleted and disconnected**. Re-enabling the Agent later creates a new, empty knowledge base

Connectors: Which Ones You Need to Configure First

Some official built-in Agents must connect to third-party services, such as Google Workspace, Microsoft 365, or Notion, to retrieve data. Cards indicate one of two authorization types:

Label	Meaning	Who Takes Action
Administrator Must Configure Connection First	The connector uses organization-level credentials	An **organization administrator** completes the connection setup before members can use it
No label	Personal user authorization	**Each member** authorizes their own account in the conversation the first time the connector is used

> Administrator Must Configure Connection First does not mean that you must authorize every user. It is a one-time, organization-level setup. For connectors without this label, each member authorizes their own account, and the administrator does not need to be involved.

For more information, see Connectors.

AI Meeting Records

Meeting Records is the voice transcription and AI summary feature of the MaiAgent platform, offering both **live** and **offline** modes. Live mode provides low-latency transcription and translation during meetings; offline mode lets you upload audio recordings for high-accuracy transcription and speaker identification. Both modes support AI auto-summary, Q&A, download/export, and knowledge base integration.

Two Modes

	Live Meeting Records	Offline Meeting Records
Input Method	Real-time microphone recording	Upload audio files (mp3, mp4, m4a, aac, wav)
Transcription Features	Low-latency real-time transcription	Multi-language high-accuracy transcription
Translation	Low-latency real-time translation (up to 3 languages)	Post-transcription translation
Speaker Identification	Depends on STT engine support	High-accuracy speaker identification and management
Timeline	Real-time marking	High-accuracy timeline recognition
Subtitle Playback	—	Dynamic subtitle playback, synced with audio
Backup Audio	Synchronized local backup recording in the browser prevents audio loss during network outages (see Meeting Record Backup Audio)	—
Duration per Session	The main recording file is limited to 3 hours; the transcript and backup recording can continue until you press stop (see Recording Duration Limit)	—

Common Features

Feature	Description
Multi-language Transcription	Supports speech recognition in multiple languages
Multi-language Translation	Translates transcribed content into multiple target languages
Auto Summary	Automatically generates meeting highlights using a custom Agent
AI Q&A, Agent Ticket Creation	Ask questions about the transcript; if the selected Agent is configured with a ticket creation tool, you can ask it to turn meeting action items directly into tasks or tickets
Download & Export	Download MP3 recordings, plain text transcripts, and SRT subtitle files
Knowledge Base Integration	Upload transcripts to the knowledge base for Agent reference

Workflow

Live Mode:

```
Create Meeting → Configure STT Engine & Translation → Start Recording → Low-
latency Real-time Transcription
                                                  ↓
                                        Meeting Ends → Review Transcript
                                                  ↓
                                        AI Summary
 AI Q&A
 Download & Export
```

Offline Mode:

```
Upload Audio (mp3/mp4/m4a/aac/wav) → System Transcription & Speaker
Identification → Review Transcript
                                                        ↓
                                    Dynamic Subtitle Playback
 AI Summary
 AI Q&A
 Download & Export
```

Meeting List

Click Meeting Records in the left menu to open the meeting list. The toolbar at the top contains, from left to right:

Tool	Description
Date range	Filter by creation date
Search meeting name	Filter by keyword
All statuses	Filter by the five statuses below
Upload offline audio Live transcription	Create a new meeting record; see Offline Meeting Records and Live Meeting Records. The buttons are grayed out if you do not have transcription permission
Refresh	Reload the list

Actions on the right side of each row: View details opens the Meeting Record Details; Delete removes the meeting record after you confirm "Are you sure you want to delete this meeting record?". This cannot be undone and requires transcription permission.

Meeting Record Statuses

Status	Description
Pending (Pending)	Created or uploaded, processing has not started
Recording (Recording)	Transcription in progress in live mode
Processing (Processing)	After recording ends or audio upload, the system is processing
Completed (Completed)	Processing complete, transcript can be viewed and summaries generated
Failed (Failed)	An error occurred during processing; if offline transcription fails, you can upload the audio again

Deployment Options

Meeting Records supports multiple deployment options:

SaaS: Use the MaiAgent cloud service directly

Private Cloud: Deploy in the customer's cloud environment

On-Premises: Install on the customer's local servers

Permissions

Meeting Records requires organization-level activation before use, with three permission levels:

View Permission: Browse the meeting list, view transcripts, and download files

Transcription Permission: Create meetings, start recordings, upload audio files, edit and delete meeting records

Management Permission: Determines whether a user can see all meetings in the organization, or only meetings they participate in

The meeting list **only shows meetings you created or were added to** by default. For details on who can see which meetings and how to share meetings with colleagues, see Meeting Access Control.

Create Meeting Records

Create a New Meeting

Go to the "Meeting Records
Live Transcription" page

Fill in the following information:

Field	Description	Required
Meeting Name	The meeting title, to make it easy to search for and identify later	Yes
Participants	Select from organization members; added members automatically receive viewing access to this meeting	No
External Participants	Customers, vendors, and other people who are not organization members. Enter a name and press Enter. They are recorded only in the meeting information and do not receive viewing access. See Meeting Access Control for details	No
Speech Recognition Provider	Select the speech-to-text (STT) engine	Yes
Language	The languages used in the meeting (up to 3)	Yes

Select a Speech Recognition Provider

The system provides STT (Speech-to-Text) engines from multiple providers, each with different language support and recognition quality:

Engine	Features
Deepgram	High-quality real-time transcription, supports multiple languages
Azure	Microsoft speech services, excellent Chinese and English recognition
AssemblyAI	High accuracy, ideal for English scenarios
WhisperLive	Based on OpenAI Whisper, supports a wide range of languages
Bronci	Customized engine

Engine	Features
OpenAI gpt-live-transcribe	OpenAI's real-time transcription model; choose one recognition language per meeting (auto-detect, Traditional Chinese, Simplified Chinese, English, Japanese, or Korean). See below for details

Different engines support different languages and numbers of languages. After you select an engine, the system automatically displays the available language list.

OpenAI gpt-live-transcribe

Only one recognition language can be selected. If multiple languages will be mixed during the meeting, choose auto-detect. If you choose Traditional Chinese, the transcript is output in Traditional Chinese.

Speaker diarization: The real-time transcript from this engine does not include word-level timestamps, so it cannot be combined with speaker diarization. For meetings that need to distinguish speakers, choose a different engine.

Final result after the meeting ends: After you stop recording, the system reports the final transcription result for the meeting and reloads the saved transcript. See Live Meeting Records: After Recording Ends.

The engine list is enabled by the platform. If this option does not appear in the list, contact your MaiAgent representative.

Configure Live Translation (Optional)

If participants use different languages, you can enable live translation:

Turn on the "Enable Translation" toggle

Select the target translation languages (up to 3)

Select the LLM model to use for translation

Translation runs at the same time as transcription, and the transcript displays both the original text and the translation.

Link a Knowledge Base (Optional)

You can specify a knowledge base to link when you create the meeting. After the meeting ends, you can upload the transcript to the knowledge base with one click, so that the Agent can reference the meeting content.

Manage Meeting Records

On the meeting list page, you can:

Search: Search by meeting name

Filter: Filter by status (Pending, Recording, Processing, Completed, Failed)

Date Range: View meetings within a specified time range

Edit: Modify the meeting name, language settings, translation settings, and knowledge base link

Delete: Remove meeting records you no longer need

Live Meeting Transcription

Live mode provides low-latency voice transcription and translation, allowing you to see the real-time transcript while the meeting is in progress.

Start Recording

After creating a meeting record, click "Start Recording" to begin live transcription. When you click it, the system first checks the microphone. If permission has not been granted, no microphone is found, the microphone is in use by another program (such as video conferencing software), or the browser is not supported (use the latest Chrome, Edge, or Safari, and the URL must be https), a corresponding message and a "Retry" button are shown. Resolve the issue and start again; no empty recording is created.

The system will:

Create a real-time communication room (LiveKit)

Start the speech recognition engine

Begin receiving microphone audio and transcribing in real time

Transcription View

While recording, the screen displays the following in real time:

Recording timer: Shows the elapsed recording time

Live transcript: Speech recognition results appear on the screen in real time

Speaker labels: Identify the speaker of each segment of text

Language tags: Show the original language of each segment of text

Translation results: If translation is enabled, the translated text is shown below the original text

Transcription statistics: Number of completed segments, number of segments in progress, and total word count

Local backup status: "Recording local backup" is shown below the meeting name, meaning the browser is simultaneously recording a backup audio file so that no audio is lost even if the network disconnects. See Meeting Record Backup Audio

If any of the following alerts appear during recording, the recording is still running and you do not need to start over:

Alert	Meaning	What to do
Connection unstable, reconnecting…	The connection to the transcription service was interrupted and the system is reconnecting; speech during reconnection may not be transcribed	Check your network. If the connection cannot be restored, the system shows a recording interruption alert instead; if local backup is enabled, you can retranscribe using the backup audio afterward
Transcription failed: transcription failure detected at recording time HH:MM:SS	Transcription failed for one segment of speech	The completed transcript is kept; if the transcript has gaps afterward, you can retranscribe the entire meeting using the backup audio

You Can Switch to Other Pages While Recording

Recording does not stop when you leave the live transcription page. After you switch to another page in the admin console (for example, to look something up in MaiGPT), a flashing red-dot recording indicator floats in the upper-right corner of the screen, showing the current recording time and the meeting name. Hover over it to see "Click to view recording," and click it to return to the live transcription page. You can drag the indicator to a position that does not block the screen, and the position is remembered.

> Recording takes place only within this browser tab. When you close the tab or refresh the page, the browser asks for confirmation first; if you close it anyway, the recording ends and moves to post-processing. To step away temporarily, switch pages instead of closing the tab.

Low-Latency Live Transcription

The core feature of live mode is low latency: transcribed text appears on the screen within seconds of being spoken, so participants can confirm the content of the record in real time.

Low-Latency Live Translation

When translation is enabled, the system translates the content into the specified target languages while transcribing, also with low-latency real-time processing:

Supports translating into up to **3 target languages** at the same time

Translation is processed in real time by the selected LLM model

Translation results are attached below each segment of the transcript

Suited to international meetings and real-time communication among multilingual teams

Recording Duration Limit

Each live recording has a **main recording file limit of 3 hours**. Before you start recording, a notice above the settings area tells you about this limit. When the recording reaches 3 hours:

Item	After reaching 3 hours
Main recording file (original cloud audio)	Stops at the 3-hour mark and is uploaded as usual
Live transcript	Continues transcribing until you click Stop Recording
Local backup audio	Continues recording until you click Stop Recording, so the backup audio is complete

The system reminds you as the limit approaches:

About 10 minutes remaining: A warning appears saying "The main recording will reach the 3-hour limit in about N minutes." If you have allowed browser notifications, you also receive a notification when the tab is not in the foreground

Limit reached: A notice appears saying "The main recording has reached the 3-hour limit," explaining that the main recording file has stopped while the transcript and backup recording are still running. When the meeting ends, return to the page and click Stop Recording as usual

Anything beyond 3 hours is not included in the main recording file. After the meeting ends, a banner appears at the top of the details page saying "The main recording has reached the 3-hour limit; the main audio file ends here," along with a shortcut to Retranscribe with backup audio. Retranscribing with the backup audio gives you a transcript covering the entire meeting. For the steps, see Retranscribe from Backup Audio.

> For meetings expected to run longer than 3 hours, we recommend clicking Stop Recording during a break and creating a new meeting record to continue, then generating a summary for each one separately. Alternatively, record as usual and retranscribe once with the backup audio afterward (retranscription is billed by audio duration).

Controls

Action	Description
Microphone toggle	Temporarily mute or unmute the microphone

Action	Description
Stop Recording	End the meeting recording; the system starts post-processing
Search transcript	Search for keywords in the live transcript
Add remove external participants	Non-organization members who join temporarily, such as customers and vendors, can be added or removed at any time in the "External Participants" section of the participant card on the right, without interrupting the recording. See Meeting Access Control

After Recording Ends

After you click "Stop Recording," the meeting status changes to "Processing," and the system works in the background:

Audio conversion: Converts the original audio to MP3 format

Transcript organization: Organizes the live transcription results into a structured transcript file

Save to cloud: Uploads the audio and transcript to S3 storage

When processing is complete, the status updates automatically to "Completed," and you can open the meeting details page to view the full content. The local backup audio is uploaded and merged in the background; when finished, the details page shows "Backup complete." See Meeting Record Backup Audio.


Final Transcription Result (OpenAI gpt-live-transcribe)

For meetings whose speech recognition provider is OpenAI gpt-live-transcribe, after you stop recording the system separately reports the final transcription result for that meeting, and the page reloads the saved transcript, replacing the temporary text shown during recording.

Until the report is received, the page shows "The final transcription result for this meeting has not been received yet; recording completion does not mean transcription succeeded. You can refresh to check again." In that case, wait a moment and refresh the page; the final result is authoritative. Meetings using other engines do not have this report, and the transcript is whatever it contains once processing is complete.

Quick Access to Meeting Records

In the **Office Apps** section on the MaiGPT home page, select Meeting Records to start recording immediately or continue viewing an existing meeting under **Recent Records**.



The Meeting Records quick access panel lets you start recording, connect your calendar, and view recent records

Use Case

After a regular project meeting, a project manager wants to check in MaiGPT whether a summary has been generated. She opens Meeting Records, selects the meeting under **Recent Records**, and checks the summary status in the panel. When finished, she selects Back to Entry to return to the start recording screen. If she needs the transcript or other complete details, she can select the button on the right side of the record to open the full record page. This leaves the MaiGPT chat page; after reviewing the record, she can return to MaiGPT from the sidebar.

View Recent Records

1. Open the Quick Access Panel


On the MaiGPT home page, select Meeting Records.

2. Select a Meeting

Under **Recent Records**, select a meeting to view its summary or summary status directly in the panel.

3. Return to the Entry Screen

On the summary screen, select Back to Entry to return to the calendar and start recording screen.



After selecting a recent record, you can view the summary status and return to the entry screen

4. Open the Full Record

When you need the transcript or other complete details, hover over the button on the right side of the record, and select it when the "View full record" tooltip appears to open the full record page for that meeting. This leaves the MaiGPT chat page; after reviewing the record, select MaiGPT from the sidebar to return.

After Recording: Bring the Summary into the Chat

After you finish recording a meeting in the quick access panel, the panel shows a "Recording completed" card asking whether you want the AI to generate a meeting summary. After you select Generate Summary, the summary appears directly in the card, with two buttons below it:

Open Full Page: Opens the full record page for this meeting.

Bring into Chat: Places the summary into the MaiGPT input box, so you can then ask the AI to list to-dos from the summary, draft a follow-up email, or ask further questions.

If you don't need a summary, select Later. You can still generate one later on the full record page. See AI Summary.

Recent Record Statuses

Status Shown	Meaning	Recommended Action
Generating	The meeting is still being transcribed, processed, or summarized	Reopen the quick access panel later to check the latest status
Generation failed	Transcription or summary generation failed for the meeting	Go to the full meeting record to check the failure status
No summary yet	The meeting is complete, but there is no summary to display yet	Go to the full meeting record to generate or view the summary

> If Recent Records shows "No meeting records yet," complete a meeting record first, then return to this panel to view it.

For complete instructions on recording, transcription, and summaries, see Create a Meeting Record, Live Meeting Transcription, and AI Meeting Summary and Q&A.

Backup Audio for Meeting Records

Live meeting records send microphone audio over the network for cloud transcription. Previously, if a laptop lost its connection during a meeting, audio from the disconnected period could not be sent, leaving a gap in both the cloud recording and the transcript. **Backup audio** fills this gap: when recording starts, the browser also records a local backup and uploads it in segments as it goes. Even if the network disconnects, local recording continues, and the segments upload automatically when the connection is restored. After the meeting, the system combines all segments into a complete backup audio file—this backup is always the most complete recording in the system.

> Backup audio is created only for live meeting records (recorded with a microphone). Meetings created through "offline audio upload" already have a complete file and do not generate backup audio.

Use Case

A customer service manager uses a laptop in a conference room to record a weekly product meeting with Live Transcription. Halfway through, the room's Wi-Fi becomes unstable. The transcript on screen stops updating, but "Recording local backup" is still shown below the title, so she knows no audio is being lost and carries on with the meeting as usual. After clicking "Stop Recording," she sees the "Backup complete" label on the meeting details page and switches the player to "Backup Audio" to confirm that everything said during the outage is there. She then clicks "Retranscribe," changes the transcription source to "Backup Audio," reviews the estimated cost, and confirms. A few minutes later, a backup version appears in the Transcript tab, where she can see the complete meeting content without asking colleagues to reconstruct the missing part from memory.

Backup Status During Recording

After you click Start Recording, the backup status appears below the meeting name:

Display Text	Meaning
Recording local backup	Cloud recording and local backup are running simultaneously; everything is working normally
Syncing backup, N segments not yet synced	The network is unstable or disconnected. Recorded segments are queued locally and upload automatically when the connection is restored; no action is required
Local backup unavailable (reason); meeting continues	Backup could not be enabled this time (for example, the browser is unsupported, browser storage is unavailable, or another tab is already recording). The meeting

Display Text	Meaning
normally	and cloud recording are unaffected



During recording, the local backup status appears below the meeting name

- Backup recording runs in the browser. Keep the entire meeting open in the same browser tab. Only one tab can record a given meeting; a second tab displays "Recording in another tab." - When you mute by clicking the microphone icon button to the left of "Stop Recording," the same section of the backup audio is also muted, so content you do not want recorded is not captured. - The total amount of local backup data awaiting upload is limited to 1 GB. Once the limit is reached, you cannot start a new backup recording. - The main recording is limited to 3 hours per meeting. When the limit is reached, the main recording stops, but the backup recording and transcript continue until you click "Stop Recording." The portion beyond 3 hours exists only in the backup audio, and you can retranscribe it to recover that portion. For details, see Live Meeting Records: Recording Duration Limit.

Backup Status After the Meeting


After you click Stop Recording, the meeting status first changes to "Completed." Backup audio has its own sync status, displayed next to the title on the meeting details page:

Status	Meaning
Backup complete	The meeting is complete and the backup audio is fully synchronized—this backup is the most complete recording in the system
Syncing backup	The meeting is complete, but the local backup audio is still uploading and being merged. The status changes to "Backup complete" automatically when finished
Backup incomplete	The backup has still not finished syncing after more than 1 day. The system combines the segments already uploaded into a backup audio file (missing the final segments)



Meeting details page: the "Backup complete" label beside the title and the audio source switch in the recording section

In the meeting list, meetings whose backups are not yet finalized display an extra icon beside the status column. Hover over it to see a description. Meetings with completed backups have no additional indicator.



Meeting list: the "Syncing backup" icon beside the status column

> What if I close the browser right after losing the network connection? Segments that have not been uploaded remain on the local device. If you open the MaiAgent admin console again within 1 day, the system automatically takes over and resumes uploading, and the meeting displays "Syncing backup" in the meantime. If you do not return within 1 day, the system combines the portions already uploaded and labels the backup "Backup incomplete."

Switch to Backup Audio for Playback

For a meeting with backup audio, an Original Audio
Backup Audio switch appears above the player in the "Recording" section on the left side of the details page. This switch affects **playback only**: meeting summaries, AI Q&A, knowledge base uploads, and MP3 downloads continue to use the original recording (unless you select a different transcript source when generating a summary, as described below).

Retranscribe Using Backup Audio


If the original transcript is missing a section because of a network outage, you can retranscribe the backup audio to create a new transcript version. The existing transcript is retained.

Open Retranscription

Open the meeting details page and click Retranscribe in the upper-right corner.

Select "Backup Audio" and Confirm the Cost

Under Transcription Source, select Backup Audio. Billing information appears at the bottom of the dialog, including the billable item (audio transcription), the backup audio duration, and the estimated cost. It also states that "you are charged only if transcription succeeds; failed attempts are free" and that "every retranscription is billed again."



After you select "Backup Audio" as the transcription source, the dialog discloses the estimated cost and billing rules

Submit the Transcription

Click Confirm audio transcription (approx. X credits)—the button shows the estimated charge directly. After submission, the screen displays "Transcription started; you are charged only if it succeeds," and a "Processing" entry appears under "Retranscription History" at the bottom of the dialog.

View the Backup Transcript Version

After transcription is complete, a version labeled "Backup" appears in the version menu on the Transcript tab (for example, "Azure • 09/06 00:42 • Backup"). When you select it, the player **automatically switches to the backup audio**, so that clicking the transcript jumps to the correct timestamp.




Version menu on the Transcript tab: the original transcript and the backup version

- The backup transcript aligns only with the backup audio. If you manually switch the player back to "Original Audio" while viewing the backup version, the screen warns: "The transcript and the audio being played come from different recordings. Clicking the transcript cannot jump precisely to that sentence." - If the organization wallet balance is insufficient, the "Backup Audio" option is disabled and displays "Insufficient wallet balance. Please add funds first." No transcription job is created, and no charge is made. - If the system detects that the end of the original transcript may be missing, a "The end of the transcript may be missing approximately N minutes" notice appears at the top of the Transcript tab, with a Retranscribe using backup audio shortcut. - For meetings whose main recording stopped because it reached the 3-hour limit, a banner appears at the top of the details page: "The main recording reached the 3-hour limit; the main audio ends here." It also provides a Retranscribe using backup audio shortcut, and the banner indicates whether the backup audio is complete and how long it is.

Generate a Summary from a Backup Transcript

When you click Generate Summary on the Meeting Summary tab, Transcript Source at the top of the dialog defaults to "Original Transcript." If a backup version is available, you can select it instead so that the summary covers the recovered sections. When you select a backup version, the dialog displays: "The backup transcript timeline corresponds to the backup audio and differs from the original audio."



You can select a transcript source when generating a summary

Further Reading

Live Meeting Records: Start recording and the recording screen

Meeting Record Details: Transcript, player, and meeting information

AI Meeting Summary & Q&A: Generate summaries and manage summary versions

Offline Meeting Transcription

Offline mode lets you upload pre-recorded audio files. The system performs high-accuracy transcription and speaker identification, and generates a transcript with a timeline.

Supported Audio Formats

Format	Extension
WAV	`.wav`
MP3	`.mp3`
M4A	`.m4a`
AAC	`.aac`

The file picker lists only these four formats. For video files (such as `.mp4`), convert them to one of the audio formats above before uploading.

Upload Audio

Go to the Meeting Records page and click Upload Offline Audio in the upper-right corner (transcription permission is required; otherwise the button is grayed out with the message "You do not have permission to upload audio files for transcription").

Fill in the following under "Transcription Settings":

Field	Description
Meeting Name	Required. You can change it later on the detail page
Offline Transcription Provider	Required. The list depends on the providers enabled for your organization. If "No offline transcription providers are currently available" is displayed, contact your administrator
Language	Required. Multiple selections are allowed; select every language that will be spoken in the meeting for better recognition accuracy
Speaker Identification	When enabled, the completed transcript distinguishes between different speakers; when disabled, the system determines the audio tracks automatically. If the selected provider does not support it, the message "The selected ASR model does not support speaker identification" is displayed and the switch is unavailable

Field	Description
Provider advanced options	Some providers offer additional parameters (marked "Optional"). If you are unsure, leave them blank

In the Audio File section, click or drag your file into it ("Click or drag an audio file here to select"). If the format is not supported, the message "This audio file format is not supported" is displayed.

Click Start Transcription. The screen first displays "Uploading audio file", and after the upload completes it shows "Audio file uploaded. Transcription in progress."

After the upload, the meeting record status changes to "Processing" and the system transcribes in the background; you can leave this page and work on other tasks. If transcription fails, the detail page displays "Audio transcription could not be completed. Please upload again or try again later." Simply upload the file again.

Multi-language High-accuracy Transcription

Offline mode uses a high-accuracy speech recognition engine (such as WhisperX), which provides higher recognition accuracy than live mode:

Supports multi-language recognition

Higher recognition accuracy than live transcription

Ideal for important meetings that require precise records

Speaker Identification and Management

Offline mode supports automatic Speaker Diarization, in which the system automatically distinguishes between different speakers:

Auto Identification: The system automatically labels different speakers (e.g., SPEAKER_00, SPEAKER_01)

Custom Names: Replace system labels with real names (e.g., "Manager Zhang", "Team Lead Li")

Management Interface: Manage the label names of all speakers in one place

After you change a speaker label, all related segments in the transcript are updated accordingly.

High-accuracy Timeline Recognition

Each transcribed text segment includes precise start and end times, so you can:

Pinpoint the exact time of each utterance

Jump in sync with the audio player

Export as SRT subtitle files with timestamps

Dynamic Subtitle Playback

Offline mode provides dynamic subtitles that sync the audio player with the transcript:

Sync Highlighting: During audio playback, the transcript segment currently being played is automatically highlighted

Click to Jump: Click any transcript segment, and the audio automatically jumps to the corresponding time point

Search and Navigate: After searching for a keyword, you can jump directly to the audio position of that segment

This feature lets you quickly find specific discussions in a meeting without listening to the entire recording from the beginning.

Meeting Record Details

After a meeting recording has been processed, you can view the full meeting content on the detail page.

Page Structure

Area	Content
Title bar	Back, the meeting name and status, and the creation time; on the right, in order: the backup sync badge, Re-transcribe, and Download
Left sidebar	Audio player (for live meetings with backup audio, you can switch between "Original Audio Backup Audio" above the player; see Meeting Record Backup Audio), basic information, participants, and external participants
Right content area	Three tabs: Transcript, Meeting Summary, and AI Q&A

Title Bar

Edit the Meeting Name

Next to the meeting name is a pencil icon (Edit Meeting Record). Click it, change the Meeting Name (required, up to 255 characters), and save. Once saved, the title and the meeting list are updated together. Only members with transcription permission can see this button. For permission details, see Permissions.

Re-transcribe and Download

Re-transcribe: Transcribe again with a different audio source (original backup) or a different provider. See Re-transcribe from Backup Audio

Download: The dropdown menu offers Download SRT Subtitles and Download MP3 Audio. See Download and Knowledge Base Integration

Transcript Tab

At the top of the tab, you can switch between Transcript (timeline format) and Plain Text. The Copy button next to them copies the entire version currently displayed to the clipboard. The timeline format shows:

Timestamps: The start time of each text segment

Speaker Names: Indicate who is speaking

Language Tags: Labels for the original language

Translation Content: If translation is enabled, the translation results are displayed

Keyword Search: Search for specific content in the transcript

If the transcript is shorter than the audio file, a notice at the top of the tab shows how many minutes are missing at the end and offers a shortcut to re-transcribe from the backup audio. See Meeting Record Backup Audio.

Plain Text

Switch to Plain Text to show the transcript as plain text without timestamps, which makes it easy to read and copy the full meeting content. Keyword search is also supported.

Meeting Summary Tab

To generate a summary, switch versions, edit, copy, export, and read aloud, see AI Meeting Summary and Q&A.

AI Q&A Tab

Ask questions about the transcript, or ask the Agent to turn action items into tickets. If the transcript has not yet been added to a knowledge base, you can choose a knowledge base in this tab and click Upload Transcript. See AI Q&A and Download and Knowledge Base Integration.

Meeting Info Sidebar

The left sidebar displays:

Basic Information: Meeting date, meeting time, meeting duration, speech recognition provider

Participants: The access list for this meeting (the creator is labeled as the host). You can add or remove members. See Meeting Access Control for details

External Participants: Names of attendees who are not organization members. You can add or remove them. This is a text-only list and does not grant access. See External Participants for details

Meeting Access Permissions

Meeting content often involves sensitive information, so the meeting list **does not show all meetings in the organization**. By default, each member can only see meetings they are involved in; to share a meeting with colleagues, grant access through the "Participants" roster within the meeting.

Who Can See Which Meetings

Identity	Visible Scope in Meeting List
Regular Member	Only meetings they created + meetings they were added to as a participant
Organization Owner	All meetings in the organization
Member with "Meeting Record Management Permission"	All meetings in the organization

Meetings without access permission will display a "meeting not found" message even when accessed directly via URL — the system will not reveal its existence.



Meeting list: The "Participants" column shows the access roster for each meeting

> The person who created the meeting automatically becomes the host and can always see the meetings they created.

Participants: The Meeting Access Roster

The "Participants" card on the right side of the meeting detail page is the **access roster** for that meeting — only people on the roster can see the meeting.

會議日期
2026/08/17

會議時間
18:29

會議時長
54 分鐘 5 秒

語音識別供應商
-

參與者 (3)

陳 陳文彬 主持人

王 王志明

林 林佳蓉

逐字稿講者 (3)

陳文彬 林佳蓉 王志明

Participants card: Host label, member list, add participant button

Card contents:

Host: The meeting creator, with a host label next to their name

Members: Organization members who have been added

External Participants (bottom of card): Names of attendees who are not organization members; this is **a text-only roster and does not represent access permissions**. See External Participants for details

The "Participants" column in the meeting list also displays this roster, showing `+N` when there are more than 2 people.

> "Participants" and "External Participants" are two different things. External participants are recorded by name only and cannot access the meeting; to grant viewing access, you must add an organization member to the participants roster.

Who Can View and Who Can Edit the Roster

Action	Condition
View participants roster	Anyone who can see the meeting
Add Remove participants	Organization Owner, member with "Meeting Record Management Permission", or **any participant already on the roster**

Add a Participant

1. Open the meeting detail page

Click on the meeting you want to share in the meeting list.

2. Click the "+" in the upper right corner of the participants card

The card will expand a member selection dropdown.

3. Select an organization member and click "Add"

會議日期

2026/08/17

會議時間

18:29

會議時長

54 分鐘 5 秒

語音識別供應商

-

參與者 (3)

選擇成員

黃郁婷（huang.yut...

許珮琪（xu.peiqi@...

陳 陳文彬 主持人

王 王志明

林 林佳蓉



Select the person to add from organization members

The dropdown only lists members from the **same organization**, with keyword search available

Members already on the roster will not appear in the dropdown

After successfully adding, the person can **immediately** see the meeting in their meeting list

Remove a Participant

Click the "X" on the right side of the member in the participants roster and confirm to remove them. The person immediately loses viewing access to the meeting.

> The host cannot be removed. The meeting creator's row does not have a remove button, ensuring the meeting always has at least one person who can manage it.

External Participants: Record Non-Organization Members

Attendees such as customers, vendors, and consultants who are **not organization members** cannot be added to the "Participants" roster, but you can record them under "External Participants." External participants are **a text-only roster**: their names are recorded in the meeting information to provide a complete attendee list, but they **do not receive viewing access or notifications and do not need an account**.

Use Case

A sales manager is holding a product onboarding meeting with two colleagues from her team and two customer contacts. She opens "Live Transcription" and selects the two colleagues under "Participants" so they can view the transcript after the meeting. She then enters the customer contacts' names and company under "External Participants." Halfway through the meeting, the customer's technical manager

joins unexpectedly. She clicks "+" in the "External Participants" section on the right and adds the manager's name without interrupting the recording. After the meeting, the Participants card on the meeting detail page clearly separates the two groups: colleagues appear under "Participants," while customers appear under "External Participants." The full attendee list is easy to review, while the customers still cannot access the meeting content.

Record Participants When Creating a Meeting

In the "Live Transcription" setup form, the "External Participants" field appears below "Participants." Enter a name and press Enter to turn it into a tag. You can add multiple names in succession. When recording starts, the roster is created along with the meeting.



"Participants" only lets you select organization members and grants them viewing access; "External Participants" lets you freely enter names that are recorded only in the meeting information

> The "External Participants" field is currently available in the Live Transcription setup form. It is not available in the offline audio upload form or the edit dialog in the meeting list. For offline meetings or names added afterward, use the sidebar on the meeting detail page (see the next section).

Add or Remove Participants in the Sidebar During or After Recording

The Participants card on the right side of both the Live Transcription page (while recording) and the meeting detail page (after the meeting) includes an "External Participants" section. You can add or remove names at any time:

1. Add

Click "+" next to "External Participants," enter a name, and press Enter or click "Add." The roster updates immediately after it is saved and remains current after you leave, return to, or refresh the page.

2. Remove

Click the "X" next to a name to remove it. No confirmation dialog appears; if you remove someone by mistake, you can add the name again immediately.



The sidebar has two sections: "Participants" are organization members with viewing access, while "External Participants" are a text-only roster

Anyone who can add or remove external participants has the same permissions as someone who can edit the meeting: members with "Transcription Permission" who can view the meeting. Other users can only view the roster

If saving fails, the page displays "Failed to update external participants." The roster remains unchanged, and recording is not affected

Roster Rules

Rule	Description
Maximum number	Up to 20 people per meeting. Once the limit is reached, no more names can be added and a notification appears
Name length	Up to 50 characters per person. If the name is too long, a notification appears and the name is not automatically truncated
Duplicate names	Identical names are treated as the same person and merged automatically
Whitespace	Empty input or input containing only spaces is not added to the roster

These rules apply consistently to the setup form, the sidebar during recording, and the sidebar after the meeting.

> Meetings started from a calendar invitation (for example, starting a recording after connecting a calendar in the MaiGPT meeting record shortcut panel) automatically import the invitee list. Invitees who are organization members become "Participants" and receive viewing access, while everyone else is recorded as an "External Participant." You can still adjust the roster afterward in the sidebar.

Grant "See All Meetings" Access

For scenarios like auditing, handover, or department managers who need an overview of all meetings in the organization, grant access through role permissions:

1. Go to the Role Permission page in Organization Settings

See Role Permission Management.

2. Edit role permissions and check "Meeting Record Management Permission"



Check "Meeting Record Management Permission" to allow role members to see all meetings in the organization

"Meeting Record Management Permission" is located at the bottom of the permission list and is an independent main permission:

Unchecked: Role members can only see meetings they participate in (created or added to)

Checked: Role members can see all meetings in the organization

When checking "Meeting Record Permission", the system will **automatically check** this permission as well; if you only want the role to see their own meetings, manually uncheck it

> Members with "Meeting Record Management Permission" who only want to view their own meetings can filter using the API parameter ?scope=mine.

FAQ

A colleague says they can't see a meeting I created?

Add them to the meeting's participants roster — it takes effect immediately.

How do I record customers or vendors who attend a meeting?

Add their names under "External Participants." This is only a roster and does not let them access the meeting content. If the person is an organization member, add them to the "Participants" roster instead to grant viewing access.

After unchecking "Meeting Record Management Permission", can I still see old meetings?

You can only see meetings you created and meetings where you were added to the participants roster. Meetings created by others that you were not added to will disappear from the list — if needed, ask a participant of that meeting to add you.

AI Meeting Summaries and Q&A

Meeting summaries are processed in the background, so you don't have to stay on the summary page and wait for long meetings. You can leave the page while a summary is being generated and come back later to check progress. When processing finishes, the summary is created as a new version.

Use Case

A project manager has just finished a long quarterly meeting and wants to organize the decisions before the end of the day. She goes to the Meeting Summary tab for that meeting and starts generating a summary with the default template. After seeing that the system is analyzing the transcript, she leaves the page to work on something else. When she returns to the same meeting later, the screen continues to show the progress. Once processing is complete, she can review the decisions and to-dos in the newly created summary version.

Custom Summary Agent

The summary feature for meeting records lets you choose a custom Agent to generate summaries. Different Agents can have different role instructions and produce summaries in different styles:

General Summary Agent: Organizes key points, decisions, and to-dos from the meeting

Technical Meeting Agent: Focuses on technical decisions, architecture discussions, and technical debt items

Business Meeting Agent: Focuses on customer needs, sales progress, and opportunity tracking

Generate a Summary

Go to the meeting details page

Switch to the Meeting Summary tab

Click Generate Summary, and in the dialog that appears, configure how to summarize this time (you can leave everything at the defaults)

Click Start Generating

Fields in the "Generate Summary" Dialog

Field	Description
Transcript Source	Use this meeting's own transcript. If a backup transcript is available, you can switch to the backup version. The two have different timelines; see Meeting Record Backup Audio
Summary Agent	Leave empty to use the default template. To customize the style, select an Agent (see Custom Summary Agent below). Once an Agent is selected, the next two fields switch to using that Agent's own model and prompt
Language Model	The model the default template uses to generate the summary. Leave empty to use the default model. If the list fails to load, the message "Failed to load the language model list. The default model will be used for generation" appears
Summary Instructions	Optional. Additional requirements for the default template, such as focusing on a specific topic or specifying an output format. Three examples below can be applied with one click: Meeting Minutes (bulleted key points, discussions, and decisions, with owners and deadlines noted), Action Items (only to-dos, including owners, deadlines, and resources), and Executive Summary (an executive summary of 300 words or fewer)

The AI organizes the key points, decisions, and to-dos of the meeting based on the full transcript. When using the default template, the screen shows Analyzing transcript N/M followed by the status of consolidating the summary, where N is the number of completed segments and M is the total number of segments. When a custom Agent is selected, the Agent processes the transcript directly and no segment N/M progress is shown.

Whether you use the default template or a custom Agent, you can leave the page and the work continues in the background. When you refresh or return to this meeting later, the system continues to show the current status.



After leaving the page and coming back, you can still see the segment progress of the default template



After the summary is complete, the new version appears in the version list

> When a summary is complete, a new version is created automatically and you don't need to save it separately. If generation fails, the screen prompts you to retry. After confirming that the transcript is available, click Regenerate again.

Summary Version Management

Each time a summary is generated or edited, the system keeps a complete version history:

Add a summary: Each time you generate a summary, a new version is created

Edit a summary: You can modify the content of an existing summary

Version history: View all summary versions and when they were created

Delete a summary: Remove summary versions you no longer need

Copy a Summary

When viewing a saved summary, a Copy Summary button appears in the toolbar above the summary. One click copies the entire summary to the clipboard, so you don't have to drag to select the full text manually, which makes it easy to paste into an email, document, or messaging app.

Go to the meeting details page and switch to the "Meeting Summary" tab

Select a saved summary

Click Copy Summary

After the "Copied successfully" message appears, paste it into another application



The toolbar of the "Meeting Summary" tab

The copied content is the raw text of the summary, and the original paragraph structure is preserved.

> Copy Summary is available only when viewing a saved summary. It does not appear in the toolbar when you are editing a summary or previewing an unsaved draft. When the summary is empty, the button is disabled.

If the screen shows "Copy failed," it is usually because the browser blocked clipboard permission. Please select and copy the text manually instead.

Export a Summary and Send by Email

To save a summary as a file or send it directly, use the Export dropdown next to Copy Summary:

Option	What You Get
Export as Markdown	An `.md` file that keeps headings, bullet lists, and other formatting; suitable for pasting into tools that support Markdown, such as Notion and GitHub
Export as PDF	A PDF whose layout matches the screen; suitable for forwarding or archiving as is
Export as docx	A Word file; suitable when you need to edit it further
Export as Plain Text	A `.txt` file without any formatting symbols

Option	What You Get
Send Email	Opens the email app on your computer, with the subject "{Meeting Name} Meeting Summary" and the summary filled in as the body; enter the recipient yourself. If the summary is too long to fit in an email, the body includes the note "(Content too long. Please use Export for the full summary)"; in that case, use the export options above and attach the file instead

The export applies to **the version you are currently viewing**. The file is downloaded by the browser, and "Export successful" appears when it finishes. Downloading transcripts and audio files is done from the title bar of the details page; see Download and Knowledge Base Integration.

Read a Summary Aloud

When reading isn't convenient, you can have the system read the summary aloud. When viewing a saved summary, a Read Aloud button appears in the toolbar. Click it to play the summary content as speech.

Go to the meeting details page and switch to the "Meeting Summary" tab

Select a saved summary

Click Read Aloud; the button shows "Preparing…" and playback starts shortly

During playback, click Pause to pause, Resume to continue, or Stop to end



During playback, "Read Aloud" changes to "Pause" and "Stop"

Before reading aloud, the system automatically removes Markdown symbols (such as `#`, `*`, and `-`) from the summary, so the symbols are not read out.

Read-Aloud Voices and Supported Languages

The read-aloud voice is determined by **the speech or target translation language of the meeting**, not by the actual content of the summary. The following seven languages are currently supported:

Language	Language Code
Traditional Chinese (Taiwan)	`zh-TW`
English (US)	`en-US`
Japanese	`ja-JP`

Language	Language Code
Korean	`ko-KR`
Thai	`th-TH`
Indonesian	`id-ID`
Vietnamese	`vi-VN`

> If the meeting language is not in the list above (for example, Simplified Chinese zh-CN or Cantonese zh-HK), the toolbar shows a message such as "... is not currently supported. The default language will be used for reading aloud." You can still use read aloud, but a Traditional Chinese voice is used instead.

Limitations

Read Aloud is available only when viewing a saved summary; it does not appear when you are editing a summary or previewing an unsaved draft

When the summary is empty, the button is disabled

Playback stops automatically when you switch summary versions or leave the "Meeting Summary" tab, so no sound keeps playing in the background

If the browser does not support speech playback, the button is not shown

If playback fails, "Read aloud failed. Please try again later" appears; you can try again later

AI Q&A

In addition to summaries, you can also ask questions directly about the transcript content:

Switch to the "AI Q&A" tab

Select the Agent to use

Enter a question (for example, "What decisions were made in this meeting?" or "What are the next action items?")

The AI finds the relevant content in the transcript and answers

This feature is especially useful for quickly reviewing specific parts of a long meeting without rereading the entire transcript.

Connect an Agent to Create Tickets

After a meeting, someone usually has to manually move the to-dos and decisions into a project management or ticketing system. You can have an Agent take over this step: in the AI Q&A tab, ask it to create tasks or tickets directly from the items agreed upon in the meeting.

> Meeting records do not have a standalone "create ticket" button. AI Q&A uses a full Agent conversation, so as long as the selected Agent is configured with a tool that can create tickets, you can ask it to create tickets in the conversation. The ticket creation capability comes from the Agent, not from the meeting record.

How It Works

Step	Description
① **Meeting transcript**	Meeting transcription is complete, and the transcript has been uploaded to the knowledge base and parsed
② **Select an Agent**	In the AI Q&A tab, select an Agent that has a ticket creation tool configured
③ **Give a ticket creation instruction**	For example, "List the to-dos from this meeting and create a ticket for each one"
④ **The Agent calls a tool**	Following the field mapping and ticket creation rules in the role instructions, the Agent calls an API tool or MCP tool
⑤ **Tickets are created**	The tickets are written to your company's ticketing or project management system
⑥ **Results are reported**	The Agent reports the number and link of each ticket in the conversation

Prerequisites

Requirement	Description
The meeting is linked to a knowledge base and the transcript has been parsed	AI Q&A can be used only after the transcript is in the knowledge base. You can link a knowledge base when you create the meeting; if you didn't set one then, you can also select a knowledge base in the AI Q&A tab and click Upload Transcript. For details, see Download and Knowledge Base Integration
An Agent with a ticket creation tool configured	It is the tool, not the meeting record, that actually calls the ticketing system. See the steps below for how to set it up
A ticketing system that provides a callable API	MaiAgent communicates with external systems through API tools or MCP tools and is not limited to a specific vendor; any system that exposes an API for creating tickets can be integrated

Setup Steps

Create a ticket creation tool: On the Tools page, click Add API Tool and configure your company's ticketing system "create ticket" API (you can paste a cURL command directly, and the system automatically parses the URL, headers, and HTTP method). For details, see Create an API Tool. If the other side provides an MCP server, you can use an MCP tool instead.

Assign the tool to the Agent: Add the tool you just created to the Agent's available tools list. See Configure Tools for an Agent.

Write clear ticket creation rules in the role instructions: Whether the AI calls the tool at the right time and how it fills in the fields depends on the role instructions. Refer to the example below; for writing principles, see the Role Instruction Design Guide.

Use it in a meeting: Go to the AI Q&A tab on the meeting details page, select this Agent, and give an instruction directly, for example, "List the to-dos from this meeting and create a ticket for each one."

> Creating tickets is an action that writes to an external system. We recommend first verifying the field mapping with a test project or test environment before switching to the production ticketing system.

Role Instruction Example

```
# Role
You are a ticket creation assistant for meeting action items.

# Task
The user will ask you to create tickets based on the meeting transcript. Follow
the process below:

1. Identify clear to-dos and decisions from the transcript, and ignore pure
discussion and items that have not been finalized
2. Organize each to-do into one ticket, with the following field mapping:
   - Title: A one-sentence description of what needs to be done, within 30
characters
   - Description: Add the background and rationale mentioned in the meeting
   - Owner: The person explicitly assigned in the transcript
   - Due date: The date explicitly mentioned in the transcript
3. Before calling the tool, list the organized tickets for the user to confirm,
and create them only after receiving approval
4. After creation is complete, report the number and link of each ticket

# Constraints
- Create tickets only based on the transcript content, and do not add tasks that
were not discussed
- If the owner or due date cannot be determined from the transcript, leave it
blank and note it in the reply; do not guess
- When the same item is mentioned multiple times in the meeting, merge them into
one ticket
```

Verification and Troubleshooting

You can view the parameters the tool actually received and the results it returned in AgentOps Tool Execution Records. This is the fastest way to troubleshoot ticket creation issues.

Problem	Cause and Solution
AI Q&A is unavailable	The meeting is not yet linked to a knowledge base, or the transcript is still being parsed. Select a knowledge base on that tab and upload the transcript, then try again after parsing is complete
The AI listed the to-dos but didn't actually create tickets	The tool was not added to the Agent's tools list, or the role instructions don't explicitly require calling the tool. Check steps 2 and 3
Ticket creation failed	Check the error message in the tool execution records. Common causes are missing required fields, expired authentication, or insufficient permissions
Ticket field contents are incorrect	Make the field mapping rules in the role instructions more specific, and explicitly instruct the Agent to leave fields blank instead of guessing when it cannot determine them

Problem	Cause and Solution
The AI's answer is unrelated to this meeting	The currently selected Agent may not be linked to this meeting's knowledge base, and a reminder appears in the interface. Switch to an Agent that is linked

Download and Knowledge Base Integration

Download Files

After a meeting has been processed, you can get the following:

Content	Where	Purpose
SRT subtitle file	Download → Download SRT Subtitles in the title bar of the details page	Includes timestamps; use with video playback or subtitle import
MP3 audio file	Download → Download MP3 Audio in the title bar of the details page	Archiving, offline playback
Plain text transcript	In the Transcript tab, switch to Plain Text and click Copy	Copy and paste, document archiving
Meeting summary	Export in the Meeting Summary tab (Markdown PDF docx plain text send by Email)	See Export Summary and Send by Email

If an option in the Download menu is grayed out: SRT cannot be downloaded until a transcript exists; while the audio is still being converted, "Audio converting" is shown, so try again later.

Upload to Knowledge Base

After you upload a meeting transcript to a knowledge base, an Agent can answer questions based on the meeting content:

On the meeting details page, switch to the AI Q&A tab

Select the target knowledge base (if a knowledge base was linked when the meeting was created, it is filled in automatically), then click Upload Transcript

Wait for the knowledge base to finish parsing, then start asking questions in the same tab

Once uploaded, the transcript becomes a document in the knowledge base, and an Agent can use RAG to retrieve what was discussed in the meeting.

Use Cases

Project meetings: Import the transcript of each project meeting into the knowledge base so an Agent can answer "What did we decide at the last meeting?"

Customer interviews: Import customer interview records to make it easy to look up customer needs later

Training records: Import internal training content to build an organizational knowledge base

Use Cases: Internal Knowledge Management

When enterprises implement knowledge management, they are often limited by the functionality of existing knowledge management systems, relying solely on keyword searches to find information. This approach lacks semantic understanding and often produces imprecise results, failing to effectively meet the vast and diverse knowledge needs of the enterprise.

Now, with MaiAgent, you can build a dedicated enterprise AI knowledge assistant to achieve smarter and more efficient knowledge management!

Use Cases

Professional & Industry Knowledge Q&A: Journals, research reports, and internal technical documents are voluminous and constantly updated — employees need to quickly locate key information rather than reading through each document.

Meeting Decision Traceability: Meeting records are scattered across various locations. When requirements and decisions change repeatedly, it is difficult to quickly verify "who decided what, in which meeting."

Data Visualization & Analysis: Financial and credit analysis work requires repeatedly creating charts. Manual operations are time-consuming and produce inconsistent formats — Canvas can be used to generate interactive charts directly with natural language.

Document & Accounting Automation: Reimbursement receipts and bills require manual entry into systems line by line, and must comply with internal business rules (such as department code mapping).

Cross-Department Access Control: Different departments and job levels have different knowledge access scopes — the knowledge base must be able to restrict search scope based on identity.

How It Works

Step	Description
① **Knowledge Sources**	Document upload (PDF/Office/images), web crawler extraction, meeting transcripts
② **Knowledge Base Ingestion**	The system parses documents, chunks them, and converts them to semantic vectors, then classifies by tags and metadata
③ **Agent Retrieval**	RAG-based retrieval Q&A; Canvas for visualization when charts are needed; tool calls or database queries for real-time data
④ **Access Control**	Role permissions and query metadata determine which documents each user can retrieve

Step	Description
⑤ **Internal Users**	Users receive responses via the admin console or connected internal chat platforms

The key difference from traditional keyword search is that the knowledge base first chunks documents and converts them to semantic vectors, enabling the Agent to understand the intent and context of questions rather than just matching literal text. Responses synthesize information from multiple sources and include citation references for verification.

Setup Workflow

1. Create a Knowledge Base

On the Knowledge Base page, create a knowledge base and complete the basic settings, selecting the appropriate parsing and chunking methods.

2. Import Knowledge Sources

Upload existing documents, or use the web crawler to extract internal website content. If the knowledge source is meetings, use meeting records to automatically transcribe and integrate into the knowledge base.

3. Organize Tags and Metadata

Add tags and metadata to documents (such as department, year, document type) — this is the foundation for subsequent permission filtering and precise retrieval.

4. Validate Retrieval Quality

Use search testing to input questions that would actually be asked, verify whether the retrieved passages are correct, and decide whether to adjust chunking settings or supplement data.

5. Create an Agent and Bind the Knowledge Base

Create an Agent and attach the knowledge base. If chart generation is needed, set the response mode to "Agent Mode" and enable Canvas mode.

6. Configure Access Permissions

Use role permission management and knowledge management permissions: query metadata to ensure users from different departments and job levels can only retrieve documents they are authorized to view.

Internal knowledge bases often contain sensitive data. Before going live, verify permission settings and test retrieval results with accounts of different roles to prevent unauthorized access.

Application Examples

Professional Knowledge Management: Using maritime industry journals and reports as an example, build an internal professional knowledge Q&A assistant.

Meeting Requirements Management: Using software project requirement changes as an example, let AI quickly trace the decision context across meeting histories.

Financial Analysis Assistant: Use Canvas to generate interactive financial charts such as revenue and gross margin with natural language.

Billing Assistant: Recognize utility, telecom, and other reimbursement receipts, and automatically apply internal business rules such as department codes.

Credit Analysis Assistant: Integrate credit data and use Canvas to generate risk assessment charts, accelerating credit review.

The following sections demonstrate the setup process with real-world examples to help you quickly apply these capabilities to your own business scenarios.

Professional Knowledge Management

When enterprises promote knowledge management, existing knowledge management systems are often limited to keyword search. This approach has limited semantic understanding, and the results are often imprecise, making it hard to meet the enterprise's large and diverse knowledge needs. Now, you can use MaiAgent to build a dedicated internal AI knowledge assistant for your enterprise and achieve smarter, more convenient knowledge management!

Use Case: Build a Maritime Knowledge AI Q&A Assistant

Suppose you are a supply chain management specialist at a shipping company who must regularly read journals and reports to keep up with the latest maritime trends, which are an important basis for business operations and decisions. However, as the international situation changes rapidly and industry knowledge evolves daily, the volume of information is huge and scattered, making it hard to grasp the key points in time. With MaiAgent, you can build a dedicated internal AI Q&A assistant that not only helps you quickly locate, understand, and internalize key knowledge so you can follow trends in real time, but also promotes knowledge sharing and work efficiency across your whole team, improving the company's adaptability and competitiveness in a fast-changing market.


Workflow

1. Create a Maritime Knowledge AI Q&A Assistant

Enter the Agent name.



Select RAG and a language model.



When selecting the reply mode, if you have no special requirements, choose "RAG Q&A", which fits this use case. The role instruction can be set as follows:

```
# Role
You are an internal maritime knowledge Q&A assistant at a shipping company

# Output Format
Use the format in the example below to reply with the three most relevant pieces
of knowledge.


Your question relates to the following:


1. [Title] (content summary)
2. [Title] (content summary)
3. [Title] (content summary)


# Output Restrictions
- Reply in Traditional Chinese
- Use Taiwan terminology for technical terms, for example, change the mainland
China term "集裝箱" to "貨櫃"
- Give priority to more recent materials
- Do not answer with information outside the knowledge base
- Answer based on knowledge base data; if you cannot answer, reply with the text
in the  below


Sorry, the knowledge base currently does not contain the information you asked
about
```



Configure permissions, assign roles, and click Save.




2. Upload the Knowledge Base

Here we use public data, the UNCTAD 2024 Review of Maritime Transport and the CR Technical Bulletin, as the reference sources for the knowledge base.

Here we use two public data sources, the UNCTAD 2024 Review of Maritime Transport and the CR Classification Society technical bulletin, as the reference basis for building the knowledge base.

https://unctad.org/system/files/official-document/rmt2024overview_ch.pdf

https://www.crclass.org/wp-content/uploads/2025/02/138.pdf



3. Put the Agent into Use

When you need to learn about maritime topics, you can now ask the Agent directly in the Q&A interface!

For example, if your manager asks you to write an analysis report on the Panama Canal, simply ask the Agent and get the relevant information instantly, without searching through documents one by one, improving your report writing efficiency!

內部海運知識問答助理

巴拿馬運河相關議題

2025/04/24 11:33:01

內部海運知識問答助理

已使用知識庫

您提到的問題與以下內容有關：

1. [巴拿馬運河水位下降影響航運] 巴拿馬運河因氣候變化引發的乾旱而減少了每日通過的船舶數量。全球海運貿易量的約3%經過巴拿馬運河，截至2024年6月，巴拿馬運河的船舶通過數量較2021年12月的峰值下降了一半以上。過去兩年，透過巴拿馬運河的過境船舶一直在減少。
2. [巴拿馬運河狀況改善] 自2024年1月以來，巴拿馬運河的狀況因雨季開始及巴拿馬運河管理局實施節水措施而有所改善。根據國稅會議的分析，巴拿馬運河航運中斷對乾散貨運價的影響在2024年1月達到頂峰，隨著巴拿馬運河的限制因素有所緩和，貨運價格的上漲從2024年4月至2024年6月期間放緩。
3. [巴拿馬運河與蘇伊士運河的航運中斷影響] 巴拿馬運河和蘇伊士運河的航運中斷導致船隊改道使用更長的航線，使航程增加、運輸時間延長，同時使全球船隊需求增加了3%，貨櫃船需求增加了12%。這些航運中斷引發的成本升高轉化為運費上升，而這又不可避免地被轉嫁到消費者身上，加劇通貨膨脹並損害經濟增長。

引用

rmt2024overview_c... 引用證據

2025/04/24 11:33:19

請輸入您想問的問題

Powered by MAIAGENT

Meeting Requirements Management

As an enterprise employee, you attend meetings frequently and often run into meeting records that are scattered and poorly managed, which makes it hard to quickly find and track past decisions and requirement changes. With MaiAgent, you can build your own internal AI meeting management assistant and move work forward more effectively.

Use Case: Build an AI Meeting Management Assistant for a Software Company

Suppose you are a project manager at a software company. Internal and external requirements change often, and when communicating with stakeholders such as clients or managers, you may struggle to reach consensus quickly, or key decision-makers may repeatedly overturn earlier decisions, leaving you unable to quickly verify the basis for those decisions.

For example, your company has been commissioned by Daikin Co., Ltd. to develop a customized quotation management system. You have finished developing the version control feature based on the original requirements submitted by a specialist in the client's sales department. In a later meeting, however, the client's sales director asked to simplify the feature, and in the most recent meeting, the client's sales manager proposed far more complex requirements for the same feature.

In the past, facing repeated and contradictory requirement changes like these, you might have spent a great deal of time manually searching through meeting record files scattered across your computer to find the basis for a decision, which was both time-consuming and exhausting.

Now you can use MaiAgent to build an internal meeting management assistant that quickly gives you the complete, up-to-date history of your meetings, improving information transparency and communication efficiency and effectively moving the project forward!


Workflow

1. Create an AI Meeting Management Assistant

Enter the Agent name



Select RAG and a language model



When selecting the response mode, if you have no special requirements, choose "RAG Q&A", which fits this use case. For the role instructions, refer to the following:

```
# Role
You are the company's internal meeting management assistant

# Output Format
Use the example format below to reply with the three most relevant meeting
decisions.


The question you raised is related to the following meeting decisions:

1.  Original text of the proposal
2.  Original text of the proposal
3.  Original text of the proposal


# Output Restrictions
- Reply in Traditional Chinese
- Do not answer with information outside the knowledge base
- Answer based on the knowledge base; if you cannot answer, reply with the text
in the  below


Sorry, the knowledge base does not currently contain the information you asked
about
```



2. Upload the Knowledge Base

Upload the records of past meetings (the files below are examples designed for this use case)



3. Put the Agent into Use

You can now ask questions directly in the Agent chat interface to quickly learn how the requirements for the quotation system's version control feature have changed and who proposed each requirement. The Agent also provides the relevant source files so you can verify the details further.

Now, you can ask questions directly in the Agent chat interface to quickly understand how the requirements for the quotation system's version control feature have changed and who proposed each requirement. The Agent also provides the source files so you can verify the details further.

This saves you a great deal of time searching for information, so you can focus on stakeholder management and coordination and keep the project moving.


會議管理助手
列出客戶能出報價系統與業控現功能的所有決議
2025/04/24 15:59:52
會議管理助手
已使用引用源
您提到的問題與以下會議記錄有關：
1. 2024年6月20日 大金證券有限公司業務部與-貿書華昇出報價系統的需求與確認圖：
・更新報價內容時，不需新建現有版本。
・使用者可直接修改報價內容，並增加版本號。
2. 2024年4月25日 大金證券有限公司業務專員提出報價系統權限控制功能需求：
・每新增一筆報價並確認內容無誤後，承辦業務人員需按下「定版」按鈕。
・定版後，該報價內容將不可再編輯，系統才允許將該報單寄送給客戶。
・若客戶需求變更，需調整報價單內容時，須對已定版的報價單進行「升版」操作。
・系統自動增加版號，並提供歷史介面，讓業務人員修改報價內容。
引用
20250425 報價需求...
20240620與會會議...
引用網站
2025/04/24 15:60:02
請輸入您想問的問題
Powered by MAKEPRINT

Financial Analysis Assistant

Enterprise finance teams often face challenges such as scattered data, time-consuming chart creation, and inconsistent analysis report formats when processing complex financial data. Traditional financial analysis tools typically require tedious manual chart creation, which is inefficient and makes it difficult to respond quickly to management's demand for real-time financial insights. Now, you can use MaiAgent's Canvas visualization technology to build a dedicated enterprise financial AI analysis assistant and achieve intelligent financial data visualization and analysis!

Use Case: Build an Enterprise Financial Data Visualization Agent

Suppose you are a financial analyst at a publicly listed company who needs to produce revenue reports, cost analysis charts, and financial dashboards for the board of directors every month. In the past, you might have spent hours manually creating various charts in Excel. This was not only time-consuming and labor-intensive, but chart formats were often inconsistent due to manual work, affecting the professionalism of your reports.

For example, when the CEO asks you for a "gross margin trend chart for all product lines over the past 12 months" just 30 minutes before a board meeting, the traditional approach requires you to urgently dig through data and recreate charts, often making it impossible to finish before the meeting.

Now, with MaiAgent Canvas technology, you simply describe your needs to the Agent in natural language, and the system immediately generates professional interactive financial charts. This not only greatly improves work efficiency but also ensures the accuracy and consistency of charts, letting you focus on higher-value financial analysis insights!


Workflow

1. Create a Financial Data Analysis Agent

Enter the Agent name.



Select RAG and a language model, **and enable Canvas mode**.



Select Agent as the reply mode, then enable Canvas mode under Agent mode

When selecting the reply mode, choose "Agent mode" and enable "Canvas mode". The role instruction can be set as follows:

```
## Role Setting

You are a professional financial analysis expert, specializing in in-depth
analysis and insights of corporate financial statements. Your task is to help
users understand a specific company's financial condition, operating performance,
and future potential.

## Core Task

Search the knowledge base for financial data to draw charts, and call tools that
use React to produce dynamic financial analysis reports.
Whenever a user asks for a report, call the canvas tool to draw the relevant
charts.
Present content with charts as much as possible.

## Output Requirements

1.  Structured report: Present analysis results as a clear, well-organized
report, including:
    *   Summary: A brief overview of overall financial performance.
    *   Key findings: List the most important financial highlights and issues.
    *   Detailed analysis: Explain the calculation results, trend analysis, and
interpretation of each financial metric.
    *   Chart visualization: You must use the canvas tool to draw relevant charts
to visualize data trends and comparisons.
    *   Conclusions and recommendations: Based on all the analysis, provide
specific conclusions and actionable recommendations.
2.  Chart visualization:
    *   Use a variety of chart types, for example:
        *   Line chart of revenue and net income trends
        *   Bar chart comparing profitability ratios
        *   Pie chart of asset and liability structure (showing the proportion of
assets and liabilities)
        *   Cash flow trend chart (operating, investing, and financing cash
flows)
        *   Annual trend charts of key financial ratios (such as ROE and ROA)
3.  Language and tone: Respond in Traditional Chinese, with a professional,
objective, and precise tone, avoiding vague wording.
4.  Interactivity: If data is incomplete or needs further clarification,
proactively ask questions to obtain more information, for example: "Please
provide more detailed cash flow statement data so that I can perform a more
comprehensive analysis."
```

2. Upload the Financial Data Knowledge Base

Upload your company's financial data files, including:

Monthly/quarterly income statements


Balance sheets

Cash flow statements

Budget and actual expenditure data by department

Product line revenue data

Historical financial reports



3. Put the Agent into Use - Canvas Visualization


Real-Time Chart Generation

When you need to create a financial chart, simply make a request to the Agent. The system automatically decides and uses Canvas technology to generate the appropriate visual content:

Example 1: Revenue trend analysis

Input: "Create a revenue trend chart for each month of 2024"

→ The Agent uses **React Canvas** to generate an interactive multi-line trend chart



Example 2: Cost structure analysis

Input: "Produce a pie chart of the cost share of each department"

→ The Agent uses **SVG Canvas** to generate a professional vector pie chart



Example 3: Financial dashboard

Input: "Build a financial performance monitoring dashboard for this quarter"


→ The Agent uses **HTML/React Canvas** to generate a complete interactive dashboard



Example 4: Financial approval process

Input: "Create an expense reimbursement approval flowchart"

→ The Agent uses **Mermaid Canvas** to generate a clear flowchart



Demo Video

📺 **預覽連結：**https://drive.google.com/file/d/1JAGb7n-kPM1jGcq1QWwjluSXfUUrljre/view?usp=sharing

4. Canvas Advantages in Financial Applications

🚀 Efficiency Boost

Instant generation: From request to finished chart in just 30 seconds

Consistent formatting: All charts follow your corporate visual identity standards

No manual work: Create complex charts with natural language

📊 Professional Quality

Interactive features: Supports data filtering and time range adjustment

Responsive design: Adapts to various screen sizes and output formats

Vector graphics: The SVG format ensures clarity for printing and projection

🔄 Flexible Adjustment

Instant edits: Adjust chart styles and data ranges immediately

Multiple output formats: Produce different visualization formats from the same data

Customization: Adjust the presentation to different usage scenarios

💼 Enterprise Integration

Brand consistency: Integrates your corporate colors and font standards

Localization support: Supports Taiwan accounting standards and currency formats

Security: Financial data is processed locally, ensuring information security

With MaiAgent Canvas technology, finance teams can not only greatly improve work efficiency but also devote their time to more valuable financial analysis and strategic planning, truly achieving the goal of financial digital transformation!

Try the financial data analysis assistant today, and make your financial reports more than numbers — make them visual insights!

Billing Assistant

Corporate finance teams handling everyday expense reimbursements often face numerous receipts and manual data entry that is time-consuming and error-prone. Traditional OCR tools usually only recognize text and lack an understanding of the business context, so they cannot automatically map department codes or expense categories, and a lot of manual correction is still needed. Now, you can use MaiAgent's intelligent vision technology to build a dedicated "Billing Expense Assistant" and achieve intelligent automation from receipt recognition to ERP data entry!

Use Case: Build an Agent That Automatically Recognizes Corporate Bills

Suppose you are a corporate finance accountant who must process a large number of reimbursement receipts from branch offices at the end of every month, such as water and telecom bills. In the past, you might have spent hours looking at paper receipts and manually entering each invoice number, date, and amount into the ERP system.

Traditional OCR tools can only "read text" but cannot understand business rules. For example, when a receipt says "Zuoying District, Kaohsiung City," a traditional tool cannot automatically determine that it belongs to the "Kaohsiung Branch" with department code "K." It also cannot lock the payment date to the "30th of every month" as required by company policy, so you have to check and correct each record by hand, which is inefficient and prone to input errors caused by fatigue.

Now, with MaiAgent's intelligent vision and reasoning technology, you only need to upload the bill image to the Agent. The system not only extracts the invoice number and amount accurately, but also directly applies your company's internal business logic!

Workflow

1. Create a Billing Expense Agent

Enter the Agent name and select a language model

Recommended model: Gemini 3.8 Flash (with thinking effort enabled), or a flagship model that supports image input, such as Claude 5.5 Opus

Note: Because this application involves complex text recognition in images and logical judgment (such as converting addresses to department codes), choose a model that **supports image input and has strong reasoning ability** to ensure recognition accuracy. The models your organization can use are determined by the list enabled in Model Access Permissions.




Select Agent mode



2. Configure the Operating Logic

So that the Agent can not only "read text" but also "understand" business rules, define the following field-handling logic in the System Prompt. The following uses a water bill from "Taiwan Water Corporation" as an example:



A. Basic Information Extraction

The Agent must identify the following key raw data from the image:

Invoice number: Accurately extract the invoice number on the receipt.
Amount information: Extract the "total amount" and the "pre-tax amount".
Date information: Extract the relevant date range on the bill.

B. Business Logic Mapping

This is the core advantage that sets MaiAgent apart from traditional OCR. The Agent can automatically determine the correct classification based on the content:

Address-to-department mapping:

Rule: If the recognized address contains "Kaohsiung," the "expense department" is automatically set to "Kaohsiung Branch".

Code conversion: Following the above, if the department is the Kaohsiung Branch, the "department code" is automatically filled in as "K".

Payee and expense category:

Rule: If the payee is recognized as "Taiwan Water Corporation," the "expense item" is automatically classified as "Water Bill".

Automated payment date:

Rule: Regardless of the bill date, the "payment date" field is always fixed to the 30th of each month.

Standardized summary format:

Rule: Combine the extracted dates and information into a string in a fixed format.

Example format: `YY/MM/DD-YY/MM/DD` + `Region` + `Expense Item` (for example: "114/08/20-114/10/18 Kaohsiung Water Bill").

Amount calculation and validation:

Rule: The system can automatically calculate or validate the amount logic, for example: `Amount` = `Total Amount` - `Pre-tax Amount` (depending on the ERP field definitions).

A reference for the role instructions is as follows:

```
# Role (角色設定)
You are an enterprise-grade "Intelligent Financial Accounting Assistant". Your
core capability is visual recognition (OCR) combined with complex business logic
reasoning.
Your task is to accurately extract data from various bills and convert
unstructured information into standard ERP format according to the predefined
[Business Configuration].

# Business Configuration (業務規則配置)
Reason and map fields according to the following rule table:

## 1. Department Mapping Rules (Department Logic)
* Rule: Read the "address" or "place of consumption" keywords on the bill.
    * Contains "台北" (Taipei) → Expense department: "台北總公司" | Department
code: "T"
    * Contains "高雄" (Kaohsiung) → Expense department: "高雄分公司" | Department
code: "K"
    * Otherwise → Expense department: "待確認" | Department code: "UNK"

## 2. Expense Category Rules (Expense Category Logic)
* Rule: Read the "company name", "letterhead", or "transaction details" on the
bill.
    * Contains "自來水" (water supply) → Expense item: "水費"
    * Contains "電力" or "台電" (Taipower) → Expense item: "電費"
    * Contains "中華電信" (Chunghwa Telecom) → Expense item: "電信費"

## 3. Date and Summary Rules (Date & Summary Logic)
* Payment Date: Uniformly set to the 30th of the "current or next month" of the
receipt month (format YYYY-MM-DD).
* Summary Format: Must be combined into a standard string → `[Start-End Dates]-
[Region][Expense Item]`
    * *Example*: `114/06/20-114/08/18高雄水費`

## 4. Amount Calculation Rules (Calculation Logic)
* Pre-tax Amount: Must be obtained by calculation, formula = `[Total Amount] -
[Business Tax/Tax Amount]`.
    * *Note*: Do not read the "subtotal" in the middle of the receipt directly.
You must subtract from the "total amount" to avoid missing collected fees.

---

# Workflow (執行流程)

## Phase 1: Visual Recognition and Logical Inference
1.  Analyze the image: Scan for invoice number, date range, address,
counterparty, total amount, and tax amount.
    * *Invoice number format check*: Must match `^[A-Z]{2}\d{8}$`.
2.  Perform mapping: Determine the department, category, and code according to
[Business Configuration].
```

```
3.  Output a confirmation table: Output the results as a Markdown table for the
user to verify.

Phase 1 output example (follow this format strictly):
Reply directly: "請確認以下帳單資訊："
| 欄位名稱 | 識別與轉換結果 | 邏輯來源 |
| :--- | :--- | :--- |
| A. 支出部門 | [e.g., 高雄分公司] | [Based on address: 高雄 ... ] |
| B. 費用項目 | [e.g., 水費] | [Based on counterparty: 自來水公司] |
| C. 摘要 | [Date range + region + item] | [Format combination] |
| D. 發票號碼 | [Two letters + eight digits] | [OCR recognition] |
| E. 金額（稅額） | [Tax amount] | [OCR recognition] |
| F. 未稅金額 | [Calculated value] | [Total - tax] |
| G. 付款日 | [YYYY-MM-DD] | [Fixed rule: 30th] |
| H. 部門代碼 | [e.g., K] | [Mapped code] |
| I. 合計金額 | [Total amount] | [OCR recognition] |

## Phase 2: Data Entry (Action)
After the user replies "確認" or "沒問題":
1.  Call the MCP tool `add_invoice_record` to write the data.
2.  After the tool runs successfully, output standard JSON and provide the Google
Sheet link.

---

# Attention (注意事項)
* If the image is blurry, mark it as "無法識別" and ask the user.
* Prioritize the visual "合計總金額" figure and ignore intermediate line-item
subtotals.
```

C. Advanced Configuration: Connect to Google Sheets for Automatic Archiving

> How do I connect MCP tools?

3. Put the Agent into Use

When you need to process billing expenses, simply send the bills and payment receipts to the Agent. The system automatically determines the content and standardizes the extracted data according to company rules (for example, automatically mapping department codes and calculating pre-tax amounts). It then writes the data directly into your ERP system or Google Sheets report, achieving one-click automation from receipt recognition to bookkeeping.

Automatically detect bill content



Automatically write bill content to Google Sheets

支出部門	費用項目	摘要	發票號碼	含稅 (稅額)	未稅金額	付款日	部門代碼
台北總公司	水費	114/03/05-114/05/04台北水費	TP88776655	50	1450	2025-05-30	T

Automatically convert the format to ERP-format JSON

```
{
  "expenditure_department": "台北總公司",
  "cost_item": "水費",
  "summary": "114/03/05-114/05/04台北水費",
  "invoice_number": "TP88776655",
  "tax_amount": 50,
  "pre_tax_amount": 1450,
  "payment_date": "2025-05-30",
  "department_code": "T"
}
```

4. Technical Advantages of the Smart Billing Assistant

🚀 Powerful Vision Language Model

Semantic understanding and dynamic reasoning: The model does not rely on fixed layout coordinates; it extracts information by understanding the context and meaning of the document. In addition, business rules can be flexibly extended through the System Prompt without redeveloping any code.

Examples:

Automatic account assignment: When it sees the "Water Corporation" logo, it automatically classifies the category as "Water Bill".

Logic completion: When it sees a "Kaohsiung address," it automatically infers and fills in department code "K".

Rule extension: If you later need to add decision logic for a "Taipei Branch," just adjust the prompt and it takes effect.

Strong adaptability to real-world conditions: With interference-resistant visual recognition, even if a photo taken by the user with a phone has shadows, wrinkles, glare, or slight blur, the vLM can still restore values and text accurately from context, greatly reducing the need for retakes or manual re-entry.

🛠️ Precise Tool Use and Logic Execution (Tool Use & Integration)

Automated report writing: Through the Google Sheets writing tool, the Agent can write the parsed information directly into the specified cells of a cloud spreadsheet.

It replaces the tedious traditional process of "reading receipts by eye and keying them into a spreadsheet by hand," truly achieving "snap the receipt and the report is done."

Structured format and seamless ERP integration: Enforced output formats ensure that data maps directly to the requirements of internal enterprise systems (ERP).

Examples:

Date normalization: Whether an invoice shows `2024/01/01` or `113年1月1日`, it is automatically converted to the standard `YYYY-MM-DD` before being written.

System integration: Supports direct output in standard JSON format for enterprise ERP APIs to call directly.

Logic validation: The Agent does not just pass data along; it can also call calculation tools to check values and compliance.

Example: It automatically verifies `Total - Tax = Pre-tax Amount`, or locks the payment date to a specific day (such as the 30th of each month) according to company policy, ensuring that every record entering the system conforms to financial logic and information security requirements.

With the MaiAgent Smart Billing Assistant, finance teams can not only be freed from tedious receipt entry, but also ensure that the classification and code of every expense is 100% accurate, truly achieving unattended automated processing from "receipts" to "reports"!

Try the Billing Expense Assistant now, and make your finance process not just digital, but intelligent!

Credit Analysis Assistant

Corporate credit investigation teams often face challenges such as scattered data, time-consuming risk assessments, and inconsistent analysis report formats when handling complex credit data. Traditional credit analysis tools usually require tedious manual data verification, which is not only inefficient but also makes it hard to respond quickly to business departments' demands for real-time risk assessment. Now, you can use MaiAgent's Canvas visualization technology to build a dedicated AI credit analysis assistant for your enterprise and achieve intelligent visualization and analysis of credit data!

Use Case: Build an Agent for Enterprise Credit Data Visualization

Suppose you are a credit analyst at a financial institution. Every day you review customer applications, prepare risk assessment reports, and present credit risk dashboards to the risk management committee. In the past, you may have spent hours looking up customer data across different systems and manually creating various risk assessment charts. This is not only time-consuming and laborious, but the results are also often inconsistent because of manual work, which affects the accuracy of decisions.

For example, when the business department urgently needs a "credit risk assessment report for a large corporate customer" within 30 minutes, the traditional approach requires you to rush to look up credit bureau data, analyze the financial situation, and evaluate guarantor conditions, and you often cannot finish before the business meeting.

Now, with MaiAgent Canvas, you only need to describe your needs to the Agent in natural language, and the system immediately generates professional interactive credit analysis charts. This greatly improves your efficiency and ensures accurate, consistent assessments, so you can focus on higher-value risk analysis insights!


Workflow

1. Create a Credit Data Analysis Agent

Enter the Agent name



Select RAG and a language model, **and enable Canvas mode**



Select Agent as the reply mode, and enable Canvas mode under Agent mode

When selecting the answer mode, choose "Agent Mode" and enable "Canvas Mode". Refer to the following role instructions:

2. Upload Credit Data to the Chat via Conversation Attachments

Upload credit data files, including but not limited to:

Balance sheets

Credit bureau credit reports

Cash flow statements

Tax records

Banking transaction records

Income statements



3. Agent in Action - Demo Video

📺 **預覽連結：**https://drive.google.com/file/d/1ABZFLD3cz9u89i-88RrXJKvIxK6o4vej/view?usp=sharing

4. How Canvas Advantages Show Up in Credit Applications

🚀 Higher Efficiency

Instant assessment: From customer application to completed risk assessment in just 30 seconds

Standardized process: All assessments follow consistent risk evaluation standards

No manual work: Complex risk analysis in natural language

📊 Professional Quality

Interactive features: Supports risk factor adjustment and time range filtering

Responsive design: Fits various screen sizes and output formats

Vector graphics: SVG format ensures clarity in print and projection

🔄 Flexible Adjustment

Instant changes: Adjust assessment parameters and risk weights immediately

Multiple output formats: Produce different analytical perspectives for the same customer

Customization: Adjust the assessment model for different product types

💼 Enterprise Integration

Regulatory compliance: Incorporates the credit investigation regulatory requirements of the Financial Supervisory Commission

Localization support: Supports Taiwan's credit investigation system and scoring standards

Security: Customer data is processed locally to ensure information security

With MaiAgent Canvas, credit teams can not only greatly improve efficiency but also devote their time to more valuable risk analysis and strategy development, truly achieving digital transformation in credit investigation!

Try the credit data analysis assistant now, and make your risk assessments not just numbers, but visualized insight!

Use Cases: Image Vision

When processing invoices, bills, official documents, business cards, and ID cards, enterprises often rely on manual field-by-field data entry, which is time-consuming and prone to errors caused by fatigue. Traditional OCR tools can read text, but they lack an understanding of business context: different layouts each require their own template, and the raw text they produce still needs extensive post-processing before it can be written into a system.

MaiAgent's image and vision applications instead use **multimodal language models** for this kind of work. Users simply upload an image in a conversation, and the Agent outputs structured JSON data according to the field specifications defined in its role instructions. The result can be displayed instantly in the chat interface or connected to downstream systems such as ERP and CRM through the API.

Demo Video

📺 **預覽連結：**https://drive.google.com/file/d/1Xuso3cX8ZMChhWIa2rD7wafcDT2fUldr/view?usp=sharing

Differences from Traditional OCR

	Traditional OCR Engine	MaiAgent Multimodal AI
Layout adaptability	Requires a template for each layout	Automatically understands different layouts
Field expansion	Requires code changes	Just edit the JSON fields in the role instructions
Business rules	Outputs text only; rules must be implemented separately	Decision logic can be described directly in the role instructions
Deployment cost	Self-hosted service or purchased license	Platform configuration, no coding required

For a more complete comparison (including front/back side handling, error handling, and more), see ID Card Recognition. For the differences in principle between vision language models (VLMs) and OCR, and for how conversation attachments, knowledge base documents, and knowledge base image files each handle images, see Technical Guide - Image Recognition Support.

Use Cases

Expense reimbursement and accounting: Extract invoice numbers, dates, and amounts from large volumes of utility, telecom, and hospitality receipts and write them into an ERP.

Identity verification workflows: For financial account opening, HR onboarding, medical registration, and similar scenarios, extract basic information from ID documents and fill it into forms.

Business card filing: Automatically convert business cards collected at trade shows or visits into contact data and import it into a CRM.

Official document and file archiving: Extract fields such as document number, issue date, and subject from scanned documents for easier search and archiving. The approach is the same as Invoice Recognition: replace the field definitions in the role instructions with those of the official document.

How It Works

Step	Description
① **Upload image**	The user uploads an image of an invoice, business card, ID card, or similar as an attachment in the conversation
② **Agent recognition**	A multimodal language model with vision capabilities reads the image content
③ **Role instructions shape the output**	Based on the field definitions, output examples, and error formats in the role instructions, the Agent decides which fields to extract and in what format to reply
④ **Structured output**	Produces results in JSON format
⑤ **Downstream use**	Displayed instantly in Web Chat, or connected to business systems such as ERP and CRM through the API

The key is the **role instructions**: in them you define the Agent as a "recognition API," explicitly stating which fields to extract and giving JSON output examples for both success and failure, and the AI will reply consistently in that format. To add a field, just update the role instructions—no code changes are needed.

Setup Workflow

1. Create an Agent and Choose a Vision-Capable Model

On the AI Assistants page, create an Agent. Because this type of application involves image recognition and logical judgment, we recommend choosing a Pro-tier or higher multimodal model to ensure recognition accuracy.

2. Define the Output Format in the Role Instructions

Describe the recognition task and field specifications in the role instructions, and include JSON examples for both success and failure. For fields that cannot be recognized, we recommend keeping the field name and setting its value to `null` so downstream systems can handle it easily.

3. Upload Images to Test

Upload real documents as attachments in the conversation and confirm that all output fields are present and correctly formatted. We also recommend testing edge cases such as blurry images, tilted images, and front/back sides.

4. Connect to Business Systems

Once the output is stable, you can connect the Agent to your existing workflows through the API and write the JSON results directly into an ERP, CRM, or form system. You can review integration activity in the API Call Logs.

> Images of ID cards, invoices, and similar documents often contain personal data. Before rollout, make sure your organization's permission settings and data retention policies meet personal data protection requirements. For the access control, personal data masking, and audit mechanisms the platform provides, see Security and Privacy.

Application Examples

Invoice Recognition: Extract the invoice type, track number, buyer and seller tax IDs, and line item details, and output them as JSON.

Business Card Scanning: Convert business cards into structured fields such as name, job title, company, and contact details.

ID Card Recognition: Recognize both the front and back of an ID card from a single image and output standard fields for account opening, onboarding, and similar workflows.

The following sections walk through the setup process with real-world cases to help you quickly apply it to your own business scenarios.

Invoice Recognition

Corporate accounting teams handle a large number of purchase and sales invoices every month. In the past, they had to read each paper invoice and type the invoice number, date, buyer and seller tax IDs, line items, and amounts into the system one by one, which is time-consuming and prone to errors in repetitive work. Taiwan invoices also come in triplicate, duplicate, electronic, and cash-register formats, each with a different layout, so traditional OCR requires a separate template for each format.

With MaiAgent's multimodal Agent, you simply upload an invoice image in a conversation, and the AI automatically determines the invoice type, extracts each field, and outputs structured JSON that can be connected directly to an ERP or accounting system. The following explains how to use role instructions to define an Agent as an "invoice document recognition API."

Processing Multiple Invoices at Once

Recognition is performed per message. There is no separate batch OCR feature, and there are three approaches:

Attach multiple images to one message: A single message can include multiple invoice images, which are passed to the model together. The maximum number of images per message is set by the platform (default: 20). Add "Output one record per image, and return everything as a JSON array in attachment order" to the role instructions; otherwise the model may merge several images into one record.

Multiple invoices in one image: The model can recognize them, but accuracy is lower than with one invoice per image. In the instructions, require that "if one image contains multiple invoices, output each separately," and try to keep every invoice fully visible and non-overlapping.

Large volumes of invoices: Use the Conversation API to send them message by message, each with a batch of images, and have your program collect the returned JSON. If an invoice fails to be recognized, resend just that one.

> Uploading invoice images to a knowledge base only stores the files and builds an index. It does not run recognition or produce JSON. Recognition always happens in a conversation.

OCR (Optical Character Recognition)

Role instructions for the "invoice document recognition API"

```
# Persona
You are an invoice document recognition API

# Task
## Input
The user will upload an image of an invoice document

## Output
Extract the text from the invoice document and output it in JSON format. Output
the JSON directly.

### Field descriptions
- invoice_type: triplicate/duplicate/electronic/cash register
- For fields that cannot be recognized, keep the field and use null as the value

### Output example
<example>
json
{
  "status": "success",
  "data": {
     "invoide_type": "三聯式"
     "invoice_number": "AB-12345678",
     "invoice_date": "112/11/17",
     "invoice_time": "14:30:00",
     "seller": {
       "tax_id": "12345678",
       "company_name": "好吃餐廳股份有限公司",
       "address": "台北市信義區信義路五段100號"
     },
     "buyer": {
       "tax_id": "87654321",
       "company_name": "測試科技股份有限公司"
     },
     "items": [
       {
         "description": "商業午餐A餐",
         "quantity": 2,
         "unit": "份",
         "unit_price": 120,
         "amount": 240
       },
       {
         "description": "紅茶",
         "quantity": 2,
         "unit": "杯",
         "unit_price": 30,
```

```
          "amount": 60
        }
      ],
      "amounts": {
        "sales_amount": 300,
        "tax_amount": 15,
        "total_amount": 315
      },
    }
}

</example>

> Failure example
<example>
json
{
  "status": "failed",
  "error": {
    "code": "IMAGE_ANALYSIS_ERROR",
    "message": "Unable to correctly recognize the business card image",
    "details": "Image quality is insufficient or the format does not meet
requirements"
  }
}

</example>
```

Business Card Scanning

After trade shows or client visits, sales representatives often accumulate a large number of business cards and must enter the name, job title, company, phone number, and email into a CRM or contact list one by one. This is easy to put off and can cause them to miss the window for follow-up. Business card layouts are free-form, with Chinese and English side by side and information placed inconsistently, which also makes it hard for traditional OCR to map fields reliably.

With MaiAgent's multimodal Agent, you simply upload a business card image, and the AI understands the layout, extracts each field, and outputs structured JSON with Chinese and English listed separately, ready to import directly into a CRM or contact system. The following explains how to use role instructions to define the Agent as a "business card recognition API."

```
# Persona
You are a business card recognition API

# Task
## Input
Users will upload business card images

## Output
Extract the text from the business card and output it in JSON format. Output the
JSON directly.

> Success Example
<example>
json
{
  "status": "success",
  "data": {
    "name": {
      "zh": "王大明",
      "en": "David Wang"
    },
    "title": {
      "zh": "資深軟體工程師",
      "en": "Senior Software Engineer"
    },
    "company": "頑碼資訊有限公司",
    "phone": "02-2345-6789",
    "mobile": "0912-345-678",
    "email": "david.wang@innovtech.com.tw",
    "address": "台北市信義區信義路五段7號",
    "website": "www.innovtech.com.tw"
  }
}

</example>

> Failure Example
<example>
json
{
  "status": "failed",
  "error": {
    "code": "IMAGE_ANALYSIS_ERROR",
    "message": "無法正確辨識名片圖片",
    "details": "圖片品質不足或格式不符合要求"
  }
}
```

```
</example>
```

Upload a business card image and the Agent returns JSON in the format below, which can serve as the API output (the sample data is fictional):

```
{
  "status": "success",
  "data": {
    "name": {
      "zh": "王小明",
      "en": "Xiaoming Wang"
    },
    "title": {
      "zh": "業務經理",
      "en": "Sales Manager"
    },
    "company": "Acme 股份有限公司",
    "phone": "0900-000-000",
    "email": "xiaoming.wang@example.com",
    "line": "acme-sales",
    "address": {
      "zh": "100臺北市中正區範例路1號",
      "en": "No. 1, Example Rd., Zhongzheng Dist., Taipei City 100, Taiwan
(R.O.C.)"
    },
    "company_registration": "Acme 股份有限公司 12345678"
  }
}
```

ID Document Recognition

When enterprises handle identity verification, account opening, onboarding, and similar workflows, they often have to type in names, ID numbers, addresses, and other details from each document by hand, which is time-consuming and error-prone. With MaiAgent's multimodal Agent, users simply upload a photo of the document, and the system automatically recognizes it and outputs structured JSON data that can be connected directly to downstream business systems.

Compared with traditional OCR solutions, MaiAgent combines the multimodal capabilities of large language models and offers the following advantages:

	Traditional OCR Engine	MaiAgent Multimodal AI
Layout adaptability	Requires a template for each document type	Automatically understands different document layouts
Front/back handling	Must be processed separately and matched manually	A single image can be recognized with both front and back
Field expansion	Requires code changes	Just edit the JSON Schema
Deployment cost	Build your own OCR service or buy a license	Platform configuration, no coding required
Error handling	Returns raw text that needs post-processing	AI understands semantics and corrects formats automatically

Use Cases


Financial account opening: Customers upload their ID card, and details such as name and ID number are extracted automatically to fill in the account opening form

HR onboarding: New employees upload their documents, and the system creates their records automatically

Medical registration: Patients upload their National Health Insurance card or ID card, and basic information is filled in automatically

Government service counters: Citizens present their documents, which are recognized instantly and carried into the application form

Solution Architecture




Mermaid 圖表

Setup Steps

Step 1: Create an Agent

In the left menu, go to **AI Features** → **AI Assistants**
Click **Create AI Assistant** in the upper right
Fill in the basic settings:

Field	Value
Agent Name	Document OCR Recognition Assistant
Large Language Model	Gemini 3.1 Flash-Lite (must support multimodal input)



Agent basic settings

> When choosing a large language model, make sure it supports multimodal input (images), such as the Gemini series. A text-only model cannot recognize image content.

Step 2: Configure the Reply Mode and JSON Schema

Switch to the **Reply Mode Settings** tab:

Field	Value
Reply Mode	RAG Q&A
Output Format	Output JSON format

After selecting **Output JSON format**, enter the following in the JSON Schema field below:

```
{
  "type": "object",
  "properties": {
    "document_type": {
      "type": "string",
      "description": "Document type, such as ROC national ID card, driver's
license, passport, National Health Insurance card, resident certificate, etc."
    },
    "name": {
      "type": "string",
      "description": "Full name of the document holder, read from the name field
on the front"
    },
    "gender": {
      "type": "string",
      "enum": ["男", "女"],
      "description": "Gender"
    },
    "date_of_birth": {
      "type": "string",
      "description": "Date of birth, in Minguo (ROC) calendar format"
    },
    "military_service": {
      "type": ["string", "null"],
      "description": "Military service status, such as exempt, completed, not yet
served, or alternative service. null for women or if the field is absent"
    },
    "place_of_birth": {
      "type": ["string", "null"],
      "description": "Place of birth, read from the back"
    },
    "id_number": {
      "type": "string",
      "description": "National ID number, 1 letter + 9 digits"
    },
    "expiry_or_issue_date": {
      "type": ["string", "null"],
      "description": "Issue date or expiry date, in Minguo (ROC) calendar format"
    },
    "address": {
      "type": ["string", "null"],
      "description": "Full address, read from the address field on the back,
including county/city, district, village, neighborhood, road/section, lane,
alley, number, and floor"
    }
  },
  "required": [
```

```
    "document_type", "name", "gender", "date_of_birth",
    "military_service", "place_of_birth", "id_number",
    "expiry_or_issue_date", "address"
  ]
}
```

Step 3: Write the Role Instructions

In the **Role Instructions** section on the same tab, enter the following:

```
You are a professional document OCR recognition assistant. Users will upload
images of identity documents, and you must carefully recognize all the text in
the image and extract the key information.

## Most important: carefully scan every area of the whole image

⚠️ Users often photograph the front and back of a document in the same image
(side by side or one above the other). You must:
1. First scan the whole image and identify how many document sides it contains
(there may be 1 or 2)
2. Recognize the text in each area separately
3. Merge the information from the front and back into the result

Never say "the back was not provided" or "the information is not in the image"
unless you have genuinely checked every area of the whole image and cannot find
it.

## Field locations on the ROC national ID card

### Front (has the national flag and photo)
- "Name" (姓名): next to the photo; this is the holder's own name
- "Date of birth" (出生年月日): Minguo year XX, month XX, day XX
- "Gender" (性別): marked "男" (male) or "女" (female)
- "ID number" (統一編號): at the bottom, 1 uppercase letter + 9 digits
- "Issue date" (發證日期): bottom left

### Back (has the parents and spouse fields; the background is usually darker)
- "Father" (父) and "Mother" (母): the parents' names (not the holder)
- "Spouse" (配偶): the spouse's name
- "Military service" (役別): military service status
- "Place of birth" (出生地): e.g. "臺北市" or "新北市"
- "Address" (住址): the full registered address

## Recognition rules
1. Document type: determine from its appearance
2. Name: must be read from the "Name" field on the front, never confused with the
father/mother/spouse on the back
3. Gender: read from the front
4. Date of birth: read from the front, in Minguo year format
5. Military service: read from the back. Women usually have none; fill in null
6. Place of birth: read from the back
7. ID number: read from the bottom of the front, recognizing it character by
character
8. Issue date: read from the "Issue date" field on the front
9. Address: read from the "Address" field on the back, including the full
county/city, district, village, neighborhood, road/section, lane, alley, number,
and floor

## Output notes
```

```
- Fill in null for any field that cannot be recognized
- All recognition results must be faithful to the image content; do not guess or
fabricate
```

Click **Save** to finish creating the Agent.

Step 4: Test the Recognition Results

Open the Agent's **Test Conversation**

Upload a document image (it may include both front and back)

Enter "Please recognize this document image"

Confirm that the returned JSON structure and field contents are correct

Usage Example

Upload an image containing both the front and back of an ID card, and the Agent will automatically recognize it and output structured JSON:


```json
{
  "document_type": "中華民國國民身分證",
  "name": "陳筱玲",
  "gender": "女",
  "date_of_birth": "民國57年6月5日",
  "military_service": null,
  "place_of_birth": "臺北市",
  "id_number": "A234567890",
  "expiry_or_issue_date": "民國94年7月1日",
  "address": "臺北市內湖區葫洲里1鄰民權東路六段283巷165弄218號"
}
```


> Recognition accuracy depends on image quality. When taking the photo, make sure the lighting is sufficient, avoid glare, and lay the document flat. If you photograph both the front and back together, arrange them side by side or one above the other.

JSON Output Field Reference

Field	Type	Source	Description
`document_type`	string	Front	Document type
`name`	string	Front	Holder's name
`gender`	string	Front	Gender (男 女)
`date_of_birth`	string	Front	Date of birth (Minguo year)
`military_service`	string/null	Back	Military service status
`place_of_birth`	string/null	Back	Place of birth
`id_number`	string	Front	National ID number
`expiry_or_issue_date`	string/null	Front	Issue date
`address`	string/null	Back	Full address

API Integration

This Agent can be connected to business systems through the MaiAgent API to automate document recognition.

Call Flow

sequenceDiagram participant Client as Business System participant API as MaiAgent API participant Bot as OCR Recognition Assistant Client->>API: POST /attachments-upload/ Upload document image API-->>Client: Return attachment ID Client->>API: POST /chatbots/{id}/completions/ Include attachment ID API->>Bot: Image recognition Bot-->>API: Structured JSON result API-->>Client: Return OCR JSON

Mermaid 圖表

Step 1: Upload the Image and Get the Attachment ID

```
curl -X POST
  -H "Authorization: Api-Key YOUR_API_KEY"
  -F "file=@/path/to/id_card.jpeg"
  "https://api.maiagent.ai/api/v1/attachments-upload/"
```

Note the `id`, `type`, `file`, and `filename` fields in the response; you will need them in the next step.

Step 2: Call the Agent for Recognition

```
curl -X POST
  -H "Authorization: Api-Key YOUR_API_KEY"
  -H "Content-Type: application/json"
  -d '{
    "message": {
      "content": "請辨識這張證件圖片",
      "attachments": [{
        "id": "{id returned in Step 1}",
        "type": "image",
        "file": "{file URL returned in Step 1}",
        "filename": "id_card.jpeg"
      }]
    },
    "isStreaming": false
  }'
  " ID}/completions/"
```

Step 3: Parse the Response

The returned `content` field is the recognition result in JSON format:

Python

```
import json
ocr_result = json.loads(response["content"])
print(ocr_result["name"])             # 陳筱玲
print(ocr_result["id_number"])        # A234567890
print(ocr_result["address"])          # 臺北市內湖區葫洲里1鄰民權東路六段283巷165弄218號
```

JavaScript

```
const ocrResult = JSON.parse(response.content);
console.log(ocrResult.name);              // 陳筱玲
console.log(ocrResult.id_number);         // A234567890
console.log(ocrResult.address);           // 臺北市內湖區葫洲里1鄰民權東路六段283巷165弄
218號
```

> For complete example code, see Playma-Co-Ltd/maiagent-api-examples.

Use Cases: Writing and Content Creation

Tasks such as translation, official documents, and marketing copy all have fixed formats and checkpoints, which makes them a good fit for a dedicated Agent. Write what the user must provide, what the output should look like, and what must not be done into the role instructions. Colleagues then open a conversation, supply the requested information, and get a consistently formatted first draft.

> Before you build one yourself, check the Agent Marketplace and the Agent Template Library. Official Agents already exist for scenarios in HR, legal, general affairs, retail, and more, such as job description writing, administrative announcement writing, press release drafting, and product listing copy. You can enable them directly, or apply a template and then modify it. If none fits, build your own following this page.

Applicable Scenarios

Agent	What the user provides	Key points to spell out in the role instructions
Translation	Text or an uploaded document, and the target language	Which language to translate into when none is specified, glossary of proper nouns, preserving the original paragraphs and formatting
Official Document Drafting	Document type (memo, letter, meeting notice, etc.), issuing and receiving units, key points for the subject and explanation, dates, attachments	Document structure and wording, asking follow-up questions when information is missing, and also accepting an existing draft and giving revision suggestions
Certified Letter Drafting	Sender and recipient details, what happened, specific demands and deadlines, follow-up actions if the other party does not comply, supporting documents	Produce only a draft, and remind users to have legal counsel or a lawyer confirm it before sending
Ad Ideas and Copy	Product or campaign, target audience, publishing channel and character limit	Offer several angles at once, and note the key appeal of each version
Copy Diagnosis	Copy type, target audience, intended goal, headline and body	Fixed scoring dimensions (for example appeal, persuasiveness, readability), strengths, areas for improvement, and a rewritten example
SEO Checkup	Page content or URL, target keywords, target audience	Checklist items (title, description, paragraph structure, keyword placement) and the report format

Agent	What the user provides	Key points to spell out in the role instructions
Training Material Design	Course topic, learners and their level, course duration	Lesson plan structure, in-class activities, and the format of exercises and quizzes
Conversation Practice Coach	The practice scenario (new-hire training, sales scripts, complaint handling) and the role to play	Play the other party first and hold the conversation, then give feedback and improvement suggestions after the user says "end"

The first four Agents each have a full build-out page, including role instructions you can paste directly, knowledge base and tool settings, test questions, and common questions:

Official Document Drafting Assistant

Legal Certified Letter Drafting

AI Smart Translation

Ad Copy and Idea Generation

Setup Workflow

1. Create the Agent

Create an Agent and put its purpose directly in the name, such as "Official Document Drafting Assistant," so colleagues can tell at a glance which one to use.

2. Write the Role Instructions

Following the table above, write down three things: what information to collect from the user, the output format, and what must not be done. For how to write them, see the Role Instruction Design Guide. Taking official document drafting as an example:

```
## Role
You are an official document drafting assistant, helping colleagues write
documents for correspondence with government agencies.

## Collect Information First
Before drafting, confirm the following information; ask about missing items one
by one and do not make assumptions:
1. Document type (memo, letter, official letter, meeting notice, etc.)
2. Issuing unit and receiving unit
3. Subject and key points for the explanation
4. Relevant dates and deadlines
5. Attachments (if any)

## Output
- Use the structure that corresponds to the document type, keep the subject
concise, and list the explanation as separate items
- When the user provides an existing draft, first list the suggested revisions,
then attach the full revised text

## Restrictions
- Do not fabricate regulation article numbers, document numbers, or dates; mark
anything uncertain as "To be confirmed"
```

3. Prepare Reference Materials (Optional)

When documents must follow company standards, upload templates, glossaries, brand voice guides, and past excellent examples to a knowledge base and attach it to the Agent. A translation Agent can hold a bilingual glossary of proper nouns, and an official document Agent can hold the templates your organization commonly uses.

4. Enable the Needed Features

To let colleagues upload documents (for translation, copy diagnosis, or supporting materials for certified letters), enable Allow file uploads in the function settings of this Agent's "Internal" chat platform.

To let the SEO checkup Agent read URLs on its own, add the Browser Tool to it. Without the tool, ask users to paste the page content directly.

To translate an entire PDF while preserving its layout, use the knowledge base's PDF document translation instead.

5. Make It Available to Colleagues

In role permissions, assign this Agent's "Internal" chat platform to the roles that need it. Colleagues can then select it from the organization-built tab of the Agent Marketplace and start a conversation. If a member cannot see the Agent, check which Agents the organization-built tab lists to troubleshoot.

Usage Reminders

For formal documents such as certified letters and official documents, AI output is a draft. Have the responsible person verify the facts, regulations, and wording before sending. When translating documents such as contracts and regulations, have a colleague fluent in both languages review the key clauses.

Official Document Writing Assistant

Official documents have fixed types, structures, and phrasing. The person handling the case knows what to say, but often gets stuck on "how to close the subject line, how to itemize the explanation, and how the wording differs between addressing a superior and a peer agency." Write these rules into the Agent's role instructions, and colleagues only need to provide the document type, the recipient, and the key points to get a correctly structured first draft, or paste an existing draft and ask the Agent to point out problems.

This page shows how to build an official document drafting Agent from scratch. What it produces is a **draft**; before issuing, the case handler and supervisor must still verify it against the agency's document handling rules.

Use Cases

Who uses it	What they use it for
Case handlers at government agencies and state-owned enterprises	Drafting replies to incoming letters, internal requests for instructions, announcements, and meeting notices
Corporate administrative, legal, and public affairs staff	Writing application letters, report letters, and reply letters to regulatory authorities
School faculty and staff	Internal requests within the school, and letters to education authorities
New hires who have just taken over document work	Paste a finished draft and ask the Agent to point out problems with structure, wording, and forms of address

Check for an Existing Official Agent First

The Official Built-in tab of the Agent Marketplace already has two similar Agents. If they meet your needs, there is no need to build your own:

Official Built-in Agent	Scenario category	Best for
Administrative Announcement Writing	General Affairs	Internal administrative announcements and notices (downtime, relocation, events, rule changes); fields that are not provided are kept as [TO BE FILLED]

Official Built-in Agent	Scenario category	Best for
Press Release Drafting	General Administration	External press releases, three headline options, short social media versions, and common Q&A

The role instructions of an official built-in Agent cannot be modified. If you need to write documents with a fixed structure such as memos (函), internal requests (簽), and letters (書函), or you want to apply your own agency's wording and templates, build one by following the steps below. You can also first apply the Administrative Announcement Writing template from the Agent Template Library to get an editable Agent and then modify its role instructions.

What to Prepare

An account that can create Agents (the role has the AI Assistants permission)

3–10 official document templates from your agency or company, covering the types you write most often (for example memos, internal requests, and meeting notices); mask personal data and sensitive content first

A glossary of preferred wording (optional): full agency names and abbreviations, commonly used closing phrases and forms of address, and the approval levels for internal delegation of authority

Decide who gets access: which roles' colleagues may use it

Setup Steps

1. Create the Agent

Go to AI Assistants and click Create AI Assistant. Name it for its purpose, for example "Official Document Drafting Assistant". For LLM Model, choose a model that your organization has enabled and that is good at long-form writing; keep the response mode at the default Agent Mode. For details, see Create an Agent.

2. Paste the Role Instructions

In Response Mode Settings, paste the following example into Role Instructions, then adjust it to your agency's rules. For writing principles, see the Role Instruction Design Guide.

```
## Role
You are an official document drafting assistant who helps colleagues write
documents for correspondence with government agencies and offers revision
suggestions on existing drafts.
You only handle drafting and revising official documents. For other requests,
politely explain that you cannot help.

## Confirm before writing
If any of the following is missing, ask for all of it at once before writing. Do
not assume anything yourself:
1. Document type: memo (函), letter (書函), internal request (簽), announcement (公
告), meeting notice (開會通知單), or other
2. Sender and recipient (full agency names; for an internal request, the handling
unit and the approval level)
3. Relationship: to a superior, to a peer, to a subordinate, or to the public or
vendors
4. Subject: the one matter this document asks the other party to know or handle
5. Key points of the explanation: background, basis (date and number of the
incoming letter, regulations, or meeting resolutions), and the facts
6. Matters the other party is asked to handle and the deadline (if any)
7. Attachments (if any)

## Structure
- Memo (函) and letter (書函): three sections: subject (主旨), explanation (說明),
and measures (辦法). Write the subject in one paragraph without itemization,
stating the purpose and expectation clearly;
  itemize the explanation and measures, numbering items in the order 「一、」「(一)」
「1.」. If there is no content for the measures section, do not force it.
- Internal request (簽): three sections: subject, explanation, and proposed action
(擬辦). The proposed action must offer a specific recommendation for approval.
- Announcement (公告): three sections: subject, basis (依據), and announcement
items (公告事項).
- Meeting notice (開會通知單): reason for the meeting, time, venue, chair, contact
person and phone number, attendees, observers, and remarks.

## Wording
- Choose forms of address and closing phrases according to the relationship: to a
superior, use 「鈞」「請鑒核」「請核示」;
  to a peer, use 「貴」「請查照」「請惠允見復」; to a subordinate, use 「貴」 or 「該」,
「請照辦」, 「請查照辦理」.
- Refer to yourself as 「本」 (本部, 本公司).
- Keep the text simple and clear, one point per sentence; write dates in ROC
calendar years and keep number usage consistent throughout.

## When revising an existing draft
First list the revision suggestions (structure, wording, forms of address,
unclear meaning), explain the reason for each point, then attach the full revised
text.
```

```
## Restrictions
- Do not fabricate incoming letter numbers, statute article numbers, dates,
amounts, or personal names; mark anything the user did not provide as 【待填】 ([TO
BE FILLED]).
- When citing regulations, write only articles that the user provided or that can
be found in the knowledge base, and remind the user to check the current text
before issuing.
- Add one line at the end of every draft: 「本稿為草稿，發文前請依貴機關文書處理規定核
對。」 (This is a draft; please verify it against your agency's document handling
rules before issuing.)
```

3. Attach a Template Knowledge Base (Optional)

To make drafts follow your agency's conventions, upload the prepared templates to a knowledge base, then attach it in the Agent's Knowledge Base Settings:

One file per template, with a file name that states the type and purpose, for example "函_復主管機關查詢.docx" or "簽_採購案請示.docx", which makes retrieval easier

The glossary of wording and the full names and abbreviations of agencies can be compiled into one document, or built as an FAQ

Add a sentence to the role instructions: "Before writing, search the knowledge base for templates of the same type and follow their format and wording"

It works without templates too; the Agent will write according to the structure and wording rules in the role instructions.

4. Enable File Upload

Colleagues often hand incoming letters or existing drafts directly to the Agent. Go to this Agent's "Internal" chat platform → Function Settings and enable Allow file uploads. To have the Agent output the draft as a Word file, also enable the Code Interpreter.

5. Open It to Colleagues

In Role Permissions, assign this Agent's "Internal" chat platform to the roles that need it. Colleagues can then select it in Internal Q&A and start a conversation.

Test Cases

Before going live, run through the following cases one by one and confirm the results match the "Expected result" column; if not, go back and adjust the role instructions.

#	Input	Expected result
1	"Write a memo for me"	Does not start writing; asks for the type, recipient, relationship, subject, and key points of the explanation all at once
2	"Our company is replying to the Ministry of Economic Affairs' letter dated March 2, ROC Year 115, stating that improvements were completed on time, with one improvement report attached"	Produces a memo draft: the subject is a single paragraph without itemization, the explanation is itemized and cites the date of the incoming letter, and the wording is correct for a superior agency; where the incoming letter's document number was not provided, it is marked [TO BE FILLED]
3	"Draft an internal request asking whether to approve an information security training for employees, with a budget of NT$120,000"	Three sections: subject, explanation, and proposed action; the proposed action gives a specific recommendation
4	"Please issue a meeting notice for a project progress meeting next Wednesday at 2 p.m. in Meeting Room 1"	All fields are filled in; fields not provided, such as the chair and attendees, are marked [TO BE FILLED], and the date is not converted into a wrong year, month, and day on its own
5	Paste a colloquial draft and ask it to revise	Lists revision suggestions and reasons first, then gives the revised full text
6	"Handle it in accordance with the Government Procurement Act, and add the article numbers for me"	Does not invent article numbers; asks the user to provide them or marks them as needing verification
7	"Write me a poem"	Explains that it only handles drafting and revising official documents

You can build these cases into a test dataset and rerun it whenever you adjust the role instructions or switch models.

FAQ

Can the document the Agent produces be issued as is?

No. What the Agent produces is a draft: the facts, dates, document numbers, legal basis, and approval level must all be verified by the case handler, and the document must go through review and approval according to the agency's document handling rules.

What if the format differs from our agency's?

Agencies often have their own conventions for item numbering, wording, and how attachments are indicated. Put your agency's templates in the knowledge base, and state the differences directly in the

"Structure" and "Wording" sections of the role instructions (for example, "our agency's meeting notices add a 'Required Documents' field"). This works more reliably than providing templates alone.

The Agent made up a document number or a statute?

Confirm that the role instructions still include the "Restrictions" section, and verify it with test case 6. If it still happens, move that restriction to the very top of the role instructions, or switch to a model with stronger reasoning ability.

Can it read scanned paper letters?

Yes. You can upload an image or PDF for the Agent to read and then draft a reply. If the scan quality is poor, recognition may be wrong, so check the dates and document numbers it quotes in its reply.

Colleagues cannot see this Agent?

This is usually because the "Internal" chat platform has not been assigned to their role. To troubleshoot, see which Agents are listed in the self-built tab of the organization.

Further Reading

Use Cases: Documents and Content Creation: design highlights of other document Agents

Legal Certified Letter Drafting

Use Official Built-in Agents

Draft Legal Notice Letters

The purpose of a certified letter (存證信函) is to preserve evidence of "what I told the other party on a given day": demanding payment of a debt, demanding performance of a contract, giving notice of termination, or demanding that infringement stop. It does not require sophisticated legal language, but it does need the **parties, facts, specific demands, deadline, and follow-up action** to be written clearly and completely. This is a good fit for an Agent to take care of: it asks follow-up questions when information is missing, and produces a well-structured draft once everything is there.

> What the Agent produces is a draft, not legal advice. Before sending, have legal counsel or a lawyer confirm the facts, the basis of the claims, and the wording. The Agent will also not send the letter on your behalf.

Use Cases

Scenario	Examples
Debt and payment collection	A loan that is due but unpaid, an overdue payment for goods
Lease disputes	Demanding unpaid rent, giving notice of lease termination, demanding return of a deposit
Contract performance	Demanding that the other party deliver, complete work, or fix defects as agreed; giving notice of rescission or termination of a contract
Consumer disputes	Demanding a refund, replacement, or repair of a defective product
Intellectual property	Demanding that the other party stop using an unauthorized trademark, image, or text

Users are typically legal, sales, or finance collections staff at a company, or case handlers who need to draft a version first and then hand it to a lawyer for review.

Check for an Existing Official Agent First

In the Official Built-in tab of the Agent Marketplace, the Legal scenario offers Agents such as Contract Drafting, Contract Risk Review, and Contract Information Extraction, which deal with the contract itself. There is currently no official Agent dedicated to drafting certified letters, so please build one by following the steps below. The two can be combined: first use Contract Information Extraction to pull the parties, amounts, and deadlines from the contract, then pass them to the certified letter Agent to draft.

What to Prepare

An account that can create Agents (the role has the AI Assistants permission)

2–5 certified letters your company has sent in the past (optional), with personal data masked, to serve as templates for tone and structure

Your company's fixed information (optional): full company name, registered address, responsible person, and the usual way of writing payment account details

Confirm who is responsible for review before sending (legal counsel or an outside lawyer), and write this into the reminder text in the role instructions

Setup Steps

1. Create the Agent

Go to AI Assistants and click Create AI Assistant. Name it, for example, "Certified Letter Drafting". For LLM Model, choose a model that your organization has enabled and that has stronger reasoning and long-form writing ability; keep the response mode at the default Agent Mode. For details, see Create an Agent.

2. Paste the Role Instructions

In Response Mode Settings, paste the following example into Role Instructions, and change the review contact in the reminder text to your company's actual practice.

```
## Role
You are a certified letter drafting assistant who helps users organize the facts and demands of a dispute into a draft certified letter,
or offers revision suggestions on an existing draft. You do not provide legal advice, and you do not judge who is right or wrong.

## Confirm before writing
If any of the following is missing, ask for all of it at once before writing. Do not assume or fill in anything yourself:
1. Sender: name or full company name, address (for a company, also the responsible person)
2. Recipient: name or full company name, address; if there are carbon-copy recipients, provide them as well
3. Relationship and basis: for example, which contract, which loan, which order (date, amount, subject matter)
4. Facts: in chronological order, what happened and where the other party failed to perform
5. Specific demands: what the other party is asked to do (pay how much, deliver what, stop which conduct)
6. Performance deadline: within how many days after receiving the letter, or a specified date
7. Follow-up if the deadline is missed: for example, pursuing remedies under the law, terminating the contract, filing a lawsuit
8. Supporting documents: contracts, IOUs, remittance records, conversation screenshots, and so on (names only are fine)

## Structure
1. Begin by stating the sender, recipient, and carbon-copy recipients
2. Subject: one sentence stating the purpose of the letter
3. Facts: list in chronological order, one matter per point, stating dates, amounts, and document names
4. Demands: clearly state what the other party is required to perform and the deadline
5. Consequences of default: the action the sender will take if the other party does not perform within the deadline
6. Closing: a short ending such as "This letter is hereby sent for your attention"

## Writing principles
- Write only the facts provided by the user. Keep the tone firm but plain, and do not use emotional, insulting, or threatening language.
- Write amounts both in Chinese capital numerals and Arabic numerals; write dates with the full year, month, and day.
- Do not cite statute article numbers the user has not provided. When a legal basis is needed, write "pursuant to the agreement between the parties and the relevant laws and regulations",
  and remind the user to have legal counsel or a lawyer add to it.
- Mark any information the user did not provide with [TO BE FILLED].
```

```
## Add this at the end of every output
"This draft does not constitute legal advice. Before sending, have legal counsel
or a lawyer confirm the content;
for the paper format and delivery method of a certified letter, follow Chunghwa
Post's regulations."

## What not to do
- Do not help fabricate facts or evidence, or write content that intimidates or
defames others.
- Do not answer questions like "Will I win?" or "Should I sue?"; ask the user to
consult a lawyer.
```

3. Add Templates and Company Information (Optional)

Upload the masked past certified letters and the company's fixed information to a knowledge base, attach it in the Agent's Knowledge Base Settings, and add a sentence to the role instructions: "Before writing, search the knowledge base for templates of similar situations and follow their tone and structure; when the sender is our company, use the full company name and address from the knowledge base."

> Templates in the knowledge base will be quoted in drafts. Before uploading, be sure to mask the names, addresses, ID numbers, and account numbers of the counterparties.

4. Enable File Upload

Users often need to upload contracts, IOUs, or conversation screenshots so the Agent can read the facts. Go to this Agent's "Internal" chat platform → Function Settings and enable Allow file uploads.

5. Restrict Who Can Use It

Certified letters involve disputed facts and personal data, so it is recommended to open the Agent only to the roles that need it, such as legal and collections: in Role Permissions, assign this Agent's "Internal" chat platform to those roles. Colleagues can then select it in Internal Q&A and start a conversation.

Test Cases

#	Input	Expected result
1	"The other party owes me money, write a certified letter for me"	Does not start writing; asks for the parties, loan date and amount, demands, deadline, and follow-up action all at once

#	Input	Expected result
2	Provides complete information: lender, borrower, a loan of NT$300,000 made on January 10, ROC Year 115, repayment agreed for April 10, still unpaid, demanding a transfer within 7 days	A well-structured draft: facts listed chronologically, amounts in both Chinese numerals and digits, a clear deadline, and the draft reminder at the end
3	Gives only the company name and no address	Marks the address as [TO BE FILLED] and reminds the user to add it
4	"Make it sound tough, say they'll regret it if they don't pay"	Keeps a firm but plain tone, does not write threatening language, and explains why
5	"Add which article of the Civil Code applies"	Does not invent an article number; suggests that legal counsel or a lawyer add it
6	Uploads a lease PDF and says the tenant is two months behind on rent	Reads the parties, rent, and payment date from the lease, and asks follow-up questions for missing information
7	"Can I win if I sue like this?"	Explains that it does not provide legal advice and suggests consulting a lawyer

FAQ

Does a certified letter written by the Agent have legal effect?

The function of a certified letter is to prove that "the sender expressed this content to the recipient on a given day". Its effect comes from being sent and retained in accordance with the post office's rules, and has nothing to do with who drafted it. Whether the content is sufficient to assert a right still has to be judged by legal counsel or a lawyer, so every draft should be reviewed by a person.

Can the draft be taken directly to the post office to send?

What the Agent produces is the body text. Certified letters at the post office have a designated paper format and number of copies, so please enter the reviewed text into the certified letter forms provided by Chunghwa Post or its online service, and proceed according to the post office's rules.

Can it cite statutes automatically?

We do not recommend letting the model cite article numbers from memory. If your company has commonly used legal basis paragraphs, have legal counsel confirm them and put them in the knowledge base, and state in the role instructions: "Only cite the legal basis paragraphs in the knowledge base."

Could the content of these disputes leak?

Conversations and uploaded files are visible only to members with permission. We recommend limiting the Agent to specific roles and masking third-party personal data in the knowledge base templates. For the platform's data protection information, see Security and Privacy.

Want external customers to use it too?

You can create a separate "Website" chat platform to offer it externally, but for external use, be sure to clearly state "does not constitute legal advice" in the opening message and at the end of every draft, and evaluate whether login authentication is needed. For setup, see Web Chat.

Further Reading

Use Cases: Documents and Content Creation: design highlights of other document Agents

Official Document Drafting Assistant

Use Official Built-in Agents

AI Translation

Translation is one of the tasks most often handed to AI, but pasting text straight into a general-purpose model tends to cause three problems: the company's product names and proper nouns are translated differently each time, the paragraphs and table formatting of the original are lost, and high-risk documents such as contracts get no reminder to be double-checked. Building a dedicated translation Agent lets you fix "which language to translate into by default, how to translate proper nouns, how to preserve formatting, and which documents need a reminder note", so colleagues can paste in content and get consistent translations.

Use Cases

Scenario	Input	Output
Everyday communication	Foreign-language emails, messages, announcements	A translation, with the original alongside when needed
Document translation	Uploaded Word, PDF, and presentation files	A translation that preserves the structure of headings, lists, and tables
Images and screenshots	Photos containing text, screenshots of system screens	Recognizes the text first, then translates it
Marketing and slogans	Ad copy, product slogans	A literal translation plus a version that fits the local feel
Product and technical documents	Specifications, operation manuals	Translated according to the company glossary of proper nouns

Three Approaches: Pick One First

Approach	Best for	How to do it
Enable the official built-in Agent	You want to use it right away and do not need custom rules	In the Official Built-in tab of the Agent Marketplace, find Multilingual Translation (Personal Productivity); an administrator enables it in Built-in Agent Management. Medical institutions also have Medical Translation (Healthcare), which preserves drug names, dosages, and units verbatim
Apply a template and then modify it	You want to start from the official design and add your	In the Agent Template Library, apply Multilingual Translation to get an editable Agent, then adjust it by following steps 2–3 on this page

Approach	Best for	How to do it
	company's proper nouns and tone	
Build from scratch	The rules are simple (for example, always Chinese to English), or you want full control of the role instructions	Follow all the steps on this page

Once an official built-in Agent is enabled, its role instructions cannot be changed, but you can import a dedicated knowledge base and put the glossary of proper nouns in it.

> To translate an entire PDF while preserving its original layout (chart positions, columns), use the knowledge base's PDF document translation instead; a conversational translation Agent is suited to text, paragraphs, and ordinary documents.

What to Prepare

An account that can create Agents (the role has the AI Assistants permission)

A glossary of proper nouns (optional but recommended): the original terms and specified translations for product names, departments and job titles, and industry terminology, in Excel or CSV format

A style guide (optional): the tone of external documents, wording to avoid, and number and date formats

Decide the default target language: which language to translate into when the user does not specify one

Setup Steps

1. Create the Agent

Go to AI Assistants and click Create AI Assistant. Name it, for example, "Translation Assistant". For LLM Model, choose a model that your organization has enabled: to translate images and screenshots, choose a model that supports image input; for short everyday texts, a faster-responding model can save Credits. Keep the response mode at the default Agent Mode. For details, see Create an Agent.

2. Paste the Role Instructions

In Response Mode Settings, paste the following example into Role Instructions, and change the default language to what your company needs.

```
## Role
You are a translation assistant who only translates and polishes translations.
For other requests, politely explain that you cannot help.

## Before you start
- When the user provides the source text and the target language, translate
directly without asking further questions.
- When no target language is specified: if the source text is Chinese, translate
it into English; if it is in any other language, translate it into Traditional
Chinese (Taiwanese usage).
- When no source text is provided, ask the user to paste text or upload a file.
- When the user uploads an image or screenshot, first list the text you
recognized, then give the translation.

## Translation principles
- Stay faithful to the original meaning: do not add information that is not in
the source, and do not omit or rewrite anything.
- Keep numbers, units, dates, amounts, personal names, place names, organization
names, code, and URLs exactly as in the original.
- Preserve the paragraph, heading, list, and table structure of the original.
- For proper nouns, first check the glossary in the knowledge base and use the
specified translation if there is one; if none is found, keep the original term
and add the original in parentheses after it,
  and do not invent an official translated name. Translate the same term the same
way throughout the text.
- Match the tone of the original: use a formal register for official documents
and contracts, and natural phrasing for marketing and colloquial content.

## Output
- By default, output only the translation. When the user requests it, switch to a
paragraph-by-paragraph "original
 translation" comparison.
- For creative content such as ad copy and slogans, provide a literal translation
plus a version that fits the local feel, and explain the difference between the
two.
- List a "Terminology" section at the end for terms that used the glossary or had
the original added in parentheses.

## Reminder
- For translations of contracts, regulations, medical documents, and financial
documents, add at the end:
  "This translation is for reference only. For formal use, please have it
reviewed by a professional familiar with both languages."
```

3. Attach the Glossary of Proper Nouns

Upload the glossary to a knowledge base and attach it in the Agent's Knowledge Base Settings. When preparing the glossary:

Put one term per row, with the columns "Original, Specified translation, Notes (applicable situations or translations that must not be used)"

List the translations of the same term in different languages in separate rows; do not cram them into one cell

When there are not many terms (a few dozen), you can also write them directly into the "Translation principles" section of the role instructions, which gives the most reliable hit rate

Frequently asked fixed translations can also be built into an FAQ

4. Enable File Upload and the Tools You Need

Go to this Agent's "Internal" chat platform → Function Settings and enable Allow file uploads, so colleagues can upload documents and images

To have the Agent output the translation as a Word or PDF file, enable the Code Interpreter

To let the Agent look up unfamiliar proper nouns online, add the built-in web search tool in the Tools tab; see Configure Tools for an Agent

5. Open It to Colleagues

In Role Permissions, assign this Agent's "Internal" chat platform to the roles that need it. Colleagues can then select it in Internal Q&A and start a conversation. To offer it to external users on your website or customer service entry point, create a separate Web Chat chat platform.

Test Cases

#	Input	Expected result
1	Paste a passage of Chinese without specifying a language	Translates directly into English without asking back
2	Paste a passage of Japanese without specifying a language	Translates into Traditional Chinese, using Taiwanese usage
3	"Translate into Japanese: This product comes with a 24-month warranty, priced at NT$12,800"	Numbers, amounts, and currency are kept as in the original
4	A sentence containing a product name from the glossary	Uses the specified translation from the glossary and lists the terminology at the end
5	A sentence containing a proper noun not in the glossary	Keeps the original and adds a note, without inventing a translated name

#	Input	Expected result
6	Paste a passage with headings, bullet lists, and tables	The translation keeps the same structure
7	Upload a system screenshot containing English	First lists the recognized text, then gives the translation
8	Paste a contract clause	The translation ends with a reminder for review by a professional
9	"Translate this slogan into English: 安心，從這裡開始"	One literal version and one version that fits the local feel, with an explanation of the difference
10	"Write an English job application letter for me"	Explains that it only translates and polishes translations

FAQ

Which languages are supported?

It depends on the language model you choose. Mainstream models give the best quality for Chinese, English, Japanese, Korean, and the major European languages; for less common languages, test with a few passages of real content first, and have a native speaker double-check important documents.

Are proper nouns still translated inconsistently?

First confirm the glossary is actually being retrieved: in the chat platform's Function Settings, enable Show cited documents and check whether the translation cites the glossary. If it does not, write the most critical terms directly into the role instructions, or split the glossary into smaller files with one term per row.

Can it translate a whole long document?

You can upload a document and ask the Agent to translate it, but for very long ones the reply may be split into parts or truncated. For a whole PDF where the layout must be preserved, use PDF document translation; for other long documents, we recommend translating chapter by chapter.

Can the translation be used externally as is?

For ordinary correspondence and internal documents, yes. For contracts, regulations, medical documents, and formal externally published documents, have colleagues familiar with both languages double-check the key clauses and numbers.

How is this different from just asking AI to translate in MaiGPT?

MaiGPT is suited to one-off personal translation; a translation Agent fixes the default language, proper nouns, and output format, so everyone in the company gets consistent translations and does not have to retype instructions every time.

Further Reading

Use Cases: Documents and Content Creation: design highlights of other document Agents

Multi-Language Support: Web Chat interface language and reply language settings

Use Official Built-in Agents

Ad Copywriting and Idea Generation

When marketers write ad copy, the most time-consuming part is often not the writing itself but finding the angle: which audience to address for the same product, which benefit to emphasize, which placement to use, and whether the length fits. The ad copywriting Agent turns this process into a routine: it first asks about the product, audience, and publishing channel, then gives you several versions with different appeals at once, each labeled with its angle and character count, so you can pick a direction and refine it further.

Use Cases

Scenario	Input	Output
Ad headlines and body copy	Product or campaign, audience, publishing channel	3–5 headlines + body copy + calls to action, each from a different angle
Idea generation	Product features and current selling points	Multiple appeal angles (features, emotion, situation, contrast, limited time), each with a one-sentence concept
Multi-channel rewriting	A finalized main copy	Versions rewritten to each channel's length and tone
A/B test material	Existing copy and the variable to test	Comparison versions that change only a single variable
Copy polishing	Existing copy	A concise version and an enhanced version that preserve the original meaning

Three Approaches: Pick One First

Approach	Best for	How
Enable the official built-in Agent	You want to start using it right away	In the Official Built-in tab of the Agent Marketplace, find Content Generation (Personal Productivity), which generates social media and marketing copy by topic and platform. For retail, there is also Product Listing Copy (Retail), which produces product descriptions and social media copy from product information or photos. An administrator enables them in Built-in Agent Management
Apply a template and	You want to add brand voice,	Apply Content Generation from the Agent Template Library to get an editable Agent, then adjust it following steps 2–3 on this page

Approach	Best for	How
then modify it	forbidden words, and a fixed format	
Build from scratch	You have clear placement specifications and output formats	Follow all the steps on this page

Before finalizing copy, check for exaggerated claims and prohibited terms. You can pair this with the official built-in Marketing Content Review (Personal Productivity): it only reviews and suggests revisions, and does not write copy for you.

What to Prepare

An account that can create Agents (the role has the AI Assistants permission)

A brand voice guide (optional but recommended): how the brand speaks, preferred and forbidden words, and how it addresses the audience

Product information: product features, specifications, prices, and what can be claimed publicly

5–10 past pieces of well-performing copy (optional) as tone examples

Length and format specifications for each publishing channel (refer to each platform's latest announcements)

Setup Steps

1. Create the Agent

Go to AI Assistants and click Create AI Assistant. Name it, for example, "Ad Copywriting Assistant". For LLM Model, choose a model that your organization has enabled and that writes well in Chinese; keep the response mode at the default Agent Mode. For details, see Create an Agent.

2. Paste the Role Instructions

In Response Mode Settings, paste the following example into Role Instructions, and replace the channel specifications and brand rules with your company's own.

```
## Role
You are an ad copywriting assistant who helps marketing colleagues brainstorm ad
angles and write ad copy.

## Confirm before writing
If any of the following is missing, ask for all of it at once before writing:
1. What the product, service, or campaign is, and the one thing people should
remember most
2. Target audience: who they are and in what situation they would need it
3. Publishing channel and placement (for example, search ads, social posts,
newsletter subject lines, website banners)
4. The action you want the audience to take (purchase, sign up, request
information, visit a store)
5. Words that must or must not appear, campaign period, and offer details (if
any)

## Output format
- Provide 3 to 5 versions at once, each using a different angle, for example:
  functional benefit, solving a pain point, usage scenario, contrast with the
status quo, limited-time incentive.
- For each version, list in order: angle (a one-sentence description of the
appeal), headline, body copy, call to action, character count.
- Control the length according to the publishing channel. If the user gives a
character limit, follow it strictly and state the actual character count.
- Finally, in one or two sentences, recommend which two versions to test first
and why.
- If the user only wants inspiration, list 5 or more angles, each with a one-
sentence concept, instead of writing complete copy.

## Writing principles
- Follow the brand voice guide in the knowledge base; if there is no guide, use
clear, conversational, and unexaggerated Taiwanese Chinese.
- Use only the product facts provided by the user or the knowledge base. Do not
invent features, figures, prices, awards, or customer testimonials.
- Do not use absolute terms such as "No. 1", "best", "only", or "guaranteed"
unless the user provides supporting evidence.
- For claims in regulated areas such as medical, health care, finance, and food,
remind the user to have legal or compliance staff review them.
- Do not disparage or allude to specific competitors.

## When revising existing copy
First point out the one to three most worthwhile things to change, then provide
one concise version and one enhanced version.
```

3. Attach Brand and Product Data

Upload the brand voice guide, product information, and past good copy to a knowledge base, and attach it in the Agent's Knowledge Base Settings:

Use one document per product, clearly stating what "can be said publicly" and what "cannot be said"

Label past copy with its channel and performance (for example, "social post, high engagement rate") so the Agent has a better basis when referencing it

Campaign schedules and offers change frequently. Update them for each campaign, or have users provide them in the conversation

4. Enable the Needed Features

File upload: Go to this Agent's "Internal" chat platform → Function Settings and enable Allow file uploads so colleagues can upload product brochures or product photos

Web references: To let the Agent read product pages or campaign pages, add the Browser Tool or the system's built-in web search tool in the Tools tab. See Configure Tools for an Agent

Images: To also produce ad concept images, add the built-in AI image generation tool

5. Open It to the Marketing Team

In Role Permissions, assign this Agent's "Internal" chat platform to marketing-related roles. Colleagues can then select it in Internal Q&A and start a conversation.

Test Cases

#	Input	Expected result
1	"Write an ad for me"	Does not start writing; asks for the product, audience, channel, action, and constraints all at once
2	"New insulated tumbler, highlighting 12-hour cold retention, aimed at commuting office workers, for a social post, with the goal of driving purchases"	3–5 versions, each with an angle, headline, body copy, call to action, and character count, ending with a recommendation of which versions to test first
3	Same as above, plus "headline no more than 15 characters"	Every headline is within 15 characters and shows the character count
4	"Don't write copy yet, just give me some angles"	5 or more angles with one-sentence concepts, without writing complete copy
5	"Write for me: No. 1 in sales nationwide, guaranteed effective"	Does not write it as is; explains that supporting evidence is needed and offers alternative wording
6	Asks to include a feature that is not in the product information	Does not invent it; asks the user to confirm or provide the information

#	Input	Expected result
7	Pastes a health supplement ad and asks it to strengthen the efficacy claims	Reminds the user that regulated claims must be reviewed by compliance staff
8	Pastes existing copy and asks for revisions	Points out the most worthwhile changes and provides a concise version and an enhanced version
9	"Turn this social post into a newsletter subject line and a search ad headline"	Rewrites to each channel's length and tone

FAQ

The output all looks alike and lacks the brand's flavor?

This is usually because there is no basis for the brand voice. Put the voice guide and 5–10 representative past pieces of copy into the knowledge base, and write the three to five most important rules directly in the "Writing principles" of the role instructions (for example, how to address the audience, and commonly used and forbidden words).

Can I publish it directly?

First have the marketing owner confirm that the facts and offer details are correct, and check that the copy complies with the publishing platform's advertising policies. Regulated industries (medical, health care, finance, food, and so on) must go through compliance review.

The character count often exceeds the placement limit?

State the character limit for each channel in the role instructions and require each version to show its actual character count. You can also say directly in the conversation, "headline within 15 characters, body within 60 characters". The model's character counts are occasionally off, so rely on the platform's own check in its console before publishing.

Can it produce many pieces at once?

Yes, you can ask in the conversation for "three pieces for each angle". For large batch output (for example, hundreds of products), it is better to use API integration and call it programmatically one item at a time.

How is this different from the official "Content Generation" and "Product Listing Copy" Agents?

The official built-in Agents work out of the box and are maintained by the official team, but their role instructions cannot be changed. If you need a fixed brand voice, placement specifications, or output format, apply a template from the template library and modify it, or build your own following this page.

Further Reading

Use Cases: Documents and Content Creation: design highlights of other content Agents, such as copy diagnosis and SEO checks

AI Smart Translation: translate finalized copy into other languages

Use Official Built-in Agents

MaiAgent Serve | Customer Service

MaiAgent Serve Overview

Make every conversation a better service experience.

MaiAgent Serve brings AI that understands your company to every customer touchpoint. Your website, LINE, Messenger, and phone line can share the same Agent, knowledge, and rules. AI serves customers around the clock and hands the conversation off to a human support agent when a person needs to step in.

Serve and MaiAgent Build are the same platform: Agents, knowledge bases, conversation platforms, and human handoff rules are all configured in Build. This section organizes the go-live steps by support option and explains how support agents and supervisors use it every day.

Three Options

Option	What it does	Who it's for	What to prepare	Start here
Text Support	The Agent replies to customers directly on conversation platforms such as your website, LINE, FB Messenger, and Email, and hands off to a human when needed	Support teams that want AI to handle large volumes of repetitive questions first	Product documents or FAQs, an account on at least one conversation platform (for example, a LINE Official Account), and support agents to take over conversations	Text Support: From Zero to Go-Live
Voice Support	The Agent talks with customers by voice: customers click the headset icon on a web page to call, or call your support hotline	Teams with a phone support hotline that want to shorten wait times	An Agent that already answers well in text, and the AI voice assistant enabled for your organization; answering phone calls also requires enabling the Call Center and preparing a SIP line	Voice Support: From Zero to Go-Live
Support Copilot	The Agent drafts a reply for every customer message behind the scenes, and the support agent confirms or edits it before sending	Support teams that want a human to confirm every reply	A connected conversation platform with a bound Agent, and support agents with the All Conversations permission	Support Copilot

The three options can be combined: the same Agent can reply by text on your website and answer calls by voice, and the same conversation platform can let AI reply automatically while Copilot helps support agents handle conversations handed off to them.

> Voice support and the Call Center are available only on MaiAgent Cloud (SaaS) and on private clouds with the voice component enabled. They are not available for on-premises deployments. See Voice Support: From Zero to Go-Live for details.

Who Should Read What

You are···	Read this
A builder (IT or Agent administrator)	Follow the steps on each option's guide page and complete the setup in MaiAgent Build: Create an Agent, Publish to a Conversation Platform, Conversation and Human Handoff Settings
A support agent	Daily Operations for Support Agents: view all conversations, take over and return to AI, draft replies with Copilot, look up contacts
A support supervisor	AI Customer Service Quality Management and Inbox Analysis: understand quality scores, find incorrectly answered conversations, and fix them

One Agent, Multiple Conversation Platforms

One Agent can be connected to multiple conversation platforms, and the knowledge and role instructions behind its answers stay the same. Settings such as appearance, greeting, and human handoff rules belong to each platform, with one set per platform. For the platforms you can connect and the credentials to prepare, see Publish to a Conversation Platform; for each platform's settings, see Conversation and Human Handoff Settings.

AI and Human Collaboration

Human handoff: Builders decide when to hand off, the service hours, and how conversations are dispatched in Human Support Handoff Settings; support agents take over, reply, and return the conversation to AI by following Human Agent Takeover and Replies.

AI drafts, humans send: After you enable Support Copilot, support agents get AI suggestions in the conversation and send them after confirming.

Continuously Improve Service Quality

AI Customer Service Quality Management: Supervisors learn to read quality scores, find incorrectly answered conversations, and fix them.

Inbox Analysis and Inbox Search: Find the questions customers ask most often from conversation records.

Add Conversation Records to FAQ: Turn questions the AI answered poorly into FAQs so it answers correctly next time.

Common Starting Point: Text Support

Most teams start with text support, then add voice or Copilot once things are stable:

Prepare a set of common questions

Organize the questions your support team answers most often into an FAQ and knowledge base documents, and give them to the Agent as the basis for its answers.

Connect one conversation platform first

Go live on the one platform your customers use most, such as the website Web Chat or a LINE Official Account, and set up human handoff.

Verify with real questions, then expand

Check answer quality with real customer questions, then connect other platforms once things are stable. For the full steps, see Text Support: From Zero to Go-Live.

Use Cases

Text Support: Regulation inquiry assistant, product inquiry assistant

Voice Support: IVR intent recognition, voice call summaries, voice call quality inspection

> To embed Web Chat in your own product with code, or to connect conversations to an existing customer service system, see Web Chat Embedding and SDK and Third-Party Customer Service System Integration in the Technical Guide.

Text Customer Service: From Setup to Launch

Text support lets an Agent reply to customers directly on conversation platforms such as your website, LINE, FB Messenger, and Email, and hand off to a human support agent when it can't answer or the customer asks for one. This page lists six steps in go-live order. The details of each step are on the corresponding MaiAgent Build feature page.

> Steps 1–5 are done by the builder (IT or Agent administrator), who needs permissions for the relevant Agent, knowledge base, and conversation platform. See Role Permission Management. We recommend involving a support supervisor in step 6.

Go-Live Steps

Create an Agent

Create an Agent, and use the Role Instructions to state clearly which company it represents, the scope it can answer, and its tone. You can also apply an official template from the Agent Template Library and then modify it. To have the Agent handle a certain type of task by a fixed process (for example, looking up orders or opening tickets), first create a skill and then bind it to the Agent. Skills travel with the Agent, so every conversation platform you connect later will use them.

Prepare a knowledge base

Create a knowledge base and upload product documents. For questions with fixed answers that need precise replies, build them as FAQs. Website content can be imported with a crawler. Use Search Test to confirm that the questions customers ask most often find the right passages, and then attach the knowledge base to the Agent.

Connect a conversation platform

In Publish to Conversation Platforms, compare the credentials each platform requires. Connect the one your customers use most first, for example Website or LINE, and select this Agent to reply. One Agent can be connected to multiple platforms at the same time: create one conversation platform for each platform and select the same Agent, and the role instructions, knowledge bases, and skills are shared, so there is nothing to redo. After connecting each platform, send a real message on that platform to confirm you get a reply before connecting the next one.

Adjust platform settings

Each platform has its own settings: the greeting and conversation starter questions are in Interaction Settings, switches such as file upload and cited sources are in Function Settings, and the hours when AI replies are in Auto-Reply Settings. For what each tab controls, see Conversation Platform Settings Overview.

Set up human handoff

In Human Handoff Settings, turn on handoff and fill in the handoff conditions, service hours, and assignment method. Then use Human Handoff Notifications so support agents receive alerts. If you want the AI to draft replies first and have a support agent send every reply, use Support Copilot instead.

Go-live check and quality monitoring

Before going live, test with real customer questions, or create a test dataset and run an automatic evaluation. Also trigger a human handoff once to confirm that support agents receive it. After going live, check regularly following AI Support Quality Management, use Conversation Platform Analytics to find common questions, and add conversations the Agent answered poorly to the FAQ.

After Go-Live

For the daily work of support agents, such as viewing all conversations, taking over from and handing back to the AI, and looking up contacts, see Daily Operations for Support Agents.

To connect additional conversation platforms, repeat steps 3–5. One Agent can serve multiple platforms at the same time.

To push conversation events to your own systems, see Webhook.

Use Cases

Use Case: Text Support: regulation lookup assistant, product inquiry assistant

Voice Customer Service: From Setup to Launch

Voice support lets an Agent serve customers by listening and speaking. There are two entry points, both using the same Agent and the same voice settings:

Web voice: Customers click the headset icon in the Web Chat input bar to talk with the Agent by voice.

Phone: A SIP line from your carrier or your own PBX is connected to the Call Center, and calls to the support hotline are answered by the Agent.

This page lists the steps in go-live order. The details of each step are on the corresponding MaiAgent Build feature page.

Before You Start

Item	Description
Deployment type	Available on MaiAgent cloud (SaaS). For private cloud, it must be enabled in the deployment settings and the real-time voice components must be deployed. On-premises deployment does not provide the voice assistant or the Call Center. For a comparison of features by deployment type, see Deployment Types and Feature Comparison in the technical manual.
Organization features	Under Advanced Features in the Organization Overview, AI Voice Assistant must be enabled. Answering phone calls also requires Call Center. If they are not enabled, contact your MaiAgent representative.
Permissions	Enabling voice requires permission to edit the Agent. Setting up a phone line requires the Call Center Inbound Call Settings permission. See Phone Support (Call Center).

Go-Live Flow

Prepare an Agent that answers questions well

First tune the role instructions and knowledge base in text and confirm the answers are correct, and then add voice. For how, see steps 1–2 of Text Support: From Zero to Go-Live.

Enable voice

In the Agent settings, find Voice Assistant Settings under Reply Mode Settings, turn on Enable Voice Assistant, and select the Voice Assistant Mode and the provider. For the differences among the three modes, interruption control, and tool limitations, see Voice Assistant (Voice Agent).

Set the voice greeting

Set the Voice Greeting in the conversation platform's Interaction Settings. Web voice uses the settings of the web platform where the customer is. Phone uses the default greeting of this Agent's API conversation platform.

Try speaking on the web

After voice is enabled, a Voice Mode button appears below the public access URL in the web platform's Basic Settings, which opens a voice conversation directly. The headset icon also appears in the input bar of Web Chat embedded in your website. Confirm that the Agent understands you, answers correctly, and has a suitable speaking speed and tone.

Connect a phone line

If you only offer web voice, you can skip this step. In the Call Center, add a SIP trunk and a number, bind the number to this Agent, and wait until the Sync Status changes to Synced. See Phone Support (Call Center).

Make a test call

Call the number from a mobile phone and confirm that the Agent answers and responds correctly. Then go to Call History to view the record of this call and its voice transcript. See Call History.

> The Call Center currently has no setting for transferring calls to a human agent or extension. If you need to transfer calls to an existing contact center system, contact your MaiAgent representative to evaluate an integration approach.

After Go-Live

Check calls: Call records and status are in Call History. Each call is also a conversation, which you can view in All Conversations.

Check usage: STT seconds, TTS characters, and voice model token counts are on the Voice Assistant tab of Usage Statistics.

Adjust how it speaks: If replies are too long or are often interrupted, go back to Voice Assistant (Voice Agent) and adjust the interaction mode and interruption control.

Use Cases

For other applications of voice data, such as IVR intent recognition, call summaries, and call quality inspection, see Use Case: Voice Support.

Customer Service Copilot

Support Copilot lets an Agent draft replies behind the scenes for human support agents: when a customer sends a message, the AI generates an "AI suggestion" that only support agents can see. Agents can send it as is, edit it before sending, or ask the AI to regenerate it. It suits support teams that want to adopt AI but still want a human to review every reply.

AI suggestions are generated by the Agent bound to the conversation platform. They use that Agent's role instructions, knowledge bases, and tools, so the quality matches replies the AI sends directly.

This page has two parts: Enable AI Copilot is set up by the builder in the conversation platform settings in MaiAgent Build; How Support Agents Use It explains how support agents generate, edit, and send AI suggestions in a conversation.

> AI suggestions are never sent to the customer. Content reaches the customer, under the support agent's identity, only after the support agent clicks Send.

Who Can Use It

Task	Required permission
Turn on or adjust AI Copilot	Conversation platform permission, with edit permission on that conversation platform
Generate and send AI suggestions in a conversation	All conversations permission, and the user's role must be assigned to the Agent bound to that conversation platform

For how to set up roles and permissions, see Role and Permission Management.

Enable AI Copilot

AI Copilot is a tab on the conversation platform settings page, configured separately for each conversation platform; for the structure of the settings page, see Conversation Platform Settings Overview. Website, LINE, Messenger, Instagram, Telegram, Microsoft Teams, WhatsApp, Email, Slack, LINE WORKS, Team+, Viber, and other platforms all have this tab.

Open the conversation platform settings

From the left menu, go to Customer Conversations → Conversation Platforms, find the platform you want to configure in the list, and click Edit. For other ways to get there, see Open the Settings Page.

Switch to the AI Copilot tab

Select the AI Copilot tab (for the website platform, it is in the Advanced Features group in the left navigation). This tab appears only after the platform has been created.

Turn it on and choose a trigger mode

Turn on Enable AI Copilot, choose when suggestions are generated under Trigger Mode, and finally click Save.



AI Copilot tab: turn it on, choose a trigger mode, then click Save

Two Trigger Modes

Mode	When suggestions are generated	Does the Agent reply to the customer directly?
Manual	Only when a support agent clicks the robot icon next to a customer message in the conversation	Works as originally configured; Copilot does not affect automatic replies

Mode	When suggestions are generated	Does the Agent reply to the customer directly?
Every incoming message	Automatically, for every customer message received	No; the support agent decides whether to send the suggestion

> After you choose "Every incoming message", the Agent no longer replies to customers automatically, and it no longer hands off automatically according to the human handoff settings. Every customer message needs to be handled by a support agent, so make sure you have enough staff to reply promptly before switching to this mode.

How Support Agents Use It

Open a conversation in Customer Conversations → All Conversations. On platforms with AI Copilot enabled, a robot icon appears below each customer message; hovering over it shows Generate AI Suggestion.



Robot icon below a customer message: click it to generate an AI suggestion

Generate a suggestion: Click the robot icon, and an AI Suggestion card appears below the message, with the content appearing word by word. In "Every incoming message" mode, suggestions are generated

automatically without a click; if you want another version, you can still click the icon to generate one again.

Check the content: When the AI cites knowledge base content, the card also shows the sources so support agents can verify them. Click the card's title bar to collapse or expand the content.

Send or edit:

Send: Sends the suggestion directly to the customer, with the same effect as a support agent sending a message from the input box.

Edit: Puts the suggestion into the input box below so you can modify it and send it yourself. Any text already in the input box is replaced.

Regenerate: Click the refresh icon in the top-right corner of the card (Regenerate), and the AI generates a new version.



AI suggestion card: status "Ready", version switcher "2
2", the regenerate icon, and Edit and Send

For how to send replies and the rules for taking over a conversation, see Human Agent Takeover and Replies.

Switch Versions

When several suggestions have been generated for the same customer message, the card's title bar shows a version switcher, such as `2
3`. Use the left and right arrows (Previous Version, Next Version) to compare versions, then pick one to

send or edit. While a new version is being generated, the card stays on the version being generated and you cannot switch for the time being.

Suggestion Status

Status	Meaning	What you can do
Generating	The AI is generating the suggestion	Wait for it to finish; you cannot send, edit, or regenerate during this time
Ready	The suggestion is complete	Send, Edit, or Regenerate
Failed	Generation did not succeed this time, and the card shows the reason	Click the regenerate icon to try again

Open the Copilot View in a New Tab

The robot icon in the conversation title bar (hovering over it shows Conversation Copilot) opens a compact view of the conversation in a new tab, keeping only the messages, AI suggestions, and the input box, which makes it easy to use side by side with other systems.

Credits Usage

Each AI suggestion generated consumes Credits just like an Agent reply, calculated based on the models and tools the Agent uses. Clicking Regenerate produces a new suggestion and is billed again. Suggestions that fail to generate do not deduct Credits.

"Every incoming message" mode generates a suggestion for every customer message, so usage is usually higher than in Manual mode. For rates and consumption records, see Credits Pricing.

FAQ

I don't see the robot icon in the conversation.

Confirm that the platform this conversation belongs to has Enable AI Copilot turned on in the AI Copilot tab and that you saved. The robot icon appears only next to messages from customers, not next to messages sent by the AI or support agents.

I clicked the robot icon and got "Suggestion generation failed."

Common causes are that AI Copilot has been turned off for the platform, or that the platform has no Agent bound. AI Copilot needs the platform's bound Agent to generate suggestions, so go to the platform's Basic Settings and confirm that an Agent is selected.

Will customers see AI suggestions?

No. AI suggestions appear only in the support agent's conversation view and are not sent to customer-facing channels such as websites or LINE. Customers receive content only when a support agent clicks Send, or sends it themselves after editing.

After switching to "Every incoming message", why has the AI stopped replying?

This is by design in this mode: the AI only generates suggestions, and the support agent decides whether to send them. To restore AI automatic replies, switch back to Manual or turn off Enable AI Copilot.

Daily Customer Service Operations

After an Agent goes live, support agents handle conversations that need a human in Customer Conversations. This section has two handbooks:

You are	Read first	Contents
A support agent	Support Agent Handbook	Getting started on day one, a day's workflow, status and tab definitions, step-by-step scenario handling, common mistakes, and a printable checklist
A support supervisor	Support Supervisor Guide	Daily and weekly routines, scheduling and availability, workload and reassignment, quality spot checks, turning wrong answers into FAQs, how to read analytics, permission setup

Handoff conditions, assignment rules, and conversation platform settings are managed by the builder in Conversation and Human Handoff Settings.

> Opening All Conversations requires the Customer Conversations permission and the All conversations permission under it. Which conversation platforms' conversations you can see depends on the permissions of your role. Administrators set permissions in Role and Permission Management; for the recommended setup, see Support Supervisor Guide: How to Assign Permissions to Support Agents.

Support Agents

Task	Where to look
Get started on day one and follow the daily routine	Support Agent Handbook
Start your shift or pause incoming assignments, set time off	Set Your Own Availability
View conversations from each conversation platform and find the ones to handle	All Conversations
Take over a handed-off conversation, reply, transfer it to a colleague, or return it to the AI	Human Agent Takeover and Replies
Let the AI draft a reply first, then confirm or edit it before sending	Support Copilot: How Support Agents Use It
Find out who the customer is and view past conversations	Contacts

Task	Where to look
Review the full course of a single conversation, including the tools the AI used	Conversation Viewer
Find past conversations by keyword	Inbox Search
Handle specific situations (the customer wants a human, is upset, or the AI answered incorrectly)	Support Agent Handbook: Scenarios

Support Supervisors

Task	Where to look
What to check every day and every week	Support Supervisor Guide
Understand what customers ask most and how much the AI resolves	Conversation Platform Analytics, How to Read Conversation Platform Analytics
Check AI answer quality and fix incorrect answers	AI Support Quality Management, Quality Spot-Check Process
Adjust support agents' availability and time off, and view each agent's workload	Support Agent Availability, Support Agent Workload
Update conversation statuses in bulk	All Conversations: Batch Update Status
Grant permissions to new support agents	How to Assign Permissions to Support Agents

Customer Service Agent Handbook

This page is for agents who handle customer conversations in Customer Conversations every day. Start with "Your First Day" to understand the interface and statuses, then follow "The Daily Workflow." For specific situations, go straight to Handling Scenarios for the steps you need. Existing pages explain each feature in full; this page tells you what to do and when.

Supervisors can find shift scheduling, workload management, quality spot checks, and permission settings in the Customer Service Supervisor Guide.

Your First Day

1. Sign In and Find Your Workspace

After signing in to the admin console, open Customer Conversations → All Conversations from the left menu. If you cannot see this menu, your role does not yet have Customer Conversations Permission and its child permission, All Conversations Permission. Ask your supervisor to follow Supervisor Guide: Configuring Permissions.

2. Understand the Interface

The interface has three columns, from left to right: platform → conversation → conversation content:

Area	What You Will Use
Leftmost column	All Conversations at the top shows all platforms. Individual Conversation Platforms (website, LINE, Teams, etc.) appear below; click one to view only that platform
Middle column	The Mine Unassigned All tabs, search box, and filter button; each conversation shows who is currently handling it
Right side	The contact name, Details, and Copilot icon at the top; the status bar and messages in the middle; the message box and the conversation's Auto Reply toggle at the bottom



The three columns on the All Conversations page: conversation platforms on the far left, tabs and the conversation list in the middle, and the status bar, messages, and message box on the right

For full descriptions of the fields and buttons, see All Conversations: Page Layout.

3. Set Your Availability

Your availability appears to the right of the list heading in the middle column. Switch to Available when your shift starts, to Pause Assignments when you leave your desk, and use My Time Off··· to set a time range for leave. Your status applies to all conversation platforms you belong to. For instructions and the effects of each status, see Set Your Availability.



Availability menu: Available, Pause Assignments, and My Time Off

> If the menu shows “Not on Assignment List,” the system does not automatically assign conversations to you, so there is no need to switch your status. You can still take over conversations from the Unassigned tab. To receive automatic assignments, ask your supervisor to add you to the platform’s Assignment List.

4. Check That You Receive Notifications

When a conversation is assigned to you, you receive an email and a notification in the notification center at the top right (depending on the Human Handoff Notification settings). On your first day, ask your supervisor to assign you a test conversation and confirm that you receive both notifications.

> Conversations waiting in the Unassigned tab that have not been assigned to anyone do not trigger emails. If your platform uses manual pickup or accepts messages left by customers, check this tab regularly. See Unassigned Conversations.

The Daily Workflow

Step	What to Do	Details
Start your shift	Set your availability to Available; check the Mine tab for unresolved conversations from yesterday	Set Your Availability
Check the queue	Switch to the Unassigned tab and look for conversations whose status bar says “Waiting for a Human Agent”; take the longest-waiting ones first	Unassigned Conversations
Take over	Conversations assigned by the system appear directly in Mine; open one to reply. To claim a conversation yourself, click Take Over	Take Over a Conversation
Review the context	Before replying, open Details at the top of the conversation to review the transfer reason, conversation summary, contact information, and tags	Conversation Details
Reply	Reply in the message box. If Copilot is enabled for the platform, you can first Generate AI Suggestion, then review it before sending or editing	Customer Service Copilot: Using Suggestions
Transfer return to AI	If you cannot handle the issue, Transfer it to a colleague and enter a reason. Once your work is done and AI can handle follow-up questions, select Return to AI Agent	Transfer and Return to AI
Resolve	Once the customer’s issue is resolved, click Resolve on the status bar. First use Edit Summary if you need to preserve context. If unsure, see Unsure Whether to Resolve	Take Over, Transfer, and Return to AI, Edit the Conversation Summary
End your shift	Resolve or transfer the conversations you are handling, then set your availability to Pause Assignments. Leave conversations you will return to tomorrow in Mine	See the Checklist below

> Send your first reply as soon as possible after receiving an assignment. If Reassign on Timeout is enabled, conversations assigned by the system that you have not replied to within the waiting timeout are automatically reassigned to a colleague.

Clicking Transfer opens the dialog below. Enter a transfer reason, select tags if needed, then click a colleague’s card to transfer the conversation to them.



Transfer a conversation: enter the transfer reason, then click a colleague’s card to complete the transfer

Status and Tab Definitions

Conversation Status

Each conversation has one of three statuses. Use Filter by Status to find them:

Status	Meaning	How It Starts	How It Ends
In Progress	The conversation is ongoing and handled by AI or an agent	The default for new conversations; resolved conversations return here when the customer sends another message	Click Resolve
Queued	Human handoff has been triggered, and the conversation is waiting for an agent to take over	AI determines that human handoff is needed, or a customer leaves a message outside service hours	Someone takes over, the customer cancels, or the queue times out and the conversation returns to AI
Resolved	The issue has been handled	Click Resolve, or a supervisor updates conversations in bulk	Click Reopen, or a new customer message automatically reopens it

> If a customer sends another message in a resolved conversation, it automatically returns to In Progress and AI auto reply resumes. The previously assigned agent is cleared. To track this customer’ s follow-up, use Filter by Contact.

Status Bar and List Indicators

When you open a conversation, the status bar above the messages tells you who is handling it and what you can do:

Status Bar Text	Meaning	Available Actions
AI Agent Handling	AI is replying automatically; the customer is not waiting for a human	Click Take Over if you need to intervene
Outside AI Reply Hours · Awaiting Agent, No AI Assistant Linked to Channel · Awaiting Agent	AI will not reply (outside AI Auto Reply Hours, or no AI assistant is selected for the conversation platform); the conversation is not automatically assigned to an agent either	Click Take Over or Assign Agent. All new conversations on platforms using only human agents have this status
Waiting for a Human Agent · Waiting N Minutes	Human handoff has occurred, and the conversation is queued	Click Take Over; take the longest-waiting conversations first

Status Bar Text	Meaning	Available Actions
No Agent Assigned	AI auto reply is off, but no agent is responsible for the conversation	Click Take Over; in the Unassigned tab, you can also use the assignment icon in the list to assign it to a colleague
You Are Handling This Conversation	This conversation is yours	Reply or Resolve; the Mine tab also offers Transfer and Return to AI Agent
“○○ Is Handling This Conversation”	A colleague is responsible	Avoid interrupting; if necessary, Transfer it to yourself or someone else
This Conversation Is Resolved	The conversation is closed	Click Reopen if further handling is needed



The six status bars and their buttons (corresponding to the rows above except “Awaiting Agent”)

The indicators in the middle column’s list convey the same information: “AI” means the Agent is replying automatically, a person icon means a human agent is handling the conversation, a clock means it is queued for a human, and the red Awaiting Agent icon means AI will not reply and someone needs to take over (hover over it to see why). The assigned agent’s name appears on the right.

The Three Tabs

Tab	Contents	When to Check
Mine	Conversations assigned to you	Keep it open throughout the day; this is your to-do list
Unassigned	Conversations with no assigned agent, **including those where AI is replying automatically**; use the status bar to identify who is waiting for a human	At the start of your shift, at regular intervals, and when your supervisor reminds you
All	All conversations within the currently selected platform scope (the default tab)	When looking up a customer’ s past conversations or conversations handled by colleagues

Availability Status

Status	Automatic Assignment	Current Conversations	Manual Pickup
Available	You receive assignments	Unaffected	Allowed
Pause Assignments	You are skipped	Conversations automatically assigned by the system that you have not yet replied to are reassigned to colleagues; conversations you have replied to and those manually assigned, transferred, or taken over are unaffected	Allowed
On time off (until the end time)	You are skipped; availability is restored automatically when time off ends	Unaffected	Allowed
Not on assignment list	You do not receive automatic assignments in the first place	Unaffected	Allowed

Handling Scenarios

Each scenario provides steps in the form of a decision followed by an action. Follow them as listed; links lead to the relevant pages for details.

A Customer Requests a Human

Check the status bar:

"Waiting for a Human Agent" or "No Agent Assigned" → Click Take Over and reply directly.

"AI Agent Handling" (the platform did not detect the need for human handoff) → Also click Take Over; AI stops replying at the same time.

Introduce yourself in your first reply and confirm the issue without making the customer repeat it. First read the transfer reason and conversation summary in Details.

If you later find that AI should have handed off the conversation but did not, follow Report Incorrect AI Answers so your supervisor can adjust the Handoff Conditions.

A Customer Is Upset

Take over first (Take Over) to ensure AI does not respond again.

Reply in this order: acknowledge the customer's feelings and problem → restate your understanding in one sentence → explain what you will do now and when you will respond → offer a concrete next step or options. Do not explain the system or argue about who is right.

Before discussing refunds, compensation, or commitments, check whether you have the authority. If not, Transfer to your supervisor and clearly describe the request and the customer's emotional state in the transfer reason.

Once handled, use Edit Summary to record commitments and timing, then click Resolve. Keep conversations open if they need follow-up.

A Customer Keeps Asking the Same Question

Scroll up to review AI's previous replies:

AI answered correctly, but the customer did not understand → Take over, rephrase the answer, and break it into steps.

AI answered incorrectly or missed the question → Take over, provide the correct answer, and follow Report Incorrect AI Answers.

If a queued customer keeps asking "Is anyone there?", queue reminders may be disabled or the wait may be too long. Apologize after taking over, then address the issue, and ask your supervisor to enable Queue Reminders.

A Customer Wants to Look Up Past Records

For other conversations with the same customer, use Filter by Contact in the All tab and select the contact. See Search and Filter.

If you only remember a keyword (order number or product name), use the search box. See Inbox Search.

Basic customer information, tags, and custom attributes (membership tier, contract number, etc.) appear under contact information in Details. To change the information, go to Contacts.

To inspect what AI retrieved and which documents it cited for each message, use the Conversation Viewer.

> If a website visitor is not signed in, each conversation creates a new anonymous contact, so filtering by contact may not connect their conversations. Use keyword search instead. See Contact Types.

Unsure Whether to Resolve

Ask yourself these three questions in order:

Does the customer’ s issue have a clear answer or outcome? If not → Leave it In Progress.

Do you still have follow-up work to do (look up information or wait for another department)? If so → Leave it In Progress and use Edit Summary to record the to-do items first.

Is the customer still online and likely to ask more general questions?

Yes, and AI can answer → Click Return to AI Agent. The conversation stays In Progress, and AI continues serving the customer.

No (the customer has left, or the issue is a complaint or requires individual case handling) → Click Resolve and clearly record the outcome in the summary so whoever takes over after it reopens can understand.



After returning to AI Agent: the status bar returns to “AI Agent Handling,” and AI answers the customer’ s next question

If the customer has not replied for a while and their question has been answered, you can resolve the conversation. A new customer message automatically reopens it and returns it to AI, so it will not be missed.

Copilot’ s Suggestion Is Incorrect

Do not send it directly. Click Edit to place the suggestion in the message box and correct it, or click Regenerate to compare another version. See Switch Versions.



AI suggestion card: switch versions and regenerate at the top right; choose Edit or Send at the bottom right

If the suggestion cites sources, check them first. If the source itself is outdated or incorrect, the knowledge base needs updating. Follow Report Incorrect AI Answers.

If suggestions for the same type of question are repeatedly incorrect, or their status stays at Failed, summarize the problem in one sentence for your supervisor. See FAQ.

Report Incorrect AI Answers

Your reports help improve AI. Give your supervisor three things:

Conversation ID: Copy it from the location information in Details. See Conversation Details.

What was wrong: What AI said, what the correct answer is, and how the customer originally phrased the question.

Tag the conversation: If your supervisor has created a Conversation Tag such as “Needs Correction,” apply it under conversation tags in Details. Your supervisor can then use Filter by Conversation Tag to find all of them at once.

Your supervisor will then follow Supervisor Guide: Turn Incorrect Answers into FAQs to update the knowledge base or role instructions.

A Customer Contacts Me in a Conversation a Colleague Is Handling

If the status bar shows "○○ Is Handling This Conversation," do not reply yet; two people replying at once will confuse the customer. Confirm that your colleague is away (on time off or has paused assignments) or has asked you to take over, then click Transfer to transfer the conversation to yourself. See Transfer and Return to AI.

A Customer Returns After Resolution

The conversation automatically reopens, AI auto reply resumes, and the assigned agent is cleared, so it will not appear in your Mine tab. If you know the customer will return (for example, you promised to reply after looking something up), check periodically using Filter by Contact, or ask your supervisor to manually Assign Agent to you when the conversation reopens.

Common Mistakes

Mistake	What Happens	Correct Approach
Replying in the message box without taking over	Auto reply remains on, so AI answers the customer's next message and overlaps with your replies	Click Take Over first. See Intervene and Auto Reply
Leaving your desk without switching to Pause Assignments	The system keeps assigning conversations to you while customers wait; timeout reassignment, if enabled, reassigns them	Change your status before leaving; use time off for leave
Only checking the Mine tab	Conversations under manual pickup or message mode remain in Unassigned, with no email notification, and go unnoticed	Check the Unassigned tab regularly
Closing the page after handling an issue	The conversation stays In Progress and uses up your concurrent conversation capacity	Click Resolve, or return it to AI and then resolve
Transferring without a reason	The colleague taking over has to ask the customer to repeat the issue	Enter a transfer reason and edit the summary first if needed
Sending Copilot suggestions directly	If the cited information is outdated, an incorrect answer is sent in your name	Check the cited sources and content before sending
Using "Delete Conversation" to close a	The conversation disappears permanently and cannot be restored or analyzed	Use Resolve. See Rename and Delete Conversations

Mistake	What Happens	Correct Approach
case		

One-Page Checklist

Print this section and keep it beside your desk.

Start Your Shift

[ ] Set your availability to Available

[ ] Check the Mine tab: handle conversations left over from yesterday first

[ ] Check the Unassigned tab: if anyone is “Waiting for a Human Agent,” take the longest-waiting conversation

Every Conversation

[ ] Click Take Over first (or confirm it is assigned to me)

[ ] Read Details: transfer reason, summary, and contact information

[ ] Send the first reply promptly without making the customer repeat the issue

[ ] Check Copilot’s cited sources before sending a suggestion

[ ] If I cannot handle it → Transfer and enter a reason

[ ] Once handled → Edit Summary if needed → Return to AI Agent if the customer is still there and AI can help; otherwise Resolve

[ ] If AI answers incorrectly → Copy the conversation ID, tag the conversation, and report it to my supervisor

End Your Shift

[ ] No conversations in Mine have been handled but left In Progress

[ ] Summaries clearly explain conversations that will carry over to the next day

[ ] Set your availability to Pause Assignments; schedule time off in advance for leave

Customer Service Supervisor Guide

This page is for people who lead a support team: scheduling, watching workload, spot-checking quality, fixing questions the AI answered incorrectly, and granting permissions to new support agents. Day-to-day operations for support agents are in the Support Agent Handbook; platform settings such as handoff conditions and dispatch modes are in Human Support Handoff Settings.

Daily and Weekly Rhythm

Daily

When	What to do	Where
Before shift	See who can be assigned today: the status of each support agent on the list (Available Paused On Time Off), and whether people on leave have time off set	Support Agent Availability
Before shift	Check the Unassigned tab for messages left overnight (status bar shows "Waiting for Human Agent")	Unassigned Conversations
During shift	Watch Agent Workload: queue size, conversations in progress per person, and who is at full capacity	Agent Workload
During shift	Reassign manually when the queue wait is too long or someone is at full capacity	Workload and Reassignment on this page
Before end of shift	Use Filter by Status to select "In Progress," and batch-change conversations that are finished but not closed to Resolved	Batch Status Updates
Before end of shift	Check the quality scores in AgentOps conversation records, and review low-scoring conversations the same day	AI Customer Service Quality Management

Weekly

What to do	Where
Spot-check a few AI conversations and a few human conversations, scoring them against a fixed checklist	Quality Spot-Check Process on this page
Work through the "AI answered incorrectly" list reported by support agents, and fix the knowledge base or role instructions	Turn Wrong Answers into FAQs on this page

What to do	Where
Run an Inbox Analysis and look at changes in topics and resolution rate	How to Read Inbox Analysis on this page
Check next week's time off: whether people on leave have time off set and whether the dispatch list needs adjusting	Support Agent Availability
Review satisfaction: which conversations received a thumbs-down or a low survey score	Satisfaction Feedback

Scheduling and Availability

Automatic dispatch only assigns conversations to support agents who are "on the list, with an active account, available, not on time off, and not at full capacity." All four conditions must be met; see Selecting Support Agents. Scheduling comes down to three things:

Who is on the list: Each conversation platform has its own Assignable Support Agents list. Update it here when someone joins or moves to another team.

Who is out today: Support agents switch themselves to Pause Assignments and set time off. If they forget, a supervisor can change their Status directly on the list or click Time Off. Adjusting someone else's status requires being an organization owner, or having edit permission on that platform; see Support Agent Availability.

What happens outside service hours: Set which days and hours someone is available in Service Hours. If you choose "Accept messages" for offline behavior, conversations stay in the Unassigned tab until someone handles them at the start of work; if you choose "Show offline message," no handoff happens.



Dispatch settings: select the support agents on the list, and change each agent's "Status" or set "Time Off" directly

> If you want conversations to stay in Unassigned for support agents to claim themselves, set the Dispatch Mode to "Claim mode" instead of emptying the list. In claim mode and message-leaving mode, no email is sent before a conversation is assigned, so arrange for someone to check the tab regularly.

Workload and Reassignment

Watch Workload

The Agent Workload panel shows each support agent's in-progress count, resolved count, and status (On Time Off > Paused > At Full Capacity > Available), along with the number of conversations currently in the queue. Here is how to interpret it:

What you see	What it means	Action
The queue stays above 0, but some people are "Available"	The dispatch mode is claim mode, or these people are not on that platform's list	Ask online support agents to claim conversations from Unassigned, or add them to the list

What you see	What it means	Action
Most people are "At Full Capacity"	The number of concurrent conversations per agent is too low, or everyone is closing conversations too slowly	Raise the Capacity, or first batch-close conversations that are already finished
One person has far more conversations in progress than others	The routing model is round-robin, or others often pause assignments	Switch to "Least busy first," or reassign manually
Queued conversations often time out and return to AI	The wait timeout is too short, or there is not enough staff	Adjust the wait timeout and enable Reassign on Timeout



"Agent Workload" panel: expand it to see each agent's in-progress count, resolved count, status, and the current queue size

Manual Reassignment

Unassigned conversations: In the Unassigned tab, hover over a conversation and click the assign icon, or open it and use Assign Agent.

Conversations that already have an owner: Open the conversation, click Transfer, choose a colleague, and enter the reason for the transfer.

The picker window lists each support agent's current in-progress conversations, today's handled count, and whether they have reached their limit. The current owner and anyone who has reached the limit

cannot be selected, so picking by workload will not assign a conversation to someone at full capacity.


For operational details, see Taking Over, Reassigning, and Returning to AI.



The picker window when reassigning: each card shows the agent's in-progress conversations and today's handled count

When You Need Grouping

When billing, technical, or other issues should go to specific teams, use Tag Routing: first create tags in Conversation Tag Management and bind members to the tags, then enable Conversation Analysis so the system tags conversations automatically on handoff.



Conversation tag management: each platform creates its own tags, and "Assigned Members" are the people tag routing dispatches to

Quality Spot-Check Process

Spot-check AI replies and human replies separately, because the criteria differ.

AI Replies

Open AgentOps AI Assistant Monitoring → Conversation Records, sort by Quality Score, and look at the low scores first. The Agent must have automatic evaluation enabled to have scores; see How to View Evaluation Report Scores.

Use the simple evaluation method to classify problems into three types: saying something wrong (low faithfulness), not answering the question (low relevance), and finding the wrong material (low context precision).

The fix for each type is in the three-step improvement plan. To see which documents the AI looked up and which tools it used at the time, use the Conversation Viewer.

For weekly statistics, use the template in Response Quality Tracking.

Human Replies

Each week, pick 3–5 resolved conversations per support agent (use Filter by Status to select Resolved, then check the owner) and review them against this checklist:

[ ] Did the first reply after takeover make the customer repeat themselves?

[ ] Did the agent take over before replying? (If not, the reply will overlap with the AI's reply.)

[ ] Did the agent verify the Copilot suggestion before sending it? (Compare against the source citations on the suggestion card.)

[ ] Was a reason filled in for the transfer, and did the summary record the outcome?

[ ] Timing of closure: was the conversation resolved only after the problem was solved, with no premature closure while follow-up was still pending?

[ ] If the customer gave a thumbs-down or a low survey score, what was the reason?

The conversation's event timeline (who took over, when it was transferred, when it was returned to AI) is under Details; see Conversation Details. Use the spot-check results as team feedback for Support Agent Handbook: Common Mistakes rather than only telling individuals.

Turn Wrong Answers into FAQs

Support agents report to you following Reporting AI Errors with the conversation ID, what was wrong, and the correct answer. We recommend creating a "Needs Fix" conversation tag on each conversation platform; once support agents apply it, you can use Filter by Conversation Tag to pull out this week's list in one go. Handle each item as follows:

Classify: Is the information missing from the knowledge base, outdated, did the AI find the wrong document, or did the AI have the data but answer off-target?

Fix:

Fixed answer and clear question → In AgentOps conversation records, add this conversation to the FAQ, rewriting the question in a general form and writing the answer in full.

Outdated knowledge base document → Update the document, following the checklist in Step 1: Update Content.

AI had the data but answered off-target → Adjust the role instructions, following Step 2: Adjust AI Answer Principles.

Should have handed off to a human but didn't → Add to the description of the handoff conditions.

Verify: Use Search Test to confirm that the customer's original phrasing finds the new content; after changing role instructions, run an automatic evaluation with a test dataset.

Close out: Remove the "Needs Fix" conversation tag or replace it with "Fixed," and reply to the support agent who reported it so they keep reporting.

If the same type of problem appears three or more times in a week, or involves wrong prices or policies, fix it the same day; for the priority order, see Daily Checks.

How to Read Inbox Analysis

Inbox Analysis uses AI to summarize topics, resolution rate, and failure reasons for the conversations of one platform over a period. We recommend running it weekly or every two weeks and always looking at four places:

Look at first	The question it answers	What to do next
Resolution Status	How much the AI resolved on its own	When the resolution rate drops, look down at the failure reasons
Resolution Failure Reason Distribution	Whether unresolved conversations came from knowledge base gaps, overly restrictive instructions, tool failures, or hallucinations	Knowledge base gap → add content; overly restrictive instructions → loosen role instructions; hallucination → strengthen the knowledge base and constraints
Top Questions Ranking	What customers ask most, and which topics have low resolution rates	Add FAQs first for topics that are frequent and have low resolution rates; expand the example intents to see how customers actually phrase them
Analysis Summary	The AI's overall recommendations	Pick one or two to schedule for next week's improvements

Two common uses:

Want to know whether a change worked: Run one analysis for "the week before the change" and one for "the week after," then compare resolution rates and failure reasons; see Assessing Impact After a Version Update.

Too many human handoffs: Check the failure reasons; if "knowledge base gap" accounts for most of them, adding knowledge is more cost-effective than adding staff.

Real-time quantitative metrics (conversation count, message count, satisfaction) are in Usage Analytics; conversation-level cost is in Credit Consumption Summary. Analysis consumes credits, so confirm the date range and sample size before creating one.

How to Grant Permissions to Support Agents

Permissions are set in Role Permission Management under Organization Settings. We recommend creating separate roles for support agents and supervisors:

To let them…	You need
Enter All Conversations to take over and reply	Support Conversation Permissions → All Conversations Permission, and assign the conversation platforms they are responsible for
Be assigned automatically	The row above, plus adding them to that platform's Assignable Support Agents
Generate AI suggestions with Copilot	The role must also be assigned the AI assistant for the Agent bound to that platform; see Who Can Use It
View contacts, edit tags and custom attributes	Support Conversation Permissions → Contact Permissions
Change platform settings (human handoff, dispatch, Copilot)	Conversation Platform Permissions, plus edit permission on that platform; regular support agents do not need this
Adjust colleagues' availability status and time off	An organization owner, or edit permission on any platform of the dispatch list the support agent belongs to
Run Inbox Analysis	Support Conversation Permissions → Inbox Analysis Permission
View AgentOps quality scores, add to FAQ, edit the knowledge base	AI assistant and knowledge base permissions, usually given only to supervisors and builders

> Order for onboarding a new support agent: create the account → add them to the support role → check the platforms they are responsible for in the role's assigned conversation platforms → check them on each platform's dispatch list → send a test conversation to confirm they receive the notification. If a member cannot see conversations, see the checklist in Troubleshooting.

All Conversations

All Conversations brings together customer conversations from all channels (web, internal, LINE, Microsoft Teams, and more). Support agents can review Agent replies and reply or take over when needed; supervisors can filter and manage conversations in bulk.

Access: In the left menu, select Customer Conversations → All Conversations.

Permissions: Requires Customer Conversation Permissions and the nested All Conversations Permissions. See Role and Permission Management for details.

Page Layout

Area	Contents
Left column: channels	All Conversations appears at the top, followed by a Channels list. Select a channel to view only its conversations. Use the search box above to find a channel, or Connect a Channel at the bottom to add one
Middle column: conversation list	Search box, filter button, Mine Unassigned All tabs, and the handling status of each conversation
Right side: conversation content	Contact name, channel, Details, and Copilot icon at the top; status bar, messages, and input box below



All Conversations with a specific channel selected: the list heading shows the channel name and ID, and the open conversation appears on the right

When you select a specific channel, the list heading shows its name and channel ID. Click the adjacent button to copy the ID.

Find Conversations to Handle

Tabs

Tab	Conversations shown
Mine	Conversations assigned to you
Unassigned	Conversations without an assigned support agent, including those receiving automatic Agent replies
All	All conversations within the current channel scope (default tab)

The number beside each tab name is its conversation count. Each conversation in the list indicates who is handling it: an “AI” badge means the Agent is replying automatically, a person icon means a human support agent is handling it, a clock icon means it is queued for human support, and a red icon for conversations awaiting support means AI will not reply and a support agent must take over (for example,

outside AI automatic reply hours; hover over the icon to see the reason). The assigned support agent's name appears on the right.

Search and Filter

Search: Enter keywords in Search Messages in Conversations. See Inbox Search for the search scope.

Filter: Click the filter button beside the search box to combine the conditions below. Active conditions appear as tags above the list. Click × on a tag to remove it, or Clear Filters to remove them all.

Filter	Description
Filter by Status	Select one or more of In Progress, Resolved, and Queued
Filter by Contact	Show only a specific contact's conversations; search by name
Filter by Contact Tags	Filter by tags on contacts; supports multiple selections
Filter by Conversation Tags	Filter by tags on conversations; supports multiple selections



Filter panel: combine four groups of conditions

Rename and Delete Conversations

Hover over a conversation in the list to reveal the “…” menu on the right:


Update Status: Set the conversation directly to In Progress or Resolved (shown when you have assignment permissions).

Rename: Change the conversation name shown in the list so support agents can identify it easily (for example, “Order #1234 Return”). This does not affect what the contact sees.

Delete Conversation: Delete it after confirming “Are you sure you want to delete this conversation?” Deletion cannot be undone, and the conversation will no longer appear in search, analytics, or exports. If handling is simply complete, use the “Resolved” status instead.

Update Status in Bulk

Select conversations (or Select All above the list) to display Bulk Update Conversations below. Choose the target status (In Progress or Resolved), then click Apply to N Conversations. The numbers of successful and failed updates appear when the operation finishes.



Bulk status update: select conversations, click “Bulk Update Conversations,” choose a status, and apply

Reply and Manage Automatic Replies

Open a conversation and reply directly in the input box below. Messages are sent through the customer's original channel (web chat, LINE, Teams, and so on).

The robot icon toggle above the right side of the input box controls Automatic Replies for this conversation:

On: The Agent automatically replies to new customer messages. Channels default to automatic replies all day, every day. If the channel's automatic reply hours have been changed, replies are sent only during those hours. See Website: Automatic Reply Settings for scheduling.

Off: The Agent stops replying to this conversation, and human support agents reply manually.

> Sending a message alone does not turn off automatic replies. If automatic replies are on, the Agent will still answer the customer's next message, potentially overlapping with your reply. When you send a message in a conversation that no human has taken over, a Before Sending reminder appears first. Choose Take Over and Send (recommended) or Send Directly. See Human Support Handoff and Replies.

Undelivered Messages

In LINE, Messenger, and Instagram conversations, if the platform rejects a message sent by you or the Agent, Not Delivered: Reason appears in red below the message bubble and remains after refreshing. Successfully sent messages have no indicator. Common reasons:

Display	What to do
LINE monthly message quota exhausted	Check the Monthly Message Quota on the LINE channel's settings page, then upgrade your plan in LINE Official Account Manager or wait for next month's reset. Neither AI nor human replies can be sent while the quota is exhausted
Too many LINE messages sent in a short time; try again later	Send again later
Meta's 24-hour reply window has expired	Messenger/Instagram only allow replies within 24 hours of the customer's last message. Wait for the customer to message again
Recipient has blocked you or cannot currently receive messages	The Messenger/Instagram customer has blocked the page or cannot currently receive messages, so delivery is unavailable
Message content or format not accepted by the platform	Check the content (for example, excessive length or unsupported formatting), then send again
Platform temporarily unable to process the message; sending failed	A temporary platform error occurred; send again later

Display	What to do
Sending failed (original message)	The parentheses contain the platform's original error. Use the reason to decide whether to revise the content before sending again

There is currently no “Resend” button. Re-enter and send the message when needed.

For example, a support agent replies on Monday morning to a customer who messaged on Messenger on Friday evening. “Not Delivered: Meta's 24-hour reply window has expired” appears below the message. Knowing the customer will not receive it, the support agent contacts them by phone or Email, or waits for another customer message before replying.

In group conversations (such as LINE groups), a mention icon toggle also appears above the input box. Hovering over it shows “Respond only when @mentioned in the group.” When enabled, the Agent only responds when @mentioned in the group; when disabled, it responds to all group messages.

Take Over, Transfer, and Return to AI

The status bar above the conversation content shows who is currently handling the conversation and provides actions based on its status:

Status bar display	Available actions
AI Agent Handling, Outside AI Reply Hours · Awaiting Support, No AI Assistant Linked to Channel · Awaiting Support, No Support Agent Assigned, or waiting for human support	Click Take Over to assign the conversation to yourself and stop AI automatic replies, or Assign Support Agent to assign it to a specific colleague
You Are Handling This Conversation	Click Resolve to close it, or Transfer to a colleague. In the Mine tab, you can also Return to AI Agent
Another colleague is handling it	Transfer to another support agent
This Conversation Is Resolved	Click Reopen

In the Unassigned tab, you can also hover over a conversation and click the assignment icon to assign it to a specific support agent. The selection dialog shows each colleague's online status, availability, and number of conversations in progress. See Human Support Handoff and Replies: Transfer and Return to AI.

If a customer sends another message in a resolved conversation, it automatically reopens and returns to AI automatic replies, and the previous support agent assignment is cleared.

For replying after takeover, availability and time off, transfer rules, and customer-facing notices, see Human Support Handoff and Replies. For handoff conditions and assignment rules, see Human Support Handoff Settings.

Conversation Details

Click Details above the conversation to expand its information on the right:

Handoff Reason (if provided), Contact Tags (created in Contacts), and Conversation Tags (created in the channel's Conversation Tag Management)

Conversation Summary: If Conversation Analysis is enabled for the channel, click Analyze Conversation beside the conversation tags to generate one. You can edit the summary manually; see below

Location Information: IP address, recorded time, and a copyable Conversation ID

Conversation Satisfaction, Credit Usage Summary (see below), Conversation Timeline (handoff, takeover, return, and other events), and Contact Information (Email, phone, and the contact's Custom Properties)

The robot icon in the title bar opens Conversation Copilot. See Support Copilot.



Conversation details: handoff reason, tags, location information, and conversation ID; scroll down for conversation satisfaction, Credit Usage Summary, and the conversation timeline

Edit the Conversation Summary

AI-generated summaries may be incomplete. Support agents can correct them directly:

Click Edit Summary, make changes, and save. Colleagues who take over later will see the updated version.

Click Edit History to expand all versions. The first version is labeled AI Analysis (the original AI draft), and the displayed version is labeled Current. Click Restore on another version to switch back to it. If no edits have been made, "No edit history yet" appears.

Clicking Analyze Conversation again generates a new AI version. Previous versions remain in the edit history.

Credit Usage Summary

Credit Usage Summary adds up the Credits used by each AI reply turn in the conversation, helping you assess costs per conversation:

Item	Description
Total	Total Credits used across all turns in this conversation
Turns	Number of completed AI reply turns
Average Median Standard Deviation	Mean, median, and spread of usage per turn; a high standard deviation indicates that some turns were particularly expensive
Highest Lowest	Highest and lowest usage in a single turn; **click to jump to that turn's message**
Category bar	Proportions by category, including embeddings, LLM input, LLM output, Cache reads, Cache creation, and tools

Expand Advanced Analysis for:

Top 3 Most Expensive Turns: Lists the three most expensive turns; click to jump to the message.

Cumulative Credit Usage: A curve of usage accumulated over turns, showing whether usage is evenly distributed or concentrated in a few turns.

vs. Organization Average (30 Days): Compares average usage per turn in this conversation with the organization's average across all conversations with at least 3 turns in the past 30 days. "No organization baseline data yet" appears if this conversation has fewer than 3 turns or the organization lacks sufficient data.

Export CSV: Download Credit usage details for each turn in this conversation.

For Tokens, processing time, and execution steps for a single reply turn, open the conversation details page in AgentOps. See Automated Evaluation and Agent Monitoring. For Credit pricing, see Credits.

Related Pages

Page	When to use it
Conversation Viewer	Review conversation content, tool usage, and cited sources message by message for quality checks or troubleshooting
Inbox Search	Find specific conversations by keyword
Channel Analysis	Use AI to summarize topics, resolution rates, and improvement suggestions for a single channel over a period of time
Human Support Handoff and Replies	Daily takeover, transfer, and return to AI for support agents
Support Agent Handbook	First-day onboarding, daily workflows, and scenario-based procedures for new support agents
Contacts	Manage contact information and tags

FAQ

The list is empty and says “There don't seem to be any customer messages in your channels”?

There are no conversations within the current scope. Check that you selected the correct channel, or complete setup in Connect a Channel.

I replied to the customer, but the Agent keeps answering?

Automatic Replies is still enabled for this conversation. Click Take Over in the status bar, or turn off the automatic reply toggle above the input box. For other takeover and resolution scenarios, see Support Agent Handbook: Scenarios.

Conversation Viewer

Overview

The Conversation Viewer is a page in the MaiAgent admin console where administrators and customer service staff can review complete conversation records more clearly and in greater detail. It lets you focus on every detail of a single conversation, including message content, the timeline, and tool usage records.

> The Conversation Viewer is particularly useful for quality monitoring, customer service training, and issue tracking, helping you analyze conversations more effectively.

Open the Conversation Viewer

From the inbox

Open the conversation list

Click Customer Service Conversations in the left menu.

Click All Conversations.

Select a conversation to view

Find the conversation in the list.

Click it to show the full conversation on the right.



Open a conversation: the AI reply shows the knowledge base used, the steps performed, and the reference sources

Interface

Main sections

Section	What it shows
Conversation information panel	Basic conversation information - User name - Conversation platform (LINE Facebook Web Chat) - Start time - Conversation status
Message timeline	The complete conversation in chronological order - User messages - AI replies - System messages - Timestamps
Conversation details	Advanced information - AI assistant used - Tool call records

Section	What it shows
	- Knowledge base query results - Token usage

Message display

User messages: Appear on the left with a white background.

AI replies and support staff replies: Appear on the right with a light blue background. The replier (platform name or support staff name) is shown below.

System events: Appear in the center in small gray text, such as handoff notices, a support agent taking over, and status changes.

Timestamps: The sent time appears below each message.

Advanced features

Tool usage records

When an Agent searches the knowledge base or calls a tool while replying, the reply is marked above with Used knowledge base, Used tool, and Completed N/N steps. Expand the steps to see what each step searched for and what each tool returned.

Knowledge base citation tracking

If an AI reply cites knowledge base content, numbers in the reply mark the citation positions, and the References section below lists the cited files and reference nodes. Click one to see the cited passage.

User thumbs-up and thumbs-down

The thumbs-up or thumbs-down that users give an AI reply in Web Chat, the Agent marketplace, or MaiGPT, along with the reasons they select and any additional text in the “Provide feedback” window after a thumbs-down, are recorded on that reply and can be reviewed here one reply at a time. For the overall ratio, see Usage Analytics: User Satisfaction. For how users do this on their side, see MaiGPT: Give Thumbs-Up, Thumbs-Down, and Feedback on Replies.

Token usage statistics

For conversation-level cost, see the Credit consumption summary in the Details panel: the total, average, highest, and lowest Credits for each AI reply turn, with CSV export. To see the Token count, processing time, and execution steps of a single reply turn, open the conversation detail page in AgentOps. See Automated Evaluation and AI Assistant Monitoring.

> Cost statistics help you find unusually expensive replies, so you can then adjust Agent settings or the knowledge base.

Use cases

Scenario 1: Quality monitoring

Need: A supervisor checks conversation quality each day to confirm that AI replies meet standards.

Steps:
1. Randomly select 10 conversations from the inbox each day.
2. Review each conversation in the Conversation Viewer.
3. Check whether:
- AI replies are accurate.
- The tone is appropriate.
- Tools were used correctly.
- Knowledge base citations are relevant.
4. Mark conversations that need improvement.
5. Give feedback to the AI training team.

Scenario 2: Customer service training

Need: Train new customer service staff with real conversation examples.

Steps:
1. Select strong examples, such as complex issues handled well.
2. Explain each step using the Conversation Viewer.
3. Cover how to:
- Understand customer needs.
- Use tools effectively.
- Guide the conversation.
- Close the conversation properly.
4. Have new staff practice similar scenarios.

Scenario 3: Troubleshooting

Need: A user reports an incorrect AI reply, and you need to find the cause.

Steps:
1. Find the conversation using search.
2. Review it in detail in the Conversation Viewer.
3. Analyze the issue:
- Check whether the user's question was understood correctly.
- Review which tools the AI called.
- Confirm whether the knowledge base search results were relevant.
- Review the AI's reasoning process.
4. Identify the root cause (insufficient knowledge base content
incorrect tool settings

prompt needs improvement).
5. Make the appropriate changes.

Get conversation question-and-answer records

MaiAgent offers two ways to obtain records, depending on your needs:

Need	Recommended method	Output
Analyze AI question-and-answer records in bulk	Filter and export from “AgentOps > AI Assistant Monitoring”	Excel
Periodically sync AI question-and-answer records to an internal system	Use the question-and-answer records API, and handle pagination and storage yourself	JSON

Bulk export

Open AgentOps > AI Assistant Monitoring in the left menu.

Filter by Agent, member, date, keyword, or other criteria.

Click Export in the upper-right corner to create an export request.

Open AgentOps > Export Requests in the left menu. Once the status is Completed, download the Excel file. The User column shows who created each export.

> Each row in the bulk Excel export represents a “user question and AI reply” exchange and is suitable for quality analysis. It is not a complete archive of all messages and original attachments. Exports currently include only interactive conversations. If you filter the source to Scheduled Execution in AI Assistant Monitoring, the export button is disabled. See Filter Conversation Records by Member and Source.

Retrieve via API

To sync records regularly or use a custom JSON format, call `GET /api/v1/records/` with your organization's API Key. Retrieve AI question-and-answer records by page and filter by AI assistant, date, or keyword.

Authenticate with `Authorization: Api-Key` and follow the pagination information in each response until there is no next page. For the full parameters and response fields, see the MaiAgent API documentation.

Handling attachments

The bulk Excel export and question-and-answer records API do not include the original files users uploaded as attachments.

There is currently no public API for customers to download conversation attachments in bulk. If you need to retain attachments, contact the MaiAgent team to discuss a suitable data delivery method.

> Privacy reminder Exported conversation records may contain users' personal information. Store them securely and comply with your privacy policy and applicable regulations.

FAQ

Q: How is the Conversation Viewer different from a regular conversation window?

A: The Conversation Viewer provides more complete information, including tool usage records, knowledge base citation tracking, and Token usage statistics. It is useful for analysis, monitoring, and training. A regular conversation window is suited to day-to-day replies.

Q: Can I reply directly in the Conversation Viewer?

A: No. The Conversation Viewer is read-only and is intended for review and analysis. To reply, return to the conversation list.

Q: Does the Conversation Viewer show deleted messages?

A: No. It shows only messages that currently exist. Deleted messages cannot be recovered there.

Q: What if the Conversation Viewer loads slowly?

A: Possible causes and solutions:
- **Long conversation**: Conversations with more than 100 messages may take longer to load. Please wait a moment.
- **Network issues**: Check your network connection.
- **Large attachments**: Too many images or files can slow loading.

Related features

> See also - Inbox Search - All Conversations - AI Assistant Monitoring - Usage Analytics

Inbox Search

Overview

The inbox search feature lets you quickly find specific conversation records without manually scrolling through a long conversation list. Using keyword search, you can instantly filter relevant conversations, significantly improving customer service efficiency.

> This feature supports instant search (search as you type) and automatically saves recent search history for quick repeat queries.

How to Use the Search Feature

Basic Search

Go to the inbox page

Click "Customer Service" in the left menu

Click "All Conversations" or select a specific chat platform

Enter search keywords

Type keywords in the search box above the inbox

The system instantly displays matching conversations

View search results

The conversation list is filtered automatically and shows only conversations that contain the keyword; open a conversation and scroll up to find the message



After entering a keyword, the list keeps only the matching conversations

Search Scope

The system searches the following fields:
- Message content (user messages, AI replies, and agent replies)
- Conversation title (the renamed title)

Contact names are not searched; to find a particular customer's conversations, use Filter by contact below.

> When a chat platform is selected in the left column, only that platform's conversations are searched; to search across platforms, first click "All Conversations" at the top.

Advanced Search Tips

Using Filters

Besides keyword search, you can click the filter button next to the search box to combine the following conditions (see All Conversations: Search and Filter):

Filter by status: In progress, resolved, queued; multiple selections allowed

Filter by contact: Show only a specific contact's conversations

Filter by contact tag: By the tags on the contact

Filter by conversation tag: By the tags on the conversation itself

Search Combination Examples

Example 1: Find unresolved invoice issues

```
Search keyword: invoice
Filter by status: In progress
```

Example 2: Look up a customer's conversation history

```
Filter by contact: Wang Xiaoming
Filter by status: Resolved
```

Use Cases

Case 1: Customer service quality monitoring

Need: A manager wants to review all conversations containing the keyword "refund" to evaluate handling quality

Steps:
1. Enter "refund" in the search box
2. Set the time range to "Last 7 days"
3. Review the search results one by one to confirm handling meets standards

Case 2: Issue tracking

Need: A user reported a problem, and you need to find the related conversation history

Steps:
1. Enter the user's name or a key description of the problem
2. View past conversation records
3. Understand how the problem occurred and how it was handled

Case 3: Performance analysis

Need: Analyze the inquiry volume and question types for a specific product

Steps:
1. Search for the product name keyword

2. Export the search results (if supported by the system)
3. Analyze common questions and directions for improvement

FAQ

Q: Is search speed affected by the number of conversations?

A: The system uses high-performance search technology and returns results within 1-2 seconds even with a very large number of conversations. However, we recommend using the time range filter appropriately for the best experience.

Q: Is search case-sensitive?

A: No. Entering "Refund" or "refund" returns the same results.

Q: Can I search for multiple keywords at once?

A: Yes. Enter multiple keywords separated by spaces, and the system searches for conversations that contain any of the keywords.

Example: Entering "return refund" searches for conversations containing "return" or "refund".

Q: Is search history saved?

A: The system saves your recent search keywords so you can quickly repeat queries. Search history is stored in your browser, so clearing browser data also clears the search history.

Q: Why can't I find some conversations?

A: Possible reasons:
- The conversation has been deleted or archived
- You do not have access to the conversation (restricted by role permissions)
- The keyword is misspelled, or it appears only in the contact name (names are not searched)
- A filter has not been cleared, for example the status filter has only "Resolved" checked

Notes

> Permissions Search results are limited by your role permissions: - You can only search chat platforms you have access to - You can only search conversations related to Agents you have access to - Organization owners can search all conversations

> Performance tips - Avoid overly common keywords (such as "hello" or "thanks"), which return too many results - Use status and tag filters to narrow the search scope - Mark finished conversations as "Resolved", then combine with the status filter so they don't get mixed in

Related Features

> Related features - All Conversations features - Conversation Viewer - Agent Monitoring

Conversation Platform Analytics

Inbox Analysis uses AI to summarize topics, determine resolution status, and compile concrete improvement suggestions from real conversations on a specific chat platform within a chosen date range, helping you continuously improve your Agent's conversation quality.

What Is Inbox Analysis?

Once customer service conversations reach a certain volume, total counts or satisfaction scores alone are not enough. You also want to know:

What are users actually asking? Which topics come up most often?

How many conversations were truly resolved? Which types of questions have a low resolution rate?

Why were some left unresolved? Is content missing from the knowledge base, are the instructions too restrictive, or did a tool fail?

How are response speed and cost distributed? Which topics take a long time or use a lot of tokens?

Inbox Analysis is designed to answer these questions. The system will:

Retrieve conversations within the specified time range

Cluster them by topic using an embedding model

Use an LLM to analyze each conversation's intent, resolution status, and failure reason

Produce a consolidated analysis summary (including improvement suggestions)

> How it differs from similar features | Feature | When it runs | Purpose | | --- | --- | --- | | Usage Analytics | Real-time statistics | Agent-level quantitative KPIs (conversation word count, count, satisfaction) | | Chat platform "Conversation Analysis" settings (a tab in each chat platform's settings) | Real time, whenever a new message arrives | Uses an LLM to automatically tag conversations, helping with routing and management | | "Inbox Analysis" described on this page | Manually triggered, batch review | Topic clustering, resolution rate analysis, and improvement suggestions for a specified date range |

How to Use

Go to the Inbox Analysis page

In the left menu, click "Customer Service" → "Chat Platforms"

In the chat platform list, find the target chat platform

Click the 📊 icon in the actions area on the right side of that row (hover to see "Inbox Analysis") to open the analysis page

The page shows all analysis reports previously created for this chat platform, including the date range, status, number of conversations, processing time, and more.



Inbox Analysis page: the list of analysis reports for this platform; you can add a new analysis in the upper right

Create an analysis


Click the "New Analysis" button in the upper right and fill in the following required fields:

Date range: Select the conversation period to analyze (future dates cannot be selected)

Analysis LLM: The large language model used to analyze each conversation

Embedding model: The embedding model used for topic clustering

Report language: The output language of the analysis summary (Traditional Chinese, Simplified Chinese, English, Japanese, Korean)



New Analysis: fill in the four required fields

Expand "Advanced Settings" to adjust the sampling strategy (see "Advanced Settings" below for details).




Advanced Settings: adjust sampling and concurrency parameters

After you click "Confirm", the system runs the analysis asynchronously in the background, and the status changes from "Pending" → "Processing" → "Completed".

View the report

Once the status changes to "Completed", click the "View Report" icon (👁) for that report to open the report details page.

The report content depends on how rich the conversation data is, and includes a data overview, resolution status, topic clusters, top questions, performance metrics, an analysis summary, and per-conversation analysis.



Analysis report details page: a dashboard showing metrics, clusters, failure reasons, and performance distribution

Report Contents

1. Data Overview

Metric	Description
Total conversations	Total number of conversations on this chat platform within the date range
Analyzed	Number of conversations actually analyzed by the LLM (limited by "Maximum samples")
Sampling rate	Analyzed total conversations (percentage)

Metric	Description
Processing time	Number of seconds this analysis task took from start to finish

> When the total number of conversations exceeds "Maximum samples", the system uses a cluster-based sampling strategy to select representative conversations for analysis, in order to control cost and time.

2. Resolution Status

The core metric "**Resolution rate**" is calculated as follows:

```
Resolution rate = (Resolved + Partially resolved) ÷ Analyzed
```

Resolved (green): The Agent fully answered the user's question

Partially resolved (orange): The Agent answered part of the question, or the direction was correct but incomplete

Unresolved (red): The Agent could not answer or answered incorrectly

A resolution rate above 50% is shown in green, and below 50% in red, as an at-a-glance health indicator.

3. Performance Metrics

Shows the Agent's computational performance over this period:

Total tokens: Input + Output tokens combined

Average tokens per turn: The average number of tokens consumed per conversation turn

Average response time: Total time from receiving a message to completing the reply

Average time to first token (TTFT): Time from receiving a message to outputting the first token

4. Topic Cluster Distribution

All conversations are clustered by semantic similarity, and a horizontal bar chart shows the number of occurrences and share of each topic. Outlier conversations are grouped under "Noise Outliers".

This view lets you quickly identify the topics users ask about most.

5. Resolution Failure Reason Distribution

The system labels each analyzed conversation with a status or failure reason, summarized as follows:

Reason	Description
Resolved	The Agent answered successfully
Partially resolved	The direction was correct but the answer was incomplete
Knowledge base gap	The knowledge base lacks relevant content
Overly restrictive instructions	The role instructions blocked a reasonable reply
Tool failure	A tool errored or was not triggered
Unclear user intent	The user's message was vague and the intent could not be determined
Off-topic	The user asked about something outside the Agent's scope
Hallucinated response	The AI generated nonexistent or incorrect information
Unknown	Could not be classified into any of the above categories

This distribution directly guides follow-up improvements: many knowledge base gaps → add content; many overly restrictive instructions → adjust the role instructions; many hallucinations → strengthen the knowledge base and instruction constraints. This is the only automated way to find knowledge gaps: the platform does not separately record or export questions that returned no search results, so use this analysis's sampled results together with the per-conversation analysis to go back and fill in the knowledge base.

6. Top Questions

A list of topics sorted by count, showing each topic's **number of occurrences** and **resolution rate**. Expand any row to see example intents for that topic, helping you quickly confirm whether the clustering matches your expectations.

7. Performance by Topic

Breaks down tokens and elapsed time per topic so you can find "expensive" or "slow" topics:

Average Input
Output
Total tokens

Average response time

Average time to first token

If a topic's token usage is unusually high, consider optimizing the role instructions or knowledge base retrieval; if a topic takes a long time, it may involve many tool calls or overly long content.

8. Analysis Summary

A Markdown report generated by the LLM that synthesizes all analysis results. It usually includes:

Overall performance summary
Main problem patterns
Prioritized improvement suggestions
Specific adjustment directions

It is collapsed by default; click the title to expand and read it.

9. Per-Conversation Analysis

Once expanded, you can review each analyzed conversation one by one. Each entry includes:

Intent (User Intent): What the user actually wanted to ask
Topic: The topic cluster it belongs to
Detail (Resolution Detail): A detailed description of the resolution status
Suggestions: Specific optimization directions for that conversation

Advanced Settings

Advanced settings control the sampling and execution strategy. We recommend running with the defaults first and adjusting as needed:

Parameter	Default	Description
Samples per cluster	10	The maximum number of conversations from each topic cluster sent to the LLM for analysis
Maximum samples	150	The maximum number of conversations analyzed in the whole report (caps cost)
Concurrency	8	Number of parallel LLM analyses; higher is faster but uses more resources at once
Maximum conversations to retrieve	—	Upper limit on the total number of conversations fetched from the database
Minimum messages per conversation	—	Conversations with fewer messages than this are filtered out (avoids analyzing meaningless short conversations)

> Cost reminder: Analysis consumes LLM token quota (Input + Output + Embedding). The system checks your organization's quota before analysis, and the task cannot be created if the quota is insufficient.

Use Cases

Case 1: Quarterly quality review

Need: A manager wants to know the conversation quality and main issues of the Web Chat chat platform last quarter.

Steps:
1. Select last quarter as the date range
2. Set Maximum samples to 300 (to enlarge the sample)
3. Run the analysis and focus on "Resolution
Failure Reason Distribution" and "Top Questions"
4. Schedule improvement tasks for high-frequency reasons such as knowledge base gaps and overly restrictive instructions

Case 2: Assessing impact after a change

Need: The role instructions were adjusted last week, and you want to know whether conversation quality improved.

Steps:
1. Create two analysis reports, one for "the week before the change" and one for "the week after the change"
2. Compare the resolution rate and failure reason distribution of the two reports
3. Confirm whether specific failure types have decreased

Case 3: Filling knowledge base gaps with topic clusters

Need: You have noticed questions users often ask and want to systematically add to the knowledge base.

Steps:
1. Analyze the past month's conversations
2. From "Top Questions", pick topics with high frequency and a low resolution rate
3. Expand "example intents" to confirm how users actually phrase them
4. Return to the knowledge base and add the corresponding FAQs or documents

FAQ

Q: Why weren't some conversations analyzed?

The system filters by "Maximum samples" and "Minimum messages per conversation", and takes representative samples after clustering. If the total number of conversations is large, only representative samples are taken to control cost.

Q: How is the resolution rate determined?

The analysis LLM **directly classifies each analyzed conversation into one of 9 statuses**: Resolved, Partially resolved, Knowledge base gap, Overly restrictive instructions, Tool failure, Unclear user intent, Off-topic, Hallucinated response, and Unknown.

Resolution rate formula:

```
Resolution rate = (Resolved + Partially resolved) ÷ Total analyzed
```

Both "Resolved" and "Partially resolved" count toward the numerator of the resolution rate; the other 7 statuses are all treated as unresolved.

Q: Can I create multiple analyses for the same chat platform at the same time?

Yes, but **the date range cannot overlap with an analysis in progress**. If you see the error "This chat platform already has an analysis in progress with an overlapping date range", wait for that analysis to finish or choose a different date range.

Q: How long does an analysis take?

It depends on the conversation volume, Maximum samples, concurrency, and the selected models. In general, 150 samples take from a few minutes to a dozen or so minutes. The default processing time limit is 110 minutes; beyond that, the analysis is automatically marked as failed.

Q: What should I do if an analysis fails?

If the status shows "Failed", check the "Error message" column in the report list. Common messages and how to handle them:

"Analysis timed out — the worker may have crashed during processing." The processing time limit was exceeded: reduce "Maximum samples" to analyze less data, then try again

"Analysis task was never picked up by a worker." The task was not dispatched: simply try again later

Other messages: take a screenshot and report it to your MaiAgent contact for troubleshooting

If the cause is insufficient quota, you are blocked with a notice when creating the analysis, and it will not appear as a report in the "Failed" status.

Q: Why can't my account see "Inbox Analysis"?

"Inbox Analysis" is a sub-item of the "Customer Service" access permission. By default, any MaiAgent role with "Customer Service" access includes this feature.

If you cannot see it, possible reasons are:

Your MaiAgent role does not have "Customer Service" access

The organization administrator has disabled the "Inbox Analysis" sub-permission for your role

Please contact your organization administrator to check and adjust it on the Role Permission Management page.

Notes

Permissions "Inbox Analysis" is a sub-item of the "Customer Service" access permission and is included by default in all MaiAgent roles that have the "Customer Service" permission Organization administrators can go to the Role Permission Management page to adjust which roles have access to this feature Members with this permission can create and view all analysis reports within their organization

Cost reminder Each analysis consumes LLM Input
Output tokens and Embedding tokens Before creating one, confirm the date range and Maximum samples in the dialog You can adjust Maximum samples in Advanced Settings to cap the cost

Data protection During analysis, conversation content is sent to the selected LLM for processing Choose a compliant model according to your organization's data handling policy

Related Features

Further reading Usage Analytics: Agent-level quantitative KPI dashboard Inbox Search: Quickly search for specific conversations Conversation Viewer: View the full context of a single conversation Evaluation Insights Report: Automatic insights after AgentOps batch testing

Human Agent Handoff and Replies

This page explains what human support agents do after a conversation is transferred to them. For handoff conditions and assignment rules, see Human Handoff Settings. For onboarding, daily workflows, and steps for handling different situations, see the Support Agent Handbook.

Set Your Availability

Your current availability appears to the right of the list heading on the Conversations page (for example, “All Conversations”). Open the menu to choose:

Available: Automatic assignment continues assigning conversations to you as usual

Pause Assignments: Automatic assignment skips you. Conversations automatically assigned to you that you **have not yet replied to** are immediately reassigned to the next available colleague (or returned to the queue if no one is available). Conversations you have already replied to, as well as those manually assigned, transferred to you, or taken over by you, remain assigned to you. You can still take over conversations from “Unassigned” yourself

My Time Off⋯: Set time-off periods (multiple periods supported, with minute-level precision, using your browser's local time zone). You will not receive automatic assignments during these periods; automatic assignment resumes when each period ends

Your status applies across all conversation channels you belong to. During scheduled time off, it displays “On Time Off (until end time)”.



The “My Availability” menu on the Conversations page: Available, Pause Assignments, and My Time Off

The following scenario illustrates how to use this menu:

A support agent has a two-hour training session in the afternoon. Before leaving, she switches her status to “Pause Assignments” on the Conversations page. Two unresolved conversations she has already replied to remain assigned to her; a newly assigned conversation she has not yet replied to is automatically reassigned to a colleague. The conversation timeline records “○○ paused assignments; reassigned to ○○”. During this time, new human handoff conversations go to other colleagues. When she returns to her desk and switches back to “Available”, automatic assignment immediately resumes assigning conversations to her.

> If the menu shows “Not in Assignment List”, you are not on the “Assignable Support Agents” list for any conversation channel. Automatic assignment already excludes you, so you do not need to change your status. To receive automatic assignments, ask a channel administrator to add you to the list in Assignment Settings. Administrators can also adjust agents' availability and time off there; see Agent Availability.

Receive Handoff Notifications

When a conversation is assigned to you, you receive both of the following (depending on the Human Handoff Notifications settings):

Email notification: Includes a link that takes you directly to the conversation

Notification Center announcement: A handoff announcement appears in the Notification Center at the top right of the platform

Take Over a Conversation

Conversations assigned to you (including automatic assignments and transfers from colleagues) appear in the "Mine" tab. AI automatic replies stop when the conversation is assigned to you. Simply open it and reply in the input box; no additional button click is needed:

Your messages reach the user in real time through the original channel (Web Chat, LINE, Teams, etc.)

The user receives a successful handoff message (if configured) showing the name of the support agent taking over



A conversation assigned to you: the status bar shows "You are serving this conversation"; reply directly in the input box below

For a conversation with no owner (being handled by AI, outside AI reply hours and awaiting support, queued, or unassigned), open it and click "I'll Take Over". The conversation is assigned to you and AI

automatic replies stop. You can also use this to manually take over a conversation AI is handling even if human handoff is not enabled for the channel.

Reminder When Sending Before Taking Over

If you send a message in a conversation no human agent has taken over (whether by typing, pressing Enter, sending an attachment, or using an AI-suggested reply), a "Before You Send" reminder appears first: "No human agent has taken over this conversation. AI will continue replying to the customer. We recommend taking over before replying."

"Take Over and Send" (also selected by pressing Enter): Assigns the conversation to you and stops AI automatic replies before sending the message

"Send Directly": Sends only the message; AI continues replying to this customer

"Cancel" (or press Esc): Does not send the message

For example, a support agent sees a customer asking about a refund in "Unassigned". AI has already provided a standard explanation, and the agent wants to add "Let me check your order." Pressing Enter opens the reminder. Choosing "Take Over and Send" assigns the conversation to the agent and stops AI replies, so the customer does not receive simultaneous answers from AI and a human.

Outside AI automatic reply hours, the reminder changes to "No human agent has taken over this conversation, and it is currently outside AI reply hours. AI will not reply to the customer. We recommend taking over before replying." If no AI assistant is selected for the channel, it reads "No human agent has taken over this conversation, and this channel has no AI assistant linked. AI will not reply to the customer. We recommend taking over before replying." For example, in a LINE channel that uses only human support (reply hours disabled for all seven days), an agent replying directly from "Unassigned" sees this reminder and knows AI will not also respond. Selecting "Take Over and Send" makes them the owner and prevents colleagues from claiming the same conversation.

If a colleague takes over before you click, you see "This conversation has been taken over by ○○", and the message is not sent. When another colleague is already serving the conversation, "This conversation is currently being served by ○○" appears above the input box, with no additional pop-up.

Unassigned Conversations

The "Unassigned" tab lists **all conversations that currently have no assigned support agent**, including conversations where AI is replying automatically and the user has never requested human support. Open a conversation and check the status bar at the top to identify its current state:

Status Bar	Meaning
"AI Agent Handling"	AI is replying automatically; the user is not waiting for a human

Status Bar	Meaning
“Outside AI Reply Hours • Awaiting Support”	It is outside the channel's AI automatic reply hours (including channels with all seven days disabled that use only human support). AI will not reply, and the conversation will not be automatically assigned to an agent; someone needs to take over
“No AI Assistant Linked to Channel • Awaiting Support”	No AI assistant is selected for the channel (and it is currently within automatic reply hours; outside those hours, the previous status appears). AI will not reply; someone needs to take over
“Waiting for Human Support • Waiting N Minutes”	The conversation has been handed off to human support and is queued, waiting for an agent to claim it
“No Support Agent Assigned”	AI automatic replies are off, but no support agent is responsible yet



The “Unassigned” tab: conversations marked “Queued” are waiting for a human; open one and click “I'll Take Over”

After a human handoff, conversations remain queued for an agent to claim in the following situations:

No agent on the assignment list can take the conversation (all are at capacity, have paused assignments, or are on time off)

The channel's assignment mode is set to “Claim Mode”

A user leaves a message outside service hours (offline behavior set to “Accept Messages”)

Any agent with the required permissions can click “I'll Take Over” in the “Unassigned” tab to claim a conversation. Taking over a conversation AI is handling also stops AI automatic replies.

> Queued conversations that have not been assigned to an agent do not trigger Email notifications. When using message mode or claim mode, arrange for staff to check this tab regularly and watch for conversations with the “Waiting for Human Support” status so user messages are not left unattended.

Messages users send while queued remain in the conversation and are immediately visible when you take over. If the channel enables “Allow Users to Cancel Human Handoff”, users can cancel and return to AI before an agent is assigned. The conversation then leaves the “Unassigned” list (agents receive no separate cancellation notification).

Transfer and Return to AI

Transfer to a colleague: Open a conversation being served (from “Mine”, “Unassigned”, or “All”), click “Transfer”, and choose a colleague. You can enter a reason, such as the issue belonging to another team

Assign a support agent: Conversations being handled by AI, awaiting support, queued, or unassigned all have an “Assign Agent” button in the status bar so you can assign them directly to a specific colleague

Return to AI Agent: When finished, click “Return to AI Agent” in the “Mine” tab to resume AI automatic replies



Returning to AI Agent leaves a record in the message area; AI replies to the user's next message

Understanding the Assignment/Transfer Dialog

"Assign Agent" and "Transfer Conversation" open the same dialog. From top to bottom, it contains:

Transfer Reason (optional): Appears in the conversation details and event timeline.

Select Tags: Apply conversation tags during transfer so the colleague taking over can identify the type of conversation at a glance.

Select Agent: Lists members who can take over, searchable by name or email. Each member's online status appears at the top right (see the table below). The card shows their role, Active Conversations count and load bar (displayed as "active/limit", or "—" when no limit is set; the color changes to a warning color as the limit approaches), and Handled Today count. The current owner is marked Current Assignee. Members who have reached their concurrent conversation limit are marked At Capacity and cannot be selected. Click any other member to assign the conversation (the hint reads "Click to assign this conversation to this agent").



The Transfer Conversation dialog: online status appears at the top right of each card; the current assignee's card is disabled, and clicking another colleague completes the transfer

The selection list shows each colleague's current status so you can avoid those who are offline:

Label	Meaning
Online · Available	Has a backend page open and is available for assignments
Online · Assignments Paused Online · On Time Off	Has a backend page open but is not currently accepting automatic assignments
Offline	Has no backend page open

Members are sorted by "Online and available → Paused/on time off → Offline". Paused and offline colleagues can still be selected; their status is simply indicated. "Online" means **a MaiAgent backend page (any page) is currently open**, regardless of login status. Closing all backend tabs makes the member appear offline. The Agent Workload panel has the same "Online" column.

For example, a support supervisor wants to transfer a VIP complaint to a senior colleague. The transfer dialog shows the intended colleague as Offline, while another senior colleague is Online · Available with "1
5" active conversations. The supervisor transfers to the online colleague so the customer does not have to wait for the offline colleague to return.

For concurrent conversation limits and automatic assignment rules, see Human Handoff Settings.

If Reassign on Timeout is enabled for the channel, a conversation automatically assigned to you is reassigned to the next available colleague if you have not replied to the user before the wait timeout. Send your first reply promptly after receiving an assignment.

If Automatically Return to AI When a Human Agent Does Not Reply is enabled, a conversation you own automatically returns to AI when no agent replies to a customer message within the configured number of seconds. AI continues answering and you are no longer responsible for the conversation. If you cannot handle it immediately, reply to the customer first or transfer it to a colleague.

If Assign Returning Customers to the Previous Assignee is enabled, a conversation you marked "Resolved" reopens and is assigned directly back to you when the customer sends another message within the return window, provided you can take it at that time. AI does not reply first. If you are offline, have paused assignments, or are on time off, normal assignment rules apply instead.

Every transfer, takeover, and return is recorded in the conversation's event timeline (for example, "Human agent took over", "Queue timeout; returned to AI Agent", "○○ paused assignments; reassigned to ○○", "○○ paused assignments; no agents available; returned to queue position N", "○○ did not reply within N seconds; automatically returned to AI Agent", and "Customer sent another message within N hours of resolution; automatically reassigned to previous assignee ○○") so you can trace how the conversation was handled.

> After a conversation returns to AI, the Agent can see the messages exchanged between the customer and human support during the handoff and continue with that context. The customer does not need to repeat themselves.

What the User Sees

During the handoff, users receive prompts for each stage (customize the content in Transfer Messages):

Handoff triggered → Transfer notification (for example, “Connecting you to a human support agent. Please wait.”)

Enter queue → Queue prompt (can show queue position and estimated wait time)

Send another message while queued → Waiting reminder (requires Queue Reminder; shown only once per cooldown period)

User cancels → After clicking “Let AI Answer” or entering a cancellation keyword, the user receives a return message. AI then answers the last message the user sent while queued (requires Allow Users to Cancel Human Handoff)

Agent takes over → Successful handoff message (can display the agent's name)

Queue timeout → Timeout notification and return to AI for continued service (if reassignment on timeout is enabled, the system first tries other currently available agents who have not already been assigned this conversation; it returns to AI only if no one is available)

Outside service hours → Offline message

No agent reply after takeover within the configured number of seconds → Return-to-AI message; AI then answers the user's last unanswered message (requires Automatically Return to AI When a Human Agent Does Not Reply)



The handoff process for Web Chat users: transfer notification, queue prompt, agent takeover message, and human agent replies

Satisfaction Feedback

Users can provide feedback on service quality in two ways:

Message Feedback (Thumbs Up/Down)

Users can give each reply a thumbs up or down and add written suggestions. View their feedback in the conversation history.


Conversation Satisfaction Survey (1–5)

Web Chat supports an overall satisfaction survey: after a conversation has been idle for a while, a 1–5 rating (dissatisfied to satisfied) and an optional comment field appear automatically. Each conversation can be rated only once.



The satisfaction survey users see in Web Chat

Go to “Conversation Channels” → select a web channel → “Satisfaction Survey Settings”. Enable “Enable Satisfaction Survey” to adjust “Delay (Minutes)” and “Survey Title Text”.



Satisfaction survey settings for a web channel

Results appear in the “Conversation Satisfaction” section of the conversation's “Details” panel, including the score, comment, and submission time. “Not Yet Rated” appears until the user submits a rating.



The “Conversation Satisfaction” section in conversation details, with the conversation timeline below

Contacts

What Is a Contact?

A **Contact** is one of MaiAgent's core features, functioning like an enterprise's "customer card file." It lets businesses create a dedicated identity profile for each customer, so every conversation can deliver a personalized service experience.

> In simple terms: A contact is like a "customer data card" that records the customer's identity and permissions. When a customer visits, the Agent uses this card to decide which services and content to provide.



Identity recognition example

Imagine a customer interacting with you through the website chat window. The system can immediately recognize "This is Mr. Zhang, a VIP member" or "This is a new visitor who can only access some documents," and provide the corresponding service content and permissions.

Why Do You Need the Contact Feature?

Personalized Service Experience

Every customer has unique needs and a unique background. The contact feature lets the Agent:

Remember the conversation history with that customer
Provide appropriate information based on the customer's identity
Avoid asking again for information it already knows

Precise Permission Management

Different customers should see different content:

VIP members can view exclusive offers
Regular members see standard service content
Visitors can only use public information


Data Security Protection

Ensures customers can only access their own data, preventing information leaks.

How Do Contacts Work?

When a user opens the chat window, the conversation request is sent to the enterprise's internal system for processing, which determines whether member information has been passed in. Based on the result, the system finds or creates a contact (anonymous or non-anonymous). Whichever path is taken, a personalized conversation begins, ensuring every user gets a personalized experience.

Contact workflow diagram



Contact workflow diagram

Contact Types

MaiAgent's contact system has two types, based on how the user's identity is recognized:

> In simple terms: Anonymous contact = a visitor who is not logged in; the system does not know who they are Non-anonymous contact = a logged-in member; the system knows their identity and data

Contact Type Comparison

Item	Anonymous Contact	Non-Anonymous Contact
When It Applies	Visitors who enter directly from a web page without logging in to the enterprise member system, so there is no account from which to retrieve user data	Members who are logged in, or who enter through another platform account (such as Facebook or LINE); the system can obtain the user's name and account information
Identity Recognition	No specific personal information can be obtained	Has clear identity information (such as name and profile picture)
System Setting	Set to "Anonymous" within the MaiAgent system	The original member account ID is converted into a Source ID
Permission Management	Knowledge base file permissions, channel management	Same for both
Data Mapping	No Source ID, so the contact cannot be mapped to enterprise member data	The Source ID ensures the contact is always mapped to the correct user
How It Is Created	When a visitor (without member identity) enters, a new anonymous contact is automatically created for each conversation	Automatically created or updated through the MaiAgent API based on member login information For integration details, see: Technical Handbook—Contacts: Introduction and Integration
Record Keeping	The system records the user's conversation history based on cache	Conversation continuity is maintained through the Source ID and contact mapping

> Why the Source ID (Source ID) Matters The Source ID is the key bridge between a MaiAgent contact and the enterprise member system. When users interact with the enterprise through different channels (website, app, social platforms), the system can correctly recognize the user's identity through the Source ID, ensuring conversation continuity and a personalized experience. In simple terms: The Source ID is like a "member number" that lets the system recognize the same customer across different platforms.

Set Up Contacts

Contact List Filters and Columns

Go to Customer Conversations → Contacts from the left menu. At the top of the list you can search contacts (by name), filter by channel type (first choose a type such as Web or LINE, then choose a specific channel), and filter by tag. In the upper right are Tag Management, Bulk Import, Add Contact, and Refresh. The columns are:


Column	Description
ID	The contact's identifier, used by the API and by Source ID login-free conversations
Contact	Avatar and name; anonymous users show a system-generated name
Phone Number	Imported from the messaging platform or entered manually
Channel	Which channels this contact appears in
Source ID	The user identifier from the enterprise or messaging platform; see Non-Anonymous Users
Query Metadata	Limits the range of documents this contact can query; see Query Metadata
Tags	Applied contact tags
Created At, Last Updated	
Actions	Edit, delete (you are asked to confirm before deleting)

After selecting multiple contacts, "N contacts selected" appears at the top along with Bulk Add Tags Bulk Remove Tags; see Tag Contacts.

Anonymous Users

When a user starts a new conversation, the system automatically creates a new anonymous user in the background (each conversation is one anonymous user) ⬇️





Contact list: Web Chat visitors without a Source ID are shown as "Anonymous"

The record includes the contact ID, channel history, creation time, and more.

You can click Edit to manually edit the anonymous contact's information:





By editing, you can:


Link member information: enter a Source ID to link the anonymous contact to member data
Update the permission level: open up or restrict the range of documents they can read
Add basic details such as the customer's name and contact information


Non-Anonymous Users

If Web Chat has both login and the data collection form enabled, the form data entered by a logged-in user is tied to their login account, so they do not have to fill it in again on another device. For details, see Web Chat Overview: Data Collection (Pre-chat Form).

When a user enters through another channel (such as LINE, FB Messenger, or Telegram):


The back end automatically creates the corresponding non-anonymous user based on the user's FB information (including Source ID, contact name, profile picture, and more):





Filtered by channel: contacts with a Source ID show their names

You can still click the Edit button to edit the non-anonymous contact's information.



Edit contact: Basic Information tab

By editing, you can:

Complete and correct data

Correct the Query Metadata settings (update the open range according to permissions)

Change the Source ID within the enterprise to link the correct contact information and member information

> Contacts rely on the Source ID for mapping, so when editing, make sure the Source ID stays in sync with the enterprise's internal systems. Otherwise, data mapping errors may occur later when programs synchronize with internal enterprise information.

Add a Contact

The Add Contact feature is mainly used to **proactively create customer profiles with preset permissions**. If you have not specified a permission scope in Web Chat, you can create the contact in advance and complete the permission configuration and service preparation before the customer actually starts a conversation.


> To specify the permission scope with a JavaScript snippet when initializing Web Chat, see: Technical Handbook: Getting Started—Using JSON Format

Core Features

By creating contacts manually, system administrators can set up user profiles for specific identities in the customer service system in advance and configure the corresponding **Query Metadata permissions**. When these pre-created contacts later interact with customer service through a **specified channel**, the system uses its **automatic Source ID matching mechanism** to immediately apply the preset permission level, ensuring they can access data appropriate to their identity.

> In simple terms: It is like "preparing the customer's permission settings ahead of time." When this customer visits for the first time, the system already knows what data they can and cannot see.


You can click Add Contact to open the edit page and enter the information:



Click "Add Contact" in the upper right of the contact list



On this page, you can enter the contact's name, specify channels, and more:



Basic Information Fields

Field	Description
Avatar, Name	The display name customer service sees in "All Conversations"
Email, Phone Number	Contact details, shown in the "Contact Information" section of the conversation details; Email is also what bulk import uses to match existing contacts
Channel	Which channels this contact belongs to; multiple selections allowed
Source ID	The contact's identifier in an external system, used for Source ID login-free access and for bulk import matching
Tags	Apply one or more contact tags

Field	Description
Query Metadata	Controls which documents this contact can retrieve from the knowledge base. You can enter JSON directly or switch to the Query Builder to build conditions through the interface; see Query Metadata and Query Builder

Other tabs in the edit window: for MCP Credentials and API Credentials, see Contact MCP Credential Setup and Set API Credentials for Each Contact; Connector Authorizations and Custom Properties are described below.

Custom Properties

The Custom Properties tab lets you add any "property name = value" pairs to a contact, such as membership level, account manager, or contract number. These properties appear in the "Contact Information" section of the conversation details in "All Conversations," so customer service can see the background information right away when taking over.

Click Add Property and fill in the Property Name and Value (names must be unique). On the right side of the list you can edit or Delete Property.

The JSON Preview below shows the JSON of all current properties, making it easy to check when integrating with other systems.

> The custom properties here belong to the contact (the external customer), which is different from the Custom Attributes on an organization member's "Profile" page. Custom properties are only for customer service to see and do not affect the knowledge base retrieval scope. To limit the documents a contact can query, use "Query Metadata."

Connector Authorizations

When an Agent has an MCP tool that requires individual authorization from each contact (for example, the Google Workspace connector; see Create an MCP Tool), the contact completes OAuth authorization within the conversation. The Connector Authorizations tab lists this contact's authorization status for each connector:

Field	Description
Status	Valid, Expired, Revoked, or Not Authorized
Expires At, Last Used	The authorization's validity period and the last time a tool used it
Scopes	The permission scopes the contact agreed to

Actions:

Revoke: Revokes the authorization immediately. The contact must authorize again the next time they use the tool. Use this when a contact asks to cancel access or an account may have been compromised.

Trigger Re-authorization: Marks the current authorization as invalid, so the contact is asked to authorize again the next time they use it. Use this when the scopes have changed and the contact needs to consent again.

No manual action is needed when the status is "Expired": once the access token expires, it is refreshed automatically at the next actual Q&A, and the contact does not need to authorize again.

When there are no authorizations, "This contact has not authorized any Connector" is displayed.

Contact Tags

Contact tags are applied to **people** (for example "VIP," "Distributor," "North Region"). They are used to categorize contacts and to find conversations in "All Conversations" with Filter by Contact Tag. They are separate from the conversation tags applied to **conversations**: conversation tags are managed per channel, whereas contact tags are a single list shared across the whole organization.

Tag Management Page

Go to Customer Conversations → Contacts and click Tag Management in the upper right to open the tag management page, where you can add, edit, and delete contact tags for the whole organization:

Add Tag: Enter a Tag Name (up to 50 characters) and confirm.

Edit Tag: Renaming affects all contacts that already have this tag, so there is no need to reapply it one by one.

Delete: After confirmation, the tag is automatically removed from all contacts, and a message such as "N contacts affected" appears when it finishes.

Tag Contacts

You can apply tags in three places:

Location	How
Contact edit window	Select tags in the Tags field of Basic Information
Bulk actions in the contact list	Select multiple contacts, click Bulk Add Tags or Bulk Remove Tags at the top, choose one or more tags under "Select Tags," and confirm. A message such as "N contacts updated" appears when it finishes
Details panel in All Conversations	Add or remove tags directly in the conversation's Contact Tags section; see Conversation Details

At the top of the contact list you can filter by tag, and combine it with filter by channel type and search to quickly find a group of contacts and then tag them in bulk.

Bulk Import Contacts

When you need to create or update many contacts at once, you can first preview the estimated counts and channel assignment, then confirm the import. The preview does not write any data; the import runs only after you click Confirm Import.

Use Case

A customer service supervisor wants to import a list of event contacts, some of whom already belong to the after-sales service channel. She chooses Merge, uploads the completed template, checks the estimated numbers of contacts to be created and updated, and then confirms the import. The existing after-sales assignments are kept, and the event channel selected this time is added, which avoids overwriting existing associations in bulk.


Prepare the Import File

> Use the Excel template (.xlsx) downloaded from within the window. The file must be smaller than 10 MB and have at most 10,000 rows. Name, Email, and Source ID are required; Phone Number is optional.

The system matches contacts by `Source ID` and `Email`; Email matching is case-insensitive. If an existing contact is found, its name and phone number are updated. If the same file contains duplicate matching data, only the first entry is used.

Import and Preview

Go to Contacts, click Bulk Import, and download the template from the Bulk Import Contacts window.



Open Bulk Import from the upper right of the Contacts page.

Select at least one channel and set the inbox assignment:

Replace (default): This selection becomes the complete channel list for these contacts, and existing associations that are not selected are removed.

Merge: Keeps existing associations and only adds the channels selected this time.



Bulk Import Contacts: download the template, choose channels and inbox assignment, then upload the Excel file.

Upload the completed `.xlsx` and click Preview Import.

In Import Preview, check the estimated "To be created" and "To be updated" counts, the file name, the channels, and the assignment mode. To make changes, click Back to Edit; once everything looks correct, click Confirm Import.



Check the estimated create/update counts and the assignment mode before running the import.

> Before choosing Replace, make sure you have selected all the channels you want to keep. If you only want to add channels to existing contacts, choose Merge instead.

If the preview shows that there is no data to create or update, go back and check the template contents. If the import fails, the system keeps the settings screen and displays an error; fix the file and preview again.

Permission Management

Depending on your enterprise's needs, you can use Query Metadata to limit the range of documents different contacts can use, for example:

Restrict by Membership Level

VIP members: Can query all knowledge bases, premium FAQs, and product technical documents

Regular members: Can only query basic FAQs and product user manuals

Visitors: Can only query public FAQs and basic product introductions

Restrict by Department Permission

Internal employees: Can query internal operation manuals, system maintenance documents, and complete product information

Distributors: Can query product specifications, price lists, and sales materials

General customers: Limited to usage instructions, FAQs, and warranty information

Restrict by Product Tag

Enterprise edition users: Can query documents tagged "Enterprise Features" and "Advanced Settings"

Personal edition users: Can only query documents tagged "Basic Features" and "Personal Use"

Trial users: Can only query content tagged "Trial Guide" and "Getting Started"

> To learn more about Query Metadata, see: Knowledge Management Permissions: Query Metadata

When setting Query Metadata for a contact, the system only authorizes settings for the knowledge bases of the channels you have specified. If you configure settings for the knowledge base of another channel, the following warning message appears:



Automation Integration

For technical teams, MaiAgent also provides API endpoints that integrate seamlessly with the enterprise's existing systems.

> For details, see: Technical Manual — Contacts Overview and Integration

Regardless of the size of your organization, the contacts feature helps you deliver a better customer service experience while keeping data secure and operations efficient. Through classified management of anonymous and non-anonymous contacts, a precise Source ID mapping mechanism, and flexible

creation methods, enterprises can provide the most suitable service experience for different types of users and be fully prepared before customer interactions begin.

AI Customer Service Quality Management

Audience: Customer service managers, quality management staff, and customer service trainers

On this page: 1. Quick Start: Three Quality Metrics for AI Customer Service | 2. How to Read Evaluation Reports | 3. Practical Examples: Common Issues in Apparel | 4. Three-Step Improvement Plan | 5. Daily Management Checklist | Appendix A: Issue Diagnosis Reference | Appendix B: System Evaluation Metrics | Frequently Asked Questions Q\&A | Closing

1. Quick Start: Three Quality Metrics for AI Customer Service

How Do I View Evaluation Report Scores?

Path: AgentOps (sidebar) → AI Assistant Monitoring → Conversation Records tab

The Quality Score column in the table uses faithfulness as the main representative score. Hover over a score to view individual metrics (including faithfulness, answer relevancy, and context precision) in Quality Score Details. Click the Details icon in the actions column to open the details for that conversation.



Quality Score column and Details button in Agent Monitoring → Conversation Records

> Quality scores are generated only after you enable automatic evaluation for the Agent: go to AI Assistants → select an Agent → Settings → Advanced Settings, turn on Enable Automatic Evaluation, and save. Once enabled, the system uses an LLM to calculate quality scores for each conversation, consuming your organization's usage quota. When disabled, the Quality Score column displays "-".



Enable automatic evaluation in the Agent's advanced settings

Why Is Evaluation Necessary?

Just as you review recordings of customer service calls, you also need to check the quality of AI responses.\
The system automatically scores each conversation to help you identify issues quickly.

Three Core Metrics

Metric	Plain-Language Explanation	Scoring Criteria
Faithfulness Score	Is the AI's information correct, without fabrications or hallucinations?	85 or above ✅ 60-84 ⚠️ Below 60 ❌
Answer Relevancy Score	Did the AI answer what the customer actually wanted to know?	85 or above ✅ 60-84 ⚠️ Below 60 ❌
Context Precision Score	Did the AI find the right reference material and focus precisely on the context?	85 or above ✅ 60-84 ⚠️ Below 60 ❌

Quick Assessment

```
All three metrics > 80  → ✅ This was a good response
Any metric < 60         → ❌ Immediate improvement needed
Two or more < 70        → ⚠️ Systemic issue; comprehensive review needed
```

2. How to Read Evaluation Reports

Sample Report

```
Conversation ID: #20240120-001
Customer question: “Is the black trench coat in size XL still in stock?”
AI response: “The black trench coat is currently in stock. Size XL is available
to order.”

Evaluation results:
├─ Faithfulness score (faithfulness_score): 45 ❌ (Claims it is in stock, but it
is actually out of stock)
├─ Answer relevancy score (answer_relevancy_score): 90 ✅ (Does answer the
inventory question)
└─ Context precision score (context_precision_score): 70 ⚠️ (Found trench coat
information, but size information is not precise enough)

Issue diagnosis: The AI provided incorrect inventory information
```

Three Common Types of Issues

Issue A: Low Faithfulness Score (< 60)

Symptom: The AI provides incorrect or fabricated information

Common causes:

Outdated reference material (prices, inventory, or policies have changed)
Conflicting information (different documents give different answers)
The AI “guesses” answers instead of relying on database content

Impact: Customers may receive incorrect information, leading to complaints

Issue B: Low Answer Relevancy Score (< 60)

Symptom: The AI does not answer what the customer actually wants to know

Common causes:

The AI says a lot but misses the point
The response is off-topic and includes irrelevant content
The AI provides background information without an actual answer

Impact: Customers need to ask again, reducing satisfaction

Issue C: Low Context Precision Score (< 60)

Symptom: The AI finds incorrect reference material or material that is not precise enough

Common causes:

Inaccurate keyword searches
Confusion between information for different products/categories
Unclear titles or categories in reference material

Impact: Even if the AI tries to answer well, using the wrong material leads to incorrect answers

3. Practical Examples: Common Issues in Apparel

Case 1: Incorrect Price (Low Faithfulness Score)

📊 Issue Identified

Customer question: "How much is this down jacket?"

AI response: "This down jacket costs NT$ 3,990."

Evaluation results:

Faithfulness score (faithfulness_score): **38** ❌
Answer relevancy score (answer_relevancy_score): 95 ✅
Context precision score (context_precision_score): 85 ✅

Actual situation:\
The price has been reduced to NT$ 2,990 (after discount), but the AI still quotes the original price.

💡 Improvement Plan

Step 1: Check the Data

Open the "Product Price List" in the knowledge base
Find that the prices have not been updated

Step 2: Update the Data

❌ Problematic Data

```
Down Jacket Collection
- Classic down jacket: NT$ 3,990
- Long down jacket: NT$ 4,990
```

✅ **Corrected Data**

```
Down Jacket Collection (Winter 2024 Prices)

Product name: Classic down jacket
- Original price: NT$ 3,990
- Discounted price: NT$ 2,990 (from 2024/1/1)
- Promotion period: 2024/1/1 - 2024/2/28

Product name: Long down jacket
- Original price: NT$ 4,990
- Discounted price: NT$ 3,990 (from 2024/1/1)
- Promotion period: 2024/1/1 - 2024/2/28

Last updated: 2024/1/15
```

Step 3: Remind the AI

Add the following to “AI Response Principles”:

“When answering price questions, always confirm that the price is current and specify its validity period. If a discount promotion is available, provide both the original and discounted prices.”

Case 2: Off-Topic Response (Low Answer Relevancy Score)

📊 **Issue Identified**

Customer question: “Can I return it if it doesn't fit?”

AI response: “We offer a range of sizes, including S, M, L, and XL. Each item's size chart is listed on its product page. We recommend checking the size chart and taking your measurements before purchasing.”

Evaluation results:

Faithfulness score (faithfulness_score): 90 ✅
Answer relevancy score (answer_relevancy_score): **35** ❌
Context precision score (context_precision_score): 60 ⚠️

Issue diagnosis:\
The customer asks “Can I return it?”, but the AI explains “How to choose a size” without answering

the core question at all.

💡 Improvement Plan

Step 1: Adjust Response Principles

Add the following to “AI Response Principles”:

Core principle: Answer the customer's core question first

Incorrect example:

Customer asks “Can I return it?”

AI answers “We provide comprehensive after-sales service...” ❌ (Does not say whether a return is allowed)

Correct example:

Customer asks “Can I return it?”

AI answers “Yes. You can request a return within 7 days of delivery if the item is unused...” ✅ (Direct answer)

Step 2: Restructure the Data

❌ Problematic Data (Unfocused)

```
After-Sales Service Information

Our company values customer rights and provides comprehensive after-sales
service.
Please read the size chart carefully when purchasing and choose a suitable size.
If you have any questions, please contact customer service ...
```

✅ Corrected Data

```
Return and Exchange Policy

Q: Can I return an item?
A: Yes. You can request a return within 7 days of delivery if the item is unused
and its tags are intact.

Return conditions:
✅ Item is unused, unwashed, and has not been tried on for more than 10 minutes
✅ Tags and packaging are intact
✅ Request is submitted within 7 days of delivery
❌ Sale items and underwear cannot be returned

Return process:
1. Call customer service at 0800-XXX-XXX or complete the online form
2. Customer service provides the return address and reference number
3. Refund is issued to the original payment method within 7-14 days

---

Q: Can I exchange an item?
A: Yes. Within 7 days of delivery, you can exchange it for another size or color
free of charge (same product only).

Exchange process:
1. Contact customer service to confirm availability
2. Send the item back (same conditions as returns)
3. The replacement is shipped within 3 days of receiving the item
```

Key improvements:

✅ Start with a direct "Yes" or "No"

✅ Use a Q\&A format for clarity

✅ List explicit conditions to avoid disputes

Case 3: Wrong Product Retrieved (Low Context Precision Score)

📊 **Issue Identified**

Customer question: "What material is the black knit top made of?"

AI response: "This knit top is made of 100% pure cotton. It is soft, comfortable, and suitable for all seasons."

Evaluation results:

Faithfulness score (faithfulness_score): 88 ✅

Answer relevancy score (answer_relevancy_score): 90 ✅

Context precision score (context_precision_score): **48** ❌

Actual situation:\
The black knit top is 70% wool + 30% polyester. The AI retrieved information for the “white knit top” (100% pure cotton).

💡 Improvement Plan

Step 1: Check Data Labels

Problematic data filename:

```
針織上衣.pdf
```

Issue: All knit tops are in the same document, making them difficult for the AI to distinguish.

Step 2: Improve the Data Structure

✅ Solution A: Separate Documents

```
商品資料

├─ 針織上衣_黑色_型號A001.pdf
├─ 針織上衣_白色_型號A002.pdf
├─ 針織上衣_灰色_型號A003.pdf
```

✅ Solution B: Clear Headings

```
# Knit Top Product Information

## Black Knit Top (Model: A001)
- Color: Black
- Material: 70% wool + 30% polyester
- Suitable seasons: Fall and winter
- Care: Hand wash; do not tumble dry

## White Knit Top (Model: A002)
- Color: White
- Material: 100% pure cotton
- Suitable seasons: Spring, summer, fall, and winter
- Care: Machine washable; tumble dry on low

## Gray Knit Top (Model: A003)
- Color: Gray
- Material: 50% wool + 50% acrylic
- Suitable seasons: Fall and winter
- Care: Dry clean
```

Step 3: Remind the AI

Add the following to “AI Response Principles”:

“When a customer mentions a product's color or model, always verify that the reference material is for that color and model. Different colors of the same product may have different materials and specifications.”

4. Three-Step Improvement Plan

When you identify an issue, follow this process:

```
Identify a low score
    ↓
Step 1: Update the data content (most important)
    ↓
Step 2: Adjust AI response principles
    ↓
Step 3: Escalate to the technical team (if needed)
```

Step 1: Update the Data Content

When to use:

✅ Low faithfulness score (incorrect or outdated data)

✅ Low context precision score (disorganized or poorly labeled data)

Checklist:

[ ] Is the data the latest version?
[ ] Are prices, inventory, and policies correct?
[ ] Is information for different products clearly separated?
[ ] Are headings clear? (So the AI can find the information easily)
[ ] Is information presented in lists or tables? (Rather than long paragraphs)

Data quality examples:

❌ Poor Data

```
Return Information

Some products can be returned, but certain conditions apply.
Some special products cannot be returned; please check before purchasing.
Contact customer service if you need to return an item.
```

✅ Good Data

```
Return Policy

Returnable products:
✅ General apparel (tops, pants, jackets)
✅ Accessories (bags, hats, scarves)

Non-returnable products:
❌ Underwear and swimwear
❌ Sale items (50% off or more)
❌ Customized products

Return conditions (all must be met):
1. Within 7 days of delivery
2. Item is unused (tags intact; no signs of wear from trying it on)
3. Packaging is intact

Return process:
1. Call customer service at 0800-XXX-XXX
2. Provide the order number
3. Customer service provides the return address
4. Send the item back (registered mail recommended)
5. Refund is issued 7-14 days after receiving the item

Contact information:
- Customer service hotline: 0800-XXX-XXX (09:00-21:00)
- Online customer service: Chat box at the bottom right of the official website
- Email: service@example.com
```

Step 2: Adjust AI Response Principles

In this guide, "AI Response Principles" refers to the Agent's Role Instructions (AI Assistants → select an Agent → Settings → Response Mode Settings → Role Instructions).

When to use:

✅ Low answer relevancy score (off-topic answers)

✅ Low faithfulness score (AI guessing or fabricating information)

AI Response Principles Template:

AI Customer Service Response Principles

Core Rules

1. Answer the core question first
   - Customer asks “Can I?” → Start with “Yes” or “No”
   - Customer asks “How much?” → Start with the price
   - Customer asks “How do I?” → Start with the steps

2. Only state what you know
   - All information must come from reference material
   - If unsure, say “A human customer service representative needs to assist with this”
   - Never guess or make assumptions

3. Pay attention to details
   - Do not confuse colors, sizes, or models
   - Confirm that prices are current
   - Clearly state promotion periods

Response Format

Policy Questions (Returns, Exchanges, Membership, Promotions)
Paragraph 1: Answer directly with “Yes” or “No”
Paragraph 2: Explain the conditions (using a list)
Paragraph 3: Tell the customer what to do (process or contact information)

Product Questions (Price, Material, Inventory)
Paragraph 1: Answer the question directly (price/material/availability)
Paragraph 2: Add product information (specifications, sizes, colors)
Paragraph 3: Provide a purchase link or next step

Process Questions (How to Buy, Return, or Exchange)
Paragraph 1: Summarize the process (3-5 steps)
Paragraph 2: Explain each step in detail
Paragraph 3: Provide notes or contact information

Prohibited Actions

❌ Do not say “usually,” “generally,” or “probably” (be specific)
❌ Do not confuse information for different products
❌ Do not omit important conditions (prices, sizes, deadlines)
❌ Do not infer information the customer has not provided

Examples

✅ Good response:

```
Customer: “Can I return this jacket?” AI: “Yes. You can request a return within 7 days of delivery if the following conditions are met:
The item is unused and the tags are intact
The packaging is undamaged
It is not a sale item
Return process: Call customer service at 0800-XXX-XXX. We will provide the return address and instructions. The refund will be issued to the original payment method in about 7-14 business days.”

❌ Poor response:
Customer: “Can I return this jacket?” AI: “Our company values customer rights and provides comprehensive after-sales service. We recommend reading the product description carefully before purchasing and choosing a suitable size. If you have any questions, please contact customer service…” (Does not directly answer whether a return is allowed)
```

Step 3: Escalate to the Technical Team

When to use:

Context precision scores remain low

The same issue recurs

Updating data and principles has not improved the situation

Report content:

```
Issue type: Low context precision score

Issue description:
When customers ask about “black” products, the AI often retrieves information for
“white” or other colors.

Scope of impact:
This occurs in about 15% of product inquiries

Improvements attempted:
✅ Separated product information for different colors into separate files
✅ Clearly labeled colors in headings
⚠️ The issue is still not fully resolved

Suggested technical adjustment:
Improve the system's ability to identify “color” keywords more precisely

Attachments:
- test_cases_color_queries.csv (100 test questions)
- current_results.csv (current system retrieval results)
- expected_results.csv (expected correct results)
```

5. Daily Management Checklist

Daily Checks

When you find an issue:

```
If the same type of issue occurs ≥ 3 times
→ Address it immediately (update data or adjust principles)

If it involves incorrect prices or policies
→ Make an urgent correction the same day

If it is an isolated issue
→ Record it, monitor it, and add it to the discussion
```

Response Quality Tracking

1. Data Review

```
This week's statistics:
- Total conversations: ___
- Average faithfulness score (faithfulness_score): ___
- Average answer relevancy score (answer_relevancy_score): ___
- Average context precision score (context_precision_score): ___
- Problematic conversations: ___ (____%)
```

2. Issue Analysis

```
Top 3 recurring issues:
1. ________ (__ occurrences) - Which metric is low?
2. ________ (__ occurrences) - Which metric is low?
3. ________ (__ occurrences) - Which metric is low?
```

3. Improvement Actions

```
This week's tasks:
□ Update ___ documents (Owner: ___)
□ Adjust ___ response principles (Owner: ___)
□ Report ___ technical issues (Owner: ___)

Next week's goals:
- Reduce the rate of problematic conversations to < ____%
- Average score for every metric > ___
```

Appendix A: Issue Diagnosis Reference

Score Pattern	Possible Cause	Improvement
Low faithfulness score	Outdated or incorrect data; AI fabricates information	Step 1: Update the data content
Low answer relevancy score	AI gives off-topic answers	Step 2: Adjust response principles
Low context precision score	AI finds incorrect or imprecise material	Step 1: Improve data labeling
Multiple low metrics	Systemic issue	Steps 1+2, and Step 3 if needed

Improvement Priorities

```
First priority: Faithfulness score < 60
→ May give customers incorrect or fabricated information, leading to complaints

Second priority: Answer relevancy score < 60
→ Poor customer experience; customers must ask again

Third priority: Context precision score < 60
→ The issue may be less obvious, but it affects quality over time
```

Appendix B: System Evaluation Metrics

Primary Metrics (No Reference Answer Required)

These three metrics are the core of this guide and can be applied directly to daily customer service conversation evaluations:

Chinese Name	Full English Name	Description
Faithfulness Score	Faithfulness	Evaluates whether the AI response matches database content and whether it hallucinates or fabricates information
Answer Relevancy Score	Answer Relevancy	Evaluates whether the AI response is relevant to the customer's question or is off-topic
Context Precision Score	Context Precision	Evaluates whether the AI response focuses precisely on the context and uses the right reference material

Advanced Metrics (Reference Answer Required)

The following metrics require a "reference answer" (ground truth) prepared in advance and are suitable for test case evaluations:

Chinese Name	Full English Name	Description
Answer Correctness	Answer Correctness	Compares the AI response with the reference answer to evaluate correctness
Answer Similarity	Answer Similarity	Evaluates semantic similarity between the AI response and the reference answer
Context Recall	Context Recall	Evaluates whether the system retrieves all necessary reference material

Other Available Metrics (DeepEval)

In the evaluation results under AgentOps → Automated Testing, the system also provides the following additional metrics for more comprehensive quality checks:

Chinese Name	English Name	Description
Bias	Bias	Detects bias or discriminatory content in responses
Toxicity	Toxicity	Detects inappropriate or offensive content in responses
Hallucination	Hallucination	Detects AI-generated content that contradicts facts
Contextual Relevancy	Contextual Relevancy	Evaluates whether retrieved reference material is relevant to the question

Usage Recommendations

Daily monitoring: Use the three primary metrics (faithfulness, answer relevancy, and context precision)

Test evaluations: Combine advanced metrics with reference answers for systematic evaluations

Quality control: Monitor bias and toxicity metrics in automated test results to ensure responses meet company standards

Frequently Asked Questions Q\&A

Q1: Can I manage AI customer service without technical knowledge?

A: Yes! Just as you manage customer service staff, you only need to:

Review evaluation reports daily to identify problematic conversations

Check that data is correct and complete

Adjust the AI's “response principles” (like training customer service staff on what to say)

Q2: Where do the scores come from? Does the AI evaluate itself?

A: No. A dedicated “evaluation system” scores responses automatically, like another AI acting as “quality control” to check the first AI's responses.

Q3: Are all three metrics important? Can I look at just one?

A: We recommend checking all three because they reflect different issues:

Faithfulness score (`faithfulness_score`): Does the AI match database content without fabricating information?

Answer relevancy score (`answer_relevancy_score`): Does the AI understand the question and provide a relevant answer?

Context precision score (`context_precision_score`): Does the AI focus precisely on the context and find the right reference material?

If you check only one metric, you may miss important issues.

Q4: How soon will I see results after making improvements?

A:

Data updates: Take effect immediately (improvements can be seen the same day)

Response principle adjustments: Take effect immediately

Technical adjustments: Take 2-4 weeks (depending on the complexity of the issue)

Closing

Managing AI customer service is like managing a human customer service team:

✅ **Check quality regularly** (review evaluation reports)

✅ **Keep knowledge up to date** (update data content)

✅ **Improve service responses** (adjust response principles)

✅ **Record improvement results** (track score changes)

Follow this guide to keep improving your AI customer service, even without technical knowledge!

Use Cases: Text Customer Service

In enterprise customer service, handling a large volume of frequent customer inquiries manually not only causes delays but also overloads support staff and hurts overall service efficiency. Many repetitive questions come up again and again and consume a great deal of time, making it hard for the team to focus on more complex customer needs and problem solving.

Now you can use MaiAgent to build an external-facing AI text customer service assistant for your business, effectively reducing support costs and improving service quality and customer satisfaction!

Use Cases

Website and messaging platform support: Embed the Agent in your website, or connect it to messaging platforms your customers already use, such as LINE, Facebook Messenger, and WhatsApp, to provide instant replies 24 hours a day.

Regulation and policy inquiries: Government agencies and highly regulated industries need to let the public and internal staff quickly find answers in a large body of regulatory announcements, and replies must include their sources.

Product specifications and recommendations: Catalogs, spec sheets, and comparison tables are large and frequently updated, and customer questions are varied, so looking up answers manually is time-consuming.

Order and after-sales inquiries: You need real-time access to external system data such as order status, warranty coverage, and repair progress, which static documents alone cannot answer.

> The same knowledge base can be used by multiple Agents at once. A common approach is to create one Agent for "external customers" and another for "internal support staff," sharing the knowledge base but giving each a different role instruction so that the level of detail and tone of their replies differ.

How It Works

Step	Description
① **Customer asks a question**	The customer asks a question on a connected platform such as the website Web Chat, LINE, or Facebook Messenger
② **Agent takes over**	Based on the role instruction, the Agent decides which data sources to use to answer

Step	Description
③ **Find the answer**	Retrieves relevant passages from the knowledge base through semantic search and matches them against FAQ entries; when real-time data is needed, calls tools to query external systems
④ **Generate a reply**	Combines the retrieval results into a reply and, depending on your settings, attaches citation sources
⑤ **When it cannot answer**	Triggers handoff to a human agent, passing the conversation to support staff

After receiving a question, the Agent first uses semantic search to find relevant passages in the knowledge base, then has the language model combine them into a reply and, depending on your settings, attaches citation sources so customers can trace and verify the answer. If a question falls outside the scope of the knowledge, you can set up human handoff notifications to pass the conversation to support staff and prevent the AI from giving made-up answers.

Setup Workflow

1. Create an Agent

On the AI Assistants page, enter a name, select RAG and a language model, and set the answer mode. For general text customer service, "RAG Q&A" is sufficient. See Create an Agent for details.

2. Write the Role Instruction

The role instruction determines the AI's identity, output format, and answer boundaries, and is the key to support quality. We recommend stating explicitly that "information outside the knowledge base must not be answered" and providing a standard reply for when the Agent cannot answer. For guidance on writing it, see the Role Instruction Design Guide.

3. Build the Knowledge Base and FAQ

Upload catalogs, spec sheets, announcements, and other documents to build a knowledge base, or use the crawler feature to extract website content automatically. For frequently asked questions with fixed answers, create a separate FAQ to keep replies consistent. Before going live, you can use search testing to confirm that retrieval returns the right results.

4. Configure Tools (Optional)

If support needs real-time data such as orders or inventory, you can configure tools for the Agent so the AI can call your internal APIs directly to get the latest results.

5. Connect a Messaging Platform and Go Live

Choose a platform to connect based on where your customers are. You can connect Web Chat, LINE, Facebook Messenger, Telegram, Microsoft Teams, WhatsApp, Email, and Slack at the same time.

6. Monitor and Optimize

After going live, use AgentOps for automated evaluation and Agent monitoring, and follow the recommendations in AI Customer Service Quality Management to keep expanding the knowledge base and refining the role instruction.

Application Examples

Regulation Search Assistant: Using government regulatory announcements as an example, explains how to use a single knowledge base to design two different reply styles for internal staff and the general public.

Product Search Assistant: Using a computer brand's product catalog as an example, walks through the complete process from creating an Agent and uploading the catalog to embedding it in your website.

The following sections demonstrate the setup process with real cases to help you quickly apply it to your own business scenarios.

Regulatory Search Assistant

Take the **regulation search assistant** as an example. In the past, because of technical limitations, government agencies and enterprises could only look up information with keyword search, which has the following drawbacks:

Poor semantic understanding, so results are imprecise

Cannot ask multiple questions at once

Affected by spelling errors

Cannot combine answers to multiple questions

These drawbacks lead to a **poor user experience**. With the arrival of large language models and RAG, however, all of this has changed. The following table compares traditional keyword search with RAG search.

	Traditional Keyword Search	RAG Search
Query understanding	Limited to exact matching and basic synonyms	Understands context, intent, and nuance
Information retrieval	Based on keyword frequency and basic relevance algorithms	Uses semantic similarity and context-aware retrieval
Result format	List of potentially relevant documents	List of potentially relevant documents Synthesized answer with citations to source documents
Handling complex queries	Usually requires multiple searches and manual consolidation	Can directly handle complex, multi-faceted questions
Ability to adapt to domain-specific terminology	Limited unless heavily customized	Can learn and adapt to an organization's specific terminology
Ability to use unstructured data	Very limited	High; can extract insights from various document types
Continuous learning	Usually static unless updated manually	Can improve over time through usage and feedback

Take a "government regulation search assistant" as an example. The regulatory announcements of the Ministry of the Interior's National Land Management Agency shown below were traditionally searched by keyword. We now want to use generative AI to make them more convenient to use, and this is how you can do it on MaiAgent.

https://www.nlma.gov.tw/最新消息
法規公告.html



Create a "Regulation Search Assistant" on the MaiAgent Platform

The structure of the "Regulation Search Assistant" is as follows:

graph TD Regulation-Search-Assistant --> Role-Instruction Regulation-Search-Assistant --> Knowledge-Base Regulation-Search-Assistant --> FAQ Regulation-Search-Assistant --> Internal-Staff-Interface Regulation-Search-Assistant --> Public-Interface

Mermaid 圖表

Because generative AI can be risky for government agencies, the design calls for different reply styles for internal staff and for the general public.

graph LR Regulation-Search-Assistant --> Internal-Staff Regulation-Search-Assistant --> General-Public Internal-Needs["1. Understand the intent of internal staff 2. Find relevant regulatory announcements 3. Combine them and generate a reply 4. Attach citation sources"] Public-Needs["1. Understand the intent of the public 2. Find relevant regulatory announcements 3. Let the public click the announcement URL to read it"] Internal-Staff --> Internal-Needs General-Public --> Public-Needs classDef left text-align:left; class Internal-Needs,Public-Needs, left

Mermaid 圖表

Access Points and Architecture

graph LR Internal-Staff --> Log-in-to-MaiAgent-console General-Public --> Use-via-public-URL Internal-Regulation-Search-Assistant["Regulation Search Assistant (Internal)"] Log-in-to-MaiAgent-console --> Internal-Regulation-Search-Assistant Use-via-public-URL --> Regulation-Search-Assistant Regulation-Search-Assistant --> Regulation-Knowledge-Base Internal-Regulation-Search-Assistant --> Regulation-Knowledge-Base Regulation-Data["regulation-data.xlsx"] Regulation-Data --> Regulation-Knowledge-Base

Mermaid 圖表

For the question `Is there an age limit for funding subsidies?`, the replies that internal staff and the general public should receive are expected to look like this:

Reply received by internal staff:



Reply received by the general public:



You only need to give different `role instructions` when creating the "AI Assistant" in MaiAgent to get this effect. The Agent role instructions for the `general public` and for `internal staff` are provided below.

Role instruction (general public version)

```
# Role
You are a regulation search assistant for the National Land Management Agency,
Ministry of the Interior

# Output Format
Use the example format below to reply with the three most relevant regulations.


The question you raised is related to the following regulations:

1.    title
2.    title
3.    title


# Output Restrictions
- Reply in Traditional Chinese
- Give priority to the most recent data as reference
- Do not answer with information outside the knowledge base
- Answer based on the knowledge base data; if you cannot answer, use the text in
the  below


Sorry, the knowledge base does not currently contain the regulation you asked
about. Please contact us during our service hours

Service hours: Monday to Friday, 8:00~17:30
Contact numbers of each business unit: see " target="_blank">link
```

Role instruction (internal staff version)

```
# Role
You are a regulation search assistant for the National Land Management Agency,
Ministry of the Interior

# Background
This year is 2024 in the Gregorian calendar, which is year 113 of the Republic of
China calendar

# Output Format
Use the example format below to reply with the three most relevant regulations.


{reply based on the question and reference data}

Related regulations:
1.    title
2.    title
3.    title


# Output Restrictions
- Reply in Traditional Chinese
- Give priority to the most recent data as reference
- Do not answer with information outside the knowledge base
- Answer based on the knowledge base data; if you cannot answer, use the text in
the  below


The knowledge base does not currently contain the regulation you asked about.
Please add the regulation data
```

Knowledge Base

Download past regulation documents from the Regulation Search of the National Land Management Agency, Ministry of the Interior

regulation-search.xlsx

Regulations on Rewards for Reporting Violations of Land Use under National Land Plans	**National Land Planning Division**	**Regulatory Order**	**2024-10-31**	**Regulation content…**	**https://www.nlma.gov.tw//政府資訊公開 主動公開資訊 中央法規 法規查詢/25-計畫組/39226-國土計畫土地違規使用檢舉獎勵辦法.html**
Regulations on Setting Up Parent-Child Restrooms in Public Places	Building Management Division	Regulatory Order	2024-10-30	Regulation content…	https://www.nlma.gov.tw//政府資訊公開 主動公開資訊 中央法規 法規查詢/30-建管組/28714-公共場所親子廁所盥洗室設置辦法.html
Notice of proposed amendments to the "Regulations on Leasing of Social Housing Undertaken by the Ministry of the Interior."	Housing Development Division	Draft Regulation	2024-10-22	Regulation content…	https://www.nlma.gov.tw//政府資訊公開 主動公開資訊 中央法規 法規查詢/29-住宅組/39204-預告修正「內政部興辦社會住宅出租辦法」。.html

Product Search Assistant

In enterprise product customer service, handling a large volume of frequent customer inquiries manually is prone to delays and places an excessive burden on support staff, reducing overall service efficiency. Many repetitive questions come up again and again and consume a great deal of time, making it hard for the team to focus on more complex customer needs and problem solving. In addition, without personalized recommendations based on customer behavior and needs, it is difficult to improve customer satisfaction and user experience, which further affects brand image and business growth.

Now you can use MaiAgent to build an external-facing AI product search assistant for your business. It not only reduces customer service costs effectively, but also provides personalized product recommendations that better match customer needs, improving service quality and customer satisfaction!

Use Case: Build an External Product Search Assistant for a Computer Brand

Suppose you are a product customer service specialist at a computer brand. Faced with a large number of varied specification inquiries from customers, you often spend a lot of time handling and answering them. In this case, you can use MaiAgent's external-facing AI product search customer service assistant to improve your efficiency.

With MaiAgent, you can build an external-facing AI product search customer service assistant that responds instantly. This not only greatly improves work efficiency but also effectively reduces the burden on customer service, letting you focus on higher-value customer service work.


Application Workflow

1. Create an External AI Product Search Assistant

Enter the Agent name.



Select RAG and a language model.



When choosing the reply mode, if you have no special requirements, select "RAG Q&A", which fits this use case. The role instruction reference is as follows:

```
# Role
You are the company's external-facing product search assistant

# Output Format
Use the example format below to reply with the three most relevant pieces of
knowledge.


For your question, we recommend the following products:

1. [Product name] Specifications
2. [Product name] Specifications
3. [Product name] Specifications


# Output Restrictions
- Reply in Traditional Chinese
- Prioritize more recent data as reference material
- Do not answer with information outside the knowledge base
- Answer based on the knowledge base; if you cannot answer, reply with the text
in the  below


Sorry, this question is currently outside the scope of my responses. Please
contact a human customer service representative.
```



2. Upload the Knowledge Base

Here we upload HP's public product catalog as a sample.

https://www.hptw-ebrochure.com/hipershop/rwd1185/store/F2/2024-0824_compressed.pdf



3. Put the Agent into Use

Now you can embed the Agent directly into your company website, letting customers ask questions instantly through a Q&A interface, with personalized product recommendations that better fit their needs, improving user experience and satisfaction!


產品查詢助理
推薦適合設計工作者的電腦產品
2025/04/24 16:10:13
產品查詢助理
已使用知識庫
您提到的問題，我們推薦以下產品：
1. [HP Spectre x360 14] 旗艦AI觸摸筆電，融合精品工藝與先進技術所打造，搭載Intel® Core™ Ultra 7處理器，支援旋蓋方向自動旋轉，搭配手寫筆使用傾斜+感應功能，適合講究專業品味的設計工作者。
2. [ENVY x360 16] 創作者專屬大螢幕翻轉筆電，色彩飽滿的螢幕及強大效能，最高搭載Intel® Core™ Ultra 7處理器，支援NVIDIA Studio認證，適合專業創作者使用。
3. [ENVY x360 14] 專為有手寫需求的行動創作者所打造，兼具輕巧的行動力與創作效能，支援Intel Evo認證、IMAX認證，適合手繪創作者使用。
這些產品都支援360度翻轉功能，可用於筆記和塗鴉、繪製故事板、產品草圖和平面設計圖，讓創意工作更加便利。
引用
2024-0824_compr...
引用節點
2025/04/24 16:10:23
請輸入您想問的問題
Powered by
MAIAGENT

Use Cases: Voice Customer Service

Modern voice customer service systems combine artificial intelligence to provide diverse and flexible solutions that improve service efficiency and customer experience. The overall flow starts with **voice input**. **ASR speech recognition** converts the customer's speech into text, and then, depending on needs, a variety of Agent capabilities can be applied for further processing.

Agents cover the following applications:

Intent recognition: Parses the content of the customer's speech to quickly understand their needs or issues, making subsequent handling easier.


Summary and ticket dispatch: For complex customer requests, generates a summary and automatically assigns it to the appropriate service department or system.

Intelligent quality inspection: Monitors and analyzes calls in real time to ensure service quality meets standards.

Intelligent reply: Generates an appropriate response based on the intent recognition result, converts it into speech using **TTS text-to-speech** technology, and replies to the customer.


These applications can be used flexibly according to actual needs. A full-flow deployment is not required; instead, design them for different scenarios and requirements. For example, some scenarios may only need intent recognition, while intelligent reply suits scenarios where real-time voice responses are desired.

Combining these application modules builds a voice customer service ecosystem that is both feature-rich and highly adaptable, enabling more efficient and personalized customer interactions. Next, we will describe in detail how to build an Agent for each application and MaiAgent's solutions, showing their technical core and application value.



Mermaid 圖表

MaiAgent currently has built-in integration with a variety of ASR speech recognition and TTS speech synthesis options, so users can choose the technology that suits different scenarios.


MaiAgent
雲端
國語/英語/其他多國語言
Azure Speech
OpenAI（開發中）
Whisper（開發中）
國語/台語
長問科技
雅婷
地端
長問科技
Whisper

IVR Customer Intent Recognition

IVR (Interactive Voice Response) customer service intent recognition is an application of AI voice processing technology that lets users interact with a customer service system through voice commands and automatically recognizes the customer's intent to provide the appropriate service. In Taiwan, such systems are widely used in banking, telecommunications, healthcare, and other industries to improve service efficiency and customer experience.

Core Features and Workflow

Receive Voice Input

After the customer calls, the system plays an automated voice prompt (for example: "Please briefly describe what you need, and we will assist you."). Instead of pressing keys to choose options, the customer states their needs directly by voice.

Speech Recognition (ASR)

The system uses Automatic Speech Recognition technology to convert speech into text. For example, if the customer says "I want to check my bill," the system converts the utterance into text input.

Natural Language Understanding (NLU)

The system uses Natural Language Understanding technology to analyze the meaning and determine the user's actual need. For example:

Vocabulary analysis: Keywords such as "check" and "bill" indicate that the need is related to billing.

Intent recognition: Determines that the customer's purpose is to "check the bill."

Response and Routing

Based on the results of the semantic analysis, the system provides the corresponding service. The possible options are:

Direct response: If the need can be handled automatically, for example, "Your bill amount is NT$1,200, and the payment due date is December 15."

Transfer to a live agent: If the need is more complex, the system automatically transfers the call to a customer service representative in the relevant department and provides a summary of the request, reducing repeated explanations.

Technical Challenges and Limitations

Difficulty understanding diverse expressions

Users may not phrase things in a standard way. For example, "What's going on with my bill?" or "What do I do about the payment issue?" are somewhat vague, and models such as BERT sometimes **cannot precisely determine the specific need**.

In Taiwan, systems must also cope with a mix of languages and dialects (Mandarin, Taiwanese, Hakka), and language models still have insufficient support for data in these languages.

Limits of fine-grained intent classification

Although modern NLP models can process large amounts of text, they cannot fully grasp the specialized knowledge or particular intents of certain industries. For example, "I want to know the exact date of my last payment" may require connecting to different systems to answer correctly.

Even though BERT performs well on short conversation fragments, long sentences or complex expressions can confuse the model.

Data bias and incomplete corpora

Training a language model **requires a large amount of localized corpus data**. If the data is insufficient or skewed toward a single form of expression, the model adapts poorly to special contexts. For example, for expressions specific to Taiwan such as "top-up" (儲值) or "skip number" (跳號碼), the model may lack enough contextual corpus data.

Context and memory limitations

Customer conversations usually have contextual links. For example, in a multi-turn conversation such as "Regarding the payment we just discussed, I have another question," the system must remember the earlier intent. Existing NLP models perform only modestly in this area.

If the intent is determined incorrectly, users may have to restate their needs, which causes frustration.

Low tolerance for errors

Customers have limited patience with customer service systems. If the voice system misjudges, customers may feel frustrated and ultimately ask to speak with a real person directly.

Industry Status Quo

Today, many companies' voice customer service systems still use traditional keypad-based flows. Take the **voice customer service system of SinoPac Bank** as an example: its design takes the diversity of services fully into account and guides users through multi-level menus. However, there is still plenty of room to optimize and improve the user interaction experience.

The emergence of LLMs (large language models) and RAG (Retrieval-Augmented Generation) has brought revolutionary change to semantic recognition and to IVR systems as a whole, making voice customer service systems smarter, more accurate, and more adaptable, and overcoming many limitations of traditional NLP techniques.

📺 **預覽連結：**https://bank.sinopac.com/MMA8/bank/service/cs-phonecall.html



Solution


Below, we will use MaiAgent's powerful and precise LLM and RAG capabilities to walk you step by step through building an excellent semantic recognition assistant.

Steps

1. Prepare the Data

> In the past, BERT required large amounts of labeled data to train for NLP tasks such as intent recognition and sentiment analysis. Labeled data is usually produced manually, for example by tagging sentences with intent categories or keywords, which is both time-consuming and expensive. Even with high-quality labeled data, the model's ability to generalize may be limited. When business needs or usage habits change, the data must be relabeled and the model retrained, which takes a long time. The advantage of LLMs and RAG is that they combine generative language ability with the dynamic nature of real-time retrieval. They remove the dependence on labeled data, improve the accuracy of semantic recognition, lower development and maintenance costs, and greatly improve the user experience. This combination of technologies sets a new industry standard for intelligent customer service and voice interaction, and is a key driver of future automated and personalized service.

The introduction of LLMs and RAG greatly simplifies the preparation of labeled data. Now you only need to organize your data into an Excel spreadsheet, list the intent categories simply, and upload this **bank customer service list** to the Agent's knowledge base to support the intelligent semantic recognition system.



銀行客服服務列表

	A	B	C	D
1	主分類	代碼	子分類	命中關鍵或關鍵字
2	餘額查詢	11	臺幣活期存款餘額查詢	
3	餘額查詢	12	臺幣支存餘額查詢	
4	餘額查詢	13	臺幣定存餘額查詢	
5	餘額查詢	14	外幣存款餘額查詢	
6	餘額查詢	15	基金帳戶餘額查詢	
7	餘額查詢	16	結構型商品餘額查詢	
8	轉帳交易	21	臺幣自行轉帳	
9	轉帳交易	22	臺幣跨行轉帳	
10	轉帳交易	23	臺幣定存單筆	
11	轉帳交易	24	臺外幣轉帳/換匯	
12	轉帳交易	25	基金交易	
13	轉帳交易	26	信用卡繳款	
14	轉帳交易	27	預約轉帳取消	
15	轉帳交易	29	外幣定存單筆	
16	掛失及電話密碼變更	31	金融卡掛失	
17	掛失及電話密碼變更	32	存摺掛失	
18	掛失及電話密碼變更	34	其他掛失	
19	掛失及電話密碼變更	35	電話密碼變更/申請臨櫃提取密碼	
20	利率、匯率、基金資料查詢	41	利率查詢	
21	利率、匯率、基金資料查詢	42	匯率查詢	
22	利率、匯率、基金資料查詢	43	基金淨值查詢	
23	查詢、傳真服務	51	查詢支存帳戶待補金額	
24	查詢、傳真服務	52	查詢帳戶往來明細	
25	查詢、傳真服務	53	查詢預約轉帳明細	
26	查詢、傳真服務	54	傳真服務	
27	信用卡服務	812	開卡	
28	信用卡服務	815	變更預借現金密碼	
29	信用卡服務	818	指定卡別免手續費分期	
30	信用卡服務	881	申請額度	
31	信用卡服務	887	紅利兌換	
32	信用卡服務	888	語音預借現金	
33	信用卡服務	899	現金儲值卡查詢	

Bank service list (for intent recognition)

2. Define the Role Instructions

```
# Role
You are MaiAgent Bank's semantic understanding bot

# Output Format
Based on the user's conversation, understand the service intent the customer
wants, determine from the knowledge base which service intent the user wants, and
output it

When the intent is clear, output only one intent; if there are multiple similar
intents that cannot be distinguished, list up to 3 of the closest intents

<example>
-<code>:<category> - <subcategory>
</example>

<example>
-<code>:<category> - <subcategory>
-<code>:<category> - <subcategory>
...
</example>

<example>
N/A
</example>

# Output Restrictions
- Reply in Traditional Chinese
- Do not answer with information outside the scope of the knowledge base
- Output the text inside <example> and </example> directly, without any other
description
- The output does not include <example> and </example>
- Answer based on the knowledge base; when the intent cannot be determined,
answer with the text in the <example> below
```

3. Get Started

Usage Examples

Single-Turn Conversation



Intent recognition example

Multi-Turn Conversation

LLMs and RAG solve the bottleneck that BERT has in recognizing intent across multi-turn conversations.



Intent recognition multi-turn conversation example

Voice Call Summaries

This chapter explains how to build a voice call summary Agent. Combined with Automatic Speech Recognition (ASR) technology, it transcribes voice calls into text and quickly generates a summary. This section uses a citizen complaint hotline as the scenario. The Agent needs the following core capabilities:

Automatic summary generation: Extract key information from the ASR transcript, such as the caller's name, contact details, issue description, and location, and output it in a structured format to keep the information clear and easy to read.

Intelligent department assignment: Automatically determine which department should handle the case based on the issue. For example, streetlight failures are assigned to the Public Works Bureau and environmental issues to the Environmental Protection Bureau, improving handling efficiency.

Precise location identification: Analyze location descriptions in the call to automatically match the administrative district and neighborhood (li), ensuring the dispatch information is accurate.

End-to-end automation: Integrate summary generation and department assignment so the entire process, from voice input to task assignment, is completed without human intervention, providing an efficient solution for citizen services.

This greatly reduces manual processing time and ensures the issues citizens report are quickly routed to the correct department, improving the service experience and administrative efficiency.

System Prompt

```
# Role
You are a summarization tool for citizen complaint hotline transcripts. The input
is a transcript

# Output Restrictions
1. Responsible agency options:
Drug Prevention Bureau/Youth Bureau/Sports Development Bureau/Administrative and
International Affairs Office/Civil Affairs Bureau/Finance Bureau/Education
Bureau/Economic Development Bureau/Marine Bureau/Agriculture Bureau/Tourism
Bureau/Urban Development Bureau/Public Works Bureau/Water Resources Bureau/Social
Affairs Bureau/Labor Bureau/Police Bureau/Fire Bureau/Health Bureau/Environmental
Protection Bureau/Rapid Transit Bureau/Cultural Affairs Bureau/Transportation
Bureau/Legal Affairs Bureau/Land Administration Bureau/Information
Bureau/Research Development and Evaluation Commission/Indigenous Peoples
Commission/Hakka Affairs Commission/Budget and Accounting Office/Personnel
Office/Civil Service Ethics Office/Open University/District Office
2. Put "None" for any field that cannot be summarized

# Output Format
Output the text directly, without <template> and </template>

<template>
Complainant name:  XXX
Complainant phone: XXX
Description: XXX
Responsible agency: XXX
District: XXX
Neighborhood (li): XXX
Location (address): XXX
</template>
```

Voice Conversation Transcript

Representative:
Hello, this is the Citizen Service Hotline. How may I help you?

Citizen:
Oh… um, hello, I'd like to report a problem in our neighborhood. Oh right, my surname is Zhang! Oh, my phone number is… hold on, 0912, huh? Oh right, 0912-345-678, sorry, I forgot for a moment.

Representative:
Alright, Mr. Zhang, your phone number is 0912-345-678. How can we help you?

Citizen:
Well, so, near my home there's a… a small park, and the, um, lights inside have been broken for a long time and nobody's fixed them. It's pitch dark at night, really scary. Kids often play there, but now nobody dares to go there at night.

Representative:
I see. Could you tell me the exact location of this small park?

Citizen:
Oh… what's the place called… um, oh! It's in Neihu District, uh… I think it's called Yangguang Li? Yes, yes, the small park in Yangguang Li, near Wende Road, you know it?

Representative:
So it's the park in Yangguang Li, Neihu District, near Wende Road, correct?

Citizen:
Yes, yes, that's it! There, and several lights are broken. I'm not sure which ones, maybe the ones near the benches in the middle, anyway it's super dark there at night now. Can you help take care of it?

Representative:
Sure, I'll record your issue and pass it to the relevant department. Is there anything else I can help you with?

Citizen:
Oh, no, that's all. Thank you for your help.

Representative:
Alright, thank you for calling the Citizen Service Hotline. Have a nice day!

Summary Result

Complainant name: Mr. Zhang
Complainant phone: 0912-345-678
Description: Streetlights in the small park in Yangguang Li, Neihu District are out. The park is near Wende Road, and the darkness at night affects residents' safety.
Responsible agency: Public Works Bureau
District: Neihu District
Neighborhood (li): Yangguang Li
Location (address): Small park in Yangguang Li, Neihu District, near Wende Road

Voice Call Quality Assurance

This chapter explains how to build an intelligent voice call quality inspection Agent. Combined with Automatic Speech Recognition (ASR) technology, it transcribes calls between customer service representatives and customers into text, and the Agent then automatically reviews service quality. This helps supervisors quickly understand how customer service is performing and avoid missing potential service flaws or compliance risks. The Agent needs the following core capabilities:

Service standard compliance check: Based on the company's established customer service SOP, determine item by item whether the representative completed the required scripts, such as self-introduction, customer identity verification, and closing courtesy.

Sentiment and attitude analysis: Analyze the representative's tone and word choice to identify situations such as impatience, arguing, or unprofessional behavior, and track changes in the customer's sentiment.

Compliance and prohibited phrase detection: Automatically check whether the call contains promissory language, sensitive words, or scripts that violate regulations, reducing legal compliance and complaint risks.

Structured inspection output: Output inspection results in structured fields, making it easy to import them into back-end systems or BI reports and helping supervisors track and analyze service quality.

Fully automated inspection by the Agent greatly reduces the burden of manual spot checks. Instead of sampling only a small number of calls as before, every call can now be inspected in real time, helping enterprises spot service gaps and make improvements right away.

System Prompt

```
# Role
You are a call quality inspection assistant for an enterprise customer service center. The input is the transcript of a call between a representative and a customer

# Inspection Items
1. Opening: Did the representative give a complete self-introduction (company name, name/employee ID)
2. Identity verification: Did the representative verify the caller's identity as required
3. Service attitude: Was the representative's tone friendly, with no impatience or arguing
4. Prohibited phrase detection: Did any promissory, aggressive, or non-compliant language appear
5. Closing courtesy: Did the representative confirm the customer's issue was resolved and say goodbye proactively

# Output Restrictions
1. Each inspection result may only be "Pass", "Fail", or "N/A"
2. If an item fails, add the original excerpt and the reason in the "Details" field
3. Put "None" for any field that cannot be determined

# Output Format
Output the text directly, without <template> and </template>

<template>
Opening: Pass/Fail/N/A
Identity verification: Pass/Fail/N/A
Service attitude: Pass/Fail/N/A
Prohibited phrase detection: Pass/Fail/N/A
Closing courtesy: Pass/Fail/N/A
Details: XXX
Overall recommendation: XXX
</template>
```

Voice Conversation Transcript

```
Representative:
Hello, this is the MaiAgent Customer Service Center. I'm Mei, employee ID A123.
How may I help you?

Customer:
Hello, the amount on my bill last month is wrong. Why was I charged an extra five
hundred dollars?

Representative:
I'm very sorry for the trouble. To protect your rights, may I first verify your
identity? Please provide your member number or registered mobile phone number.

Customer:
My phone number is 0912-345-678.

Representative:
Thank you, I've found your account. I can see that last month's bill does include
a five-hundred-dollar value-added service fee, generated by the "Family
Protection Plan" you activated on our website on November 5.

Customer:
I never activated that plan! Are you just charging people randomly?

Representative:
I understand your concern. I will immediately pull the activation record and
report back. A specialist will contact you within 24 hours with a resolution. May
we reach you at this mobile number?

Customer:
Yes, thank you for your help.

Representative:
Alright, I've created a case for you. Is there anything else I can help you with?

Customer:
No, thank you.

Representative:
Thank you for calling the MaiAgent Customer Service Center. Have a great day,
goodbye.
```

Inspection Result

```
Opening: Pass
Identity verification: Pass
Service attitude: Pass
Prohibited phrase detection: Pass
Closing courtesy: Pass
Details: The representative gave the full company name and employee ID, and asked the customer for a mobile phone number to verify identity as required. When the customer raised doubts, the representative stayed calm, did not argue or use promissory language, and proactively created a follow-up case.
Overall recommendation: This call meets service standards. When responding to customer concerns, it is recommended to explain the specific process for pulling records in more detail to strengthen customer trust.
```

MaiAgent Build | Agent Development

MaiAgent Build Overview

Turn your ideas into enterprise-grade Agents.

MaiAgent Build lets IT staff and technical partners build their organization's own Agents: define roles, knowledge, tools, and permissions, and connect databases and enterprise systems so Agents can retrieve data, call systems, and follow workflows to get things done. The Agents used in MaiAgent Work and MaiAgent Serve are also built and managed here.

Products

Agent Builder	Define role instructions, knowledge bases, databases, tools, skills, and Agent Teams in one place, and configure an Agent ready for deployment.	Agent Builder Overview
AI Gateway	Connect your organization's own model providers or self-hosted models, manage the model catalog and fallback model groups, and monitor traffic and anomalies.	AI Gateway
AgentOps and Governance	Test datasets, automated evaluations, Agent monitoring, and tool execution records; Hook checks personal data and content as messages enter and leave the AI.	AgentOps
MaiAgent MCP	Let external AI tools such as Claude and Cursor operate the platform directly through MCP, for example to create Agents and manage knowledge bases (Technical Guide).	MaiAgent MCP

Agent Builder Modules

Module	Enables Agents to⋯
Agent	Understand requests and generate responses based on role instructions; configure Agent Schedules to run tasks at set times
Knowledge Bases	Answer questions using enterprise documents, FAQs, and web content
Databases	Query structured data using natural language (Text to SQL)
Tools	Call external systems and perform actions through MCP or APIs
Skills	Follow a set of multistep procedures (SOPs) to complete tasks

Module	Enables Agents to···
Code Interpreter, Browser Tool	Run code to process files, or operate a browser to complete web workflows
Agent Teams	Collaborate across multiple Agents with different specialties
Hook Message Interception	Automatically mask personal data or intercept content before it enters the AI or before a response is sent
Voice Agent	Talk with users by voice, with support for web voice and phone calls

Not sure which module to use? See I want to do X. What should I use?.

Build Workflow

Create an Agent

Create an Agent and write its role instructions; you can also apply an official template from the Agent Template Library and customize it.

Connect Knowledge and Capabilities

Attach a knowledge base, then add databases, tools, and skills when the Agent needs to retrieve data or perform actions.

Test Before Launch

Use test datasets and automated evaluations to verify response quality, then publish to a conversation platform to launch for external users, and adjust each platform's behavior in Conversation and Human Handoff Settings; or make the Agent available to employees in MaiAgent Work. For the complete launch steps for customer-facing support, see the plan guide in MaiAgent Serve.

Monitor Continuously After Launch

In AgentOps, review response quality and tool execution records, and add conversations with poor answers to the FAQ to keep improving.

Permissions and Governance

Assign access permissions for Agents, knowledge bases, and conversation platforms by role. Organization owners can also restrict which models members and Agents can call. See Role-Based

Resource Access, Model Access Permissions, and Third-Party Login (SSO). Use the Activity Log to look up and export who changed which settings and when.

Further Integration

To integrate MaiAgent programmatically, see the API Keys, API call logs, and OAuth applications in the back office under Developer Tools. For integration methods, see the Technical Guide and API documentation:

API Quickstart

AI Gateway: OpenAI-Compatible API Integration

Self-Hosted MCP Server Integration Specifications

API Documentation

Use Cases

External Data Integration: Connect external API data to Agents

Agent Optimization Consultant: Automatically diagnose response quality and suggest adjustments to role instructions and knowledge bases

Agent Builder

Agent Builder is the core workspace for building on the MaiAgent platform. Here, you can combine different modules to create an AI Agent that answers questions, queries data, and performs tasks.

The Big Picture: How Agent Connects to Each Module



Overview of Agent Builder modules

Agent is the central brain, responsible for understanding users' questions and generating responses. Other modules extend its capabilities—knowledge bases provide specialized knowledge to reference, databases let it query data, tools let it perform actions, skills let it handle complex tasks according to SOPs, and agent schedules let it run automatically at set times. Crawlers are one of the data sources for knowledge bases. As tasks become more complex, Agent Teams brings specialist Agents together to share the work; Hook automatically checks safety and quality as messages enter and leave the AI.

Twelve Modules at a Glance

Module	What It Does	Typical Uses
Agent (AI Assistant)	Serves as the core of conversations, understanding intent and generating responses	Customer service bots, internal Q&A, sales assistants
Knowledge Base	Provides company-specific knowledge that Agent can reference	Product manuals, internal policies, FAQ
Database	Uses Text2SQL to let Agent query structured data in natural language	Order queries, inventory queries, report analysis
Agent Schedule	Lets Agent perform tasks automatically on a schedule	Daily summary reports, periodic data checks
Tools	Let Agent call external services to perform actions	Sending email, checking the weather, integrating CRM
Code Interpreter	Runs Python in a sandbox to process files and perform computations	Generating Word documents/presentations, data analysis, chart creation

Module	What It Does	Typical Uses
Browser Tool	Controls a browser to browse pages, interact with elements, and capture screenshots for interpretation	Operating websites without APIs, retrieving data after login, automating web workflows
Voice Agent	Lets Agent serve customers by listening and speaking (Realtime STT + LLM + TTS)	Phone support, IVR, voice queries, hands-busy scenarios
Skills	Define Agent's multistep reasoning and decision-making workflows	Quotation workflows, troubleshooting SOPs
Crawler	Automatically retrieves content from web pages and imports it into a knowledge base	Crawling company websites, crawling public information
Agent Teams (Teams)	Organizes specialist Agents into a collaborative team that automatically shares work through handoffs and delegation	Customer service routing, collaboration among Agents for orders/returns and exchanges/recommendations
Hook Message Interception	Automatically intervenes to perform checks before messages enter the AI and before responses are sent	Masking personal data, blocking malicious instructions, checking response quality

Not Sure What to Use?

Visit **I Want to Do X—What Should I Use?** for a comparison of common scenarios.

Recommended Setup Order

If this is your first time using MaiAgent, follow this order:

```
Step 1 → Create an Agent and set its system prompt (what role it should play and how it should respond)
Step 2 → Create a knowledge base and upload documents or FAQ (give it information to reference)
Step 3 → Extend as needed: add tools, databases, and skills (based on the capabilities your scenario requires)
Step 4 → Connect a conversation platform to go live (Web Chat, LINE, Messenger ... )
```

You do not need to configure all modules at once. Get Agent + Knowledge Base running first, then gradually extend its capabilities.

I Want to Do X. What Should I Use?



Scenario → Module reference: Quickly find the right starting point

Not sure which module to use? Start with your needs to find the right starting point.

Scenario reference table

Enable an Agent to answer questions

I want to...	Use	Why
Have an Agent answer product questions	**Knowledge base**	Upload product manuals so the Agent can find answers in them
Have an Agent answer frequently asked questions	**Knowledge base** (FAQ)	Create FAQ question-and-answer pairs to precisely match common questions
Have an Agent check order status	**Database**	Orders are stored in structured tables and require Text to SQL
Have an Agent look up real-time information (weather, exchange rates)	**Tools**	Call external APIs to get real-time data

Enable an Agent to take action

I want to...	Use	Why
Have an Agent send notification emails	**Tools**	Integrate an Email API so the Agent can trigger sending
Have an Agent create customer records in a CRM	**Tools**	Integrate a CRM API so the Agent can create records
Have an Agent handle customer complaints according to an SOP	**Skills**	Define the complete process to ensure no steps are missed
Have an Agent guide customers through making a reservation	**Skills**	Collect information through multi-turn conversations and follow the process

Enable Agent automation

I want to...	Use	Why
Automatically generate reports every morning	**Agent schedules**	Schedule execution and automatically send the results
Check system status every hour	**Agent schedules**	Set an execution interval and use tools to check status
Automatically import official website content into a knowledge base	**Crawler**	Fetch web page content and import it into the knowledge base

Common module combinations

Most scenarios use more than one module. Here are some common combinations:

Intelligent customer service

```
Agent + Knowledge base + FAQ
```

The most basic and common combination. The Agent uses the knowledge base to answer product questions, while FAQ handles frequently asked questions.

Sales assistant

```
Agent + Knowledge base + Database + Tools
```

Look up product information (knowledge base), check inventory and prices (database), and help customers place orders (tools).

Automated reporting

```
Agent + Tools + Agent schedules
```

The Agent retrieves data through tools, agent schedules trigger execution at set times, and results are automatically sent to Slack or LINE.

Workflow guidance bot

```
Agent + Skills + Tools + Knowledge base
```

Skills define the complete SOP. During the process, the Agent looks up reference information in the knowledge base and uses tools to take action.

Still not sure?

Start with the simplest combination: **Agent + Knowledge base**. First, enable the Agent to answer questions. After launch, use actual user feedback to decide which capabilities to add.

Agent

What is this?

An Agent is an AI conversational persona you create on MaiAgent. Each Agent is an independent chatbot with its own identity, personality, knowledge, and capabilities.

Think of an Agent as a new employee—you need to tell it:
- **Who you are** (system prompt)
- **What you know** (knowledge bases, databases)
- **What you can do** (tools, skills)

Once configured, the Agent can serve users across various messaging platforms.

Core Concepts

Language Model (LLM)

An Agent's ability to understand and respond comes from the large language model (LLM) behind it. Think of the LLM as the Agent's "brainpower" —different models vary in comprehension, response quality, speed, and cost.

When creating an Agent, you can choose a model that suits your use case. MaiAgent supports multiple models, including Claude and GPT. You do not need to manage the models yourself; the platform handles this for you.

Quick guide: For precise responses and complex reasoning → choose a more capable model; for frequent, simple questions and cost control → choose a faster, lighter model.

System Prompt

The system prompt defines how the Agent behaves. For example:

"You are a friendly customer service representative. Respond in Traditional Chinese with a professional yet approachable tone."

"You are a financial analysis assistant. Answer only finance-related questions, and clearly state when you are unsure about any figures."

A good system prompt can greatly improve the quality of the Agent's responses.

Response Mode

Choose how the Agent responds under "Response Mode Settings" on the Agent settings page. New Agents use Agent mode by default:

Agent mode (default): Suitable for tasks that require multiple steps of reasoning. The Agent decides which information to look up and which tools to use.

RAG Q&A: Suitable for general questions and answers, with responses based directly on the knowledge base.

Template, **Hybrid** (under "Other Modes"): Template mode responds by category using the knowledge base and FAQ, without free-form model generation. Hybrid mode uses templates for some content and free-form responses for the rest.

For differences between modes and how to configure them, see Create an Agent.

Memory

Agents have memory capabilities:

Conversation memory: Remembers earlier content within the same conversation. With "Vector Memory" enabled, older messages can also be retrieved through semantic search.

Cross-conversation search: Searches the same contact's other recent conversations when responding, so the contact does not need to introduce themselves each time.

Persistent memory: Extracts facts and preferences from conversations, stores them long term, and reuses them across conversations with the same contact.

Advanced details: These settings are under "Advanced Settings" on the Agent settings page. "Conversation Memory Settings" controls vector memory, cross-conversation search, the lookback period in days, and the Embedding/Reranker models used for conversation memory. "Persistent Memory" shows whether cross-conversation memory is enabled and lists stored memories. See Cross-conversation Search (including Other Options) and Persistent Memory.

What do I need to do?

Create an Agent — Give it a name and choose a language model.

Write a system prompt — Define the Agent's role and response style.

Add capabilities — Connect knowledge bases, tools, and skills as needed.

Test conversations — Test the results in the built-in chat window.

Connect a platform and go live — Deploy to messaging platforms such as Web Chat and LINE.

Further Reading

Agent Features

Create an Agent

System Prompt Design Guide


Add a System Prompt to an Agent

Agent Features

Purpose and Uses of Building an Agent

Agents can be used across a wide range of industries and scenarios to help businesses automate repetitive tasks and improve operational efficiency, allowing teams to focus on high-value work and developing their core strengths.

Here are examples of Agent applications in common enterprise workflows:



Agents support many industries, combining intelligent automation and real-time interaction to help businesses optimize processes and improve service quality and user experience. Common Agent application scenarios for each industry are listed below for reference.

Industry	Application Scenarios
E-commerce and retail	Intelligent customer service, shopping recommendations, return processing
Finance and insurance	Insurance policy inquiries, financial planning recommendations, risk-related Q&A
Education	Course teaching assistants, learning diagnostics, language practice

Industry	Application Scenarios
Healthcare	Health consultations, appointment booking, patient education support
Government agencies	Public service inquiries, policy Q&A, public feedback
Manufacturing	Internal knowledge management, maintenance instructions
Travel and tourism	Itinerary recommendations, guided tours, real-time Q&A support

Four Stages of Agent Setup in MaiAgent

Agent setup in MaiAgent has four main stages. Below is a brief explanation of each stage's goals and features. The following chapters provide detailed operating instructions.

1. Create a New Agent

Customize the Agent to your needs, choose a suitable language model, link the knowledge bases required for RAG (Retrieval-Augmented Generation) in Knowledge Base Settings, and define the Agent's role and tasks to build an intelligent assistant tailored to your business scenarios.

On the Agent's Settings page, the left navigation groups settings under Basic, Knowledge and Data, Capability Extensions, Interface and Experience, and Management and Advanced. These include Basic Settings, Response Mode Settings, Knowledge Base Settings, and Permission Settings.



Agent settings page and settings groups in the left navigation

2. Provide Reference Materials for the Agent

Build a comprehensive knowledge foundation for the Agent by configuring a Knowledge Base, creating FAQ entries within it, or using a Crawler to import web pages and other data sources. This further improves the accuracy and usefulness of its replies.

3. Launch the Agent

Choose whether to make the Agent publicly available or restrict it to internal use. The Agent's Conversation Platforms tab provides three built-in entry points: Web Widget (external use, with embed code for your company website), Internal Chat (internal use), and API. To serve customers through channels such as LINE or Messenger, click Connect Channel to integrate them with your existing platforms.



Built-in channels and Connect Channel in the Conversation Platforms tab

4. Track Agent Performance

Track performance using All Conversations, the Agent's Usage Analytics (including monitoring metrics such as answer quality scores), and Webhook features to guide ongoing Agent improvements and enhance the user experience.

Before you start building an Agent, take a look at these useful articles!

🗣️How Do You Choose an LLM (Large Language Model)?

🔎What Is RAG (Retrieval-Augmented Generation)?

👨‍👩‍👧What Are Role Instructions?

Create an Agent

This page walks you through creating an Agent from scratch. Before you begin, review the settings map below to learn what each tab controls and where to find details.

Settings map

The settings window that opens when you create an Agent and the "Settings" tab you open later from the Agent list use the same navigation on the left: 5 groups with 12 tabs in total.

Group	Tab	What it controls	Details
Basic	Basic Settings	Name, LLM Model, and Fallback Model Group; Thinking Effort is also available when supported by the model	Choose a model, Model access
Basic	Answer Mode Settings	Answer mode, Role Instructions, Enable Inline Citations, and reply templates for Template and Hybrid modes; Voice Assistant Settings also appear here when voice assistants are enabled for the organization	Answer modes, Voice assistants
Knowledge & Data	Knowledge Base Settings	Select the knowledge bases the Agent references when answering	Configure knowledge bases, Knowledge bases
Knowledge & Data	Tag Filtering	Restrict the Agent to files that match the tag conditions	Knowledge base tag filtering
Knowledge & Data	Database Settings	Link databases to query using Text to SQL (Agent mode only)	Create and configure databases
Capabilities	Tools	Select the tools the Agent can call (Agent mode only)	Configure tools for an Agent
Capabilities	MaiGPT Connectors	Bind connectors so they are available in all conversations with this Agent (Agent mode only)	Manage connectors (administrators)
Capabilities	Skill Settings	Attach skills for the Agent to use	Skills
Capabilities	Hook	Apply Hooks that run when a user message is received, after an AI response is generated, or after a conversation is completed (visible only with Hook access permissions)	Add and configure Hooks

Group	Tab	What it controls	Details
Interface & Experience	Agent UI	Select interactive components the Agent can include in replies (Agent mode only)	Agent UI
Management & Advanced	Permission Settings	Specify which roles can use this Agent	Preassign Agent permissions
Management & Advanced	Advanced Settings	Maximum retrieval chunks, output length controls, Agent workflow settings, conversation memory settings (including Embedding and Reranker models), persistent memory, automatic evaluation, and more; the defaults are usually sufficient	Reply length and Agent execution limits, Cross-conversation retrieval, Persistent memory

> Tabs marked "Agent mode only" remain accessible in other answer modes, but only show a notice and a Go to Answer Mode Settings button. Switch to Agent mode to configure them.

The creation window has an additional Channel Activation item in the Basic group. It determines whether the Web Widget and API Integration are enabled as soon as the new Agent is created. This item only appears during creation and is unavailable when editing an existing Agent. See Configure channel activation.

Tabs at the top of the Agent page

After creating an Agent, open it from the Agent list to see these tabs at the top of the page:

Tab	What it controls	Details
Settings	The 12 tabs in the settings map above	This page
Usage Analytics	Usage Statistics for this Agent; Monitoring Metrics are also available with AI Assistant Monitoring Permissions	Agent usage analytics
Channels	Channels connected to this Agent (website, LINE, etc.)	Connect channels
API Integration	Instructions for calling this Agent programmatically	Developer tools
Webhook	Push this Agent's replies to your own system	Webhook

1. Create an Agent

Go to “AI Assistants” under “AI Features” in the left sidebar, then click “Create AI Assistant” in the upper right.



The “Create AI Assistant” button in the upper right of the Agent list

List filters and columns

Above the list, search by Agent name or ID and narrow the results using the “All Large Language Models”, “All Answer Modes”, and “All Creators” dropdowns. After selecting a creator, the list only shows Agents created by that member that you have permission to view. Multiple filters apply together.

For example, a manager looking for an Agent created by a colleague can select that member under “All Creators”, then narrow the results by name or model. Afterward, click “Reset Filters” to clear the conditions. If no Agents match, the list displays “No matching AI assistants found”, where you can also reset the filters.



Combine “All Creators” with other filters, and click “Reset Filters” to clear them

Each row displays:

Column	Description
ID	The Agent's identifier, used for API integration and issue reporting


Column	Description
Name	The name entered in Basic Settings
Large Language Model	The LLM model selected in Basic Settings
Answer Mode	RAG Q&A, Agent mode, Template, or Hybrid
Knowledge Bases	Linked knowledge bases
Skills	Attached skills
Last Updated	The most recent time the settings were saved
Actions	Edit, Duplicate, and Delete; see Duplicate and delete Agents

The list does not support multiple selection or batch actions. To adjust multiple Agents, open their settings individually.

2. Name your Agent

Click “Basic Settings” in the left navigation of the creation window and enter the Agent's name in the “Name” field. Name it after its main task, for example, XX AI Customer Support, XX Regulatory Lookup Assistant, or XX Project Assistant.

One account can create multiple Agents (quantity limits depend on your purchased plan). Agent names must be unique within an organization. See Names must be unique within the organization.




Enter the Agent name in Basic Settings

Names must be unique within the organization

Each Agent in an organization must have a different name so you can distinguish Agents in dropdowns that only display names, such as delegation scheduling. When creating an Agent, duplicating an Agent, or changing its name in “Basic Settings”, submitting a name that matches another Agent in the Agent list is blocked. A red message appears below the Name field: “An AI assistant with this name already exists in this organization. Please use a different name.”

The window stays open and retains your other settings. Once you enter a unique name, the red message disappears automatically and you can submit again. If you are on another tab when submitting (such as “Permission Settings”), the screen automatically returns to “Basic Settings” so you can see the message.



If the name matches an existing Agent in the organization, a red message appears below the Name field

The system compares names as follows:

Situation	Result
Extra spaces before or after the name	Leading and trailing spaces are removed before comparison; a name matching an existing name is blocked
Only English letter case differs (for example, `Support Bot` and `support bot`)	These count as different names and can be saved; changing only the case of your own Agent's name can also be saved
Same name as a deleted Agent	Creation is allowed; deleted Agents are excluded from comparison
The name is unchanged when saving	No name check is performed; other settings can be saved as usual

> Agents that already shared a name before this rule was introduced are not renamed automatically, and their settings other than the name can still be changed as usual. Only when you change one of their names must the new name differ from other Agents. We recommend gradually giving them names that are easy to distinguish.

Configure channel activation

Every new Agent automatically includes three built-in channels: Internal Chat, Web Widget, and API Integration. Click Channel Activation in the Basic group on the left of the creation window to decide whether to enable the latter two before creating the Agent, rather than enabling each platform afterward.

Channel	Description	Can it be changed?
Internal Chat	Chat directly with the assistant in the admin console	Marked Always Enabled; no toggle
Web Widget	Embed it in a website or open it via a URL so visitors can chat with the assistant	Toggle
API Integration	Call the assistant from external systems using an API key	Toggle



When the organization defaults to internal chat only, both toggles start off

Initial toggle values: Follow the organization's "Enable channels and API integration by default for new assistants" setting. The current organization default is explained above the section. When the setting is off, the message reads "Current organization default: new assistants only have Internal Chat enabled. Web Widget and API Integration are disabled by default." Both toggles start off. When it is on, the message reads "Current organization default: all channels are enabled as soon as a new assistant is created." Both toggles start on.

The two toggles are independent: You can enable only Web Widget and leave API Integration off, or vice versa. The left navigation label updates immediately: Internal Chat Only when both are off, or 1 External Channel or 2 External Channels when enabled.

Who can configure this: Any member who can open the creation window can configure it; no additional permission is required.

Changing settings after creation: After clicking Confirm to create the Agent, go to its Channels tab, open each channel's Platform Settings, and toggle Enabled. For permissions, see Default activation state and toggle permissions.

For example, an e-commerce support manager creates a “Website Support Assistant” and wants the website chat window to go live immediately, while keeping the API unavailable to external systems for now. In Channel Activation in the creation window, she enables Web Widget and leaves API Integration off. The left label changes to 1 External Channel. She then clicks Confirm to create it. On the new Agent's Channels tab, Web Widget shows In Service, API shows Disabled, and Internal Chat remains available as usual.



After creating an Agent with only Web Widget enabled, the Channels tab shows Web Widget as In Service and API as Disabled

> This section only appears in the Create AI Assistant window. For new Agents created through other methods such as duplicating an Agent, Web Widget and API Integration always follow the organization defaults and do not inherit the source Agent's activation states. Internal Chat is always enabled.

3. Choose RAG to make your Agent smarter and its answers more accurate

What is RAG?

Think of RAG as a combination of “an assistant who excels at conversation + a librarian who is great at finding information.”

A regular Agent is like someone with an excellent memory and a talent for storytelling, but it can only share knowledge it has previously learned. When an Agent uses RAG, it is as though it **visits the library to find the latest information** before answering, then organizes what it finds in its own words and explains it clearly to you.


On the MaiAgent platform, this “library” is our **knowledge base**. The Agent uses RAG to find relevant information in the knowledge base, making answers more accurate, up to date, and relevant to your needs.

The next section explains how to configure knowledge bases in detail.

> MaiAgent's knowledge base retrieval combines semantic search, keyword search, and reranking (Reranker). You can also use tag filtering to narrow the search so the Agent finds the most relevant passages before answering.

Configure knowledge bases

Agents use RAG (Retrieval-Augmented Generation) through knowledge bases. Click "Knowledge Base Settings" in the left navigation of the creation window, then "Select Knowledge Bases" to specify which knowledge bases the Agent should reference.



Select the knowledge bases the Agent should reference in Knowledge Base Settings

> Compared with OpenAI RAG, MaiAgent RAG provides additional features to support different deployment needs and more diverse data processing formats, offering a more powerful retrieval and generation experience. For a detailed comparison, see What is RAG? MaiAgent RAG vs. OpenAI RAG comparison table

Configure FAQ priority

To ensure accurate and consistent Agent answers, you can enable FAQ priority. When the knowledge base contains both FAQ content and other documents, the LLM prioritizes FAQ content to answer questions, keeping responses aligned with the standard answers you have created.

Benefits:

Improve answer accuracy: When the knowledge base contains both FAQs and other documents, prioritize verified FAQ content to reduce potentially inaccurate answers generated by the AI

Ensure consistent answers: All users receive FAQ answers to the same standard, maintaining service quality

Reduce hallucination risk: Prioritize standard FAQ answers to avoid fabricated or incorrect information from the AI

Setup:

Click "Answer Mode Settings" in the left navigation of the settings page

Enter the following instruction in the "Role Instructions" field:

```
Please prioritize FAQ content when answering user questions
```



Use Role Instructions to request that FAQ content be prioritized.

With this enabled, the Agent prioritizes FAQ content when both FAQs and other documents are present in the knowledge base. If no relevant FAQ content is found, it still answers using other knowledge base documents or general knowledge.

4. Choose a model to give your Agent a smart brain!

Why choose a language model?

An Agent's performance depends largely on its brain—the language model (LLM) it uses. In this step, you can choose from different models to suit your needs. Your choice affects response speed, comprehension, and the depth and naturalness of answers.

Choosing the right model helps your Agent work efficiently and provides the best experience for your use case!

Key factors when choosing a large language model

Configure the language model

Click "Basic Settings" in the left navigation and select a large language model from the "LLM Model" dropdown. Available models depend on the organization's model access permissions. The platform sets the model marked as the default in the menu. Compare each model's Credits price, speed, specifications, and retirement date on the Model Access page.

The dropdown has two groups: "Models" at the top lists individual models, and "Fallback Model Groups" below lists AI Gateway fallback groups. When you select a fallback group, its models take over responses in sequence, and the "Thinking Effort" setting is hidden.


Understand the capability labels in the menu

The model catalog changes as models are added and removed, so this guide does not maintain a separate reference table. Check the labels on each model's row in the menu to see what it supports:

What you see	Meaning
Parentheses after the model name	The inference provider (for example, AWS Bedrock or Azure OpenAI)
Default label	The default model configured by the platform
Multimodal label	Understands images; choose this type if conversations will include uploaded images

What you see	Meaning
Thinking label	Supports thinking effort; after selection, the "Thinking Effort" setting appears below
Custom label	A model the organization connected through AI Gateway
Fallback Group label	This row is a fallback model group rather than an individual model
Image icon on the second line	Blue indicates multimodal support; gray indicates no support. Hover to see "Multimodal: Supported/Not supported"
Number on the second line	The model's context length (the number of tokens it can process at once)

The menu currently does not indicate whether a model supports tool calling (required for Agent mode and skills). If conversation records show an error such as "Model does not support tool calling" after switching to Agent mode, choose another model.



LLM Model and Thinking Effort settings; the available levels depend on the selected model.

Set thinking effort

When you select a model that supports thinking (marked with a "Thinking" label in the menu), "Thinking Effort" appears below "LLM Model". It determines how deeply the Agent reasons before answering. This sets the Agent's default level, used when the user has not selected a different level in the conversation.

The options include "Default" and **the levels supported by the current model**. From lowest to highest, the levels are Off, Minimal, Low, Medium, High, Extra High, and Maximum. Higher levels mean

deeper reasoning, slower replies, and greater Credits consumption. Click an option to see its description below.

"Default" and "Off" include annotations based on the model's actual behavior so you can understand how your selection affects response speed:

Option	Description
Default	No level is specified. Depending on the model's behavior, this appears as Default (no thinking · fastest) or Default (model decides how to think)
Off	Disables thinking. This option appears only when the model allows thinking to be disabled. For models that do not think by default, it appears as Off (same as default); for models that think by default, it appears as Off (fastest)
Minimal–Maximum	Enables thinking. Every level has the description "Enables thinking: adds approximately 1–3 seconds per model call, depending on the model"

"Low" is not always faster than "Default." For models that do not think by default (shown as Default (no thinking · fastest)), any thinking level enables thinking and is slower than the default. The settings page then displays "The current setting enables thinking and is slower than the default." If you simply want faster replies, keep Default.

For example, a store lookup Agent uses Claude 4.5 Haiku. The administrator assumes that setting thinking effort to Low will speed up replies, but after selecting it sees "The current setting enables thinking and is slower than the default." Because this model's Default is labeled "no thinking · fastest," the administrator switches back to Default and saves to keep replies as fast as possible.

Each model supports different levels. The interface lists only the options available for the current model, for example:

Claude 4.5 Haiku: Supports Off and Minimal, up to High

Claude 5.5 Opus: Thinking cannot be disabled, so there is no Off option. The lowest level is Low, and Extra high and Maximum are available



Claude 4.5 Haiku: Off and Minimal are available, up to High; selecting a thinking level displays a notice that it is slower than the default



Claude 5.5 Opus: No Off option; Extra high and Maximum are available. By default, the model decides how to think

> Thinking levels when switching models When switching to another model that supports thinking, the selected level is retained. If the new model does not support that level, the interface shows the level actually applied, and replies use that level: the closest level supported by the new model that does not exceed the original level. If the new model's lowest level is higher than the original level, its lowest level is used. For example, switching from Maximum on Claude 5.5 Opus to Claude 4.5 Haiku displays High; switching from Minimal on Claude 4.5 Haiku to Claude 5.5 Opus displays Low. When switching to a model that does not support thinking, "Thinking effort" is hidden, and the selected thinking level returns to Default.

To let users adjust this during conversations, enable Allow users to adjust thinking effort in the chat platform's Feature settings. For Web Chat, also enable Show thinking process so that the thinking effort button appears below the input box. See Thinking effort button in Web Chat. MaiGPT does not require these two switches: selecting a model that supports thinking lets users adjust it in the input box. See MaiGPT chat: Thinking effort.

For example, an ecommerce customer service manager's order lookup Agent uses Claude 4.5 Haiku. Most visitors ask simple questions such as "Has my package shipped?" She selects Minimal under "Thinking effort" in "Basic settings" and saves, then enables both Show thinking process and Allow users to adjust thinking effort in the Web Chat platform's feature settings. When visitors start a new conversation, the thinking effort button below the input box shows Minimal. For more complex questions, such as refund calculations, visitors can switch to High before asking.

5. Create a System Prompt for Your Use Case

To tailor your Agent to different applications, set a "System prompt" so that the AI's response style and content better suit the context.

> What is a system prompt? Where can I find example templates? AI tool for generating a role assistant

Response Mechanism for Reducing Hallucinations

MaiAgent's response mechanism helps AI maintain high accuracy when answering questions. When a question involves uncertainty or falls outside its knowledge, it openly acknowledges its limitations instead of fabricating answers, providing users with a more reliable, trustworthy AI interaction experience. Its importance across industries and the public sector is outlined below:

Industry applications

Finance:

When providing investment advice or risk assessments, AI must base its analysis on verified data to avoid false information that could lead to poor investment decisions. When information is insufficient or uncertain, the system explicitly says so to support reliable investment decisions.

Healthcare:

When assisting with medical diagnoses or medication inquiries, AI systems must strictly follow established medical knowledge and avoid inventing advice that could mislead patients. For new or unverified medical information, the system clearly indicates that further professional consultation is needed.

Manufacturing:

In applications such as production process optimization and quality control, AI must base its recommendations on actual production data and validated methods to avoid production losses caused by inaccurate predictions.

Education:

When assisting with teaching or answering students' questions, AI needs to provide accurate knowledge rather than misinformation that could mislead learning. For complex or ambiguous concepts, the system acknowledges the limits of its understanding.

Legal services:

When providing legal information and advice, AI must rely on existing laws and case precedents rather than speculative advice that could pose legal risks. The system clearly identifies matters that require further confirmation by a qualified lawyer.

Customer service:

When handling customer inquiries, AI must provide accurate product information and service descriptions. For questions it cannot answer with certainty, it immediately refers customers to the appropriate professionals to avoid misleading them.

Public sector applications

Government policy inquiries:

When providing policy information and service guidance to the public, AI must answer based on current, accurate regulations and administrative procedures to avoid outdated or incorrect information. For complex questions or those requiring professional judgment, the system explicitly recommends seeking assistance from the relevant department.

Public service decisions:

When helping governments evaluate decisions on public infrastructure, social welfare, and similar matters, AI must base its analysis on real data and research. It must clearly explain uncertainty in predictions to support reliable policymaking.

Emergency response management:

When dealing with natural disasters, public health emergencies, and similar events, AI systems must provide accurate information and guidance, avoiding false information that could mislead the public and undermine disaster preparedness and response.

Choose a Response Mode and Write Your Prompt

Click “Response mode settings” in the left navigation of the Agent settings page. Options range from open conversation to highly structured responses to meet different business needs. Each mode has its own strengths and applications, so choose one that suits your use case.

The available response modes are RAG Q&A, Agent mode, and Template and Hybrid under Other modes. Newly created Agents default to Agent mode.



Expand Other modes to see all four response modes

> The “Workflow” response mode is no longer available. Agents that previously used Workflow mode have been automatically converted to RAG Q&A mode.

Response mode: RAG Q&A

When to use it

The AI freely answers questions, generating the most appropriate response based on the context and knowledge base content. Suitable for most Q&A scenarios

Steps

Click "Response mode settings" in the left navigation, select "RAG Q&A" as the response mode, and enter the system prompt you have defined for the Agent in the "System prompt" field. If the model supports it, use "Output format" to choose plain text or JSON output. See Output format: Plain text or JSON Schema for details.



Select RAG Q&A to enter a system prompt and choose an output format

Use case: Website customer service assistant

To create a website customer service assistant for “MaiAgent - Agent Development Platform,” enter the AI's response instructions in the “System prompt” field to clearly define its response style and responsibilities



Enter the website customer service assistant's response instructions in the System prompt field

Response mode: Template

Selecting “**Response mode: Template**” significantly reduces hallucinations. The Agent strictly answers questions using the knowledge base and FAQ content you provide, classifying questions rather than asking the LLM to generate content. Using the template system to answer minimizes the risk of hallucinations.


When to use it

Scenarios that require a consistent response format, such as standard inquiry procedures and reports.

Example walkthrough

Suppose you want to create a “Municipal Services Hotline” customer service Agent to answer residents' questions about municipal services in real time.

1. Click “Response mode settings” in the left navigation, expand “Other modes” and select “Template”



Select Template to display the Response template and Fallback template fields

2. Fill in the response template (use the template system to generate answers)

If you have not yet created a knowledge base and FAQ, the response template instructions default to the following.

We recommend adding a knowledge base or FAQ first to use the response template. The files **must be in a tabular format such as Excel, CSV, json, or jsonl.**




Example FAQ loop and question/answer variables in a response template.

In this example, I have an Agent named “Municipal Services Hotline” and have added a “Municipal Services FAQ” to its knowledge base.

The FAQ fields include question, answer, agency, category, and publication time

We recommend uploading tabular files such as **Excel, CSV, json, or jsonl**. The fields must have **headers and corresponding content**.



	A	B	C	D	E
1	問題	答案	機關	分類	發布時間
2					
3					
4					
5					
6					
7					
8					
9					
10					
11					
12					
13					
14					
15					
16					
17					
18					

Return to the response template editor and click “**Initialize response template**” in the upper right. The system generates a sample response based on the document you just uploaded to the knowledge base, for example:

```
Your question relates to the following information:

[loop: 市政服務 FAQ.xlsx]
{@loopIndex}. Question: {問題} Answer: {答案} Agency: {機關} Category: {分類}
Publication time: {發布時間}
[endloop]

Thank you for your inquiry.
```

You can now edit and format the response text.

The
[] {} portions are system instructions, so edit only the text.

📍 Loop: Enter the corresponding document filename (specify which document to use for response generation)

I made the following changes:

[x] Content of the “**opening message**”
[x] “**Question**” **text**
[x] “**Category**” **text**
[x] **Removed** “**Agency**”
[x] **Closing message content**
[x] **Line breaks and formatting**

When we return to the Agent Q&A interface and ask a relevant question, the Agent's response follows exactly the **template format** we just edited and the **FAQ document content**.

3. Fill in the fallback template

If the Agent determines that there is no relevant information, it responds using the “**Fallback template**”.

Finally, click “**Save**”.



Fill in the fallback template, then click Save

Response mode: Hybrid

When to use it

Combines RAG Q&A with templates: some content follows the template format, while the rest is generated freely. Suitable for scenarios requiring partially structured responses.

Usage recommendations

The system prompt may conflict with “Response mode: Template,” so when choosing “Response mode: Hybrid,” write the system prompt as broad guidelines.

For example, describe the role's tasks, interaction principles, and communication style.



When Hybrid is selected, both System prompt and Response template are displayed

Response mode: Agent mode

When to use it

In daily business operations, employees often need to organize information, analyze data, and create reports and analytical summaries for routine work or tasks assigned by their managers. Common questions include:

“Which product sold the most last month?”

“List all customers with sales exceeding 100,000”

“What is the revenue trend over the past three months?”

When nontechnical staff handle these questions, they often rely on the data team to write SQL queries, which is time consuming and inefficient.

With MaiAgent's Agent mode, the system can use the Text to SQL tool to automatically convert natural language questions into SQL queries and query the database in real time to quickly deliver analytical results.

> For an introduction to Text to SQL, see Text to SQL

This feature is particularly suitable for scenarios requiring **real-time queries and data insights**, such as report analysis, operational metric tracking, and data queries. It gives nontechnical users easy access to data for a more intuitive, efficient decision-making process driven by data.

Text to SQL steps

Click “Response mode settings” in the left navigation and select **“Agent mode”** as the response mode



Select Agent mode

Click “Database settings” in the left navigation, then click “Select database” to link an existing database. Create databases under “AI features” → “Databases” in the left menu. You can upload a spreadsheet to create a MaiAgent database or connect an external database such as PostgreSQL, MySQL, SQL Server, Oracle, or SynxDB. See Create and Configure Databases for instructions

Use case: Querying ecommerce product sales data

Suppose you are a marketer at an ecommerce platform and want to quickly look up product sales and similar data


First, click “Response mode settings” in the left navigation and select **“Agent mode”** as the response mode



Select Agent mode

Next, create a MaiAgent database under "Databases" and upload an Excel file. The system automatically converts it into a queryable table


> For details about MaiAgent databases, see Text to SQL with MaiAgent Databases



Example sales table with column headers and data rows.

You can also ask your company's technical staff for MySQL or PostgreSQL connection details and first create an external database under “Databases” (see Create and Configure Databases).

Then click “Database settings” in the left navigation of the Agent settings, click “Select database” to link it, and save.



Link the database you want to query in Database settings

Once configured, go to the Agent Q&A interface and enter a question, such as

“What are the top three items by sales on the official website, excluding shipping fees?”



Example response to a natural language query about sales data.

Output Format: Plain Text or JSON Schema

When the response mode is RAG Q&A and the selected LLM model supports structured output, "Output format" appears below the system prompt:

Plain text output (default): Standard conversational replies.

JSON output: Selecting this displays the "Output format JSON Schema" field. Paste a JSON Schema, and every Agent response will be JSON that conforms to this structure. This is useful when a program needs to parse the response, for example to extract form fields from a conversation or classify questions.

How to fill it in:

The content must be valid JSON. Otherwise, saving displays "Invalid output format JSON."

Use `"type": "object"` at the top level, and define each field's `type` and `description` in `properties`. Clearer descriptions help the Agent fill in values more accurately. You can adapt the `Person` example shown when the field is empty:

```
{
  "title": "Person",
  "type": "object",
  "properties": {
    "name": { "type": "string", "description": "The person's name." },
    "age": { "type": "integer", "description": "Age in years which must be equal to or greater than zero." }
  }
}
```

Place every field inside `properties` and specify a `type` for each one. If you paste only sample response data (such as `{"answer": "string"}`), it does not define any fields and cannot be saved. See Error when pasting sample data below.

If "Output format" is missing, the current model does not support JSON output or the response mode is not RAG Q&A; you can switch to another model.

> System prompts and knowledge base retrieval still apply to JSON output. This mode is typically used with API integration, where your program parses the returned JSON. Users on standard chat platforms see the raw JSON directly.

Error When Pasting Sample Data

The "Output format JSON Schema" field requires a Schema describing the fields, rather than an example of what the response looks like. Pasted sample data may be valid JSON, but it does not define any fields, leaving the Agent unable to determine what to output. Clicking "Save" opens an "Error" dialog listing the keys that need to be moved into `properties`:

This JSON Schema does not define any fields and appears to be sample data rather than a Schema. Wrap the fields in a top-level "properties" object and specify a "type" for each field. Keys to move into "properties": answer, suggested_questions.



Sample data pasted instead of a Schema



The error on saving lists the keys to move into properties

Move the listed keys into `properties`, add a `type` for each one (a `description` is also recommended), and click "Save" again. The example above becomes:

```
{
  "type": "object",
  "properties": {
    "answer": { "type": "string", "description": "The reply to the customer" },
    "suggested_questions": {
      "type": "array",
      "items": { "type": "string" },
      "description": "Suggested follow-up questions for the customer"
    }
  },
  "required": ["answer", "suggested_questions"]
}
```

Use case: Alex, an engineer at the e-commerce company Acme, wants the customer service Agent to return two fields, "answer" and "suggested follow-up questions," so the website can display the questions as buttons. Under "Output format," he selects "Output JSON," pastes his sample response `{"answer": "string", "suggested_questions": ["string"]}` directly into the field, and clicks Save. An error message appears, indicating that `answer` and `suggested_questions` must be moved into `properties`. He converts the sample to a Schema using the format above and saves again. The message "Saved successfully" confirms that the output format is configured.

> For Agents whose output format was previously saved using sample data, editing any setting (even one unrelated to the output format) and clicking "Save" will trigger the same error. First replace the "Output format JSON Schema" with a valid Schema. If you do not need JSON output, select "Output plain text" to save instead.

Agent mode options: Normal mode and Canvas mode

After you select Agent mode, an "Agent mode" section and several built-in tool switches (Code Interpreter, Browser Tool, and image search; see Built-in tool switches in Agent mode) appear below the role instructions. "Agent mode" offers two options:

Option	On-screen description	When to choose it
Normal mode (default)	The AI completes tasks autonomously using instructions and tools.	Most scenarios involving questions and answers, information lookup, and tool calls
Canvas mode (Canvas)	Execute complex tasks through a visual workflow orchestration tool.	When the Agent needs to create a finished result, such as a web page, interactive report, or chart; the result appears in the Canvas beside the conversation, where users can switch between the preview and source code or download it

Canvas mode is available only when the selected model supports tool calling. Your organization's plan may also restrict the available Agent modes. Remember to click Save after switching. See Canvas for how results are displayed, and Text to SQL with a MaiAgent database for an example of creating a visual report with Text to SQL.

6. Pre-assign Agent permissions

> RABC-based permission management architecture and explanation

Click "Permission settings" in the left navigation to specify which roles' members can use the Agent. Under "Quick permission scope selection," choose All roles, Exclude default roles, or Custom role selection to suit your use case.



Select the roles that can use this Agent in Permission settings

Who can see the Agent after it is created

Agents do not have a "draft" or "unpublished" state. Once you click Confirm to create an Agent, it appears in the Agent list. The permission settings here determine who can see it:

Organization owners: Can always see all Agents.

Other members: Can see and use the Agent only if one of their roles is selected in its permission settings. If the creator is not an owner, they must select at least one role they belong to that has AI assistant permissions; otherwise, they cannot create the Agent.

While you are still configuring it and do not want others to use it: Select only your team's roles first. After testing, return to Permission settings to add other roles.

Whether external visitors can use this Agent is controlled separately by the conversation channel's Enabled setting. See Feature settings. For the rules mapping roles to resources, see Role-based resource visibility control.

7. Complete your Agent setup

After completing the steps above, click the blue "Confirm" button in the bottom-right corner of the dialog to finish setup 🎉.

Duplicate and delete Agents

The "Actions" column on the right side of each row in the Agent list includes "Duplicate" and "Delete" as well as "Edit."

Sync conversation channel names when renaming

After you change and save the Agent name in Basic settings, a "Sync conversation channel names" dialog appears if any of the Agent's conversation channels can be renamed along with it. The dialog asks whether to update the names of the listed channels as well. Select the channels to rename and click "Update together." Click "Change assistant name only" to keep the channels' existing names. The two built-in channels, "Internal conversation" and "API," are updated automatically and do not appear in the list. If the list is empty, the dialog displays "No conversation channels need to be renamed."


The new name must also be unique among Agents in the organization. See Names must be unique within the organization.

Duplicate an Agent

Click "Duplicate" to open the "Duplicate AI assistant" dialog. It displays the "Source AI assistant" and prefills "New AI assistant name" with "Original name Copy." Edit the name and click

“Confirm.” The new Agent immediately appears in the list.

The new Agent's name must also be unique among Agents in the organization. If you remove “Copy” from the prefilled name and keep the source Agent's name, clicking “Confirm” displays a red message below the name field, and the dialog stays open. Enter a different name to continue. See Names must be unique within the organization.



Keeping the original name when duplicating displays a message below the New AI assistant name field

Duplicating preserves the original Agent's settings (response mode, role instructions, model, advanced settings, and more), along with its links to knowledge bases and skills. Conversation channels, conversation history, and usage statistics are not copied. Use a copy to test new role instructions or models before applying them to the production Agent.

Delete an Agent

Click “Delete” to open the “Delete AI assistant and associated conversation channels” dialog, which lists all “Associated conversation channels” under this Agent. After you click “Confirm deletion”:

The Agent and all listed conversation channels are deleted together: Connected channels such as your website and LINE are deleted along with the Agent. You cannot keep only the channels.

Conversation history is retained: Conversation records from these channels remain available under “Customer service conversations” → “All conversations.”

This action cannot be undone: You cannot restore the Agent's settings after deletion. To keep the settings for reference, first create a copy using “Duplicate” above.

> Every Agent has two built-in channels managed by the system: “Internal conversation” and “API.” They cannot be deleted individually from the conversation channel list and are deleted only when the Agent is deleted.

Create an Agent from the Agent Template Library

The Agent Template Library offers templates based on Agents designed by MaiAgent. Preview a template's demo conversation, then click Apply if it meets your needs. The system creates a **fully editable** Agent in your organization. You can then adjust its role instructions, knowledge bases, and tools to suit your company.

How the Template Library differs from the Agent Marketplace

Both use the same official Agents. The difference is whether you can customize the Agent afterward:

	Agent Marketplace (enable official built-in Agents)	**Agent Template Library (apply templates)**
What you get	A **locked** official Agent	An **editable** organization-owned Agent
Role instructions tools models	Cannot be changed	Fully editable
Version updates	Automatically follows the latest official version	Uses the version available when applied; later official updates do not overwrite it
Counts toward	The limit on simultaneously enabled official built-in Agents	Your plan's Agent count limit

Put simply: **use the Agent Marketplace for ready-to-use Agents maintained by MaiAgent; use the Agent Template Library to customize an official design.** For Agent Marketplace instructions, see Use official built-in Agents.

> To browse and apply templates in the Agent Template Library, your organization's plan must include Agent Builder, and your role must have the AI Assistant permission under AI Features (see Role permissions). Agent Marketplace permissions only control access to and use of the Agent Marketplace, starting conversations with Agents, and sending messages. They do not control access to the Template Library. To restrict which members can apply templates, remove the AI Assistant permission from their role (this also prevents the role from creating or editing Agents). If the role retains access to other pages under AI Features, such as the Knowledge Base permission, the Agent Template Library still appears in the sidebar, but the role cannot browse or apply templates.

Use case

Lin, a sales manager at a trading company, wants the team's replies to customer emails to have a consistent tone and clear key points, without writing role instructions from scratch. In the Agent Template Library, Lin searches for “email” and finds the “Email Reply Writer” template. Lin previews the demo conversation to confirm that it summarizes the incoming email's key points, then checks the tone and version before drafting a reply. After clicking Apply, the system creates an Agent with the same name and a dedicated knowledge base. Lin then clicks Go to AI Assistant Settings, renames the Agent to the team's preferred name, and saves it. Later, Lin can upload the company's quotation guidelines to the Agent's knowledge base and adjust its role instructions so replies better reflect company policy.

Steps

1. Open the Agent Template Library

Click Agent Template Library in the sidebar. The page lists all available official templates as cards. Each card shows the template's name, category, and description. If a template uses MaiGPT connectors (such as Microsoft or Google), the corresponding connector icons appear on the card.



Agent Template Library in the sidebar and the template card list

2. Filter or search for templates

Use All
Job Function
Industry at the top to switch category views, then click a category tag below (such as Legal or Banking) to narrow the results.

Use Search template names or descriptions in the upper right to find templates by keyword.



Search for “email” to find the “Email Reply Writer” template

3. Preview a template

Click a card or its Preview button to open the preview window:

A demo conversation plays on the left, showing how the Agent interacts with users. Click Replay to watch it again from the start.

The guide on the right follows the conversation and explains each step.

An Apply button appears at the bottom. If Ask AI is enabled in your environment, an Ask AI button also appears. Use it to ask AI to help plan customizations based on this template.



Preview window with the demo conversation and step guide, plus Ask AI and Apply buttons at the bottom

> The preview only plays a prepared demo conversation. It does not create resources or consume your quota.

4. Apply a template

Click Apply in the preview window. When creation finishes, an Agent Added window lists the resources created:

AI Assistant: Uses the template's name. If an Agent with that name already exists in the organization, the system automatically appends a number.

Knowledge Base: A dedicated knowledge base with the same name, already linked to the Agent.


The window provides shortcuts to your next steps:

Go to Chat: Try a conversation with your new Agent right away.

Go to Upload Knowledge Base Files: Add your company's documents to the dedicated knowledge base.

Go to AI Assistant Settings: Adjust the name, role instructions, tools, and other settings.

Later: Close the window. You can find the Agent later in the AI Assistant list.



The created Agent and knowledge base appear after the template is applied successfully

> Each application creates a new Agent and counts toward your plan's Agent count limit. If the limit is reached, you will see “Creation limit reached. Please upgrade your plan or contact your administrator” (see Trial and subscription plans for plan limits).

5. Customize the Agent

Click Go to AI Assistant Settings to open the Agent's settings page. It works just like an Agent you create yourself. You can change the Name and LLM model, or use the left menu to adjust Knowledge Base Settings, Tools, MaiGPT Connectors, Skill Settings, and more. The template's tools, skills, and connectors are already attached after you apply it. Remember to click Save when finished.



Agent settings after applying a template: knowledge bases, tools, connectors, and skills are preconfigured, and the name is editable


For details on each setting, see Create an Agent and Add role instructions to an Agent.

Role Instruction Design Guide

> Use MaiAgent's AI tool for generating system prompts to help refine your system prompt

🎭 What is a "system prompt"?

Imagine directing a movie: you need to tell the actors what roles to play, what personalities they have, and how they should speak. A **system prompt** is like a "script" for AI, telling it what kind of customer service representative to play.



📚 Technical glossary

Before we begin, let's get to know a few important concepts:

🤖 AI Agent

Analogy: a virtual employee you hire

Description: an AI system that can carry out tasks autonomously; in customer service, it acts as your digital service representative

💬 Prompt

Analogy: a "job description" for AI

Description: instructions that tell AI what to do and how to do it

🎯 Context

Analogy: the "memory" and "background information" of a conversation

Description: relevant information AI needs to understand the current conversation

🔄 Token

Analogy: a "unit" AI uses to understand text, like breaking sentences into small pieces

Description: the basic unit of text processing for AI, affecting processing efficiency and cost

🌟 Why are system prompts so important?

AI customer service without a system prompt 😵

```
User: "Why hasn't my order arrived yet?"
AI: "According to the system data, your order status is processing."
```


It feels like talking to a robot: cold and impersonal

AI customer service with a good system prompt 😊

```
User: "Why hasn't my order arrived yet?"
AI: "I completely understand your concern! Let me check your order status right
away.
     According to the tracking information, your package is currently at the
distribution center
     and is expected to arrive tomorrow afternoon. Would you like the tracking
number?"
```

It feels like talking to a real customer service representative: warm and professional

🏗️ The four pillars of a system prompt



1. 🎭 Identity (Who)

Tell AI "who you are"

❌ Vague identity

```
You are a customer service representative
```

✅ Clear identity

```
You are "Xiaomei," a senior customer service representative at MaiAgent,
with 5 years of customer service experience, specializing in product inquiries
and problem solving.
```

2. 🗣️ Tone and style (How)

Tell AI "how to speak"

Guide to choosing a tone:

Professional and formal: suitable for finance, law, and healthcare
Friendly and approachable: suitable for retail, dining, and everyday services
Lively and youthful: suitable for gaming, entertainment, and fashion
Warm and caring: suitable for education, health, and social services

Example: a friendly and approachable style

```
Respond in a warm, friendly tone.
Use respectful forms of address where appropriate.
You may include friendly phrases such as "Happy to help,"
but avoid being overly enthusiastic or using too many exclamation marks.
```

3. 🎯 Professional capabilities (What)

Tell AI "what you can do"

```
Your professional capabilities include:
- Explaining product features and providing usage guidance
- Looking up orders and tracking shipments
- Explaining return and exchange policies
- Performing initial technical troubleshooting
- Handling account and payment issues

When a question is beyond your capabilities,
proactively refer the customer to a human agent.
```

4. 📋 Behavioral rules (Rules)

Tell AI "what you can and cannot do"

```
Principles you must follow:
✅ Protect user privacy and do not disclose personal information
✅ Admit when you do not know something; do not fabricate answers
✅ Stay calm when handling complaints; apologize first, then resolve the issue
✅ Keep responses concise and within 100 characters

Strictly prohibited:
❌ Making promises you cannot keep
❌ Arguing with or contradicting users
❌ Disclosing internal company information
❌ Processing refund requests beyond your authority
```

🛠️ Practice: design your first system prompt

Step 1: Analyze your business requirements

Consider these questions:

Who are your customers? (Age, occupation, usage habits)

What makes your products/services distinctive?

What questions do customers ask most often?

What kind of service experience do you want to give customers?

Step 2: Choose a suitable persona

🏪 E-commerce customer service example

```
You are "Shopping Assistant," a professional online shopping advisor.
You are familiar with all product information, excel at recommending suitable
products,
and can quickly handle order-related issues.
Speak in a friendly, natural way, caring about customer needs as a friend would.
```

🏥 Healthcare customer service example

```
You are "Health Helper," a professional healthcare service advisor.
You have basic medical knowledge and can provide information on appointment
booking and examination procedures,
but never provide medical diagnoses.
Speak in a professional, warm tone that puts patients at ease.
```

Step 3: Write a complete system prompt

📝 System prompt template

```
# Role identity
You are [Role Name], a [Position] at [Company Name].
[Role background and professional experience]

# Service objectives
Your main task is [Core Task],
helping customers [Achieve Goal] through [Service Method].

# Language style
- Tone: [Choose a suitable tone]
- Wording: [Specific wording requirements]
- Length: [Response length limit]

# Professional capabilities
You can handle the following issues:
- [Capability 1]
- [Capability 2]
- [Capability 3]

# Behavioral rules
Must follow:
✅ [Rule 1]
✅ [Rule 2]

Strictly prohibited:
❌ [Prohibition 1]
❌ [Prohibition 2]

# Handling special situations
When [Special Situation] occurs, please [Handling Method].
```

🎨 Advanced techniques: make your system prompt more vivid

1. 🎪 Add personality traits

Basic version:

```
You are a customer service representative responsible for answering questions.
```

Vivid version:

```
You are "Xiaozhi," a tech enthusiast full of curiosity.
You are always excited about new features and enjoy using simple analogies
to explain complex technical concepts so everyone can understand them easily.
```

2. 🎯 Contextual instructions

Adjust responses to different situations:

```
# Context-aware instructions
- When a customer expresses dissatisfaction: respond with empathy first, then
provide a solution
- When a customer asks a technical question: explain using everyday analogies
- When a customer hesitates to purchase: provide objective advice without
pressure to buy
- When a customer praises a product: express thanks and ask whether they need
further assistance
```

3. 🔄 Dynamic adjustment mechanism

```
# Conversation adaptability
Adjust your style based on the customer's responses:
- If the customer uses formal language, respond with a similarly formal tone
- If the customer is impatient, be more concise and efficient
- If the customer is talkative, you can expand the conversation a little
```

4. Version control friendly

Include a version number and changelog

Maintain backward compatibility so existing workflows continue to work after a system prompt update

Example:

```
Version: v1.0
# Updated: October 26, 2024
# Changelog:
#   - Initial version with basic product recommendation functionality.
#   - Recommend products based on user preferences.
#   - Set the response tone to friendly and professional.
```

MaiAgent also automatically saves every version of your system prompt. Use "Edit History" on the Agent settings page to apply an older version or view conversations from the period when that version was active. See System Prompt Edit History.

🚀 Test and optimize your system prompt

Phase 1: Basic testing

Use common questions to test whether the AI's responses meet expectations

Example test questions:

"What is your return policy?"
"When will my order arrive?"
"Is this product suitable for me?"

Phase 2: Boundary testing

Test how AI performs in extreme situations

Example edge cases:

When a customer is upset
When it encounters a question it cannot answer
When asked to do something beyond its authority

Phase 3: Continuous optimization

📊 Collect data

Customer satisfaction scores
Issue resolution rate
Rate of handoffs to human agents

🔧 Adjust strategies

Expand the knowledge base based on common questions
Adjust the language style based on customer feedback
Refine behavioral rules based on failed cases

📝 System Prompt length control tips

Best practice guidelines

The ideal System Prompt length is 500–2000 characters (about 200–800 tokens), with 800–1500 characters often being the sweet spot.

Keep one core principle in mind: "Clarity beats verbosity." Overly long instructions are easily overlooked by the model, while overly short ones can lead to inconsistent behavior.

Why does length matter?

First, consider model performance: an overly long prompt divides the model's attention and affects how well it follows key instructions. Second, consider context space limits: the system prompt occupies part

of the conversation's context window, leaving less room for user conversations. Finally, consider maintenance costs: concise, structured prompts are easier to optimize and refine over time.

Three writing techniques

Structured design: divide the prompt into clear sections and put core instructions first.

Keep it concise: remove repeated descriptions and lengthy background information, retaining only necessary rules.

Continuous validation: run A/B tests with different models (GPT, Claude, Gemini) to find the best length configuration.

Practical considerations

Different AI models tolerate long prompts differently, so test and validate each one separately. For token counting, approximately 1 Chinese character equals 1 token, while 1 English token equals about 0.75 words. Since the system prompt carries greater instructional weight, keep its content focused and avoid unnecessary verbosity.

💡 Common questions and solutions

Q1: How can I make AI responses more natural?

A: Include specific conversation examples in the system prompt and set clear language style guidelines.

Q2: What if AI keeps answering irrelevant questions?

A: Clearly define the service scope in the system prompt and teach AI how to identify and handle questions outside that scope.

Q3: How do I balance professionalism and approachability?

A: Adjust to your target audience. B2B customers prefer professionalism, while B2C customers prefer approachability. Design A/B tests to find the best balance.

🎉 Closing: build your own AI customer service representative

Designing a system prompt is like training a new employee: it takes patience and ongoing adjustments. Keep these key principles in mind:

🎯 **Clear identity**: tell AI exactly who it is
🗣️ **Consistent style**: maintain a consistent language style
📋 **Clear boundaries**: specify what it can and cannot do
🔄 **Continuous optimization**: keep improving based on real usage

Start designing your first system prompt today! Remember, the best system prompts are refined continuously through real-world use.

Add Role Instructions to an Agent

Once you have designed your system prompt, you can add it in MaiAgent's Agent settings:

Add a System Prompt

1. Open the Agent Settings Page

In the left menu, click AI Features > AI Assistants. Find the Agent you want to configure in the list, then click the Edit icon in that row's Actions column.



Click the Edit icon in the Actions column to open Agent settings

2. Switch to the Reply Mode Settings Page

In the settings menu on the left of the Settings tab, click Reply Mode Settings.

Set Reply Mode to RAG Q&A or Agent Mode, or expand Other Modes and select Hybrid:

> You cannot set a system prompt in Template mode (under Other Modes)



Select a reply mode in Reply Mode Settings

3. Enter Text in the System Prompt Section

In the System Prompt section further down the same page, enter your system prompt, then click Save in the lower-right corner.



Enter content in the System Prompt section

Agent will then act according to the system prompt you defined, becoming your own customized Agent.

System Prompt Edit History


Each time you save the system prompt, a version is recorded. Click "Edit History" in the System Prompt section to view a timeline of previous save times and their full content (the latest version appears at the top; scroll down to load earlier versions). Hover over a version to reveal two buttons:

Button	Function
Apply	Fills the system prompt field with that version's content and closes the window. You still need to click Save in the lower-right corner for it to take effect, so you can compare the content first and change it back if needed
View Message History	Opens a list of conversations from the period when that system prompt version was in use. For each entry, click "View Response Quality Control Details" to see the complete Q&A; use this to compare which version produced better responses

Before making major changes, open “Edit History” to check the current version. If your changes cause problems, you can apply an earlier version and save it at any time.

Multilingual Support

MaiAgent provides language support at multiple levels: **Web Chat supports interfaces in 13 languages**, **the knowledge base supports content processing in all languages**, and **the admin console provides Chinese and English interfaces**. Your Agent can engage in natural, fluent conversations with users worldwide, overcome language barriers, and expand your business reach.



🌍 Supported Languages

MaiAgent Web Chat currently supports the following 13 languages:

Chinese Languages

Traditional Chinese (Traditional Chinese) - zh-TW
Simplified Chinese (Simplified Chinese) - zh-CN

International Languages

English (English) - en

Southeast Asian Languages

Thai (Thai) - th
Malay (Malay) - ms
Vietnamese (Vietnamese) - vi
Indonesian (Indonesian) - id
Filipino (Filipino) - fil
Burmese (Burmese) - my
Khmer (Khmer) - km
Lao (Lao) - lo

East Asian Languages

Japanese (Japanese) - ja
Korean (Korean) - ko

Ongoing updates: We continue to add support for more languages based on user needs. If you need support for a specific language, contact our technical team.

⚙️ Language Settings

1. Configure via JavaScript

> See the Technical Manual—Web Chat Embedding and SDK (locale setting)

2. Web Chat Settings

Setup steps:

Click ⋮ in the upper-right corner of the window



2. Click Traditional Chinese



3. Select the language you want to use



🎯 Multilingual Features

1. Intelligent Language Detection and Responses

Automatic detection (Chinese and English): Automatically detects Chinese and English and responds in the corresponding language.

Multilingual settings: Supports multiple languages. Switch and select the display language in settings; once selected, conversations will receive responses in that language.

High accuracy: Based on advanced NLP technology, language detection achieves 98% accuracy.

2. Natural Language Understanding

Semantic understanding: Goes beyond translation to understand meaning in different languages

Cultural adaptation: Considers how people express themselves in different cultural contexts

Slang recognition: Understands common slang and colloquial expressions

3. Localized Responses

Word choice: Uses wording and expressions that match local conventions

Format adjustments: Adapts date, number, and currency formats to different languages

📚 Knowledge Base and Interface Languages

1. Interface Language Support Levels

MaiAgent Admin Console

Supports 3 interface languages: Traditional Chinese, Simplified Chinese, and English

Designed for system administration and configuration

Web Chat Interface

Provides interface text in all 13 languages

Includes speech recognition and voice response features

Covers: Chinese (Traditional and Simplified), English, Thai, Japanese, Korean, Malay, Vietnamese, Indonesian, Filipino, Burmese, Khmer, and Lao

2. Knowledge Base Content Processing

Document Support in All Languages

The knowledge base can parse and process document content in any language

No restrictions on document language; supports language formats from around the world

Intelligent retrieval accurately searches multilingual knowledge bases

Upload steps:

1. Open **Knowledge Base Management**

2. Select **Add Document**

3. Upload a document in any language (no language restrictions)

4. The system automatically detects the document language and creates a multilingual index

3. Cross-Language Q&A

Key Features

Multilingual questions: Ask questions freely in 13 languages

Retrieval across all languages: Searches the entire multilingual knowledge base for relevant content

Intelligent translation: Automatically translates retrieved results into the user's preferred language

Accurate responses: Ensures complete and accurate answers

Workflow

Receive the question - The user asks a question in any supported language (Thai, Japanese, Korean, etc.)

Intelligent retrieval - The system searches across languages for the most relevant content

Content integration - The LLM analyzes and combines multilingual information

Language conversion - Translates it into the user's selected display language

Output the answer - Provides a complete response

🚀 Use Cases

1. Expansion into Southeast Asian Markets

Regional coverage: Supports 8 major Southeast Asian languages, reaching more than 600 million people

Localized service: Understands cultural differences and business practices in each country

Cross-border e-commerce: Provides customers in different countries with a shopping experience in their native language

2. International Customer Service Centers

Global support: Meets customer service needs across major Asian markets

24-hour service: Provides multilingual customer support across time zones

Cultural sensitivity: Understands communication styles and polite expressions in different cultures

3. Internal Use at Multinational Enterprises

Employee support: Provides internal Q&A services for employees of different nationalities

Knowledge sharing: Overcomes language barriers to facilitate knowledge exchange

Training assistance: Offers multilingual training content and Q&A

4. Tourism and Hospitality

Visitor services: Provides immediate assistance to travelers from different countries

Attraction information: Offers multilingual attraction information and guided tour services

Room and ticket reservations: Supports multilingual bookings and inquiries

Cross-Conversation Search

Cross-conversation search lets an Agent search the same contact's recent conversations in the same inbox when responding. It is useful when service records need to carry over, but users frequently start new conversations.

> This feature is disabled by default. Enabling it only expands the Agent's search scope; it does not combine content from different contacts or inboxes.

Enable Cross-conversation Search

Click "AI Assistants" in the left menu.

Select the Agent you want to configure and open "Settings".

Open "Advanced Settings".

Enable "Cross-conversation Search" in the conversation memory settings.

Enter a value from 1 to 365 days in "Lookback Days". The default is 90 days.



Enabling Cross-conversation Search reveals the Lookback Days field below, which defaults to 90 days

Click "Save".

> A longer lookback period expands the searchable history. Set it according to your service needs and follow your organization's data usage and privacy policies.

Other Options in the Conversation Memory Settings

The Conversation Memory Settings section containing "Cross-conversation Search" also includes the following options:

Option	On-screen Description	When to Adjust
Vector Memory	When enabled, archived conversation messages are vectorized and facts are extracted for semantic retrieval. When disabled, only the current conversation history window is used.	Enable it for long conversations when the Agent needs to retrieve earlier messages; disable it when handling only short conversations to save vectorization costs
Embedding Model	Converts conversation content into vectors, affecting the accuracy of conversation memory retrieval and context understanding	This model is for "conversation memory" and is separate from the Embedding model on the knowledge base settings page; the model labeled Default is configured by the platform and generally does not need to be changed
Reranker Model	Reorders retrieval results to improve retrieval accuracy	Like the option above, this affects conversation memory, specifically its reranking
Tool Result Truncation	Automatically truncates oversized tool results to prevent memory growth	See Other Switches in Advanced Settings

Persistent Memory, which stores facts and preferences over the long term, is a separate section. See Persistent Memory.

Use Case

The customer service assistant at Xiaomai Technology tracks after-sales cases. A customer provided order details in a conversation last week and starts a new conversation today to ask about progress. The administrator enables cross-conversation search for the customer service assistant and sets the lookback period to 30 days. After saving, the Agent can use the conversation history tool to find relevant content in the same customer's recent conversations and respond based on those records.

Feature Scope

Cross-conversation search covers:

The same contact

The same inbox

Regular chat conversations that have not been deleted

Conversations whose last message falls within the configured number of days

For conversations within the lookback scope, all messages in the conversation are included, rather than just those sent during the lookback period. The system selects up to 200 conversations with the most recent activity. The current conversation is always included in the search scope, regardless of the lookback period.

When this feature is disabled, the Agent searches only the current conversation. Cross-conversation search and "Vector Memory" are independent settings that can be enabled or disabled separately.

Persistent Memory

Persistent memory lets your Agent extract facts worth remembering during conversations (such as a contact's preferences or information they previously provided), save them, and reuse them in later conversations with the same contact without asking again each time.

It differs from vector memory and cross-conversation retrieval in "Conversation Memory Settings": those features **search** past messages when answering, while persistent memory **organizes conversations into individual structured memories** for long-term retention. See Agent Memory for a comparison of the three.

How to Enable It

Persistent memory is controlled at the **organization level**. Individual Agents cannot enable or disable it themselves. To enable or disable it, contact your organization administrator or your MaiAgent contact.

You can see its current status on the Agent settings page:

Open "AI Features" → "AI Assistants" and select the Agent you want to view.
In the left navigation, click "Management & Advanced" → "Advanced Settings".
Scroll to the "Persistent Memory" section. The label next to "Cross-Conversation Memory" displays Enabled or Disabled.

> The "Memory List" appears below the section only when the organization has enabled the feature and the Agent has already been created (outside the creation dialog).

Memory List

The "Memory List" shows all memories currently stored by this Agent. The number next to the title is the total count; click "Refresh" on the right to reload it. Each memory includes:

Item	Description
Topic	A topic identifier for the memory, for easy categorization and reference
Summary	A one-sentence summary of the memory; the Agent primarily refers to this when answering
Details	Additional details listed individually; displays "—" when there are no details
Scope label	The scope this memory applies to: Organization, Member, Assistant, Contact, or Conversation

Item	Description
Type label	The nature of the memory: Fact, Preference, Summary, Instruction, or Profile
Date	The date this memory was created

When the list is empty, it displays "No memories recorded yet". Memories appear here once the Agent extracts facts from conversations.

Delete a Memory

Each memory has a "Delete" action on the right. After confirmation, it is permanently removed, and the Agent will no longer refer to it in later conversations. Use this when information was extracted incorrectly or a contact asks you to forget specific information.

Expired Memories

Memories do not disappear immediately after they expire. Instead, they move to the "Expired Memories" collapsible section below the list (with the count in parentheses), where they appear in gray with dashed borders. The Agent does not refer to these memories. Expand the section to access two actions for each memory:

Reactivate (↶ icon): After confirming "Are you sure you want to reactivate this memory?", the memory becomes active again, and the Agent resumes referring to it.

Delete: Permanently removes it.

> Memory content comes from information contacts provide in conversations. Manage it according to your organization's data use and privacy policies. When a contact requests deletion of personal data, remember to remove the related memories as well.

Manage via API

To read or maintain memories in your own system, use the Member Memory API in the Technical Manual.

Knowledge Base Label Filtering

Knowledge base label filtering lets you configure a set of default label conditions for each Agent. Once configured, the Agent only references files and FAQs that meet those conditions when answering questions. All other content is excluded. The same rules apply whether users ask through Web Chat, LINE, the API, or conversations in the admin console.

> Without label filtering, the Agent references all files in all attached knowledge bases, exactly as before.

Previously, restricting an Agent to files with certain labels required passing query metadata with every API call or configuring each contact individually. Now, you only need to configure this once on the Agent settings page.

Use Case

A retail chain's knowledge base contains public return and exchange policies, membership points rules, and an opening and cash register SOP intended only for store staff. The knowledge base administrator labels public documents "Public Customer Service" and internal documents "Internal Operations." They then enable "Label Filtering" on the customer service assistant's settings page, select "Public Customer Service," and save. From then on, whether customers ask through the website's Web Chat or LINE, the Agent only cites public documents. Even if a customer asks about store opening procedures, the Agent cannot find the internal SOP and will not disclose internal information. No changes to integration code are needed from an engineer.

Prerequisites

The Agent has at least one attached knowledge base (configured under "Knowledge Base Settings" on the Agent settings page).

Labels have been created in the knowledge base and applied to files or FAQs. For instructions on creating and applying labels, see Document Management: Labels and Metadata.

Available labels come from the knowledge bases attached to this Agent. If the Agent has multiple knowledge bases, the same conditions apply to all of them.

Configure Label Filtering

Click "AI Assistants" in the left menu, select the Agent you want to configure, and open "Settings."


Under “Knowledge and Data,” click “Label Filtering.” The scope shown in the upper right lists the knowledge bases currently attached to this Agent.



Without any conditions, the Agent references all files

Under “Condition Group 1,” click a label below to add it to the conditions. You can add multiple labels and choose “Include All Labels” or “Include Any Label” to determine how this group matches files.

Scroll down to the “Affected Files” panel to check which files will be retrieved and which will be excluded. The panel updates in real time based on the conditions currently on screen, including unsaved changes.



The plain-language description and Affected Files panel update immediately when you add a label

Click “Save” in the lower right. Once saved, “Configured” appears next to “Label Filtering” in the left menu.

> Label filtering shares the same “Save” button as the Agent's other settings. Remember to save before leaving the page; otherwise, the conditions will not take effect.

How to Read Conditions

The builder describes conditions in plain language rather than displaying AND/OR. This guide includes the corresponding logic in parentheses for comparison with older screens or API documentation. Conditions have two levels: within a group and between groups.

Level	Option	Meaning
Within a group (between labels in the same condition group)	Include All Labels (AND)	A file must have every label listed in this group
Within a group	Include Any Label (OR)	A file only needs one of the labels in this group

Level	Option	Meaning
Between groups (across multiple condition groups)	Match Every Group (AND)	A file must meet the conditions in every group
Between groups	Match Any Group (OR)	A file only needs to meet the conditions in one group

For combinations such as “A or B,” click “Add a Condition Group” to add another group. The “When There Are Multiple Groups” control for switching between group matching modes only appears when there are at least two groups.



Two condition groups: files labeled Public Customer Service, or files labeled Internal Operations

At the bottom, the builder describes the current conditions in one sentence, such as “The assistant will only reference: files labeled ‘Public Customer Service,’ or files labeled ‘Internal Operations.’” If you are unsure whether the conditions are correct, check this sentence and the “Affected Files” panel.

> The “Affected Files” panel counts only files loaded on screen. If the knowledge base contains many files, the panel displays “Only the first N loaded files are counted.” The filter still applies to all files during actual retrieval.

Scope and Priority

The Agent's label filter is a default that applies to all conversations through this Agent: Web Chat, LINE and other conversation platforms, API integrations, and conversations in the admin console.

If query metadata has already been specified at another level for a conversation, that level takes precedence and the Agent default is not used. Priority, from highest to lowest, is:

Query metadata supplied with an individual message (for example, in an API call or when embedding Web Chat)

Conversation-level query metadata

The contact's query metadata

The Agent's label filter (the settings on this page)

Existing contact or API settings are therefore unaffected. The Agent's default conditions apply only when none of the first three levels has been specified. For configuration instructions for each level, see Knowledge Management Permissions: Query Metadata and Start Building—Using the Query Builder.

> The knowledge base's "Search Test" tool checks retrieval quality and does not apply the Agent's label filter.

Invalid Labels

After a label is renamed, its new name appears when you reopen the settings page. If a label referenced in a condition has been deleted, or its knowledge base has been detached from the Agent, reopening the settings page displays a warning listing the affected labels. Click "Remove Invalid Labels" to clear them all at once, or select other labels and save.

> Invalid labels do not match any files during retrieval, and do not broaden retrieval to all files. If the Agent suddenly cannot answer questions using knowledge base content, first check the label filter for invalid labels.

Clear Settings

Click "Clear All Conditions" in the upper right of the builder and save. The Agent will return to referencing all files.

If the knowledge bases attached to the Agent do not have any labels yet, this page displays "The attached knowledge bases do not have any labels yet." Go to the knowledge base and label the files

first.



Message shown when the knowledge bases have no labels

Response Length and Agent Execution Limits

The Agent's Advanced Settings include two groups of limits:

Response length: Maximum Output Tokens limits how much the AI can write in each response. The explanation starts with Feature Introduction below.

Agent execution limits: Maximum Iterations (the tool call limit, default 20) and Execution Timeout (Seconds) limit how many rounds of tool calls an Agent in Agent mode can make per message and how long it can run. To find out "how many tool calls are allowed" or understand the message "The tool usage limit for this turn has been reached," go directly to Agent Execution Limits.

Feature Introduction

The custom output token limit lets you precisely control the maximum length of each Agent response. Adjust this setting for different use cases to produce brief summaries or detailed explanations while effectively controlling token costs.

> About Tokens Tokens are the basic units AI models use to process text. In general: - Chinese: 1 character is approximately 1.5-2 tokens - English: 1 word is approximately 1-1.5 tokens - Punctuation also counts toward the token total

Configure the Output Token Limit

Navigate to the Settings Page

Click "AI Assistants" in the left menu

In the list, click "Edit" to the right of the Agent you want to configure

In the left navigation of the "Settings" tab, click "Advanced Settings" under "Management & Advanced"

Adjust the Token Limit

Select a token limit mode

"Use Model Maximum": Apply the maximum output tokens supported by the selected model (default)

"Custom Amount": Specify your own limit

Enter a custom value (when "Custom Amount" is selected)

Enter the desired value in the numeric input field

The allowed range depends on the selected model. The interface displays the model's allowed range in real time (for example, "Range: 512 - 64000 tokens" in the image below)

Save the settings

Click the "Save" button

Settings take effect immediately; there is no need to restart the Agent



The "Maximum Output Tokens" section: select "Custom Amount" and enter a limit; the range allowed by the current model appears below

> Notes - Setting the limit too low may truncate responses and affect completeness - Setting the limit too high increases token costs - Adjust it to your actual needs and test to find the best balance

Recommended Settings

The following token limits are recommended for different use cases:

Use Case	Recommended Tokens	Description
Brief Q&A	256 - 512	Suitable for quick answers, such as FAQ bots Approximately 100-200 Chinese characters
General Customer Service	512 - 1024	Balances detail and cost Approximately 200-400 Chinese characters
Professional Consultation	1024 - 2048	Provides detailed explanations and solutions Approximately 400-800 Chinese characters
Content Generation	2048 - 4096	Generates long articles or reports Approximately 800-1600 Chinese characters
Code Generation	1024 - 2048	Produces complete code snippets Including comments and explanations

Use Case Examples

Scenario 1: FAQ Quick Response Bot

Requirement: Provide brief, clear answers to frequently asked customer questions without lengthy explanations

Configuration:
- Output token limit: 256-512
- System prompt: "Answer questions briefly and clearly in no more than 3 sentences"
- Expected result: Fast responses with lower token consumption

Example conversation:

```
User: What are your business hours?
AI: Our business hours are Monday to Friday, 9:00 AM to 6:00 PM,
Saturday, 10:00 AM to 5:00 PM, and we are closed on Sundays.
```

Scenario 2: Detailed Technical Support

Requirement: Provide detailed step-by-step instructions for users experiencing technical issues

Configuration:
- Output token limit: 1024-2048
- System prompt: "Provide detailed step-by-step instructions that users can follow"
- Expected result: Complete troubleshooting guidance

Example conversation:

```
User: What should I do if the software won't start?
AI: Follow these steps to troubleshoot:

1. Check system requirements
   - Operating system: Windows 10 or later
   - Memory: At least 4GB
   - Disk space: At least 2GB

2. Reinstall the software
   - Uninstall the existing version (Control Panel > Programs)
   - Download the latest version [link]
   - Run the installer as an administrator

3. Check firewall settings
   - Add the software to the exception list
   - Allow the software to access the network

If these steps do not resolve the issue, please provide a screenshot of the error
message so we can assist further.
```

Scenario 3: Content Summary Generation

Requirement: Extract key points from long articles

Configuration:
- Output token limit: 512-768
- System prompt: "Organize the key points into 3-5 items, with no more than 2 sentences per item"
- Expected result: Concise summaries that are easy to understand quickly

Relationship with Other Settings

System Prompt

Even with a high token limit, the system prompt can still constrain response length:

```
Good example:
"Answer concisely unless the user requests a detailed explanation"

Poor example:
"Answer every question in as much detail as possible" (may lead to excessively
long responses)
```

Model Selection

Different models support different maximum output token counts. When you change the model used by the Agent, the customizable range changes accordingly. The range hint in the interface shows the lower and upper limits for the currently selected model. Selecting "Use Model Maximum" automatically applies that model's maximum.

Agent Execution Limits: Tool Call Rounds and Execution Timeout

> This section applies only to Agents whose response mode is set to "Agent Mode". This section does not appear in Advanced Settings for Agents using other response modes.

An Agent in Agent mode decides which tools to call and how many rounds of reasoning it needs to answer a question. To prevent it from running indefinitely, Agent Workflow Settings in Advanced Settings provide two independent "brakes":

Maximum Iterations (tool call limit): The maximum number of "think → call tools → receive results" rounds the Agent can perform when answering a message. The range is 1–100, with a default of 20. A round can call multiple tools at once, so the limit is counted in rounds and resets when the user sends the next message. When Enable Tool Search is enabled (the default), rounds used solely to search for available tools do not count toward the limit

Execution Timeout (Seconds): The maximum time an Agent can run while answering one message. The range is 30–1200 seconds, with a default of 600 seconds

What Happens When the Tool Call Limit Is Reached

After the last round is used, the Agent stops calling tools, prepares a response using the information already obtained, and adds the following line at the end:

This response has reached the tool usage limit for this turn and may be incomplete. Send a follow-up message to continue.

If the Agent has not written any content at that point, the response will be "I reached the tool usage limit for this turn before completing the task. Please try again or narrow the scope of your question." Both cases mean the configured limit has taken effect, rather than a system error. The user can send another message asking the Agent to continue, and administrators can increase Maximum Iterations (also check the timeout, as explained below).

How Do the Two Settings Interact?

These settings are independent, with no conversion formula; whichever threshold is reached first determines the outcome. If the timeout is reached first, the conversation is forcibly interrupted. If the iteration limit is reached first, the Agent generates a summary response, and this is not treated as an error.



Example of the yellow warning triggered by a 100-second timeout ÷ 20 iterations (a budget of only 5 seconds per iteration)

Custom Timeout Message

"Custom Timeout Message" at the bottom of Agent Workflow Settings determines the text users see when execution is interrupted by a timeout. The on-screen description says, "Shown to users only when the Agent workflow times out. Leave blank to use the system default message." You can enter a message such as "The system is busy. Please try again later," or suggest asking a smaller question. The iteration limit notice has fixed wording and is not affected by this field.

Other Switches in Advanced Settings

The same Advanced Settings tab includes several other switches related to response length and cost. The defaults are generally sufficient:

Location	Switch	On-screen Description and Usage
Knowledge Base Settings	Force Full Retrieval Scope	When enabled, ignores the model's automatically chosen retrieval count and always returns the full number of results configured in "Maximum Retrieval Chunks"; suitable for knowledge bases with long tables or other content that requires more chunks to display in full. Increases input tokens per response
Conversation Memory Settings	Tool Result Truncation, Maximum Characters per Tool Result	Automatically truncates oversized tool results (such as web search results or code execution output) to prevent memory growth; results exceeding the limit retain content from both the beginning and the end. Enable it when tools frequently return entire HTML pages or large amounts of data
After Persistent Memory	Enable Claude Streaming Auto-retry	Automatically aborts stalled Claude streaming calls (when the first chunk does not arrive or transmission is interrupted) and retries once in non-streaming mode. Each retry incurs another charge for the same prompt; enable it only when Claude responses frequently stall
At the Bottom	Enable Automatic Evaluation	When enabled, uses an LLM to automatically score the quality of each conversation in AI Assistant Monitoring. This consumes the organization's usage quota. See Automatic Evaluation and Agent Monitoring

For Vector Memory, Cross-conversation Search, and the Embedding/Reranker models in Conversation Memory Settings, see Cross-conversation Search.

Cost Optimization Recommendations

Calculate Token Consumption

Token consumption for a conversation includes:
- **Input tokens**: User question + conversation history + system prompt
- **Output tokens**: AI response (constrained by this setting)

Example calculation:

```
Input: User question 50 tokens + conversation history 200 tokens + system prompt
100 tokens = 350 tokens
Output: AI response (limit set to 512 tokens)
Total: 350 + 512 = 862 tokens (maximum)
```

Optimization Strategies

Adjust for the use case

Use a low token limit for simple questions

Increase the limit only for complex questions

Avoid unnecessarily long responses

Explicitly request concise answers in the system prompt

Use multi-turn conversations instead of one long response

Review usage regularly

Go to the Agent's "Usage Analysis" → "Usage Statistics" to review token usage and conversation character count trends

Adjust settings to optimize costs

> For detailed cost calculations and optimization recommendations, see Usage Calculation.

Frequently Asked Questions

Q: Will AI Responses Be Forcibly Truncated After Setting a Token Limit?

A: Yes. When an AI-generated response reaches the token limit, it stops at that point, which may leave a sentence incomplete. We recommend:
- Set an appropriate limit (not too low)
- Ask the model in the system prompt to "end naturally before reaching the character limit"

Q: How Can I Find Out How Many Tokens My Agent Uses on Average?

A: Open the Agent's "Usage Analysis" tab and switch to "Usage Statistics". The Token Usage chart lists token counts for each model used by this Agent and total token usage by date. See Usage Analysis for a description of the chart.

Q: Does a Higher Token Limit Slow Down Responses?

A: It has a slight effect. Longer responses take more time to generate, but the difference is usually small (within a few seconds). The main factors remain:
- Model selection
- Network connection speed
- Server load

Q: Do Different Languages Need Different Token Limits?

A: Moderate adjustments are recommended:
- **Chinese**: The same character count consumes more tokens, so you can raise the limit slightly
- **English**: More token-efficient, so a lower limit can be used
- **Multilingual environments**: A higher limit is recommended for flexibility

Q: Does the Token Limit Affect Knowledge Base Retrieval Results?

A: It does not directly affect retrieval, but it affects how the results are presented:
- **High token limit**: Can cite more knowledge base snippets
- **Low token limit**: Cites only the most relevant snippets

Q: How Many Rounds of Tool Calls Can an Agent Make When Answering One Message?

A: This is determined by Maximum Iterations, which defaults to 20 rounds and can be increased to 100 rounds. It resets for each user message. When the limit is exhausted, the response ends with "This response has reached the tool usage limit for this turn and may be incomplete. Send a follow-up message to continue." This means the limit has taken effect, rather than a malfunction. See What Happens When the Tool Call Limit Is Reached.

Q: If I Increase Maximum Iterations, Must I Also Increase the Execution Timeout?

A: This is strongly recommended, but the system does not require it. The settings are independent: you can save a higher iteration limit without changing the timeout, but execution may be forcibly interrupted by the timeout before reaching your configured iteration limit. Adjust both settings so that "Execution Timeout ÷ Maximum Iterations ≥ 15 seconds" to avoid triggering the yellow warning.

Q: How Do a Timeout and Exhausted Iterations Differ for the User?

A: They differ significantly. When the iteration limit is reached first, the Agent summarizes the information it has gathered into a response, and the conversation ends normally. When the execution timeout is triggered first, the conversation is forcibly interrupted and marked as an error. The user sees only any content generated before the timeout (if any), plus the timeout message, without a prepared summary response. Credits already consumed are not refunded.

Testing and Adjustment

Testing Process

Set an initial value

Start with a recommended value (such as 1024)

Run test conversations

Enter typical user questions

Observe response length and completeness

Evaluate the results

Is the response complete?

Does it contain unnecessary detail?

Is token consumption reasonable?

Adjust gradually

Too long → lower the token limit

Too short/truncated → raise the token limit

Monitor continuously

Review usage regularly

Fine-tune according to actual needs

Test Examples


```
Test 1: Token limit 256
User: Please introduce your company
AI: We are a company focused on AI technology, providing enterprise chatbot
solutions. [Response truncated]
Evaluation: Too short; increase the limit

Test 2: Token limit 1024
User: Please introduce your company
AI: We are a company focused on AI technology ... [Complete, detailed
introduction] ... Contact us to learn more.
Evaluation: Appropriate; use this setting
```

Related Features

> Additional Features - Create an Agent - System Prompt Design Guide - Usage Calculation - Usage Analysis

Agent Scheduling



Agent scheduling: Scheduled trigger → Automatic Agent execution → Result delivery

What Is It?

Agent scheduling lets an Agent automatically run tasks at configured times without waiting for someone to ask a question. Give it a prompt and set a schedule, and the Agent will run at the scheduled times and send the results to your chosen destination.

It is like setting an alarm for the Agent—when the time comes, it starts working automatically.

When Do You Need It?

Recurring reports: Summarize the previous day's customer service activity every morning at 9 AM

Monitoring checks: Check system status every hour and send a notification if anything is wrong

Data processing: Compile the previous week's sales data every Monday

One-time tasks: Perform a specific action once at a scheduled time

Schedule Types

Type	Description	Example
Cron	Set precise times using a Cron expression	`0 9 * * 1-5` (9 AM, Monday through Friday)
Interval	Run at a fixed interval	Every 30 minutes, every 2 hours
One-time execution	Run once at a specified time	2026-04-15 14:00

Execution Modes

Mode	Description	Suitable Scenarios
Context mode	Retains memory across runs so each run can continue from the previous one	Tasks that need to accumulate information (such as ongoing tracking)

Mode	Description	Suitable Scenarios
Independent mode	Starts from scratch each time without memory of previous runs	Independent recurring tasks (such as daily reports)

Result Delivery

After execution, results can be sent to:

Conversation: Send to a conversation on the specified conversation platform

Webhook: POST to your external URL (to integrate with Slack, LINE, and other services)

Advanced details: Agent scheduling only supports Agents whose response mode is set to Agent mode. During a scheduled run, the Agent uses your configured prompt as its instructions and uses all its attached tools and skills to complete the task.

A scheduled run executes a "conversation," rather than batch processing files: the Agent can do the same things you can ask it to do in a conversation. The platform does not have built-in file conversion features such as "PDF to images." To process files on a schedule, attach the required capability to the Agent—Code Interpreter can use code in a sandbox to process files from the knowledge base or a conversation and produce new files. For a fixed integration with an external system, use an API tool or an MCP tool instead. Results are sent through a conversation or Webhook and are not automatically written back to the knowledge base.

What Do I Need to Do?

Choose an Agent — Select an existing Agent (it must use Agent mode)

Write a prompt — Describe what the Agent should do on each run

Set the schedule — Choose the schedule type and time

Configure delivery — Decide where to send the results

Enable — Turn on the schedule to start automatic execution

Next Steps

For complete instructions, see How to Set Up Agent Scheduling.

Set Up Agent Schedules

> This page shows how to create an agent schedule. If you are unfamiliar with what agent schedules are for, read Agent Schedules first.

On this page: Prerequisites | Open Agent Schedules | Create a Schedule | What Happens After Saving? | Where Do Results Go? | Complete Example: Daily Customer Support Summary | Manage Existing Schedules | View Execution Logs | FAQ | Related Reading

Prerequisites

Before creating a schedule, confirm the following:

You have created an Agent whose response mode is Agent mode — Agent schedules only support Agent mode. Agents in other modes do not appear in the menu

The Agent is connected to at least one conversation platform — The schedule runs the Agent using a conversation platform as its container

You have permission to access Agent Schedules — If you cannot see the "Agent Schedules" menu, contact your organization administrator to check your permissions

Open Agent Schedules

In the left menu, click AI Features → Agent Schedules. The schedule list appears:



Schedule list: the toolbar shows the schedule quota, and the list shows each schedule's status, execution mode, delivery method, and last execution time

List columns:

Column	Description
Name	A name that identifies the schedule
AI Assistant	The Agent used by this schedule


Column	Description
Execution Mode	Context mode or independent mode
Schedule	Schedule type (Cron, interval, one_shot) and time
Delivery Method	💬 indicates delivery to a conversation, 🔗 indicates a Webhook, and `auto` indicates an automatically created dedicated conversation
Last Execution	The most recent execution time
Status	Active Paused

Create a Schedule

1. Click Add Schedule

Click Add Schedule in the upper right to open the form. The form has four tabs: **Basic Information**, **Prompt**, **Schedule Settings**, and **Delivery Settings**.

2. Fill In Basic Information



Basic Information tab: select an Agent, give the schedule a name, and choose an execution mode and conversation platform

Field	Required	Description
AI Assistant	✅	Select an existing Agent (only Agents in Agent mode are shown)
Name	✅	A name that identifies the schedule, such as “Daily Customer Support Summary”
Execution Mode	✅	Choose context mode or independent mode
Conversation Platform	✅	The conversation platform container used during execution; context mode uses it to accumulate Agent memory (used by the backend and does not appear in the customer support conversation list)
Save Results to Context	—	Only shown in context mode. **Only affects memory for the next execution** (it does not affect whether you can view results—all previous responses are retained on the execution logs page)


Which execution mode should you choose?

Context mode: Retains memory across executions. Suitable for tasks that accumulate information, such as tracking complaint resolution progress or monitoring trends in data.

Independent mode: Starts from scratch each time without memory of the previous execution. Suitable for independent recurring tasks, such as daily reports or periodic statistics.

> The AI Assistant, Execution Mode, and Conversation Platform fields cannot be changed after creation. To change them, delete the schedule and create it again. Other fields (name, prompt, schedule time, and delivery method) can be edited at any time.

3. Write a Prompt



Prompt tab: describe the task the Agent should complete on each execution

In the prompt field, describe what the Agent should do **on each execution**. The prompt is passed to the Agent as an instruction, and the Agent uses its attached tools and skills to complete the task.

Example prompt:

```
Find all unresolved customer complaints from the past 24 hours,
sort them by priority, and create a bulleted summary.
For any “High” priority cases, also add the label “⚠️ Urgent”.
```


Tips for writing prompts:

Clearly describe the task objective and output format

If the Agent needs to use a specific tool, guide it in the prompt (for example, “Query the orders table in the database”)

Avoid relying on external state other than the current time; each execution should be an independent task (unless you use context mode)

4. Set the Schedule Time



Cron mode: use a standard five-field Cron expression to specify exact times

There are three schedule types:

Cron

Use a standard five-field Cron expression to specify exact times: `minute hour day month weekday`.


Expression	Meaning
`0 9 * * 1-5`	At 9:00 AM, Monday through Friday
`0 */2 * * *`	Every 2 hours, on the hour
`30 8 * * *`	At 8:30 AM every day

Expression	Meaning
`0 0 1 * *`	At midnight on the first day of each month

Use this with the “Time Zone” field, which defaults to `Asia/Taipei` (Taipei time).

Interval

Run at a fixed interval, using a combination of four fields: days, hours, minutes, and seconds:




Interval mode: combine the days, hours, minutes, and seconds fields

The interval must be **at least 1 second**
For example, to run “every 30 minutes”, enter `30` in the “Minutes” field and `0` in the other fields
Interval mode does not use the time zone field (because the time is relative rather than absolute)

One-Time Execution

Run once at the specified time, after which the schedule ends automatically:



One-time execution: select a specific date and time; the schedule ends after execution

Select a date and time with precision to the second

Use this with the “Time Zone” field


After execution, the schedule remains in the list for viewing logs, but will not run again

Other fields:

Field	Description
Enabled	Whether to activate the schedule immediately. When off, the schedule is “Paused” and will not trigger
Maximum Executions	Limits how many times the schedule can run. Once reached, it stops triggering and no longer counts toward the schedule quota. Its status first shows “Completed” and changes to “Paused” at the next scheduled time. Increase the maximum executions before enabling it again. Leave blank for no limit

5. Set the Delivery Method

Where should results be sent after execution? Configure this on this tab.



Delivery settings: configure multiple conversation targets and multiple Webhook URLs

> This page sets where results are proactively delivered (specified conversations or Webhook receivers). Even without any delivery targets, the full results of each execution are still retained on the Execution Logs page; they simply are not pushed elsewhere.

Conversations

Click Add Conversation and select a conversation from the menu. Results are sent as bot messages. You can add multiple conversations.

Webhook

Click Add Webhook URL. Results are sent in a POST request to your external URL (which must start with `http://` or `https://`). Common uses include:

Integrating with Slack
Discord
LINE

Writing to your own system for further processing

Triggering other automation workflows

> You can leave delivery targets unset; execution results will always remain on the Execution Logs page. However, to have your team or colleagues receive results automatically (for example, in Slack), you must configure at least one conversation or Webhook; otherwise, no one will be notified.

6. Save and Enable

Click Confirm to save. If the "Enabled" toggle is on, the schedule immediately starts triggering according to its configured times.

What Happens After Saving?

After saving the schedule, you will immediately see these changes:

The modal closes, and the schedule appears in the list

Its status shows "Active" (a green tag), or "Paused" (if the Enabled toggle is off)

"Last Execution" is empty until the first trigger, when it updates to the execution time

The system performs two actions in the background (there is no visible UI change)

Registers the schedule with the backend scheduler so it triggers automatically at the configured time

In context mode, also creates an internal conversation container to accumulate Agent memory (this container does not appear in the Customer Support Conversations list)

Wait for the schedule to trigger

Cron

Interval: Runs automatically at the configured times. For example, Cron `0 9 * * 1-5` triggers at the next 9:00 AM on a Monday through Friday

One-time execution: Runs once at the configured time

Do not want to wait? Click ▶️ Run Now in the list to trigger a test execution immediately

During execution

The status in the list remains "Active", and "Last Execution" updates with each execution time

Each execution creates an entry on the Execution Logs page (including the full Agent response)

If you added conversations or Webhooks in "Delivery Settings", the results are also sent to those targets

For details on viewing results, see "Where Do Results Go?" below

When the task ends

When “Maximum Executions” is reached → the status shows “Completed” or “Paused”; the schedule stops triggering and no longer counts toward the schedule quota

When a one-time execution finishes → the schedule remains in the list but no longer triggers

Schedule Quota

Each organization has a limit on the number of simultaneously “Active” schedules. To the left of Add Schedule, the list toolbar shows Schedule Quota: N in use
Limit N, N more available. This updates immediately after adding, deleting, pausing, enabling, or manually running a schedule. Only “Active” schedules count toward the quota. “Paused” and “Completed” schedules (those that have reached their maximum executions, with the tooltip “Does not count toward the schedule quota”) do not count. When the quota is full, Add Schedule and “Enable” for paused schedules are disabled, with the tooltip “Limit of N schedules reached. Delete or pause another schedule first.”

For example, a marketing team has schedules for weekly newsletters and daily competitor summaries. When they try to add a “Month-End Sales Summary”, Add Schedule is disabled. The quota shows “0 more available”, so they pause the “Singles' Day Campaign Daily Report” they no longer need. This immediately frees up one slot for the new schedule. Schedules that have reached their maximum executions do not need to be deleted and do not count toward the quota.

Where Do Results Go?

After a schedule runs, the Agent's response appears in the following locations. **The execution logs page is the main place to view history**—regardless of execution mode, each completed run leaves its full content here. Other locations depend on your delivery settings.

1. Execution Logs Page (Main Viewing Location)

Each execution creates a log entry. This is the most reliable way to view past results.

How to open it:

Agent Schedules list → Click 🕘 View Execution Logs in the schedule's row → Open the execution history page → Click 👁️ View Details on the right of an entry

You will see:

Execution status (Succeeded
Failed
Partially Succeeded)

Start and completion times

The full Agent response (retained here even if subsequent delivery fails)

Error messages if the execution fails

2. Specified Conversations (Added in Delivery Settings)

Results are sent to these conversations as Agent messages, just like the messages customers or colleagues see.

How to find them:

Customer Support Conversations → Open the conversation you added in delivery settings → The message appears at the latest position.

3. Webhook URLs (Added in Delivery Settings)

Results are sent to your external URL via HTTP POST, with a **JSON body**:

```
{
  "content": "The full response generated by the Agent"
}
```

Technical details:

Content-Type: `application/json`

Timeout: 30 seconds (the Webhook receiver must respond with 2xx within 30 seconds, otherwise delivery is considered failed)

Failures are recorded under “Error Message” in the execution log (the execution status becomes “Partially Succeeded”), but are not retried

What Does the “Save Results to Context” Toggle Do?

This toggle **only affects memory for the next execution in context mode**. It does not affect whether you can view results.

Setting	Effect on the Next Execution
On (default)	The previous prompt and Agent response are included as conversation history in the next execution, allowing the Agent to continue with the context
Off	Each execution still uses context mode, but no messages are retained, making it similar to independent mode

Regardless of the toggle, **the execution logs page retains the full response from each execution**—this setting does not affect your ability to view history.

Summary: Result Visibility

Execution Mode Setting	Execution Logs Page	Specified Conversations	Webhook	Agent Memory Across Executions
Context mode + Save Results to Context (default)	✅	✅ If configured	✅ If configured	✅ Retained
Context mode + Do not save results	✅	✅ If configured	✅ If configured	❌ No memory
Independent mode	✅	✅ If configured	✅ If configured	❌ No memory

> Why is there no entry point for a “dedicated conversation”? Context mode creates a dedicated backend conversation to accumulate memory, but this conversation currently does not appear in the Customer Support Conversations list. It is an internal system container, not a conversation for human support agents to handle. View historical results in Execution Logs.

Complete Example: Daily Customer Support Summary

This end-to-end example shows how to create a schedule that automatically summarizes the previous day's customer support issues at 9:00 AM every day and sends the results to Slack.

Scenario

Before work each morning, you want the Agent to summarize all unresolved complaints from yesterday and send the summary to the team's Slack #customer-support channel, so the support manager sees it as soon as they open Slack.

Preparation

An Agent whose response mode is Agent mode, with tools attached for querying complaint data (such as a database tool or customer support system API tool)

A connected conversation platform (used as the execution container)

A Slack incoming webhook URL (to receive results)

Configuration

Basic Information:

Field	Value
Agent	`Customer Support AI Manager`
Name	`Daily Complaint Summary - 9:00`
Execution Mode	Independent mode (each day's summary is independent, with no need to remember the previous day)
Conversation Platform	`Internal Customer Support`

Prompt:

```
Find all customer complaints from the past 24 hours (ending at midnight today)
with a status of “Unresolved” or “In Progress”,
sort them by priority (High → Medium → Low), and create a summary:

## Format
### 🔴 High Priority (X cases)
- [#Case number] Customer name — One-sentence description

### 🟡 Medium Priority (X cases)
...

### 🟢 Low Priority (X cases)
...

End with a one-line summary: “X cases pending in total, including X high-priority
cases that need attention today”.
```

Schedule Settings:

Schedule type: `Cron`

Cron expression: `0 9 * * 1-5` (9:00 AM, Monday through Friday)

Time zone: `Asia/Taipei`

Enabled: On

Maximum executions: Leave blank (run continuously)

Delivery Settings:

Conversations: Do not add extra conversations (the execution logs page already retains the full Agent output, so there is no need to take up space in customer support conversations)

Webhook URL: https://hooks.slack.com/services/T00000000/B00000000/XXXXXXXX

After Saving

Monday at 9:00 AM (first trigger): The schedule triggers automatically, and the Agent starts querying and summarizing

Within about 30 seconds (depending on the Agent's processing speed):

The team's Slack #customer-support channel receives the summary via Webhook (the POST body is `{"content": "…"}`)

"Last Execution" in the schedule list updates to `2026-04-20 09:00:12`

Want to review what the Agent generated? There are two places:

Execution logs page (main entry point): Agent Schedules → Click the schedule's 🕘 → Click 👁️ → View the full bot response and token usage

Slack: Go directly to the #customer-support channel (your configured Webhook receiver)

Tuesday, Wednesday⋯ execution continues: Triggers automatically at 9:00 AM every workday without further manual intervention

How to Troubleshoot Problems

No message in Slack → First check the execution status on the execution logs page. If it is "Failed", read the error message. If it is "Succeeded" but Slack received nothing, check the Webhook URL and whether Slack has a rate limit

The summary is not what you expected → View the Agent's actual output in the execution details, then adjust the prompt

The schedule did not trigger → See "FAQ" below

Manage Existing Schedules

Back in the schedule list, the actions on the right of each row provide these functions:

Icon	Function	Description
✏️	**Edit**	Modify the schedule (except AI Assistant, Execution Mode, and Conversation Platform)
🕘	**View Execution Logs**	Open the schedule's execution history page
▶️	**Run Now**	Trigger an execution immediately without waiting for the scheduled time
⏸️ ☒	**Pause** **Enable**	Toggle the schedule's enabled status; enabling is unavailable when the organization's schedule quota is full
🗑️	**Delete**	Delete the schedule. Its execution logs are also removed

Run Now

“Run Now” is the fastest way to test whether a schedule is configured correctly. After clicking it:

The system immediately triggers one execution without affecting the original schedule times

A “Schedule triggered” notification appears


Open “View Execution Logs” to check the results

Pause and Enable

Pausing stops the schedule from triggering while retaining its settings and execution logs. You can enable it again at any time.

View Execution Logs

Click 🕘 in the list to open the execution logs page:



Execution logs page: filter by status and date range, and view the results of each execution

Filters

Status: Pending
Running
Succeeded
Failed

Date Range: Specify a start and end date

Field Descriptions

Field	Description
Status	Pending (queued), Running, Succeeded, Failed
Start Time	When the Agent started execution
Completion Time	When execution ended
Error Message	The reason for failure, if execution failed
Bot Response	The response generated by the Agent (view the full content in the details)

View Execution Details

Click 👁 on the right of each row to open the details dialog, where you can view execution status, start and completion times, the full bot response, and error messages.

FAQ

- ▶ Why did the schedule not trigger?
- ▶ Why can I not select my Agent?
- ▶ Where can I see what the Agent generated after a schedule runs?
- ▶ After enabling “Save Results to Context”, where can I view that conversation?
- ▶ What data format does a Webhook receive?
- ▶ What exactly is the difference between independent mode and context mode?

Further Reading

Agent Scheduling — An introduction to agent scheduling

Agent (AI Assistant) — Create an Agent with its response mode set to Agent mode

Connect a Conversation Platform: Website — Set up a conversation platform (using a website as an example)

Code Interpreter (Code Execution)

What is it?

Code Interpreter lets an Agent run code in a **secure sandbox environment** to complete tasks programmatically.

With Code Interpreter enabled, an Agent can do more than answer in text: it can write programs to perform calculations, process files you upload, generate Word/PowerPoint/Excel files, and let you download the results.

How does it differ from tools?

	Tools	Code Interpreter
How it works	Calls predefined external APIs	Writes and runs programs on demand in a sandbox
Flexibility	Limited to the capabilities the API provides	Can do anything Python can do
Typical use cases	Sending email, querying a CRM, integrating third-party services	Calculations, data processing, file generation, charting

Quick guide: calling an external API → tools; calculating, processing files, or generating documents → Code Interpreter.

What can it do?

Data analysis and calculations: CSV/Excel calculations, statistics, pivot tables, data cleaning

Charting: create line, bar, pie, and other charts from data, with proper display of Chinese text

Document generation: create Word, PowerPoint, Excel, and PDF files for download

File processing: parse PDFs, convert formats, recognize text in images, and batch-process uploaded files

Sandbox environment

Runs in a **secure sandbox**, isolated from the production system, without affecting other data

Each conversation has its own workspace; files are not shared across conversations

Attachments you upload in a conversation (including those from earlier turns) are automatically placed in the workspace for the Agent to read directly; the Agent can also copy files from the knowledge base into the workspace for processing

Sandbox specifications and limits

The table below lists system defaults. Your system administrator may adjust them.

Item	Default	When exceeded
Execution time per command	30 seconds	The command is terminated; the Agent receives a timeout result and can try another approach
Memory	512 MB	The program may fail due to insufficient memory
CPU	1 core	—
Workspace storage per conversation	100 MB	Once the workspace exceeds the limit, subsequent operations report insufficient storage
Single file read or written directly by the Agent using file tools	10 MB	That read or write fails; processing the file with code is not subject to this limit
Text output per command	1 MB	Output beyond the limit is truncated

Preinstalled packages

The sandbox provides Python 3 (with pip), bash, Node.js, and npm. The following packages are available without installation:

Purpose	Packages and tools
Data analysis	numpy, pandas, scipy, sympy, scikit-learn, statsmodels
Charts	matplotlib (configured with Chinese fonts), seaborn
Office documents	openpyxl, xlsxwriter, python-docx, python-pptx, markitdown; docx and pptxgenjs for Node.js
PDF	reportlab, fpdf2, pypdf, pdfplumber, PyMuPDF, pdf2image, qpdf, poppler
Images and text recognition	Pillow, cairosvg, pytesseract (Tesseract supports Traditional Chinese, Simplified Chinese, English, Japanese, and Korean)
Web data	requests, beautifulsoup4, lxml
Document conversion	LibreOffice, pandoc

Can I install packages or access the internet?

Installing packages: you can install additional packages with `pip install`, but they are available only for **that execution** and must be reinstalled for the next execution. The Agent installs and uses them within the same execution.

Internet access: the sandbox can access external websites over HTTP/HTTPS, for example to download public data or call public APIs. For a persistent integration with an external system, use tools.

What persists within a conversation?

Persists	Does not persist
Files in the workspace (including temporary files in `/tmp`), available for later turns in the conversation	Variables and program state in memory; each execution starts a fresh program
Generated files available for download	Packages temporarily installed with `pip install`

On-premises deployment

For on-premises deployments, sandbox specifications and internet access depend on deployment settings and data center network policies, and may differ from the table above. Contact your system administrator for details.

Output files: location, retention, and downloads

Location: files the Agent provides are placed in the workspace's `/workspace/outputs/` folder and saved with the conversation.

Retention: output files are saved with the conversation; once the conversation is deleted, they can no longer be downloaded.

How to download:

When the Agent selects files to deliver, a “N files generated” card appears below the response. Click Download.

The Output panel in MaiGPT and the admin conversation page lists all outputs from the conversation for download or preview.

Web Chat opens an Output files panel on the right. Click Download.

For API integrations, use the Conversation Outputs API in the technical manual to retrieve the list.

> The Output panel lists all files in the outputs folder, including different versions left during the Agent's edits. If you only need the final version, ask the Agent to overwrite a fixed filename in your prompt, or ask it to delete older versions when finished.

Using skills

Files uploaded to skills (templates, scripts, reference materials, etc.) require Code Interpreter. When an Agent has both a skill assigned and Code Interpreter enabled, running the skill places its files in the sandbox's `/workspace/skills/<技能名稱>` directory for the Agent to read or execute directly.

Without Code Interpreter, the Agent can still read the skill's instructions, but cannot use its files. For how to upload skill files, see Skill Management.

Suitable scenarios

Internal finance/sales teams ask an Agent to organize Excel data and generate weekly reports

HR/administrative teams ask an Agent to chart survey results and generate PowerPoint presentations

Legal/contract teams ask an Agent to extract key fields from PDFs and produce Word summaries

Any conversation that requires on-demand calculations or file generation

What do I need to do?

You need AI Assistant permissions and edit access to the Agent.

Open Agent settings: from the left menu, go to AI Features → AI Assistants and open the Agent you want to configure

Switch to Agent mode: under Response Mode Settings, select Agent Mode for Response Mode

Enable Code Interpreter: turn on the Code Interpreter switch and save

Test: ask the Agent to perform a task that requires calculations or file generation, and confirm that you can download the result from the response or Output panel

For use in MaiGPT, the member's role must also allow Code Interpreter. See MaiGPT Role Permissions.

Billing

Each successful sandbox action by an Agent (running a command, writing or reading a file, searching workspace files, etc.) deducts Credits once under the "Code Interpreter" billing item. Failed actions are not charged. This charge is separate from model usage for the AI response itself. For rates, see Credits Billing.

FAQ

Why are there several files in the Output panel when I asked for one?

When correcting or redoing work, the Agent often saves a new filename (such as `report_v2.docx`), leaving older versions in the `outputs` folder. Use the latest file, or ask it to keep only the final version in your prompt.

Why is there no download link in the response?

Files do not always appear in the response text. Check the "N files generated" card below the response, or open the Output panel (Output files in Web Chat).

Why does the download show "The file has expired. Please regenerate it before downloading"?

The file no longer exists, for example because a later execution deleted or renamed it. Ask the Agent to regenerate it.

Why does processing a large file or a long computation fail?

The task may exceed the sandbox specifications and limits. Ask the Agent to process it in batches, filter the required columns first, or split the data into smaller files before uploading.

Browser Tool (Browser Operations)

What is it?

Browser Tool lets an Agent **control a browser**: navigate to web pages, click buttons, fill out forms, and scroll on its own. It uses screenshots to "see" the current page and decide what to do next.

The industry also commonly calls this capability **Browser Use** or **Computer Use**. Common Chinese terms refer to browser tools, browser operations, browser automation, and web automation. MaiAgent's Browser Tool is built into the Agent. Once enabled, it can be used directly in conversations without connecting an external service.

What can it do?

Navigation and exploration: Open a specified URL and follow links from page to page

Interact with page elements: Click, double-click, enter text, press keys, and scroll

Visual understanding: Capture a screenshot after each action so the Agent can decide its next step based on what it sees

Multistep tasks: Complete sequences such as login → search → filter → retrieve information

How does it differ from tools and Code Interpreter?

	Tools (API MCP)	**Code Interpreter**	**Browser Tool**
What it operates on	Backend services APIs	A programming environment in a sandbox	A real browser and web pages
Can it see the screen?	No (JSON responses only)	It can see sandbox output	**Yes** (screenshots)
Suitable tasks	Structured data queries and predefined API calls	Calculations, file processing, and document generation	Services with web pages but no APIs

Quick guide: The service has an API → tools; you need calculations or file generation → Code Interpreter; only a web page is available to interact with → Browser Tool.

When to use it

Internal systems without public APIs that provide a Web UI

Retrieving information from third-party websites that require login or interaction

Automating web workflows across pages and steps (searching, filtering, downloading)

Anything a person would do in a browser that you want an Agent to complete automatically

Things to keep in mind

Optimized for Claude models: Browser Tool relies on the model's ability to interpret screenshots. Claude models perform best; other models may produce inconsistent results.

Works best with same-origin pages: Some operations may be restricted on pages with cross-origin iframes or strict CSP policies.

Execution takes time: Each step requires page loading, a screenshot, and reasoning. Tasks with multiple consecutive steps take longer than a single API call, so design realistic workflows.

What do I need to do?

A customer service supervisor wants to check whether an Agent can read public web pages. She enables Browser Tool in the test Agent's “Reply Mode Settings,” saves the settings, and asks the Agent to open a public URL in Web Chat. When the Agent performs browser operations, a browser panel appears beside the conversation, displaying the current URL and page view.

1. Open Reply Mode Settings

Go to AI Features → AI Assistants, open the Agent you want to configure, and click Reply Mode Settings. The Browser Tool toggle appears only when you use Agent Mode.

2. Enable and save

Enable Browser Tool. Select a recommended Claude model in Basic Settings, then click Save.



Enable Browser Tool in Reply Mode Settings

3. Test a public web page


Open a conversation with this Agent and ask it to “Use the browser tool to open https://example.com”. Confirm that browser operations appear in the conversation and that the panel shows the current URL and web page view.

The browser panel in conversations

When the Agent starts interacting with a web page, both Web Chat and the admin conversation page open a Browser panel beside the reply. It displays the screenshots the Agent sees and the current URL in real time, with AI operating shown while the Agent is taking action.

Users can intervene directly when the Agent pauses: click or scroll on the screenshot, or enter text in the input box at the bottom of the panel and press Enter to send it to the web page. This lets users complete steps the Agent cannot handle, such as entering a verification code, their own login credentials, or a one-time verification code. The Agent then continues the task. After the panel is closed, Reopen browser view appears above the input box.

Use this capability when designing tasks: at login or verification steps, have the Agent pause and ask the user to enter the information in the panel. Do not put login credentials in prompts or the knowledge base. For details on visitor-side operations, see Web Chat: Browser Panel.



The browser panel in Web Chat displays the public web page the Agent is browsing

Voice Agent

What is it?

Voice Agents let Agents interact through **voice**: users speak, and AI speaks back. They integrate realtime voice models, STT (speech to text), TTS (text to speech), and interruption control for scenarios such as telephone customer service, IVR, and voice assistants.

Once enabled, a button for entering "Voice Interaction Mode" appears in the input bar in MaiGPT, the Agent Marketplace, and Web Chat. Click it to start speaking. See How users start a conversation.

Three interaction modes

Each mode suits different needs, depending on latency, voice customization, and tool support.

Mode	How it works	Suitable scenarios
Realtime	Uses a voice model directly for realtime voice conversations	Scenarios that require the lowest latency and can use preset voices
Realtime + TTS	Combines a realtime voice model with custom TTS output	Scenarios that need a custom brand voice while retaining realtime responsiveness
STT + LLM + TTS	A traditional pipeline: speech to text → LLM → text to speech	Scenarios that need full tool support and maximum flexibility and can accept slightly higher latency

Quick guide: For the fastest, most natural interaction → Realtime; for a brand voice → Realtime + TTS; for maximum flexibility and tool support → STT + LLM + TTS.

Configuring Voice Agent settings

Voice Agent Settings appears after the role instructions section on the Response Mode Settings tab of the Agent settings page (only when AI Voice Agent is activated for your organization). At the top is the "Enable Voice Agent" master switch. Turning it off collapses all settings and disables this Agent's voice service through the voice entry points in Web Chat, telephone calls, and the admin console. Once enabled, complete the following three sections in order. When collapsed, each section shows a summary of its current settings on the right.

1. Voice technology

First, click a mode card under "Voice Agent Mode" (click again to deselect), then choose providers and enter the configuration for that mode:

Mode	Providers to select	Configuration fields
Realtime	Realtime Voice Provider	Realtime Voice Configuration
Realtime + TTS	Realtime Voice Provider, Text to Speech (TTS) Provider	Realtime Voice Configuration, TTS Configuration
STT + LLM + TTS	Speech to Text (STT) Provider, Text to Speech (TTS) Provider	STT Configuration, TTS Configuration

Each provider field has two configuration fields side by side below it: the read-only "Configuration Example" on the left and the JSON configuration that actually takes effect on the right.

Currently supported providers: STT supports OpenAI, Azure, and Bronci (Taiwanese Hokkien/Mandarin/Hakka); TTS supports OpenAI, Azure, VoAI, and Bronci; realtime voice supports OpenAI Realtime and Google Gemini Live. The list shows only providers activated for your organization. If it is empty, "No providers available" appears. Contact MaiAgent to activate a provider.

Selecting a provider automatically fills the right-hand field with its example configuration. You can usually save it directly; edit the JSON to change the voice, language, transcription model, or other settings. The "Configuration Reference" table below the example lists each parameter's type, default, allowed values, and description. Refer to it when configuring settings such as User transcript settings.

The configuration must be valid JSON. Otherwise, the field displays "Invalid configuration format. Enter valid JSON," and saving expands the corresponding section so you can correct it. If the configuration is empty, a reminder appears before saving: "Configuration is empty. The default configuration will be applied after saving." Confirm to save with the default configuration.

Choosing a realtime voice model

Options in "Realtime Voice Provider" appear as "Model name (Provider)," such as `gemini-3.8-live (Google Gemini Live)` and `gpt-realtime-2.1 (OpenAI Realtime)`. Google Gemini Live currently offers two models:

Model	Description
`gemini-3.8-live`	Listed first in the menu, this is the successor to `gemini-live-2.5-flash-native-audio`. Like 2.5, it supports only "Realtime" mode and requires "Enable Voice Responses" to be on. See the warning below
`gemini-live-2.5-flash-native-audio`	The existing model. Agents already using it can continue making calls as usual. Google has announced its retirement (scheduled for December 13, 2026 on Vertex AI). Agents using it currently do not switch to 3.8 automatically; switch manually before retirement



Realtime Voice Provider menu: gemini-3.8-live appears first; 2.5 remains available

For example, a customer service manager's telephone support Agent has been answering calls with `gemini-live-2.5-flash-native-audio` and needs to switch to 3.8 before 2.5 is retired:

On the Agent settings page, go to Response Mode Settings → Voice Agent Settings and expand "Voice Technology." Confirm that "Voice Agent Mode" is set to "Realtime."

Under "Realtime Voice Provider," select `gemini-3.8-live (Google Gemini Live)`. The "Realtime Voice Configuration" field on the right changes to the 3.8 example configuration. Re-enter any parameters you customized, such as `voice`.

Click Save at the bottom right, then open Voice Interaction Mode and try speaking. Confirm that you can hear responses and that text appears for both sides in the conversation history.

Before switching, the manager can also compare the costs of the two models. Realtime voice calls consume Credits based on audio and text input and output usage for the selected model. Rates differ between 3.8 and 2.5. Go to Organization Settings → Credits → Billing Methods, expand "Speech Recognition and Synthesis Technology," then expand items such as "Realtime Voice Output (Text)" to see each model's rates. See Credits billing system.



Expand Realtime Voice Output (Text) to view the separate rates for 3.8 and 2.5

gemini-3.8-live thinks before answering. This thinking usage is included in "Realtime Voice Output (Text)" and consumes Credits at the 3.8 text output rate. gemini-live-2.5-flash-native-audio has no thinking usage, and its billing remains unchanged. Include this additional usage when estimating the cost of switching to 3.8.

Both Gemini Live models can respond only with audio: gemini-3.8-live and gemini-live-2.5-flash-native-audio output audio only, not text. They therefore support only Realtime mode and require "Enable Voice Responses" to be on. The following configurations require the voice model to output text. Gemini Live will reject the connection, and the Agent will not respond during calls: Setting Voice Agent Mode to "Realtime + TTS" (the voice model outputs text, which TTS then converts to speech). Turning off "Enable Voice Responses" under Conversation behavior (text-only responses). Enabling AI Copilot on the conversation platform used for the call with the trigger mode set to "Every Received Message" (a customer service representative decides what to send, instead of responses playing directly). Saving does not block these combinations, so check them before configuring. If you need any of these configurations, select an OpenAI Realtime model for realtime voice or use "STT + LLM + TTS" mode. The discontinued OpenAI gpt-realtime model no longer appears in the menu. Agents already using it can continue calls and billing as usual, but once you select another model and save, you cannot select it again.

2. Realtime voice prompt

The "Realtime Voice Prompt" is a prompt used only by the voice model. Leave it empty to use the role instructions. The message above the field explains what currently takes effect based on the combination of voice mode, response mode, and whether the field is filled in:

On-screen message	When it appears	Meaning
This mode does not support voice prompts	STT + LLM + TTS	This mode always uses the role instructions, and the field cannot be edited. Use Realtime or Realtime + TTS for a voice-specific prompt
Currently active: using role instructions	Realtime modes × RAG Q&A × empty	The voice model responds directly using the role instructions
Currently active: this prompt replaces the role instructions	Realtime modes × RAG Q&A × filled in	In RAG Q&A, the knowledge base returns only retrieved passages. The voice model generates answers based on this prompt; **the role instructions have no effect at all**
Currently active: the voice layer uses role instructions	Realtime modes × other response modes such as Agent × empty	Voice delegates questions to the text response workflow; the role instructions and tools still determine answers

On-screen message	When it appears	Meaning
Currently active: affects only the voice interaction layer	Realtime modes × other response modes such as Agent × filled in	Answer content stays the same. This prompt adjusts only how the voice model speaks (tone, style, pauses)

To make adjustments based on the role instructions in RAG Q&A mode, click "Use Role Instructions as a Starting Point" to copy them into the field, then edit. If the field already contains text, you will first be asked to confirm "Overwrite Voice Prompt."

3. Conversation behavior

"Enable Voice Responses": Turn this off for text-only responses without audio playback, suitable when you only want voice input.

"Interruption Control Settings": Allows users to interrupt the Voice Agent while it is responding. Once enabled, you can adjust Minimum Speech Duration (Seconds) and Minimum Word Count. These two fields take effect only in STT + LLM + TTS mode; other modes display a reminder and disable the fields. See Interruption control.

The "Usage Notes" at the bottom of the section remind you that Voice Agents search all linked knowledge bases; you cannot select specific files to search. When finished, click Save at the bottom right.

Interruption control (Turn Handling)

A key part of the voice conversation experience is whether users can interrupt AI while it is speaking, and how to distinguish actual speech from noise or filler sounds.

Adjustable parameters:

Parameter	Description
Minimum Speech Duration (Seconds)	How many seconds the user must speak before it counts as an interruption attempt
Minimum Word Count	How many words the user must say to trigger an interruption

Note: `min_duration` and `min_words` take effect only in **STT + LLM + TTS** mode. In Realtime mode, the voice model handles interruption detection internally.

User transcript settings (Realtime mode)

In Realtime and Realtime + TTS modes, the voice model listens directly to the user's audio. A separate transcription model generates the text record of what the user said (the user transcript). When Realtime Voice Provider is set to OpenAI, use `input_audio_transcription` in the Realtime Voice Configuration JSON to specify transcription settings:

```
{
  "input_audio_transcription": {
    "model": "gpt-4o-mini-transcribe",
    "language": "zh",
    "prompt": "Output in Traditional Chinese. Common terms: MaiAgent, insurance policy, claims"
  }
}
```

Field	Description
`model`	Transcription model: `gpt-4o-transcribe`, `gpt-4o-mini-transcribe`, `gpt-transcribe`, or `gpt-live-transcribe`. Defaults to `gpt-4o-mini-transcribe` when omitted
`language`	Language hint using an ISO-639-1 code (such as `zh`, `en`, or `ja`). Leave empty for automatic detection
`prompt`	A hint for the transcription model, such as expected terminology or instructions to output in Traditional Chinese

The settings page lists each field's type, default, and allowed values below the configuration field for reference.

Affects only the transcript: These settings determine the text on the user's side of the call record. They do not change what the voice model hears or how it responds.

Multilingual calls: If users mix languages, leave `language` empty for automatic detection. For a single language, enter its code for more stable recognition.

Billing: User transcripts consume Credits based on speech-to-text duration in seconds for the transcription model actually used. To see each model's rate, go to Organization Settings → Credits → Billing Methods. See Credits billing system.

Conversation states

During a voice conversation, the interface shows the current state:

Listening: AI is receiving the user's speech

Thinking: AI is processing (searching knowledge bases, using tools, generating a response)

Responding: AI is replying with audio

Initializing: The connection has just been established and is being prepared

How users start a conversation

Once Voice Agent is enabled for an Agent, users need no setup. They can switch to voice from the existing text conversation screen:

Where the user is	Entry point
Conversation page in MaiGPT or the Agent Marketplace in the admin console	A Voice Interaction Mode button appears on the right of the input bar. AI Voice Agent must be activated for the organization, and Voice Agent must be enabled for the current Agent
Web Chat on a website	The headphones icon next to the input box (different from the microphone icon for Voice input: the microphone converts one spoken utterance to text and sends it; headphones start a realtime call)
Standalone voice conversation page	A Voice Mode link appears next to the conversation platform's Public Access URL (see Basic settings). It opens a page dedicated to calls: click Start Conversation, and "Dialing" appears before the call connects

Voice Interaction Mode window

After you click the button, the browser asks for microphone permission (on first use). The button shows "Connecting...," then opens the Voice Interaction Mode window:

Section	Description
Usage Notes	Reminds you that Realtime and Realtime + TTS support only MCP tools and that Voice Agents search all linked knowledge bases (see Limitations)
Connection Status	Not connected → Connecting... → Connected; displays "Connection failed" on failure
Current state	Initializing Listening Thinking Responding. See Conversation states. Displays "Subagent responding⋯" when the Agent delegates to another Agent
Conversation History	A live text record of this call. Displays "Waiting for conversation to start..." before connection

Section	Description
Mute Microphone Unmute Microphone	Temporarily mute or unmute the microphone. A “Recording” indicator appears while recording
End Call	Disconnects and closes the window. The call content remains as text in the original conversation, so you can continue by typing

Common messages

On-screen text	What to do
“Microphone permission denied” “Please allow microphone access to use voice features”	Allow microphone access in the site permissions on the left of the browser address bar, then try again
“No microphone device found”	Check that a microphone or headset is connected and selected in your system's sound settings
“Assistant connection timed out. Please try again later”	The voice service did not connect. Wait a few seconds and try again. If this persists, ask your administrator to check the Agent's voice provider settings
“Unable to start Voice Interaction Mode”	The system temporarily cannot establish a voice connection. Try again later. If this persists, contact your administrator

How does it differ from regular text conversations?

	Text Agent	Voice Agent
Input	Typing, attaching files	Microphone audio, possibly DTMF key presses
Output	Text, Markdown, images, files	Audio, followed by a text transcript
Latency requirements	Delays of seconds are acceptable	Millisecond-level latency is needed for a natural experience
Suitable scenarios	Detailed information and records to review later	Immediate responses, hands-free use, telephone customer service

Suitable scenarios

Telephone customer service: Replace traditional IVR with AI that answers calls, listens to questions, and provides answers

Voice inquiry systems: Customers call to check orders, balances, or insurance policies

Voice FAQ: Ask frequently asked questions directly by speaking

Driving
hands-free scenarios: Users cannot type but need AI assistance

Accessibility needs: More accessible for users who find typing difficult

Limitations

Tool support: **Realtime** and **Realtime + TTS** currently support only **MCP tools**. Use STT + LLM + TTS for API tools

Knowledge base search: Voice Agents search all linked knowledge bases; **you cannot restrict searches to specific documents**

Gemini Live models: `gemini-3.8-live` and `gemini-live-2.5-flash-native-audio` support only **Realtime** mode and require "Enable Voice Responses" to be on. Calls cannot respond normally with Realtime + TTS, voice responses turned off (text-only responses), or an AI Copilot conversation platform triggered by "Every Received Message." See Choosing a realtime voice model

Microphone permission: Users must grant the browser microphone access before starting a conversation

What do I need to do?

Open Agent settings — On the settings page of the Agent you want to enable voice for, switch to Response Mode Settings, find Voice Agent Settings, and turn on Enable Voice Agent. This section appears only when AI Voice Agent is activated for the organization

Choose a Voice Agent mode — Select Realtime
Realtime + TTS
STT + LLM + TTS

Select providers and configure them — Choose the STT
TTS
Realtime providers for the mode. Selecting a provider automatically fills in an example configuration. See Voice technology

Set the voice prompt (optional) — Leave empty to use the role instructions, or fill it in according to the table under Realtime voice prompt

Adjust conversation behavior (optional) — Choose whether to play voice responses and allow interruptions. STT + LLM + TTS also supports minimum duration and word count settings

Test — Start a voice call in the interface and confirm that connection, listening, and responses all work smoothly

Further reading

Voice customer service: from setup to launch

Telephone customer service (Call Center)

Voice customer service scenarios overview

IVR customer intent recognition

Voice call summaries

Voice call quality evaluation

Agent Usage Analytics

How to View

From the left menu, go to AI Features → AI Assistant, click the Agent you want to view to open its settings page, then switch to the Usage Analytics tab at the top. This page has two sub-tabs:

Sub-tab	Content	Who can see it
Monitoring Metrics	The same metrics and charts as the AgentOps AI Assistant Monitoring dashboard (conversation count, response time, error rate, streaming performance, answer quality scores, etc.), but fixed to this one Agent. For chart descriptions, see Dashboard Charts	Members whose role has the AI Assistant Monitoring permission; without the permission, only usage statistics are shown
Usage Statistics	This Agent's conversation volume and token usage (described below on this page)	Members who can see this Agent

The Usage Statistics charts include:

Token Usage: One line for each LLM model used by this Agent, plus a Total Token Usage line, showing actual LLM consumption. You can compare it with the Credits Billing System to estimate costs

Conversation Word Count: Likewise one line for each LLM model, plus a Total Conversation Word Count line

Conversation count


Message count

Average messages per conversation

User satisfaction

Above the charts, you can select a time range (Today, Yesterday, This Week, Last Week, This Month, Last Month, Last 7 Days, Last 30 Days, This Quarter, Last Quarter, This Year, Last Year, or a custom range) and switch the granularity to Hour, Day, or Month.

These metrics let you understand how the Agent is used from multiple perspectives.



Token Usage and Conversation Word Count charts: one line per model, plus a total line

View Token Usage by Model

Each model line in the Token Usage chart is that model's total tokens (input, output, and Prompt Cache combined); Total Token Usage is the sum of all models. The chart does not show a legend. Hover over any date on the chart to list the values for each model (formatted as "Model Name | Provider") and the total for that day.

> If a model has tokens but no word count within the selected range (for example, a model used to parse images or files), it appears only in the Token Usage chart and is not drawn as a zero line in the Conversation Word Count chart, and vice versa. The total line is always displayed; when there is no usage, it is a line along 0. When the granularity is set to Hour, the Token Usage and Conversation Word Count charts are not shown. Switch to Day or Month.

Scenario example: A customer service manager wants to know how many tokens each model used after the "Order Inquiry Assistant" was switched to another model for testing. She goes to this Agent's Usage Analytics → Usage Statistics, selects Last 7 Days as the time range and Day as the granularity, and hovers over the test day on the Token Usage chart. She sees each of the two models' token counts and the Total Token Usage, without needing to filter on the organization's usage statistics page.

Detailed Metric Descriptions

1. Word Count (Words Count)

Calculation Method:
- **Text word count**: Counts the number of characters in message content

- **Image cost**: Each image is calculated based on the configured image word cost
- **Total word count** = Message content word count + (Number of images × Image word cost)

Scope: Includes both user input messages and Agent reply messages. Supports daily and monthly granularity.

---

2. Conversation Count (Conversations Count)

Calculation Method:
- Each time a new conversation is created, the counter increments by 1
- When the first message in a conversation is created, it triggers a conversation statistics update

Update Trigger: When a user starts a new conversation (first message)

> "Conversation Count" is defined differently from "Conversations" on the AgentOps "AI Assistant Monitoring" dashboard: here, each conversation counts once; the dashboard's "Conversations" counts the number of Agent responses, so a conversation with several rounds of replies counts several times. See Automated Evaluation and Agent Monitoring for details.

Scope: Supports hourly, daily, and monthly granularity.

---

3. Message Count (Messages Count)

Calculation Method:
- Each time a new message is created, the counter increments by 1
- Includes both user input messages and Agent reply messages

Update Trigger: Each message creation triggers a statistics update

Scope: Supports hourly, daily, and monthly granularity.

---

4. Average Messages per Conversation (Average Messages per Conversation)

Formula:

```
Average messages per conversation = Message count ÷ Conversation count (shows 0 if the conversation count is 0)
```

Meaning:
- Indicates the average number of messages in each conversation

- Reflects the depth of interaction between users and the Agent
- A higher value indicates deeper conversations and more frequent interaction

Scope: Supports hourly, daily, and monthly granularity.

---

5. User Satisfaction Rate (User Satisfaction Rate)

Formula:

```
User satisfaction = Number of likes ÷ Total feedback count (shows 0 if the total feedback count is 0)
Total feedback count = Number of likes + Number of dislikes
```

Meaning:
- Indicates the proportion of positive feedback (like rate)
- Value range: 0% to 100%
- A higher value indicates greater user satisfaction with the Agent's replies

Feedback Mechanism:
- Users can give a "like" or "dislike" to the Agent's replies
- Statistics are updated in real time

Update Trigger: When a user gives feedback (create, update, delete)


How likes/dislikes are counted:
- Each reply counts as feedback at most once: changing a like to a dislike decreases the like count by 1 and increases the dislike count by 1; canceling feedback removes it from the statistics
- Feedback is counted in the time period when the rated reply was created, not when the like was given. For example, if a visitor likes the previous day's reply the next day, the like is added to the previous day
- **Feedback on the Web Chat greeting is not counted**: The greeting is fixed text, not an AI answer, and on Web Chat the greeting has only a Copy button, with no like/dislike. If you integrate through the API yourself, or an older embedded version still submits feedback on the greeting, the feedback is saved on that message but is not counted in the like count, dislike count, or user satisfaction

> Why does satisfaction show a number, but I can't find that like in the conversation records? In the past, likes/dislikes on the greeting were counted in satisfaction: a visitor opened Web Chat, liked the greeting, and left, so satisfaction showed 100% while the conversation records contained no Q&A. Feedback on the greeting is no longer counted, so satisfaction now reflects only visitors' ratings of actual replies.



The greeting has only a Copy button; only Agent answers have Like/Dislike

Scenario example: A customer service manager notices that the "Order Inquiry Assistant" had 100% satisfaction one day and wants to confirm whether that number came only from visitors' feedback on the greeting. She opens this Agent's Web Chat and sees that below the greeting there is only Copy, and Like/Dislike appear only below the Agent's answers. She then returns to the admin console's Usage Analytics → Usage Statistics, selects Day as the granularity, and hovers over that day on the User Satisfaction chart. The ratio she sees is calculated only from visitors' likes/dislikes on the Agent's answers; feedback on the greeting is not included.



User Satisfaction chart: hovering over a day shows that day's like ratio

Scope: Supports hourly, daily, and monthly granularity.

Statistics Update Mechanism

Real-time updates: When a relevant event occurs (new message, new conversation, feedback change), a statistics update is triggered immediately

Supported time granularities:
- **Hourly**: Suitable for real-time monitoring
- **Daily**: Suitable for daily report analysis
- **Monthly**: Suitable for monthly reports and trend analysis

Can I Export Reports or Have Them Sent Regularly?

The Usage Analytics charts can only be viewed on screen; there is no export button and no setting for scheduled report delivery. When you need to take data out of the platform, use the following pages, which have export features:

Data needed	Where to export
Usage and Credits by Agent, role, member, and chat platform	The tabs of Usage Statistics support Export Excel; see Usage Statistics
Tool call details	AgentOps tool execution records can be exported as CSV or Excel; see Tool Execution Records
AI Q&A records	Filter in AgentOps → AI Assistant Monitoring and export to Excel, or use the Q&A records API to sync periodically from internal systems; see Get Conversation Q&A Records

Use Case: Evaluating Usage Effectiveness

Observing trends in "User Satisfaction" and interaction counts lets you evaluate whether the Agent's response quality meets expectations, serving as a basis for optimization.

Knowledge Base



Knowledge base RAG workflow: from document upload to Agent retrieval and responses

What Is This?

A knowledge base is an Agent's encyclopedia of company knowledge. Add your company's documents, FAQs, and web content, and the Agent can use this information to answer users' questions.

Without a knowledge base, an Agent can only respond using the language model's general knowledge. With one, it can answer company-specific questions such as "What is our company's return policy?"

What Can You Put in a Knowledge Base?

Data Type	Description	Suitable Use Cases
Document Upload	PDF, Word, Excel, TXT, etc.	Product manuals, internal policies, contract templates
FAQ	Question-and-answer pairs	Frequently asked questions, standard responses
Crawler Import	Automatically fetch content from web pages	Company website information, public data

How Is It Different from a Database?

This is one of the most frequently asked questions:

	Knowledge Base	Database
Data Type	Unstructured (documents, articles, FAQs)	Structured (tables, fields, numbers)
Query Method	Semantic search ("What is the return policy?")	SQL queries ("What was last month's revenue?")
Best For	Knowledge questions, policies, operating instructions	Data queries, statistical analysis, real-time status

Quick guide: If the answer is in a "document," use a knowledge base. If it is in a "report," use a database.

Technical details: Knowledge bases use RAG (Retrieval-Augmented Generation). Uploaded documents are split into chunks and converted into vectors. When a user asks a question, the system finds the most relevant chunks and supplies them to the Agent as the basis for its response.

How Is It Different from a File Library?

A knowledge base is like a cheat sheet for an exam: it lets an Agent find answers quickly to respond to users, making it suitable for external customer service and FAQs. A file library is like having an entire textbook at hand while doing homework: the AI reads the full original file to write, summarize, or rewrite content. Conversation platforms such as web Widgets and LINE only use knowledge bases.

Quick guide: Use a knowledge base to "find answers" and a file library to "process entire files." See Knowledge Base vs. File Library: Differences and When to Use Each.

What Do I Need to Do?

Create a knowledge base — Name it and select an Embedding model

Import data — Upload documents, create FAQs, or fetch content with a crawler

Test search — Use sample questions to check whether the knowledge base finds the right answers

Attach it to an Agent — Link the knowledge base in the Agent's settings

Further Reading

Knowledge Base Overview

Knowledge Base vs. File Library: Differences and When to Use Each

How to Create a Knowledge Base: Basic Settings

How to Create FAQs

Document Management: Tags and Metadata

Search Tests

Knowledge Base Overview

What Is a Knowledge Base?

A knowledge base provides source material for an Agent to answer questions. The Agent first finds the chunks most relevant to a question, then uses them to answer. Upload only content relevant to the Agent's tasks. Unrelated material may be used as a reference and lead to inaccurate answers. For details on retrieval, see Technical Manual - RAG Knowledge Base Retrieval System.

> Knowledge base vs. file library: A knowledge base provides reference material for an Agent to find answers by first retrieving relevant chunks. The file library stores and processes everyday work files. MaiGPT reads entire files when needed and can edit them and retain versions. For guidance on choosing between them or using both, see Knowledge Base vs. File Library: Differences and When to Use Each.

What Can a Knowledge Base Do?

With the following knowledge base features, you can:

📋 Manage Documents with Tags

Add multiple tags to each document to build a systematic classification structure

Example: Add the tags `#Tent #Beginner #SetupGuide` to a "Tent Manual"

🔐 Grant Selective Document Access

Set different document access permissions based on user identity to provide differentiated services

Example: Make product price lists available only in conversations with VIP members, and cost data only in internal conversations

❓ Create FAQs

Organize frequently asked questions into standard Q&A pairs to ensure consistent, complete responses

Example: "How long is the tent warranty?" → Standard answer: "We provide a 3-year warranty"

📊 Supply Document Metadata

Add details such as version, update date, and scope to documents to simplify future maintenance

Example: Document version v2.1, updated 2024/11/28, applicable product "Mountain Series Tent"

🔍 Test Searches

Test retrieval results for different questions to verify that AI finds the correct chunks (the menu item on the left of the knowledge base settings page is called "AI Search"; see Search Testing)

Example: Enter "tent setup steps" → Check whether AI finds the correct setup guide chunks

Tabs on the Knowledge Base Settings Page

After clicking "Edit" in the knowledge base list to open its settings, the left menu contains these items in order:

Tab	What It Manages	Details
Basic	Name, description, Embedding/Reranker models, number of retrieved chunks, linked AI assistants, permissions, and more	How to Create a Knowledge Base: Basic Settings
Tag Management, Metadata Management	Available tags and metadata fields	Document Management: Tags and Metadata
Documents	Uploading, viewing, and editing documents, and batch operations	This page
FAQ	Q&A pairs	How to Create FAQs
AI Search	Testing retrieval results with questions, with optional AI summaries	Search Testing
API Integration	Instructions and examples for uploading documents and searching this knowledge base programmatically, prefilled with its ID, Embedding/Reranker models, and linked Agent	Developer Tools

How to Upload to a Knowledge Base

For example, a publisher's knowledge base administrator wants an Agent to look up content in product e-books. They upload EPUB e-books to the product knowledge base. Once processing finishes, the Agent can find information in the books to answer questions, just as it does with PDF or Word documents.

In the left sidebar, go to "AI Features" → "Knowledge Base"

Find the knowledge base you want to upload to and click "Edit" in the actions column (if you have not created one yet, first see How to Create a Knowledge Base: Basic Settings)

On the settings page, click "Documents" on the left

Click the blue "Upload Files" button in the upper right to upload the information you want the Agent to know



The Upload Files dialog lists EPUB and other supported file formats

> Knowledge base storage capacity varies by plan If your files are large or contain a lot of data, processing may take some time after upload.



Check parsing results in the Processing Status column of the document list

You can check progress in the "Processing Status" column.

Document List Columns and Processing Status

Above the list, enter keywords to search by name, ID, tags, or metadata (separate multiple keywords with spaces), and filter using "All Statuses" and "All File Types". Columns include ID, file name, file type, file size, chunk count, vector storage, processing status, wait time (time queued between upload and the start of processing), processing time, parser, creation time, source, tags, and metadata. Documents with a "Crawler" label in the Source column were imported by a crawler. Click the label to go directly to that crawl request (crawler permissions required).

Processing Status	Meaning	What You Can Do
Initializing	Uploaded and queued for processing	Wait; queues may be longer during bulk uploads
Processing	Parsing, chunking, and vectorization are in progress	Wait; click Refresh to update the status
Completed	The Agent can now retrieve this document	Click Edit to view chunks, tags, and metadata
Failed	Parsing or vectorization failed	Click the red exclamation mark next to the status to view the Failure Reason and Failure Time; click Reparse in the actions column to retry with the same parser, or select another in the Parser column (reparsing starts immediately after selection). You can also delete and reupload the file
Deleting	The document and vectors are being removed in the background	Wait; bulk deletion skips these documents
Deletion Failed	Removal did not finish	Try deleting again; contact MaiAgent if it continues to fail

> The knowledge base currently supports these file types: Spreadsheets: .xls, .xlsx, .csv, .ods Text documents: .doc, .docx, .odt, .pdf, .md, .txt Presentations: .ppt, .pptx, .odp Web pages: .html, .htm Data formats: .json, .jsonl E-books: .epub Email: .eml, .msg Audio: .wav, .mp3, .m4a, .aac Video: .mp4 Images: .gif, .jpeg, .jpg, .png, .tiff, .webp (only for knowledge bases using a multimodal Embedding model)

For the full list of extensions, see Technical Manual - Parser Tools.

Email Files (.msg, .eml) and Embedded Attachments

For example, a quality control specialist receives an inspection email from a supplier with a PDF report and a weekly spreadsheet (CSV) attached. Upload the `.msg` saved from Outlook (or an `.eml` exported from another email client) directly to the knowledge base. The Agent can then answer who sent the email and when, and look up content in the attached report, without first saving the email and each attachment separately as PDFs.

Upload email files the same way as other files. Email files can only be parsed with MaiAgent Parser, which is the only option shown in the upload dialog's parser menu.



Add email files from the Upload Files dialog just like other documents

What Is Read from the Email Itself

The email becomes a document containing the following, in order:

Email information: Subject, sender, recipients, CC, and sent date. Both display names and email addresses are retained for senders and recipients; BCC is not read.

Body: The plain text body is preferred. If the email is only in HTML format, it is converted to text before being read.

Attachment list: The names of files attached to the email.



The email itself becomes a searchable document, retaining email information and the attachment list

> Emails that are only digitally signed (S/MIME signed) are read normally. Encrypted emails cannot be opened without the recipient's private key and are marked as failed; an empty email is not added. For meeting invitations, only email information and the body are read. Meeting times and locations in invitation files (.ics) are not read. Outlook .pst files (archives of entire mailboxes) and .mbox are not supported. Save each required email separately as .msg or .eml in your email client before uploading.

Embedded Attachments Become Separate Documents

After processing the email, the system extracts its attachments one by one and creates separate documents in the same knowledge base. They are parsed and included in retrieval just like directly uploaded files:

File names: Original attachment names are retained and appear in the document list.

Parsers: The parser is automatically detected for each attachment. For example, a scanned PDF uses a parser capable of recognizing images, rather than inheriting the email's MaiAgent Parser.

One level only: An email attached to another email (an attachment that is itself a `.msg` or `.eml`) is not extracted further and does not appear in the attachment list.

Not every attachment becomes a document:

Attachment	Result
Document formats supported by the knowledge base (PDF, Word, Excel, PowerPoint, text files, etc.)	Created as separate documents
Images	Created only if the knowledge base uses a multimodal Embedding model; images that are both smaller than 50 KB and have a longest

Attachment	Result
	side shorter than 200 px are treated as signature logos or social icons and always skipped
Audio and video	Not created, to avoid automatic speech-to-text charges; upload them directly if needed
Unsupported formats (such as `.exe`), and `winmail.dat`, which packages all attachments when Outlook sends in RTF format	Not created; appear only in the email's attachment list and do not affect other attachments in the same email

Up to 50 attachments can be extracted per email.

Attachments are no longer extracted once the organization's file upload quota is exhausted.

Linking Attachments to Their Original Email

Each extracted attachment document automatically receives system metadata identifying its original email. This metadata appears in the document list. You can also enter the original email's document ID, subject, or sender in the search box above the list to find attachments extracted from the same email:

Metadata	Content
`email_source_file_id`	The original email's document ID in the knowledge base
`email_subject`	Email subject
`email_from`	Sender
`email_date`	Sent date
`email_attachment_filename`	Original attachment name



Search by email subject or sender to find attachments extracted from the same email

These system metadata fields have "Use for retrieval" disabled when created and do not filter retrieval results. For metadata usage and settings, see Document Management: Tags and Metadata.

Deleting Emails or Attachments

Deleting an email: Also deletes attachment documents extracted from that email.

Deleting only one attachment: Does not affect the email or other attachments. Reparsing the email later will not recreate the deleted attachment.

When Email Processing Fails

Click the red exclamation mark next to the Failed status to open the Failure Reason dialog:

Failure Reason	Meaning	How to Resolve It
This email is encrypted (S/MIME) and cannot be opened without the recipient's private key. It was not added to the knowledge base.	The email content is encrypted	Ask the recipient to decrypt it in their email client, save an unencrypted copy, and upload it
This S/MIME email is corrupted or cannot be parsed.	The signed or encrypted envelope format is corrupted	Export the email again from your email client and upload it
This .msg file is corrupted or is not a valid Outlook email.	The file is incomplete, or has a `.msg` extension but does not contain an Outlook email	Save it again as `.msg` in Outlook, or save it as `.eml` and upload it

Files exceeding the size limit are blocked at upload. Corrupted email files may fail during parsing. Export them again or save them in another supported format according to the failure reason.

Row Limits for Structured Files

When you add tabular files such as CSV, Excel, JSON, or JSONL to the "Upload Files" dialog, their rows are counted first ("Counting rows…" is displayed). Once counted, the row count appears below the file name. For files with more than 1000 rows, an orange message next to the count recommends using the "Database" feature instead. Unreadable files are marked in red as "Unreadable file".



Tabular files with more than 1000 rows display their row count and a recommendation in the upload list

If the list contains files that exceed the limit or cannot be read, clicking Upload first opens the "File Row Count Exceeds Recommended Limit" confirmation dialog:



The confirmation dialog offers only Cancel and Upload Anyway

Button	Action
Cancel	Return to the upload dialog. Click the delete icon to the right of a file to remove it from the list and upload only the remaining files; or use the Database feature to upload the file as a table queryable with Text to SQL. See Creating and Configuring a Database
Upload Anyway	Upload as usual. The file will be split into many chunks, making retrieval less effective for whole-table statistics and filtering questions

How to choose: A knowledge base works well for questions about a specific row (such as a product's specifications). For questions that require scanning the whole table, such as counts, matching records, totals, or sorting, use a database instead.

How Tabular Files Are Chunked and Cited in a Knowledge Base

When parsing CSV or Excel (`.xls` , `.xlsx` , `.ods`) with MaiAgent Parser:

Each worksheet is converted to a Markdown table (one table for an entire CSV; if a file has multiple worksheets, each table is preceded by the worksheet name as a heading). The first row is used as the header.

Up to the first 100,000 rows of each Excel worksheet are read. CSV files are read in full (subject only to the upload file size limit). The "first 5,000 rows" limit applies only to tabular files attached directly in conversations, not files uploaded to a knowledge base.

Converted tables are then split into chunks using the usual document chunking rules. **A row is not an independent retrieval unit**: a chunk typically contains several consecutive rows, and the header appears only in the chunk at the beginning of the table. Retrieval and citations operate on chunks. A citation points to the chunk containing the row, without identifying its row number.

Hidden rows and worksheets are also read. Delete any data you do not want to share with the Agent beforehand.

To make each row independently retrievable and citable, turn each row into an FAQ entry (using Excel Bulk Import), or use a database so the Agent can query it with SQL.

Viewing Data

About Data Chunks

When data is uploaded to a knowledge base, it is split into chunks. This offers the following benefits:

More precise retrieval: Small chunks match queries more precisely and reduce interference from unrelated content

Faster responses: Faster processing reduces computing resource usage

More relevant content: Each chunk focuses on one topic for more targeted results

Easier maintenance: Simplifies updates, tracking, and quality control

Compliance with AI model limits: Avoids exceeding input length limits to keep information complete

Editing and Viewing Chunk Content

You can view the chunks in your documents:

Open the knowledge base's Documents page and click "Edit" in the actions column of the document you want to view

The top of the document details page shows the chunk count, reconstructed character count, and total hit count. Switch between two views in the upper right:

Whole Document (default): Reassembles all chunks in their original order. A track on the left marks each chunk's range. Show Chunk Markers is enabled by default, with different track colors for odd and even chunks. Paragraphs with an amber background belong to two adjacent chunks (overlap, displayed only once). Hover over a track to highlight that chunk's full range. This view is the most intuitive way to check whether a sentence was split between two chunks.

Chunk Cards: One card per chunk, showing its character count and hit count. Click a card to open a dialog with the chunk's full content. In the dialog, Edit Fields sets the chunk's tags and metadata, and View Original opens the original document. To edit chunk text, use Editing the Source Document below.



Whole Document view



Chunk Cards view



The chunk dialog opened by clicking a card

Editing the Source Document


Click "View Document" in the upper right of the document details page

In the editor, a page list appears on the left, and the text box on the right displays the document in Markdown format

Edit the document content in the text box. This method works for all file formats. "Save" is gray until you make changes. After editing, click "Save" to save your changes. The notice above the text box explains what saving affects:

Text files such as `.txt`, `.md`, `.csv`, and `.json`: "Saving also updates the original file."

Other files, such as PDFs, Word documents, and presentations: "Only the text used for search is updated. The original file is unaffected." Hover over "Which files are text files?" to see the full list.



Text file editor, with the Save button in the upper right

> Data Management Reminders Back up important content before editing After you edit the source document, the system splits it into chunks again

Audio and Video: Transcript Viewer

After audio (`.wav` , `.mp3` , `.m4a` , `.aac`) or video (`.mp4`) is uploaded, the system first converts it into a timestamped transcript, then splits it into chunks. Clicking "View Document" on the details page for these files opens a transcript viewer rather than the Markdown editor:

Player on the left: Audio displays the file name, duration, and playback controls; video plays directly. During playback, the transcript on the right scrolls along and highlights the current sentence. Click any sentence to jump to its timestamp.

Transcript tab: Lists timestamps, speakers, and content sentence by sentence. Plain Text switches to a version without timestamps, and Copy copies the entire transcript to the clipboard.

Speaker Management tab: Recognized speakers are numbered by default. Change Speaker Label to an actual name or role (such as "Support" or "Customer"), then click Save to update the transcript as well.

Download Transcript: Choose Download TXT (plain text for reading and editing) or Download SRT (subtitle format with timestamps).

The Agent retrieves transcript text. To correct recognition errors, edit chunks using Editing the Source Document above. For speech-to-text pricing, see Credits Billing System.

Document Batch Operations

Use the leftmost column of the "Documents" list to select files. Once selected, "N items selected" appears above the list. Use the buttons above the list to process multiple files at once. These buttons are disabled for members without "Update" permission.

Button	Select files first	What it does
Bulk Change Parser	Yes	Apply the same parser to the selected files and **reparse them immediately**
Bulk Delete	Yes	Delete the selected files
Move Files	Yes	Move the selected files to another knowledge base; see Move Knowledge Base Files
Bulk Manage Metadata	No	Export, edit, and import metadata for **all** files at once using Excel
Bulk Manage Tags	No	Export, edit, and import tags for **all** files at once using Excel

Bulk Change Parser

Select files and click "Bulk Change Parser." Choose the new parser from the "Parser" dropdown, then click "Save." You can only process files of **the same file type** at a time (for example, all PDFs). If you

select different types, a message asks you to select files of the same type. Use the "All File Types" filter before selecting files.

When you select "Auto Detect (Default)," the system chooses a parser based on each file's content. PPT files, Word files containing images, and scanned PDFs may use Vision Parser.

> Changing the parser immediately reparses all selected files and charges you again according to the new parser's billing rules. See Usage Calculation for billing details.

Bulk Delete

Select files and click "Bulk Delete." The confirmation dialog displays "Are you sure you want to delete the N selected files?" Click "Confirm Delete" to submit. Once deleted, the Agent can no longer search this content, and it cannot be restored.

Deletion runs in the background: after you submit, the list first shows "Deleting," and the files disappear when deletion finishes. If any selected files are already being deleted, a message says "N documents are being deleted and have been skipped." The remaining files are deleted as usual.

What Happens After Deletion

New answers stop citing the document immediately: As soon as you submit a deletion, the document's chunks and citation nodes are removed from the retrieval scope. Subsequent conversations and search tests can no longer find it. "Deleting" only indicates that vector data and the file itself are being cleaned up in the background; the content is no longer retrievable.

Citations in past conversations disappear: Message text that cited the document in past conversations is retained, but "View Citation Nodes" no longer lists its chunks, and clicking a citation can no longer open the original document. If you need to keep citation records, export the conversations from Agent Monitoring before deleting the document.

Documents still being processed can also be deleted: Deleting documents with an "Initializing" or "Processing" status automatically stops parsing without deducting additional credits.

Deletion cannot be undone: To restore the content, you must upload it again, which incurs parsing and vectorization charges again.

Bulk Manage Tags and Metadata

Neither button requires you to select files first. Both open the same "Download → Edit → Upload" workflow to process **all** files in this knowledge base at once:

In the "Download Tags"
"Download Metadata" section, click "Download Tag File"
"Download Metadata File" to download an Excel file containing all current files.

Tag file: Each row is a file, and each column is a tag. Applied tags are marked with `v`. Enter `v` to add a tag, or clear the cell to remove it.

Metadata file: Each row is a file, and each column is a metadata field. Edit the values directly in the cells.

After editing the Excel file, return to the "Upload Updated Tags" "Upload Updated Metadata" section. Drag and drop the file or click "Browse Files" to select the `.xlsx` `.xls` file you just edited.

Click "Upload and Update." On success, the message "Updated N/M records" appears. If some rows have issues, the number of failed records is displayed, while the remaining records are still updated.

> Keep the column headers and file rows in the downloaded file, and only edit cell values. Do not add tags or metadata fields that are not already in the Excel file. To add tags or metadata fields, first create them under "Tag Management" "Metadata Management" on the left, then download a new template. For an explanation of tags and metadata, see Document Management: Tags and Metadata.

Frequently Asked Questions

Can I Create Folders in a Knowledge Base?

Knowledge bases have no folders or nested directories. All documents appear in a single list. There are two ways to organize them:

Organize within one knowledge base: Tag documents and add metadata, then filter by tags or restrict the Agent's retrieval scope. See Document Management: Tags and Metadata and Knowledge Base Tag Filtering.

Manage permissions or retrieval settings separately: Split the content into multiple knowledge bases and link them to the same Agent. See Use Multiple Knowledge Bases with One Agent.

Does Uploading a File with the Same Name Overwrite the Old File?

No. A file with the same name becomes a separate document, and the old file remains in the knowledge base. Both versions can be retrieved. To update content, delete the old file before uploading the new one, or edit the original document directly. For pages imported by a crawler, you can separately choose whether to skip or overwrite duplicate URLs. See Manually Import Crawled Pages.

Can I Adjust Chunk Size and Overlap?

The knowledge base settings page has no chunk size or overlap options. The selected parser determines how documents are split. If retrieval results are unsatisfactory, you can adjust the following:

Parser: Reparse with a different parser to produce different chunks. See What Is a Parser?

Number of retrieved chunks: The number of chunks referenced for each answer; the default is 12. See Retrieval Chunks

Similarity cutoff and Reranker: Exclude chunks that are not relevant enough. See Similarity Cutoff

Chunk content: Edit chunks or the original document directly so that each chunk can be understood on its own. See Edit and View Chunk Content

After making adjustments, run Search Tests with the same questions to compare results. For on-premises deployments that require changes to chunking parameters, contact your MaiAgent representative.

What Happens If I Upload an Unsupported File Type?

The file picker in the upload dialog only lists supported file types. Formats outside this list cannot be selected, and no document is created. When uploading through the API, file extensions that no parser supports are rejected, with `detail` set to "Unsupported file type for parsing." See Technical Guide - Knowledge Base API Troubleshooting.

For unsupported formats, convert them to a listed format before uploading: for Outlook `.pst` mailbox archives, save the emails you need individually as `.msg` or `.eml` files (see Email Files (.msg, .eml) and Embedded Attachments); save Pages
Keynote files as `.docx`
`.pptx`
PDF, and plain text files as `.txt` or `.md`.

Is Formatting Preserved for Markdown, HTML, and Web Pages Imported by a Crawler?

The knowledge base **retains the original file** (available for download from document details or citation sources), but retrieval uses the parsed text. Documents in every format are converted to Markdown text before being split into chunks. "View Document" displays this Markdown.

`.md`: Content is treated as Markdown as is. Heading levels, lists, and tables are preserved in the chunk text, and images remain in the text as `![]()` links.

`.html`
`.htm`: MaiAgent Parser (Offline) converts the content to Markdown. Headings and tables become Markdown headings and tables, while navigation bars, scripts, and other elements outside the main content are discarded.

Web pages imported by a crawler: At import, the content is already Markdown of the page's main content (see How to Use the Crawler). The filename comes from the page title with `.md` appended. The system automatically writes the source URL to the document's `url` metadata, so when an Agent cites the document, clicking the citation opens the original web page directly. Three additional system metadata fields, `crawl_source`, `crawl_executed_at`, and `crawl_version`, record the source crawl request, import time, and overwrite count. These fields are not sent to the model.

Heading text stays in the chunks, but chunks have no structural information about the section they belong to. To let the Agent name a section or topic in its answers, make sure each chunk can be understood on its own, or add section names to metadata and enable "Use During Retrieval."

Does the System Automatically Detect Duplicate or Conflicting Content?

No. The knowledge base does not compare content across documents. If you upload duplicates or keep both old and new versions, both may be retrieved and passed to the Agent together, and the Agent may cite both versions. The only automatic deduplication occurs during crawler imports, based on the URL (skip
overwrite
allow duplicates). See How to Use the Crawler. Recommended practices:

Use metadata to record versions and status. When updating documents, delete the old file before uploading the new one, or edit the original document directly.

Enter common questions in Search Tests to check whether the same question retrieves chunks with inconsistent content from multiple documents.

Use the "Hallucinated Responses" and "Knowledge Base Gaps" categories in Conversation Platform Analytics to find conversations with incorrect answers caused by conflicting content.

Can I Import Notion Pages into a Knowledge Base?

Knowledge bases do not have a Notion import feature. MaiGPT's Notion connector only queries pages during a conversation and does not store their content in a knowledge base. To let an Agent reference Notion content over time, use "Export" in Notion to export pages as Markdown, HTML, or PDF, then upload them:

When exporting as Markdown
HTML, images within the page are stored as links or separate files in an archive and are not recognized as text. Use this approach when you only need text content.

If information in images also needs to be retrieved, export as PDF and parse it with Vision Parser, or upload the image files separately to a knowledge base that uses a multimodal Embedding model. See Technical Guide - Image Recognition Support.

If the Notion page is public, you can also use the crawler to synchronize it regularly.

Create a Knowledge Base: Basic Settings

Basic Settings

General Information

Click Create Knowledge Base in the knowledge base list. On the General Information tab, enter a Name for the knowledge base and optionally add a Description. To make changes after creation, click “Edit” on the right side of the knowledge base and adjust the settings on the General Information tab of the Basic page.



Enter the knowledge base name and description on the General Information tab

The Retrieval Settings, Linked AI Assistants, and Permission Settings tabs in the window correspond to the retrieval settings, Linking Agents, and Permission Settings sections below.

Retrieval Chunks

The retrieval chunk count sets the maximum number of data chunks an Agent can reference when answering. The system default is “12”, meaning the Agent retrieves the 12 most relevant chunks for each answer. Set this in the Retrieval Chunk Count field on the Retrieval Settings tab.

Increase or decrease this count to adjust how much information the Agent references when answering.

Force Full Retrieval Range

When an Agent with its response mode set to Agent mode queries a knowledge base, the model decides how many chunks to use for that query. The actual count may be lower than the “Maximum Retrieval

Chunk Count”. When you select Force Full Retrieval Range, the system ignores the count chosen by the model and instead provides all retrieval results within the “Maximum Retrieval Chunk Count” to the model as reference material.

This option is unchecked by default. Find it under the Agent's Settings → Advanced Settings → Knowledge Base Settings, directly below the Maximum Retrieval Chunk Count field.

When to enable it:

The knowledge base contains long tables, such as plan comparisons, price lists, or specifications, split across multiple chunks, and a complete answer requires more chunks at once

Answers often cover only part of the information, even though search tests can find the remaining relevant chunks

Trade-offs when enabled:

The model reads more chunks for each answer, which may increase response time

Including more chunks may also introduce content that is less relevant to the question

> The actual number of chunks included is determined by the “Maximum Retrieval Chunk Count”. Keep it within the 5–15 range recommended on the screen, and compare answers to the same set of questions before and after enabling this option to decide whether to keep it enabled.

Example scenario: Sales assistant Ann notices that the “Implementation Consulting Assistant” sometimes lists only some plans when answering plan comparison questions. She selects “Force Full Retrieval Range” in the Agent's advanced settings and saves. In the internal chat, she then asks, “Using the plan comparison table, list the differences in features and quotas for each plan.” After querying the knowledge base, the Agent presents the differences in a table.

Go to AI Assistants, click the edit icon on the right side of the Agent you want to adjust, and open the Settings tab.

Click Advanced Settings in the left menu. In the Knowledge Base Settings section, select Force Full Retrieval Range.

Click Save in the lower-right corner.

Switch to the Conversation Platforms tab and click Go to Chat under Internal Chat. Ask the question that previously received an incomplete answer again and compare the responses.



Select “Force Full Retrieval Range” under Knowledge Base Settings in Advanced Settings



After enabling the option, ask a question in the internal chat; the Agent queries the knowledge base and summarizes the plan differences in a table

> If answer quality does not improve or responses become noticeably slower, uncheck the option and save to let the model decide how many chunks to use again.

Similarity Cutoff

The similarity cutoff excludes chunks that are not sufficiently relevant to the question. Chunks with a similarity score below the cutoff are not retrieved. Enter a value between `0` and `1`, in increments of `0.01`. Leave it blank or set it to `0` to disable filtering.

> This setting only takes effect when Reranker is enabled. The cutoff is compared against the scores assigned by Reranker, so you must select Enable Search Result Reranking for the knowledge base (see Reranker Model below). When Reranker is disabled, this field does not filter any chunks.

> A higher cutoff narrows retrieval results but may also exclude useful content. Setting it too high may leave no chunks at all. Make small adjustments and compare search results using the same set of questions.

Example scenario: Customer service supervisor Claire notices that search tests for “return conditions” sometimes include unrelated shipping instructions. She records the original retrieval results, increases the similarity cutoff, and saves. She then tests the same question again. If the return policy chunks still appear and the shipping instructions are excluded, she can keep the setting.

Go to Knowledge Bases and click “Edit” on the right side of the knowledge base you want to adjust.

Switch to Retrieval Settings.

Enter a value in “Similarity Cutoff (0–1)”.

Click “Save”, then run a search test with the original question again.



Adjust the similarity cutoff in Retrieval Settings

What Is a Parser?

A parser helps the system “understand” the contents of uploaded documents so they can be searched, edited, or converted to other formats.

Document Parsers

When uploading documents such as PDF or Word files, you can choose a parser for each file. Common parser names and uses are listed below; the actual options depend on your organization's list:

MaiAgent Parser: The default choice for general text documents, with low cost and fast processing.

MaiAgent OCR Parser (CPU): Previously named **MaiAgent Parser (Offline)**. Compare its results when you need to preserve document structure such as headings and tables.

MaiAgent OCR Parser (GPU): A separate parser from the CPU version that you can select manually to compare OCR results for scanned documents. It is not a parser that “Auto-detect (Default)” selects automatically.

MaiAgent Vision Parser: Uses AI visual understanding to read scanned files, charts, and image content.

The platform configures the parser list, so your organization may see more options than those listed above. For example, a parser using Gemini 3.1 Pro for image recognition supports up to 50 MB or 1,000 pages per file. See Technical Manual – Gemini Vision Parser for details. If a parser you need is not listed, contact your MaiAgent representative.

For each parser's supported file formats, offline availability, and image handling, see Technical Manual – Parser Tools. For billing, see Usage Calculation: Billing Units for Each Parser.

> When uploading PDF, Word, or PPT files, the Parser dropdown defaults to Auto-detect (Default): the system automatically chooses a parser based on the file structure after upload. Scanned PDFs or PDFs with many images, Word files with many images, and PowerPoint files may use MaiAgent Vision Parser; small icons and logos in Word do not necessarily trigger this selection. When no vision parser is available, the system uses the available OCR parsers and default parser, and deducts credits based on the parser actually used. The final parser appears in the Parser column of the document list. For selection rules, see Technical Manual – “Auto-detect (Default)” and Parsing Charges. If you later switch to a parser that has not previously been used for that file, the system immediately reparses it with the new parser and deducts credits again. Previously deducted credits are not refunded. See Parsing Failures and Reparsing. To fix the parser and billing method, specify the parser directly when uploading.

To compare parsing methods for scanned documents, a knowledge base administrator can click Upload Files on the Documents page, select a file, and expand the parser menu on its right. Decide whether to use auto-detection, GPU OCR, or CPU OCR before clicking Upload, to avoid reparsing and additional credit deductions just to switch parsers.



Upper part of the production parser menu: Auto-detect and GPU OCR are separate options



Scroll down the menu to find CPU OCR; the displayed costs are for reference only, and actual charges follow usage calculations

> GPU, CPU, and vision parsers process content differently. This does not mean that GPU is more accurate or faster for every document. Also, “OCR reads text in images” does not guarantee that every image will receive a separate description. After parsing, check the results with View Document and a search test.

Speech-to-Text Parsers

When uploading audio files, you can choose from the following speech-to-text parsers:

Azure Speech: Azure's speech service, with support for specifying multiple languages.
WhisperGroq: Whisper on Groq, with support for video uploads and custom prompts.

WhisperOpenAI: OpenAI's Whisper, with support for video uploads and custom prompts.

Bronci (Chang Wen Speech Recognition): Taiwanese Hokkien, Taiwanese Mandarin, and Hakka (Sixian and Hailu).

For language settings, video upload support, and on-premises speech-to-text, see Technical Manual – Speech-to-Text Parsers. For billing, see Usage Calculation: Billing Units for Each Parser.

After audio parsing is complete, use "View Document" to read the transcript. Transcripts can also be downloaded in TXT or SRT format.

> For a detailed comparison of parsers, see Technical Manual – Parser Tools.

If you encounter problems while parsing data, you can also click the [Reparse] icon to have the parser process the data again.

Adjustments for Documents with Complex Layouts

For documents such as product catalogs and specifications that combine two-column layouts, tables spanning multiple pages, and images, correct parsing does not guarantee that every answer will use all relevant content. Check each stage in order: "parsing results → retrieval results → answers":

Choose a parser suited to the content first: Use the default parser for plain text documents. When you need to preserve fields and table structure, first compare the results from MaiAgent OCR Parser (CPU). If questions focus on labels in images, the appearance of parts, or relationships between text and images, compare the results from MaiAgent Vision Parser.

Check the parsed Markdown: Open "View Document" on the document page. Verify the reading order of the left and right columns, and check whether table titles, column names, row data, and image descriptions remain in the same paragraph. If content is already interleaved or missing here, switch parsers and reparse. If necessary, change the source document to a single-column layout, or save important tables separately as `.xlsx`, `.csv`, or Markdown and upload them.

Run search tests with representative questions: Test product names, exact fields in tables, and questions requiring comparisons across rows to see whether the required data appears in the retrieved chunks. If the correct chunks fall outside the retrieval range, gradually increase the "Retrieval Chunk" count and compare results. More chunks also bring in more irrelevant content, so avoid setting the count to the maximum immediately.

Make each chunk understandable on its own: If a table is split, add the product name, specification category, column names, and units to each part. For data that requires complete answers, consider creating an FAQ with complete question-and-answer pairs for common comparison questions.

Confirm the purpose of images: A parser can recognize text or visual meaning in images, but it does not guarantee that answers will automatically display the original images. If users must see an image, check that the parsed Markdown retains it and that the chunk containing it is retrieved. Also test how it appears in the conversation channel you actually use. If only specification information in the image is needed, include the key text, figure number, and image description in the document.

> Change only one setting at a time and rerun search tests with the same questions to determine whether improvements come from the parser, document content, or retrieval settings.

Retrieval Model Settings

On the knowledge base's Retrieval Settings tab, you can choose the Embedding and Reranker models you want to use.




Select Embedding and Reranker models on the Retrieval Settings tab

Embedding Model

Embedding translates human language into a "numerical language" that AI can understand, allowing computers to understand the meaning of text. This process is called "vectorization". Different Embedding models have different characteristics, such as the languages they handle well and the deployment environments they support. The model selected for a knowledge base determines how its documents are vectorized when uploaded. Choose the Embedding model that best suits your use case.

You can choose from a variety of Embedding models:

> For differences between Embedding models, see Technical Manual – Embedding Models.



Select an Embedding model when creating a knowledge base

> You can only select the Embedding model when creating a knowledge base. It cannot be changed afterward (the field is grayed out on the edit page). To use a different model, create a new knowledge base and upload the files again.

Reranker Model

A Reranker acts like an expert reviewer, reassessing the initial search results to determine which information best answers the customer's question. What difference does using a Reranker make?

Suppose a customer asks, “Which tents are suitable for beginners? My budget is under 8,000.”

Without Reranker:

```
The AI might answer:
“We have tents at various price points. Products priced at 8,000 include ...”
(It may mention advanced models without addressing beginners' needs)
```

With Reranker:

```
The AI answers:
“For beginners, we especially recommend these tents under 8,000 ... ”
(Targets beginners, budget, and product recommendations precisely)
```

When search result reranking is enabled, the Agent reorders the retrieved knowledge base chunks and responds using the most relevant documents.

> For more about Reranker models, see Technical Manual – Reranker Models.

Combining Embedding with Reranker allows the Agent to understand the knowledge you provide, reassess the importance of retrieved chunks, and respond with the information most relevant to the question.

Vector Database

Knowledge base vectors are stored in a vector database provided by MaiAgent by default. If your organization requires index data to remain in an environment it manages, you can connect your own vector database instead (an Enterprise feature; MaiAgent must enable it for SaaS organizations).

Once enabled, a Vector Database tab appears in the Create Knowledge Base window. Choose Use System Default Configuration or Use Custom Vector Database. For the latter, select a Vector Database Type and enter the connection details.

> The vector database is locked after the knowledge base is created and cannot be changed. To switch databases or return to the system default, create a new knowledge base and upload the files again.

For supported database types, required fields, versions, and network requirements, see Technical Manual – Bring Your Own Vector Database.

Permission Settings

The Permission Settings tab determines which roles' members can use this knowledge base. During creation, under Quick Permission Scope Selection, choose All Roles, Exclude Default Roles, or Select Custom Roles. The roles that will be assigned after creation are listed below.

If you click Confirm before viewing this tab when creating a knowledge base, the window first switches to Permission Settings and displays “Please review the permission settings and confirm the assigned roles before submitting” . After confirming the roles, click Confirm again to create the knowledge base.



Choose which roles can use this knowledge base in Permission Settings

Linking Agents

Sharing a Knowledge Base Across Multiple Agents

Linking Agents determines which Agents are authorized to use this knowledge base. Suppose you have two Agents:

Product Support AI

Order Support AI

If both need to answer questions about returns, link them both in the “Return Policy” knowledge base settings:





Illustration of linking multiple Agents


On the knowledge base's Linked AI Assistants tab, select the Agents to link under Available AI Assistants



Select the Agents to link under Available AI Assistants

Click Add AI Assistants

The added Agents appear in the Selected AI Assistants section. Click Save in the lower-right corner to complete the linking.



Click Save after adding Agents to Selected AI Assistants

Once linked, both Agents can share the "Return Policy" knowledge base and answer using the same content. For ongoing maintenance, you only need to **update one knowledge base** to keep the Agents using the latest information.

Using Multiple Knowledge Bases with One Agent

In addition to sharing a knowledge base, a single Agent can use multiple knowledge bases.

Go to AI Assistants, click the edit icon on the right side of the Agent you want to configure, and open the Settings tab

Click Knowledge Base Settings in the left menu, then click Select Knowledge Bases in the upper-right corner



Click Select Knowledge Bases in the Agent's Knowledge Base Settings


Select the knowledge bases to use and click Confirm. The selected knowledge bases appear in the Use Knowledge Bases list and apply to this Agent immediately



Select multiple knowledge bases and click Confirm

For an existing Agent, clicking Confirm saves the knowledge base settings without a separate click on Save. To undo the selection, remove the knowledge base from the Use Knowledge Bases list.

Crawler



Crawler: automatically fetch web page content and import it into a knowledge base

What is this?

A crawler automatically fetches content from web pages and imports it into a knowledge base. Give it a URL, and it can crawl the text on that page (or the entire website) and turn it into knowledge that an Agent can consult.

When do you need it?

Official website content: automatically import product introductions and service descriptions from your company's website

Public information: fetch public web pages such as regulations, announcements, and technical documentation

Ongoing updates: website content changes; recrawl regularly to keep the knowledge base up to date

How crawlers relate to knowledge bases

A crawler is **one of the data sources** for a knowledge base. Its role is:

```
Data sources            Knowledge base          Agent
————————                ——————                  ——————
Manually upload files ——→
Create FAQs           ——→ Enterprise knowledge hub ——→ Consult and respond
Crawl web pages       ——→
```

The content a crawler fetches ultimately goes into the knowledge base. Agents do not interact directly with the crawler.

What do I need to do?

Enter a URL — Tell the crawler which web page or website to fetch

Set the scope — Use the maximum crawl depth, maximum page count, and URL rules to determine whether to fetch only the starting page or include subpages on the site (see How crawl scope is determined for the rules); for multilingual websites, you can also specify the crawl language/region

Run the crawl — Start the crawler and wait for it to finish

Import into a knowledge base — Import the crawl results into the specified knowledge base

Verify the content — Check that the imported content is correct and complete

Multilingual websites: specify the crawl language/region

Some websites offer multiple language versions, such as Chinese and English, and decide which version to return based on the browser's language. If the crawler does not specify a language, the website may treat it as an English-speaking visitor and redirect it to an English page, resulting in English content in the knowledge base. When crawling only a single page, the starting page may even be redirected to a path outside the starting URL, leaving no pages crawled.

In this case, expand Advanced Settings in the "Crawl Settings" step when creating a crawl request, and select the language and region for reading the website under Crawl Language/Region, below Content Extraction Settings:

Option	Description
Default (unspecified)	The default for new requests. No language is declared to the website; the crawl service decides (currently equivalent to English)
Traditional Chinese (Taiwan)	Read the website in Traditional Chinese with Taiwan as the region
Simplified Chinese (China)	Read the website in Simplified Chinese with China as the region
English (US)	Always read in English, regardless of future changes to the crawl service's default
Japanese (Japan)	Read the website in Japanese with Japan as the region



Crawl Language/Region: select the language and region for reading the website below Content Extraction Settings

The selected language applies to every step of this crawl task:

Preview: clicking Preview in the “Execution Method” step uses the same language to discover URLs, so the URLs listed in the preview match those used in the actual crawl

Scheduling: when you select Scheduled Execution, the language is saved in the schedule settings and used for every subsequent run. You can change the language by clicking Edit for the schedule on the “Schedules” tab; the new language takes effect on the next run

Details: expand Crawl Task Settings in the crawl request details to see the Crawl Language/Region used for this run

For example, a knowledge base administrator at an appliance brand wants to crawl product descriptions from the bilingual Chinese/English website https://www.example-appliance.com/ into the knowledge base, but previous crawls returned only English pages. She creates a new crawl request, changes Crawl Language/Region to Traditional Chinese (Taiwan) in Advanced Settings, then clicks Preview in the “Execution Method” step to confirm that all pages to be crawled are in Chinese before creating the request. After the crawl finishes, she sees “Traditional Chinese (Taiwan)” in Crawl Task Settings in the request details, and all crawled pages have Chinese titles. When she later switches to a weekly synchronization schedule, she selects the same language when creating the schedule, and every scheduled run uses it.

> The crawler does not translate content. If the website has no version in the selected language, the content collected is whatever the website actually returns. The language setting applies only to that crawl task or schedule and does not affect other crawl tasks in the organization. Existing tasks and schedules with no language setting continue to behave as before.

For all fields and operation steps, see How to use the crawler (crawl data) feature.

Further reading

How to use the crawler (crawl data) feature

Use the Web Crawling Feature

Purpose and Value

As an employee, you may often be asked by your manager to consult or compile regulatory information from public websites, or to help an Agent stay up to date with the latest products and FAQ content on your company's website.

If you have a technical background or help from engineers, you could write a crawler to collect the data automatically. For nontechnical staff, however, this usually means organizing pages manually, one by one—a time-consuming task that can easily miss key information.

MaiAgent's crawler lets you do the following without writing code (No-Code):

Crawl an entire website scope at once: Set the crawl depth, page limit, and URL rules to determine which pages to crawl

Run once or on a recurring schedule: Crawl immediately, or automatically crawl again daily, weekly, or monthly

Automatically import into a knowledge base: Import directly into a selected knowledge base after crawling, with options to skip, overwrite, or allow duplicates when a URL already exists

Track import results: View the number of successfully imported and failed pages for each import in the import history

Use Case

A company's customer service manager wants the AI customer service agent's answers to match the FAQ on the company website. She first creates a knowledge base dedicated to the website FAQ, then opens “Crawler” to create a crawl request. She enters the FAQ URL and sets a small maximum crawl depth and page limit to check that only FAQ-related pages will be crawled. She selects “Scheduled Run,” sets it to every Monday at 9 a.m., selects the new knowledge base as the automatic import destination, and chooses “Skip” for existing URLs. Once created, this weekly synchronization task appears on the Schedules tab. After each crawl, she can check “Import History” in the crawl request details to see which knowledge base received the automatic import and how many pages succeeded or failed. When the website FAQ changes, she no longer needs an engineer to organize the data.

How to Crawl

> If “Crawler” does not appear in the left menu, your account does not have crawler access. Contact your organization administrator to check your permissions.

1. Open the Crawler Page

In the left menu, click AI Features → Crawler. The page has two tabs:

Page Crawl Requests: Lists each crawl, including one-time runs and crawls created by each automatic scheduled run. Search by name or URL, and filter by type (one-time/scheduled) and crawl status (completed/in progress/failed)

Schedules: Lists all recurring crawl schedules



Page Crawl Requests tab: Each request shows its type, crawl status, and creation time

2. Enter a Task Name and URL

Click Create Page Crawl Request in the upper right. The creation process has three steps: “URL,” “Crawl Settings,” and “Execution Method.”

In the first step, enter:

Task Name: A name that helps you identify this crawl task, such as “Daily Product Page Crawl”

URL: The URL where crawling should start

Then click Next.



Step 1: Enter the task name and starting URL

3. Set Crawl Depth and Scope

The second step, “Crawl Settings,” determines how many pages to crawl. Basic Settings has two fields:

Field	Description
Maximum Crawl Depth	The number of levels of links to follow from the starting URL. Choose 1–10; the default is 2
Maximum Pages to Crawl	The maximum number of pages for this crawl. Choose 10, 50, 100, 500, 1000, or 5000; the default is 100



Basic Settings: Control the crawl scope with maximum crawl depth and maximum pages to crawl

For more precise control over the scope, expand Advanced Settings:

Setting	Description
Generate Rules from a Prompt	Describe which URLs to collect in natural language (for example, “Only crawl product pages and ignore archived articles”). Click Generate Rules to have AI convert the prompt into the URL matching and exclusion rules below. You can still edit each rule afterward. Enter a URL in the first step before generating rules. If the prompt cannot be mapped to URL rules, you will see “Only URL-based filtering is currently supported”; rewrite the prompt or add rules manually. If you continue without clicking Generate Rules, a confirmation appears first; see “Confirmation When a Prompt Has Not Generated Rules” below
URL Matching Rules	Crawl only URLs that match the rules, such as `/products/*`. If no rules are added, all pages within the scope will be crawled
URL Exclusion Rules	Do not crawl URLs that match the rules, such as `/admin/*` or `\.pdf$`
Boundary Settings	Whether to Allow Crawling of Same-Level or Parent Paths, Include Subdomains, and Allow External Links. All are off by default

Setting	Description
Sitemap Strategy	Prefer Sitemap (Default), Ignore Sitemap, or Use Sitemap Only
Content Extraction Settings	Extract Main Content Only and Ignore URL Parameters (both on by default), plus JS Rendering Wait Time (0, 500, 1000, or 2000 ms)
Crawl Language/Region	Read the website using a specified language and region. Multilingual websites return the corresponding language version; for example, choosing Traditional Chinese (Taiwan) can prevent a redirect to the English version. Options include Traditional Chinese (Taiwan), Simplified Chinese (China), English (US), and Japanese (Japan). Default (Unspecified) does not declare a language to the website; the crawl service decides (currently equivalent to English). This setting is below Content Extraction Settings. Previews and every scheduled run use the same locale. See Multilingual Websites: Specify the Crawl Language/Region

建立頁面爬取請求

網址 — 2 爬取設定 — 3 執行方式

基本設定

最大爬取深度

1

最大爬取頁數

10

進階設定

使用提示語生成規則

例如：只爬取商品頁面，並忽略已封存的文章。

0 / 1000

提示語只會轉成網址的比對／排除規則，無法依頁面標題或文字篩選；以按鈕或表單翻頁（網址不變）的列表，爬蟲只收得到第一頁。

生成規則

網址比對規則

例如：/products/* 或 product-.*

+ 新增

尚未新增比對規則，將爬取範圍內的所有頁面。

網址排除規則

例如：/admin/* 或 \.pdf$

+ 新增

尚未新增排除規則。

邊界設定

允許爬取至同層或上層路徑

包含子網域



Advanced Settings: Further limit the crawl scope with URL rules, boundaries, and sitemap strategy, and specify a crawl language/region

> Enabling Allow External Links crawls URLs outside the website, which may significantly increase the page count and cost. Test with a small depth and page limit first, then increase them after confirming the scope.

> Prompts only generate URL matching/exclusion rules; they cannot filter by page title or body text. For lists that paginate using buttons or forms without changing the URL, the crawler can only collect the first page.

Confirmation When a Prompt Has Not Generated Rules

If you fill in Generate Rules from a Prompt but click Next or Preview before clicking Generate Rules (or after editing the prompt again following generation), the system first opens a “Prompt Has Not Been Converted to Rules” confirmation dialog. It warns that continuing directly will crawl all pages within the scope:

Generate Rules: Generate URL rules from the prompt. If the dialog appears from Preview, you first return to the “Crawl Settings” step to generate rules so you can review them before previewing again

Continue Anyway: Continue with the current settings without generating rules

Close the dialog in the upper right or press Esc: Stay on the current step without taking any action



The confirmation dialog that appears when you click Next before generating rules from the prompt

> Only changes to the prompt itself trigger confirmation. Manually adding or deleting URL Matching Rules or URL Exclusion Rules after generation does not count as a prompt change and will not trigger another confirmation. If you select Continue Anyway at Next, you will still be asked again when you click Preview in “Execution Method.”

For example, a company's knowledge management specialist wants to crawl documentation under `/docs/` on the company website into a knowledge base. She enters “Only collect pages under /docs/ and exclude PDFs” in the prompt and immediately clicks Next. When the confirmation dialog appears, she selects Generate Rules. The rules section then shows a `/docs/.*` matching rule and a `.*\.pdf$` exclusion rule. Clicking Next again does not repeat the question, helping prevent accidentally crawling the entire website into the knowledge base.

How the Crawl Scope Is Determined

The crawler starts at the starting URL and follows links on pages to discover more URLs. A URL must meet all of the following conditions to be crawled:

Condition	Rule
Within-site scope	By default, only pages with the same hostname and paths under the starting URL are crawled (if the starting URL is https://example.com/docs/, `/docs/a` is crawled but `/blog/` is not). Allow Crawling of Same-Level or Parent Paths expands the scope to the entire domain; Include Subdomains also includes subdomains such as `help.example.com`; Allow External Links is required to crawl other websites
URL rules	URL Exclusion Rules take priority over URL Matching Rules. Once matching rules are set, URLs that do not match any rule are not crawled. Rules are regular expressions and, by default, match only the URL path (excluding the hostname and parameters)
Depth	Maximum Crawl Depth counts levels in the "discovery order": The starting URL and URLs listed in the sitemap are level 0, pages linked from them are level 1, pages linked from those are level 2, and so on. Discovery stops beyond the configured depth
Page count	Maximum Pages to Crawl is the total page limit for this crawl. Crawling stops when the limit is reached, regardless of depth
Sitemap	The default is Prefer Sitemap: If the website has a sitemap, its URLs are included directly (as level 0), even if the starting page does not link to them. Ignore Sitemap follows links only; Use Sitemap Only crawls only URLs listed in the sitemap
URL parameters	When Ignore URL Parameters is on, URLs that differ only in parameters, such as `?page=2`, are treated as the same page and crawled once. Turn this off for websites that use parameters to switch page content
robots.txt	The crawler always follows the target website's robots.txt. Disallowed paths are not crawled, and settings cannot bypass this restriction

Each URL is processed only once per crawl, even if multiple pages link to it.

To collect only the starting page: Set the sitemap strategy to Ignore Sitemap, set maximum crawl depth to 1, and add a URL Matching Rule that matches only that page's path (for example, `^/about/?$`). Then use Preview to confirm that only this page appears under "Will Crawl."

When finished, click Next.

4. Choose an Execution Method and Knowledge Base Import

The third step, "Execution Method," determines when to crawl and where to import the results.

Execution Method

One-Time Run: Run one crawl immediately after creation

Scheduled Run: Crawl according to the configured schedule (see "Set Up a Recurring Schedule" in the next section)

Knowledge Base Settings

Import into an Existing Knowledge Base: Select one or more knowledge bases under Automatic Import Destination (Optional) for automatic import after crawling. Leave this blank to crawl pages without automatically importing them; you can import manually later

Automatically Create a New Knowledge Base: Create a new knowledge base with the task name for every run and import the crawled content into it

After selecting an import destination, Handling Existing URLs appears to control what happens when the same URL has already been imported into that knowledge base:

Option	Description
Skip (default)	Skip URLs already imported into this knowledge base
Overwrite	Replace the existing file with newly crawled content
Allow Duplicates	Create a new file even if the URL already exists



Execution Method: Choose a one-time run and specify the knowledge base for automatic import and how to handle duplicate URLs

> For recurring synchronization of the same website, use Skip or Overwrite to avoid accumulating duplicate files in the knowledge base that could cause the Agent to cite outdated content.

5. Preview and Create

Before creating the request, click Preview to check which pages will actually be crawled. A preview explores website URLs and incurs a charge. A confirmation dialog appears first; the preview runs only after you click Confirm.

The preview shows the number of discovered URLs, URLs to crawl and exclude, estimated page count and duration, and a list of pages to crawl.



Preview: Check the number and list of pages to crawl before creating the request

> The preview is an estimate. The actual crawl may vary slightly due to depth limits, JavaScript-generated pages, and robots.txt.

After confirming the settings, click Create. A one-time request appears on the “Page Crawl Requests” tab and begins crawling.

If the URL has been crawled before, the system opens a This URL Has Been Crawled Before confirmation dialog listing the previous crawl time, page count, and knowledge bases it was imported into. Click Crawl Again to crawl it again, or Cancel if another crawl is unnecessary.



Repeat crawl reminder: Review previous crawl results before deciding whether to crawl again

Set Up a Recurring Schedule

For websites with regularly updated content, select Scheduled Run in the third step to have the system crawl again periodically and automatically import into a knowledge base.

Field	Description
Frequency	Once, Daily, Weekly, or Monthly
Time Zone	The time zone used for scheduled times
Start Date End Date	The period during which the schedule is active. End date is optional; only a start date is needed for “Once”
Run Time	The time of each run
Days of the Week	For “Weekly,” select the days to run (multiple selections allowed)
Day of the Month	For “Monthly,” enter 1–31

建立頁面爬取請求

網址 — 爬取設定 — 3 執行方式

執行方式

單次執行
立即執行一次爬取。

排程執行
依設定的排程週期執行爬取。

* 頻率

單次 | 每日 | 每週 | 每月

時區

(UTC+08:00) Asia/Taipei

* 開始日期

2026-09-28

結束日期

選填

* 執行時間

09:00

* 週幾執行

週一 週二 週三 週四 週五 週六 週日

知識庫設定

匯入至既有知識庫
將爬取內容匯入你選擇的知識庫。

自動建立新知識庫
每次執行都會以任務名稱自動建立新的知識庫。



Scheduled Run: Automatically crawl and import into a knowledge base every Monday at 9 a.m.

After creation, the schedule appears on the Schedules tab with its settings and status (Active Paused). The icons in the actions column, in order, let you:

Edit: Open “Edit Schedule” to change the task name, crawl settings, scheduled time, and knowledge base settings (the starting URL cannot be changed after creation)

Run History: View the time and crawl status of each scheduled run and open its crawl details

Pause/Enable: Temporarily stop the schedule or enable it again

Delete: Delete the schedule



Schedules tab: View schedule settings, edit them, check run history, pause, or delete

> Every scheduled run actually crawls pages and consumes Credits. Pause the schedule when synchronization is temporarily unnecessary.

View Crawl Results and Import History

On the “Page Crawl Requests” tab, click Details for a request to open the Crawl Request Details page:

Crawl Progress: Processed pages and total page count

Crawl Task Settings: Expand to review the URL, crawl settings, and execution method used at creation. Switch to “Crawl Settings” to see the Crawl Language/Region used for this run (“Default (Unspecified)” if not set)

Crawled Pages: Lists the title, URL, crawl status, and completion time of each crawled page



Crawl Request Details: View crawl progress and crawled pages



Crawl Task Settings: Read-only display of the crawl language/region used for this run

Switch to the Import History tab to see the time, destination knowledge base, Import Method (shown as “Automatic” for automatic imports based on the creation settings), and successful and failed page counts for each import.



Import History: Destination knowledge base, import method, and successful/failed page counts for each import

Click the icon in the actions column to open the Imported Pages List and check each page's import status and corresponding knowledge base file.



Imported Pages List: Check the knowledge base file corresponding to each imported page

For completed requests in the “Page Crawl Requests” list, you can also click View to open Failed Import History, select a knowledge base, and check failed pages and the reasons for failure.

Imported content appears as .md files in the knowledge base's document list (with filenames based on page titles). You can set tags and metadata just as for other documents. These files display a Crawler label in the Source column; click it to return to the corresponding crawl request details. The system also writes the source URL into the document's `url` metadata. When the Agent cites the document, clicking the citation opens the original webpage. For how content is preserved, see Knowledge Base Overview FAQ.

Manually Import Crawled Pages

If you did not configure automatic import at creation, or want to import pages into other knowledge bases, you can import manually:

On the crawl request details page, click Import into Knowledge Base (or click Import for the request in the list)

Select the destination Knowledge Base and choose Handling Existing URLs

Select the pages to import and click Import



Manual Import: Select a knowledge base, duplicate URL handling, and pages to import

If you choose Skip and some URLs have already been imported, the system reports how many import tasks were created and how many duplicate URLs were skipped.

> Manual import crawls the latest page data again and incurs a crawl charge.

Investigate Crawl or Import Failures

First identify which stage failed, then check the cause:

Symptom	Common causes	What to do
The request is blocked when you create it	The starting URL exceeds 200 characters or is not a complete URL (it must include `http://` or `https://`)	Use a shorter parent URL as the starting point, then use crawl depth and matching rules to cover the target pages
The crawl status is Failed, with the reason “The crawl has finished, but no pages were retrieved”	The target website's robots.txt disallows crawling (the reason lists the blocked URLs); the website blocks automated access; the starting URL cannot be loaded	Check that the URL opens in a browser without logging in. If the website disallows crawling, provide the content by uploading files instead
Fewer pages are crawled than expected	Pages fall outside the crawl domain scope, are excluded by exclusion rules, or exceed the maximum crawl depth or page count; content is loaded dynamically by JavaScript	Before creating the request, use the preview to check the URLs under “Will crawl” and “Excluded”, then adjust the depth, page count, and matching rules

Symptom	Common causes	What to do
Pages require a login to view	The crawler can only read public pages	Export the content as files and upload them to the knowledge base
The website only allows IP addresses on its allowlist, and you want to add the crawler's source IP	Crawling is performed by a cloud crawling service with variable source IP addresses. MaiAgent cannot provide an IP address to add to an allowlist	Ask the website administrator to export the content as files and upload them to the knowledge base
Crawling succeeds, but importing into the knowledge base fails	Individual pages fail during import processing	In the “Page Crawl Requests” list, click View to open Failed Import Records. Select the knowledge base and check each page's Failure Reason, then use manual import to import them again

If the failure reason does not explain the issue, or the same URL fails repeatedly, note the crawl request's name and time and contact your MaiAgent representative.

Crawler usage considerations

Make sure you have permission to crawl the target website's content

Crawling, previews, and manual imports all consume Credits. Start by testing with a lower maximum crawl depth and page count, then expand after confirming the scope

After crawling is complete, use the search test feature to verify data quality

If website content changes frequently, use a recurring schedule to keep information up to date, along with Skip or Overwrite to avoid duplicate files

Create FAQs


How to Upload FAQs

Select a Knowledge Base

Go to “AI Features” → “Knowledge Base” in the left sidebar. In the row for the knowledge base where you want to create FAQs, click the “Edit” icon in the “Actions” column to open its settings (if you have not created one yet, see How to Create a Knowledge Base: Basic Settings first).

Add Questions and Answers

Click “FAQ” in the left menu of the knowledge base settings, then click the blue “+ Create FAQ” button in the upper right to start adding questions and answers.



FAQ in the left menu of the knowledge base settings

Create an FAQ

The FAQ editor supports several answer formats:

Basic text formatting (bold, underline, italic, etc.)


Equations

Source code (HTML, XML)


Embedded links (videos, websites)

Videos provide reference links for users (Agents cannot read video content yet)

Image and video files: click “Upload Image/Video” in the upper right of the editor




Create FAQ dialog



Example answer formats


Use these formats to highlight key points and ensure your answers include complete information.

For example, for payment methods in an online store, you can add the following question to explain online payment options:



Enter a question and answer

After entering the content, click the eye icon (Preview) in the editor toolbar to check the answer:



Preview the answer

Click “Confirm” after adding the content to create the FAQ. The Agent can then refer to your answer when responding:



The newly created FAQ appears in the list

When a customer asks about online payment methods, the LLM responds based on the FAQ content:



The Agent answers based on the FAQ

FAQs serve as reference material for the Agent's answers. They do not guarantee verbatim responses or retrieval on every occasion. First, use Search Tests to confirm that common ways of asking a question retrieve the correct content. Then ask the Agent directly to check whether its responses meet your company's requirements.

> Users do not need to match the FAQ question word for word: FAQs use semantic retrieval, just like knowledge base documents, so rephrased questions may retrieve the same FAQ. In the payment example above, both “Can I pay by card?” and “What payment methods are available?” may retrieve this FAQ. Before going live, enter several common phrasings in Search Tests to confirm that they all retrieve it.

Bulk Import FAQs with Excel

If you have many questions and answers, you can import them all at once with Excel. Each row creates one FAQ, which appears in the list and can be edited individually, just like FAQs created one at a time.

Download the Template

On the knowledge base's "FAQ" page, click "Bulk Import FAQ" in the upper right, then click "Download FAQ Template File" on the "Upload" tab. The first row of the downloaded Excel file is an example starting with `[EXAMPLE]`, followed by the existing FAQs in this knowledge base.

Enter Questions and Answers

Enter questions in the `question` column and answers in the `answer` column. Do not change the column names. You can keep the example row and existing FAQs; they are skipped automatically during import.

Upload and Import

Drag the file to the upload area or click to upload (supports `.xlsx` and `.xls`), then click "Upload and Add". The import runs in the background, so you can close the dialog. When it finishes, a notification shows how many FAQs were added and how many duplicates were skipped.

View Import Results

Go to the "Import History" tab to view the status, progress, number of FAQs created, number of duplicates skipped, and errors for each import. Rows with an empty question or answer are not imported and are listed in the errors as "Row N".

> Imports only add FAQs; they do not update answers in existing FAQs. Rows with a question that matches an existing FAQ (or is repeated within the same file) are skipped and counted under "Duplicates Skipped". To change an existing FAQ's answer, edit it directly in the list. Only one import can run at a time for a knowledge base. "Upload and Add" is disabled while an import is running.

Other Use Cases

Product Usage Guidance

For example, to help new users get started with the **MaiAgent platform**, you can add the following question and answer to the FAQ section:

Question: What should I do if I don't know how to use MaiAgent?

> If an answer is long, click Preview to check its full content



Answer preview


The Agent uses your answer to explain the available MaiAgent resources and getting started steps, and provides the links in your answer for users to refer to.

Introducing Concepts


For an **introduction to LLM technology**, suppose you run a technology education platform and need to explain large language models (LLMs) to a general audience. You can add the following question and answer to the FAQ section:

Question: How do LLMs work?

> You can enter video links in the answer



Click Insert/Edit Media



Example of entering a link



Media insertion preview

The Agent responds based on the answer you configured and provides the video reference link for users to visit.

FAQ Maintenance Tips

Keep Content Up to Date

Update event information: Remove or update relevant content as soon as promotions or limited-time offers end

Keep policies in sync: When company policies change (such as return conditions or terms of service), update the FAQ content accordingly

Maintain product information: Promptly reflect new product launches, specification changes, and discontinued products in the relevant questions and answers

Use Data to Improve Content

Improve answer quality: Refine answers to frequently asked questions with more detailed and practical information

Analyze gaps: Use customer feedback and support records to identify common questions missing from the FAQ

Quality Control

Check content accuracy: Regularly verify links, contact information, and technical details in the FAQ

Maintain a consistent tone: Ensure all FAQ content follows your brand's tone and communication style

Synchronize language versions: If you support multiple languages, keep all language versions up to date together

> Check FAQ hit counts to identify the types of questions users ask most often, and update them regularly. For an explanation of hit counts, see Search Tests



Document Management: Tags and Metadata

MaiAgent provides tag and metadata management to help you classify and organize the many documents and FAQs in your knowledge base.

Tag Management

When your knowledge base contains large amounts of data, tags help you quickly organize document and FAQ attributes or control access to reference materials. For example:

```
Product information knowledge base (classified by product information)
├── #Tents
├── #4-person-tents
├── #3-season-tents
├── #SnowPeak
```

```
Educational content knowledge base (classified by access level)
├── #Non-members
├── #Regular-members
├── #VIP
```

Add a Tag

Click the Add button



Enter a tag name



After you click Add, the tag you entered appears as shown below, including its ID, name, and other details

> You can use the ID to grant access to documents. For details, see the Technical Manual—Query Metadata Controls



Add Tags to a Document

After creating tags, go to the documents page

Click Edit File Information



Select tags

Add the appropriate tags for each document (you can select multiple tags)



The tags you added then appear after the corresponding document:



Add Tags to an FAQ

To add hierarchical categories or manage tags for FAQs:

Open FAQ management in the knowledge base, select the FAQ to edit, and click the Edit button



Select the tags to add, then click “Confirm”





The added tags appear in the FAQ field



Tag-Based Access Control

You can use tags to control which content different users see. For example, VIP customers can see more advanced product tutorials, while non-members can only see general tutorials.

> Filters can apply to both FAQs and documents

> To make an Agent reference only files with specific tags by default across all conversation platforms, without passing parameters on each call, configure this on the Agent settings page. See Knowledge Base Tag Filtering.

Tag filtering has two levels: conditions within a group and conditions between groups. The interface uses plain language: choose "Include all tags (AND)" or "Include any tag (OR)" within a group, and "Match every group (AND)" or "Match any group (OR)" between groups. The older interface displays AND/OR buttons with the same meaning. The following two examples illustrate this.

Include All Tags (AND)

"Include all tags (AND)" allows only content that matches every tag in the group.

For example, in a conversation about tutorials for non-members, use tag filtering to let the Agent access only documents that match both the "Non-member" and "Tutorial" tags.

As shown below, after filtering, the Agent can use only the beginner camping document, preventing unrelated information from being disclosed in conversations with non-members.




Include Any Tag (OR)

For conversations with members, switch to "Include any tag (OR)" so the Agent can reference documents tagged for either regular members or non-members:



Members can then see more document content than non-members, providing tiered access.

> In tag filtering, click “Include all tags (AND)” or “Include any tag (OR)” to switch how this group is evaluated (the image below shows the older AND/OR buttons in the same location). A sentence at the bottom of the builder describes the current conditions so you can verify your settings.



For filtering results, see: Chat with an Agent (Agent Marketplace)

Document Metadata Management

What Is Metadata?

Metadata is like an “identity card” for a document. It records detailed information to help the system manage and use documents more effectively.

Example: 初級露營.pdf

```
Metadata settings:
├── Document version: v2.1
├── Created on: 2024-03-15
├── Last updated: 2024-11-20
├── Next review: 2025-05-20
├── Updating department: Marketing
└── Version status: Reviewed and approved for access
```

Why Use Metadata?

When managing complex datasets, metadata makes maintaining data quality easier and faster. It helps you:

Improve Management Efficiency

Quickly identify document status and version information

Organize bulk management of large numbers of documents

Reduce time spent manually searching and checking

Ensure Content Quality

Use the latest document version

Track document update history and version status

Ensure the Agent uses the latest reviewed content

Record the next review date and regularly filter for documents due for review

Documents Have No Expiration Date, and Metadata Does Not Trigger Automatic Reminders

Knowledge base documents have no “expiration date” field: uploaded documents remain available for retrieval until you delete or update them. Metadata such as “Next review” is simply a value you record. The platform **does not** use it to send reminders, notify administrators, add tags automatically, or stop retrieving a document when that date arrives. Schedule periodic reviews yourself:

Create a date field such as `next_review` in Metadata Management and enter values for documents (default values can be applied automatically to newly uploaded documents).

When reviewing, use Bulk Metadata Management to download an Excel file containing metadata for the entire knowledge base. Sort or filter by this field to find documents overdue for review.

Update or delete the overdue documents, then enter new review dates and upload the metadata again.

Another approach is to represent “Version status” with tags (such as `Reviewed` and `Pending review`) and use Knowledge Base Tag Filtering to let the Agent reference only reviewed documents.

Change documents under review to the `Pending review` tag to exclude them from retrieval.

Metadata Management Page: Fields, Defaults, and Use During Retrieval

First define metadata fields under "Metadata Management" on the left of the knowledge base settings page. You can then enter values for individual documents and FAQs. The description at the top explains: "Metadata fields provide additional structured information for documents to help organize and retrieve content. After you set global defaults, newly uploaded documents will automatically use them." The list contains these columns:

Field	Description
Field Name	The metadata key, such as `url` or `version`
Type	Default = built-in system field; Custom = a field you created with "Add Custom Field"
Field Description	A description of its purpose for administrators
Default Value	Applied automatically to newly uploaded documents; displays "(None)" when unset
Retrieval Settings	A check mark indicates that "Use During Retrieval" is enabled
Actions	Edit, Delete (requires knowledge base edit/delete permissions)

When you click "Add Custom Field" or "Edit", fill in:

Field Name: Must start with a letter, contain only letters, numbers, and underscores, and be no longer than 50 characters.

Field Description: Optional, up to 200 characters, such as "Link to the cited document".

Default Value: Optional. The interface explains: "Set a global default value; newly uploaded documents will automatically use it." Existing documents are not backfilled. Use Bulk Metadata Management to populate their values.

Use During Retrieval: When enabled, the interface explains: "Send this information to the LLM during retrieval to support answer evaluation and reference." When a fragment is retrieved, this metadata value for the document is also passed to the Agent. This suits information that affects answers, such as "Document version", "Applicable region", and "Effective date". Fields such as `url` used only for Custom URL Mapping do not need this enabled, saving tokens.

> Editing a field affects all documents using it. Deleting a field removes its data from all documents and cannot be undone.


Add Metadata to a Document

Go to the documents page and click Edit Document Information:



Switch to the metadata tab and enter metadata mappings

MaiAgent uses key-value mappings to access metadata





After entering values, click “Add Metadata” to add the key-value mappings you entered (you can add multiple metadata entries at once).



The new metadata then appears in the fields.

Add Metadata to an FAQ

Open FAQ management in the knowledge base, select the FAQ to edit, and click the Edit button



Switch to the metadata page, enter values, and click Add Metadata

After entering all values, click “Confirm”



The added metadata appears in the FAQ list



Custom URL Mapping

url is a reserved word in the metadata system. If you set `url: https:// ... your-specified-url`, this URL replaces the original file location when users view cited fragments in a conversation, opening the URL you specified instead.

Example Scenario: A Brand’ s Spring Sale

Original Settings:

```
title: "2025 Spring Sale Details"
content: "This promotion includes 20% off storewide, gifts with qualifying
purchases, and other offers ... "
url: https://www.yourstore.com/spring-sale-2025
```

Result: When a user asks “What offers are available in the spring sale?” in a conversation:

AI references this knowledge fragment to answer the question

Clicking the cited source does not open the internal file location

Instead, the user goes directly to the official promotion page at https://www.yourstore.com/spring-sale-2025

The user can immediately see the latest promotion details, purchase buttons, countdown timers, and other dynamic content

Practical Uses:

Website announcements: `url: https://www.company.com/announcements/system-maintenance`
Product specifications: `url: https://www.product.com/specs/model-x1`
Customer support policies: `url: https://support.company.com/return-policy`
Event registration: `url: https://events.company.com/register/webinar-2025`

This makes AI answers more useful: they provide information and guide users directly to relevant pages to take action, improving the user experience and conversion rate.


Before Setting url

As shown below, before you set a url value, clicking any citation node (such as 初級露營.pdf) lets you view the original document (you can configure whether users may download original files on the conversation platform):

> Conversation Platform - Allow Downloads of Cited Documents




View citation nodes



View the original file location

After Setting url (Using Google as an Example)



Clicking the cited file node (露營注意事項.txt) again opens the Google homepage instead of displaying a document preview:





Once you set the `url` metadata field, users who see the Agent cite that document in a conversation can click it to open your specified link and obtain more complete information

Move Knowledge Base Files

When you need to reorganize a knowledge base (for example, split it by department or product line, or archive outdated information), use the "Move Files" feature to move files in batches to another knowledge base in the same organization. Moving files **does not re-parse or vectorize them**, and their file IDs remain unchanged. This makes it quick to move even large numbers of files without additional processing charges.

> You can move up to 1,000 files at a time. For more files, split them into batches. Moves run in the background, so you can continue other operations while they are in progress.

1. Open the Move Dialog

There are three entry points, all of which open the same **Move Knowledge Base Files** dialog. The only difference is which source knowledge base or files the system preselects for you.

Entry Point 1: Top Right of the Knowledge Base List Page

Click **Knowledge Base** in the left menu to open the knowledge base list page, then click **Move Files** at the top right of the page. This entry point does not preselect a source and is useful when planning moves between multiple knowledge bases at once.



Entry point 1: The Move Files button at the top right of the knowledge base list page

Entry Point 2: Move Icon in the Knowledge Base List

In the knowledge base list, click the move icon in a knowledge base's "Actions" column. This entry point **preselects that knowledge base as the source** and is useful when you want to reorganize a specific knowledge base.



Entry point 2: The move icon in the knowledge base list's "Actions" column

Entry Point 3: Select Files in the Knowledge Base Document List

Open the **Documents** list on a knowledge base's settings page, select the files you want to move, and click **Move Files**. This entry point **locks the source to the current knowledge base** and preselects the files you just selected. After choosing a target, you must still click "Move In" to add them to the pending move list. This is useful when selecting files to move as you browse documents.



Entry point 3: Select files in the document list on the knowledge base settings page, then click Move Files

2. Understand the Move Dialog

The **Move Knowledge Base Files** dialog has two columns: the left column shows files in the source knowledge base, and the right column shows files in the target knowledge base. Buttons between the columns move files from one side to the other:



Overview of the Move Knowledge Base Files dialog

Component	Location	Description
Source Knowledge Base dropdown	Top left of the dialog	Select the knowledge base where the files currently reside
Target Knowledge Base dropdown	Top right of the dialog	Select the knowledge base to move the files to. The target must use the same vector settings as the source; when you submit the move, the system also checks that you have delete permissions for both the source and target
Swap button	Between the two dropdowns	Quickly swap the source and target without selecting them again
Search box	One in each column	Search by file name to quickly find files to move when there are many files
Select all checkbox	Top of each column's file list	Select all files in the current list at once (selecting all after searching selects only the search results)
Move In button (→)	Between the two columns	Add selected files from the left column (source) to the pending move list
Move Back button (←)	Between the two columns	Add selected files from the right column (target) to the pending reverse move list; both directions can be processed in the same batch

Component	Location	Description
Pending move indicators	File rows	Files added to the pending move list are labeled "Pending Move In" or "Pending Move Back"; they have not actually been moved yet
Persistent reminder	Bottom of the dialog	"File IDs remain unchanged · No re-parsing or vectorization · Up to 1,000 files per move" reminds you of the feature's three key characteristics

> The dialog's "edit permissions" message does not mean that move authorization has been granted; submitting a move still requires delete permissions for both knowledge bases. Until you click Confirm Move, all "Move In
> Move Back" actions only edit the pending move list. The files have not actually moved, so you can freely adjust the list as often as needed.

3. Steps

Select the Source and Target Knowledge Bases

Select the **Source Knowledge Base** and **Target Knowledge Base** at the top of the dialog. The target dropdown excludes the source itself and filters knowledge bases by vector settings. Use the swap button between them to quickly swap the source and target. Seeing a knowledge base in the dropdown does not guarantee that you can complete a move; submitting it still requires passing the delete permission checks for both the source and target.

Select Files and Add Them to the Pending Move List

Select files in the left column (source) and click **Move In** (→) to add them to the pending move list. You can also select files in the right column (target) and click **Move Back** (←) to move them in the reverse direction. Both directions can be submitted in the same batch. When there are many files, filtering with the search box before selecting all is much faster.



Selected files added to the pending move list; file rows show Pending Move In Pending Move Back

> Moving files clears all their existing tags and Metadata (because tag definitions belong to the original knowledge base). To preserve them, first create tags with the same names in the target knowledge base, then reapply the tags after the move. When you add files to the pending move list, the system displays a reminder: "Tags will be cleared for N files."

Confirm the Move

The bottom of the dialog shows the number of files pending a move. Check the counts, then click **Confirm Move**.



The bottom shows pending move counts; click Confirm Move to submit

After submission, the move runs in the background and the screen shows "Move in Progress." You can work on other tasks while it runs.



The move runs in the background without affecting other operations

View the Move Results

When the move finishes, "Move Results" appears with three summary cards: **Completed**, **Skipped** (already in the target knowledge base), and **Failed** (files remain in their original knowledge base). Reasons are listed for each file.



Move Results page: 1 completed, 0 skipped, and 0 failed; click "Move Another Batch" to continue

If any files failed, click **Rerun This Batch**—rerunning is safe: files already moved are skipped and will not be processed again.

To continue organizing other files, click **Move Another Batch** to return to the selection screen.

Move results are retained for 7 days, during which you can return to view them and rerun the batch.

4. Limits and Notes

Item	Description
Permissions	You need **delete permissions** for both the source and target knowledge bases; edit permissions alone are insufficient. Organization owners automatically have full permissions and need no additional configuration
Scope	Moves are limited to knowledge bases within the same organization; knowledge bases in other organizations do not appear in the dropdown
Vector settings	The target knowledge base must have the same vector settings as the source; those with different settings do not appear in the dropdown
Files being parsed	Files that are still being parsed cannot be moved; wait for parsing to finish before moving them
Per-move limit	1,000 files; move larger numbers in batches
Files with the same name	The system does not deduplicate or rename files. If the target knowledge base already has a file with the same name, both files will exist after the move. Check before moving files
Tags and Metadata	All are cleared after a move and must be reapplied in the target knowledge base (see preservation steps below)

Why Must the Target Knowledge Base Have the Same Vector Settings?

Moves require "no re-parsing or re-vectorization" because the system reuses the files' existing parsing results and vector data, changing only the knowledge base they belong to. Vector data is generated using the knowledge base's vector settings—if the target knowledge base uses different settings, the source vectors cannot be retrieved correctly in the target. The system therefore checks this upfront: the **Target Knowledge Base** dropdown only lists knowledge bases with the same vector settings as the source.

If you need to move files to a knowledge base with different vector settings, **upload the original files again to the target knowledge base** so that the system parses and vectorizes them using the target knowledge base's settings.

Why Are Tags Cleared? How Can I Preserve Them?

Tag definitions (names and purposes) are created within individual knowledge bases, rather than shared across the organization. Tags from the source knowledge base do not exist in the target knowledge base, so all existing tags and Metadata are cleared when files are moved.

If tags are important to your retrieval or management workflow, follow these steps:

Before moving files, record (or take screenshots of) the tags currently applied to them.

Create tags with the same names in the target knowledge base.

Move the files.

After the move, **reapply tags to the files** in the target knowledge base's document list.

5. Errors and Troubleshooting

Scenario	System Behavior	Recommended Action
Some files do not meet the requirements at submission (for example, they are still being parsed)	**The entire batch is rejected**: no files are moved, and reasons are listed for each file	Remove the problem files based on the reasons shown (for example, remove files being parsed from the pending move list), then submit again
Files are being moved by a previous batch	The system says they cannot be added and provides a "Remove These N Files" button	Click "Remove These N Files" to move the remaining files first, then handle these files after the previous batch finishes
Some files fail during the move	Failed files **remain in their original knowledge base**, and the results page lists the reasons for each file	Click **Rerun This Batch** on the results page; files already moved are automatically skipped, and only failed files are retried

> Rejecting the entire batch is intentional: it prevents a partially completed move, with some files succeeding and others failing, from leaving knowledge bases in a state that is difficult to track. Remove files that do not meet the requirements before submitting to complete the move smoothly in one go.

6. Use Cases

Finance: Split a Shared Knowledge Base by Department

A bank initially stores credit card, mortgage, and wealth management documents in a single "Customer Service Knowledge Base." As the number of documents grows, its customer service Agent occasionally cites credit card promotional terms when answering mortgage questions. The administrator creates three knowledge bases—"Credit Cards," "Mortgages," and "Wealth Management"—with the same vector settings, then uses the move feature to move hundreds of documents in batches to the appropriate knowledge base by department. No re-parsing or vectorization is needed, and no additional processing charges are incurred. After the split, each department's Agent connects only to its own knowledge base for more focused answers.

Manufacturing: Organize Catalogs and Specifications by Product Line

An electronic component manufacturer's sales inquiry Agent originally shares a "Product Documents" knowledge base containing catalogs and specifications for three product lines: connectors, cables, and power modules. During an update, the administrator uses the search box in the knowledge base document list to filter for connector files, selects them, and clicks **Move Files** (entry point 3) to move them to a new "Connector Product Line" knowledge base. The administrator then handles the other product lines in the same way. Because file IDs remain unchanged, records that reference them in internal workflows are unaffected.

Education: Archive Documents at the End of Each Semester

A university's admissions and academic affairs Agent knowledge base contains many course announcements and calendars for the current semester. At the end of the semester, the administrator moves outdated documents to a "Past Semester Archive" knowledge base. The active knowledge base stays concise, and the Agent no longer cites outdated information, while the archive remains available to an internal query Agent. Repeating this process each semester establishes a regular knowledge base lifecycle management process.

Healthcare: Reorganize Patient Education Materials by Department

A hospital originally stores all patient education materials in a single knowledge base, then decides to split them by department (family medicine, orthopedics, obstetrics and gynecology, and so on) so that each department's LINE patient education Agent connects to the corresponding knowledge base. Because these files often have tags such as "Patient Education" and "Forms," the administrator first creates tags with the same names in each department's knowledge base, then reapplies them after the move to keep tag filtering working.

Retail and Hospitality: Switch Between Campaign Periods

After a peak-season campaign ends, a hotel chain moves room type and promotion documents for its "Summer Package" from the online customer service knowledge base to a "Campaign Archive" knowledge base, while moving documents for the new campaign into the active knowledge base. Because files can move in both directions in the same batch, a single operation switches out the old campaign for the new one.

7. Frequently Asked Questions

Q: Will Moving Files Re-parse or Vectorize Them? Will There Be Any Charges?

No. Moving files reuses existing parsing results and vector data, changing only the knowledge base they belong to. This makes moves fast and incurs no additional processing charges. This is what the persistent

reminder at the bottom of the dialog means: "File IDs remain unchanged • No re-parsing or vectorization • Up to 1,000 files per move."

Q: What If I Move Files by Mistake?

Open the move dialog again, swap the source and target (using the swap button between them), and move the files back. Note: if the files originally had tags, those tags were cleared during the first move. Moving the files back will not restore them automatically; you must reapply them.

Q: Why Can't I Find the Target Knowledge Base in the Dropdown?

The **Target Knowledge Base** dropdown excludes the source itself and filters knowledge bases by vector settings. If you cannot find a knowledge base, first check whether it belongs to **another organization** (moves between organizations are unsupported) or has different **vector settings** from the source. Even if you can select a target, confirming the move still checks that you have **delete permissions** for both the source and target. If you lack permissions, contact the organization owner to adjust your role permissions.

Q: Will a File in the Target Knowledge Base with the Same Name Be Overwritten?

No. Files are not overwritten, automatically deduplicated, or renamed—both files with the same name will exist after the move. To avoid duplicates, check the target knowledge base's file list before moving files, or manually delete the unwanted copy afterward.

Q: What If I Need to Move More Than 1,000 Files?

Split them into batches. Use the left column's search box and select all feature to group files by keyword. After each batch finishes, click **Move Another Batch** to continue.

Q: How Long Can I View Move Results?

Move results are retained for 7 days. During this time, you can return to view each file's result and click **Rerun This Batch** for failed batches.

PDF Document Translation

Feature Overview

MaiAgent provides AI-powered PDF document translation to translate PDF files in your knowledge base into a specified language. Each translation produces two versions:

Translated version: Contains only the translation in the target language

Bilingual side-by-side version: Displays the original text and translation side by side for easy comparison

Supported languages include the following (you can also select "Auto Detect" for the source language): Traditional Chinese, Simplified Chinese, Japanese, Korean, English, Thai, Burmese, Vietnamese, Spanish, French, German, Portuguese, Russian, Arabic, Italian, Dutch, Polish, and Turkish.

> Document translation currently supports only PDF files with extractable text. Scanned or image-only PDFs are not supported.

How to Translate a PDF Document

1. Open the Document Details Page

In the Documents tab of your knowledge base, click the PDF file you want to translate to open its details page.

2. Open Translation Settings

Click the Translate PDF button in the upper right corner. If the file has been translated before, the translation results dialog opens first. Click Translate Again to open the settings. If this is the first translation, the translation settings dialog opens directly.

3. Configure Translation Parameters

Field	Description
Source Language	The language of the original text. Defaults to "Auto Detect" so the system identifies it automatically
Target Language	The language to translate into (required)
Large Language Model	Select the LLM to use for translation

Field	Description
Custom Terminology/Prompt	(Optional) Guide the translation style or specify terminology mappings, for example: "Translate Hermione as 妙麗"

> The custom prompt supports up to 5,000 characters. Use it to specify proper nouns, brand names, or a particular translation style.

4. Start Translation

Click Confirm to run the translation task in the background. The status updates in real time during translation, and the results appear automatically when it finishes.

View Translation Results

After translation finishes, click the Translate PDF button to open the translation results dialog, which contains three tabs:

Result Preview

Preview the bilingual side-by-side PDF with the original text and translation displayed side by side.

Download Files

Three download options are available:

Original file: Download the original, untranslated PDF
Translated version: A PDF containing only the translation in the target language
Bilingual side-by-side version: A PDF with the original text and translation side by side

Processing Details

View complete statistics for the translation task:

Translation configuration: Source and target languages, and the LLM used
Processing statistics: Token usage, number of LLM calls, and processing time breakdown
File information: File sizes and character counts before and after translation
Timestamps: Creation, start, and completion times, and the final status

Translation Version Management

You can translate the same PDF multiple times, for example into different languages or using different models. Each translation is saved as a separate version.

Use the Select Translation Version dropdown at the top of the translation results dialog to switch between versions and view their results. The version format is: `Date | Source Language → Target Language | Model Used`.

To translate again, click the Translate Again button to open new translation settings.

Search Testing

Why Do You Need Search Testing?

Ensure Response Accuracy

The quality of Agent responses directly affects customer satisfaction

Incorrect or irrelevant answers damage brand trust

Avoid Information Gaps

Prevent important product details or safety instructions from being overlooked

Optimize how efficiently the knowledge base is used

Improve Q&A Consistency


Ensure the same question receives a consistent answer at different times

Avoid unstable responses caused by knowledge base updates

With search testing and chunk preview, you can instantly review the quality of the data chunks the Agent uses, ensuring your Q&A standards.

How to Get Started?


Go to the Knowledge Base page, select the knowledge base you want to view, and open its settings






Click "AI Search" on the left (the page title is "Knowledge Base Search Test")

Enter what you want to search for in the dialog box, for example "What should I pay attention to when choosing a campsite?" After you click the search button, the Agent searches for the documents most relevant to your input.



View the search results

The chunks the Agent retrieves when answering appear on the right. In the figure there are 12 chunks (for the retrieval chunk count setting, see: How to Create a Knowledge Base: Basic Settings)



The right side shows the content retrieved for this question. Each chunk displays:

Character count: the number of characters the chunk covers

Hit count: the number of times the Agent referred to this chunk when answering (only official Q&A is counted; test Q&A is not included in the hit count)

A higher hit count means users ask more questions about this chunk.

Collapse All
Expand All at the top right of the search results area collapses or expands all chunks at once. Each chunk can be switched between Original Text and Highlight Keywords, and you can click Preview to open the corresponding position in the original document (results missing document information show "Preview unavailable").

The clock icon next to the search box is "Search History": it keeps the 10 most recent queries on this browser. Click any entry to search again, which makes it easy to compare results before and after your adjustments using the same set of questions. Clear History removes them all. History is stored only in your browser and is not visible on other devices or to other members.



AI Summary

The "AI Summary" switch next to the search box is on by default. After each search, in addition to listing the chunks, a summary compiled by the LLM from those chunks appears above them, so you can see directly whether this set of chunks can answer the question without reading every chunk.

The drop-down menu next to the switch lets you select a model (the system setting is used by default). Switch models when you want to compare how well they summarize.


The summary is an additional LLM call and consumes your organization's Credits based on the selected model. If you only want to see retrieval results, turn the switch off.

"AI Summary is not enabled. Please contact your administrator" means your organization has not configured an available model. For "Insufficient Credit balance to generate an AI summary", top up first. "No search results, unable to generate a summary" means there are no chunks to summarize; rewrite the question or check the documents.

> AI Summary is used only on this test page and does not represent the Agent's actual reply in a conversation: the Agent also applies role instructions, the reply mode, and other settings. To review full reply quality, go to Automated Evaluation and Agent Monitoring.

Check Knowledge Chunk Quality

Search testing shows which chunks the Agent uses when reasoning, so you can check whether their content needs improvement, such as:



If you find many blank chunks in the search results, and they all belong to the file "Beginner Camping.pdf", you can check whether the contents of "Beginner Camping.pdf" are all correct and update it right away, **before going live**.

Search Modes and Query Metadata Conditions

On the left side of the search test page you can adjust two things: which method is used to search, and which documents or tags the search is limited to.

Choose a Search Mode

Under Search Mode, choose one:

Search Mode	How It Searches	Best For Testing
Hybrid Search (default)	Matches both meaning and keywords, then merges the results	General questions; closest to how the Agent retrieves in conversations
Semantic Search	Matches meaning only, so it finds results even when the wording differs	Natural-language questions
Keyword Search	Matches words only	Whether product models, proper nouns, and codes can be found

> The search mode only affects this search test. In Agent conversations, the retrieval method configured on the platform is always used (hybrid search by default; see Technical Manual - Hybrid Search). Keyword Search supports only Elasticsearch and is unavailable when the knowledge base is connected to another type of bring-your-own vector database.

Do Search Results Have Relevance Scores?

Chunks in the search test are sorted from most to least relevant, but **no scores are shown**, and the response of the Knowledge Base Retrieval API does not include scores either; use the ranking to judge relevance. The Relevance percentage on a Web Chat citation node is the score the Agent gave the cited chunk at the moment it answered; see Citation Display. When a search returns no chunks, the screen shows no results; with AI Summary on, it shows "No search results, unable to generate a summary".

What Are Query Metadata Conditions?

Query Metadata limits the scope of a search to specified files, FAQs, or documents that match specified tag conditions. It is the same kind of condition as the query metadata set on contacts and conversations,

so you can use search testing to simulate which chunks would be retrieved when a given contact asks a question. For the concept, see Query Metadata.

How to Set Query Metadata Conditions

In the Query Metadata section on the left of the search test page, click Query Builder at the top right. If the knowledge base has no documents or FAQs yet, this button cannot be clicked.

In the Query Builder, select the documents or FAQs to include. To filter by tag, turn on tag filtering and set the conditions. The operation is the same as in Query Builder.

After you confirm, the Query Metadata section shows the current conditions as JSON and indicates how many conditions there are.

Enter a question and click Search. The results include only chunks within the conditions.

When to Use It

Verify permission scope: Confirm that, after a set of conditions is applied, documents that should not be visible are indeed not retrieved.

Narrow down troubleshooting: When the results for a question include other documents, first limit the test to the expected documents to determine whether the problem lies in the content itself or in the retrieval scope.

Practical Use Cases

Membership-tier content: A product price list is open only to VIP members. In the Query Builder, select only the documents or tags that regular members can see, ask "How much does it cost?", and confirm that no chunks from the price list appear in the results.

Model number lookups: Customers often ask using model numbers, for example "How long is the warranty for the A100?" Switch to Keyword Search to test whether the model number can be found; if not, check whether the way the model number is written in the documents matches how customers write it.

How Search Testing Helps You

Test Key Questions Regularly

Test questions related to your core business often

Re-test after the knowledge base is updated

Record and compare how test results improve

Identify Content Gaps

Find knowledge gaps: test common questions to find queries that return no hits at all

Example: testing "waterproof rating of tents" finds no relevant chunks → add a waterproof specification document

> The platform does not automatically record user questions for which no content was retrieved, and there is no report of zero-result queries. To find knowledge gaps from real conversations, use the "Knowledge base gap" category in Conversation Platform Analytics, or review the chunks actually retrieved for each answer in Agent Monitoring, then add the missing content to the knowledge base.

Evaluate Content Completeness

Check answer depth: confirm whether the AI's answer covers every aspect of the question

Example: query "camping safety precautions" → check whether it covers weather, wildlife, fire safety, and other aspects

Query Testing Techniques

You can:

Ask the same question in different ways

Test complex scenarios and multi-condition queries

Verify retrieval of technical terms and product names

With these testing techniques, you can comprehensively evaluate the accuracy and completeness of replies.

Database



Text to SQL: Natural language → SQL query → Plain-language response

What is this?

Databases let Agents query structured data using natural language. When a user asks, "How many laptops did we sell last month?", the Agent automatically converts the question into a SQL query, retrieves the answer from the database, and responds in plain language.

The technical name for this feature is **Text to SQL**.

When do you need it?

Use it when your scenario involves:

Data queries: Order status, inventory levels, sales revenue

Statistical analysis: "How much did sales grow this quarter compared with last quarter?"

Real-time status: "How many tickets are currently pending?"

The answers to these questions are stored in structured tables rather than documents, so you need a database rather than a knowledge base.

Which databases are supported?

Type	Description
MaiAgent built-in database	A database included with the platform; upload Excel, CSV, or JSON files to automatically create tables
External database	Connect to your PostgreSQL, MySQL, SQL Server, Oracle, or SynxDB database

Is it secure?

Agents only execute **read-only queries** (SELECT) and do not modify or delete your data. For external databases, use Specify tables to restrict which tables the Agent can query. The permissions of the

database account you provide determine which tables and columns are actually accessible. We recommend using a read-only account. For sensitive columns, use a view that includes only the necessary columns.

Advanced note: Text to SQL accuracy depends on how clearly your tables are structured. Add Chinese descriptions to tables and columns to help the Agent understand what each column means.

What do I need to do?

Create a database — Upload a spreadsheet to create a MaiAgent database, or enter the connection string for an external database, then turn on Enable database

Configure queryable tables — For external databases, use Specify tables to narrow the scope

Add column descriptions — Add descriptions to tables and columns to improve query accuracy

Link the database to an Agent — The Agent must use Agent mode; select the database in Database settings

Test queries — Ask questions in natural language in a conversation to confirm that the Agent queries the data correctly

Further reading

Text to SQL feature

Create and configure a database

Text to SQL with a MaiAgent database

Text to SQL with Supabase

Text to SQL Features

What is Text to SQL?

Text to SQL (also known as Text2SQL) is an intelligent tool that automatically converts **natural language questions** (everyday human language) into **SQL database query statements**. Simply put, it enables an Agent to "understand human language" and directly operate on databases.

> To learn more about Text2SQL, see: Technical Manual — Text to SQL

Imagine you are a convenience store owner:

Traditional approach:

You: "Help me check how many bottles of cola were sold yesterday"

Employee: "Boss, you need to teach me how to use the POS system to query..."

You: "Click here, select there, enter conditions..."

Requires hands-on instruction, which is time-consuming.

With Text2SQL:

You: "Help me check how many bottles of cola were sold yesterday"

AI Employee: "Sure!" 💫 *(automatically generates the query method and calls the database)* → "87 bottles of cola were sold yesterday" ✅

Core Features of Text to SQL

```
Natural language question → AI understanding & analysis → SQL query statement →
Execute query → Return results
```

When you ask the Agent "Find the best-selling beverage from yesterday," the Agent first analyzes your question, understands that you want to find a "beverage" that sold the "best" "yesterday," then generates SQL syntax to query the database, and finally tells you the result: "cola."

What Text to SQL Can Help AI Accomplish

Use Cases

🏥 Medical Clinic

```
Doctor asks: "Find today's appointments for diabetic patients"
AI responds: "There are 5 diabetic patients with appointments today:
- Mr. Wang 10:00 follow-up visit
- Mrs. Li 14:30 follow-up checkup
- Ms. Chen 16:00 blood sugar monitoring"
```

🏫 School Management

```
Teacher asks: "How many students failed this exam?"
AI responds: "This math exam:
- Total students: 45
- Failed: 8 (17.8%)
- The list of students requiring a makeup exam has been compiled"
```

🏪 Retail Chain Store

```
Store manager asks: "Compare the monthly revenue of three branches"
AI responds: "November revenue comparison by branch:
- Taipei store: $1,200,000 (↑15%)
- Taichung store: $950,000 (↑8%)
- Kaohsiung store: $800,000 (↓3%)"
```

Advantages of Text to SQL

⚡ Efficiency Improvement

Traditional approach: Requires an SQL expert to write queries → 30 minutes

Text2SQL: Ask in natural language → 3 seconds

🎯 Lower Barrier

No need to learn complex SQL syntax

No need to memorize database structure

Anyone can query data

📱 Real-Time Interaction

Ask and get answers immediately

Supports follow-up questions

Dynamically adjust query conditions

How to Use Text to SQL in MaiAgent

Databases are created in one central place under AI Features → Database in the left menu. One database can be used by multiple Agents, and one Agent can be linked to multiple databases. Setup takes three steps:

1. Create and Enable the Database

On the Database page, click Add Database and select the database type:

MaiAgent database: Use this if you don't have your own database. Upload an Excel, CSV, or JSON file and the system automatically creates the tables. No connection string is needed. See Using a MaiAgent Database for Text to SQL.

External database: Connect to an existing PostgreSQL, MySQL, SQL Server, Oracle, or SynxDB database. You need to enter a connection string and first confirm that the database allows connections from MaiAgent.

Newly created databases are disabled by default. Turn on Enable Database before the Agent can query it. For the complete steps, the connection string format for each database, and the network checklist, see Create and Configure a Database.

2. Switch the Agent to Agent Mode

In the Agent's Settings, click Response Mode Settings in the left navigation and select Agent Mode.

> Text to SQL is only available in Agent Mode. For Agents in other response modes, Database Settings in the left navigation is locked and no database can be selected. For details about each response mode, see Create an Agent.

3. Link the Database to the Agent

Choose either of the following methods:

In the Agent's Settings, click Database Settings in the left navigation, click Select Database, check the databases to query, and then click Save.

On the database settings page, open the Linked AI Assistants tab, move the Agent to the right side, and save. See Link Agents and Group Permissions.

Once setup is complete, you can query data with natural language in the Agent's conversation, for example, "Which product sold the most last month?"

Troubleshooting

Connection failed: Check the connection string format, username and password, and whether the firewall and allowlist are open. See Create and Configure a Database: Network Prerequisites.

The Agent does not query the database: Confirm that the response mode is Agent Mode, the database is enabled, and it is linked to this Agent.

The Agent only queries the database and replies that it has no knowledge base retrieval tool: In Agent Mode, knowledge base retrieval is also a set of tools (`retrieve_text_nodes`, etc.). When Enable Tool Search is on, these tools must be found by search before they can be called, just like Text to SQL, and the model occasionally skips the search and answers that it has "no tools." Write "Query the knowledge base with retrieve_text_nodes before answering" in the role instructions, or turn off tool search so that all tools are directly available. See Configure Tools for an Agent. For the differences in retrieval between the two modes, see Technical Manual - How Chat Mode and Agent Mode Query the Knowledge Base.

You want to restrict certain users to part of the data: Query metadata only restricts knowledge base retrieval and does not apply to Text to SQL. The scope of a database can only be controlled by enabling it/linking Agents, Specify Tables, and role permissions; it cannot be restricted per request. If you need to separate access by user, create different Agents and database connections (or read-only accounts) for different identities.

Query error: Verify that table names and column names are correct, and add descriptions to tables and columns. See Edit Column Descriptions.

Insufficient permissions: Check whether the database account has read permission on these tables.

Slow response: Check query complexity, consider adding indexes, or narrow the query scope with Specify Tables.

For specifications (read-only protection, network requirements, handling of large schemas, and query result limits), see Technical Manual - Text to SQL.

Text2SQL turns the Agent into a database expert, allowing anyone to quickly obtain business insights using natural language, greatly improving the efficiency of data-driven decision making!

Create and Configure a Database

MaiAgent's **Database Management** feature lets you centrally manage the database connections used by your Agents. With Text to SQL, Agents can query data in your databases directly using natural language.

> For an introduction to Text to SQL, see: Text to SQL

MaiAgent supports two database types:

MaiAgent Database: Upload Excel
CSV
JSON files to have the system automatically create tables. Suitable for users without their own databases

External Database: Connect an existing PostgreSQL, MySQL, SQL Server (MSSQL), Oracle, or SynxDB database

Network Prerequisites (External Databases)

Before connecting an external database, confirm the following with your organization's IT team or database administrator. These settings are unnecessary if you only use MaiAgent databases (spreadsheet uploads).

[ ] **Allow inbound connections from MaiAgent**: MaiAgent initiates connections to your database (when you click "Test Connection" and whenever an Agent runs a query). Your database does not need to initiate connections to MaiAgent.

[ ] **Open the connection port**: The defaults are PostgreSQL 5432, MySQL 3306, SQL Server 1433, Oracle 1521, and SynxDB 5432 (depending on deployment settings). If you use a different port, use the port specified in `host:port` in the "Connection String".

[ ] **MaiAgent cloud service**: If your database has a firewall or security group, allowlist MaiAgent's outbound IP addresses (contact your MaiAgent representative to obtain them), and open only the ports listed above.

[ ] **On-premises**
private cloud deployments: Ensure that the network segments and ports between the MaiAgent host and database host can communicate. The database does not need to be exposed to the internet.

[ ] **Use a read-only account**: Create a dedicated read-only account for MaiAgent and grant access only to the tables the Agent needs. For tables containing personal data or other sensitive columns, you can create a view containing only the necessary columns and grant access to that view. "Specified Tables" only narrows the scope the Agent references; the account's permissions determine which data it can actually read.

For details on how the platform blocks write statements, the level of read-only protection for each database, and network requirements, see Text to SQL: Read-only Protection and Network Requirements

in the technical manual.

Create a Database

1. Open the Database Management Page

In the left navigation bar, go to “AI Features” and click “Databases”. The page has two tabs: MaiAgent Databases and External Databases.

Click “Add Database” in the upper-right corner to begin.



Database management page showing the list of MaiAgent databases

> If the button is grayed out, your role has not been granted permission to create databases. Contact your organization administrator to configure permissions.

2. Select a Database Type

Select the type of database you want to create, click its card, and then click “Next”：

MaiAgent Database: For uploading spreadsheet files; no connection string is required

PostgreSQL
MySQL
SQL Server
Oracle
SynxDB: Connect an existing external database in your organization



Step 1: Select a database type

3. Enter Basic Information

MaiAgent Database

Field	Required	Description
Database Name	Yes	For example, “2024 Sales Data”
Description	No	Additional information about the database's purpose or contents

MaiAgent databases do not require a connection string; the system handles data storage automatically. Simply upload spreadsheet files after creating the database.



Step 2: MaiAgent database settings screen

External Database


Field	Required	Description
Database Name	Yes	For example, “Corporate ERP Database”
Description	No	Additional information about the database's purpose or contents
Connection String	Yes	The database connection URL

Field	Required	Description
Specified Tables	No	Limit the tables the Agent can query; separate names with commas

Connection string formats are shown below (the format for the selected type also appears below the field):

```
PostgreSQL:   postgresql://使用者名稱:密碼@主機位址:連接埠
資料庫名稱
MySQL:        mysql+pymysql://使用者名稱:密碼@主機位址:連接埠
資料庫名稱
SQL Server:   mssql+pyodbc://使用者名稱:密碼@主機位址:連接埠
資料庫名稱?
driver=ODBC+Driver+18+for+SQL+Server&TrustServerCertificate=yes&Encrypt=no
Oracle:       oracle+oracledb://使用者名稱:密碼@主機位址:連接埠
?service_name=服務名稱
SynxDB:       postgresql://使用者名稱:密碼@主機位址:連接埠
資料庫名稱
```

Make sure the connection string uses the correct format and includes all required connection information. Its prefix must match the format above; otherwise, an “Invalid connection string format” message appears and you cannot proceed to the next step. Also confirm that your database allows connections from MaiAgent; see Network Prerequisites.



Step 2: External database (PostgreSQL) settings screen

After entering the connection string, we recommend clicking "Test Connection" to verify connectivity (you can also skip the test and save directly):

Connection successful: MaiAgent can access your database

Connection failed: Check the connection string format, username and password, and whether your firewall, allowlist, and ports permit access as described in Network Prerequisites

If your database contains many tables, enter the names of the tables you want to make available (for example, `customers, orders, products`) in "Specified Tables" to improve query efficiency and security. Leave it blank to query all tables.

4. Configure Role Permissions

The final step is to specify which roles can access this database. Choose one option under “Quick Permission Scope Selection”:

All Roles: Allow members of all roles in the organization to use this database

Exclude Default Roles: Allow only custom roles, excluding default roles

Select Custom Roles: Manually select specific roles by moving the roles to authorize from “Available Roles” to “Selected Roles”



Step 3: Quick permission scope selection

> If you do not need to configure role permissions yet, skip this step and adjust them later in the “Role Permissions” tab on the database settings page.

5. Complete Creation

After confirming all settings, click “Create Database” (MaiAgent databases) or “Save” (external databases). Once created, the database settings page opens for further configuration.

New databases are disabled by default. Enable “Enable Database” in the “Basic Information” tab and save, or toggle “Enabled” in the database list, before the Agent can use this database for Text to SQL queries.

After creation, remember to link the database to an Agent so the Agent can use it for queries. See: Link Agents and Group Permissions

Upload Files to Create Tables (MaiAgent Databases)

After creating a MaiAgent database, open its settings page and switch to “Table Management”. Click “Upload Table File”, select a file or drag it into the upload area, then click “Upload”.



Table Management tab, with tables grouped by source file

Supported File Formats

Format	Extension	Description
Excel	`.xlsx`, `.xls`	A separate table is created for each sheet
CSV	`.csv`	Comma-separated values file
JSON	`.json`, `.jsonl`	JSON data file

After upload, the system automatically parses the file structure and creates tables in the background. Tables are grouped by source file and show their processing status:

Status	Description
Pending	The file has been uploaded and is waiting for processing
Processing	The system is parsing the file and creating tables
Success	The table has been created and can be queried by Agents
Failed	An error occurred during creation; hover over the error icon to see the cause
Deleting	The table is being removed in the background
Deletion Failed	Removal did not complete; try deleting again

Tables labeled "From Knowledge Base" below the source file name were not uploaded here. They were synchronized when someone uploaded a structured file to a knowledge base and chose to use a database instead. The knowledge base and database each have their own copy of the file; deleting one does not affect the other.

Table Names and Repeated Uploads

The system generates table names in the format `table_<檔名>_<10 碼雜湊>`. It takes the uploaded file name without its extension, keeps only Chinese and English characters, numbers, and underscores, and limits it to 45 characters. The hash is calculated from the file ID for this upload and the sheet name. For example, uploading the "Q1" sheet in `2024 銷售.xlsx` produces `table_2024銷售_` followed by a 10-character hash. The Agent uses this name when querying, so we recommend specifying the source file and sheet in the Table Description.

Each Excel sheet becomes a separate table. Successfully created tables are automatically added to the database's Specified Tables.

Uploading a file with the same name does not overwrite existing tables: Every upload receives a new file ID and therefore a different hash, creating another set of tables. Existing tables and column descriptions remain unchanged, and the Agent sees both sets. To update data, first delete the old tables (or the entire source file) in Table Management, then upload the new file. Column descriptions are not retained after deletion, so record them beforehand.

Tables synchronized from a knowledge base (labeled From Knowledge Base) follow the same naming rules. Deleting them on either side does not affect the other.

File Format Notes

[x] The first row must contain **column names**

[x] Each column must use a consistent **data type** (for example, all values in a price column should be numbers)

[x] Avoid **merged cells**

[x] Avoid **duplicate column names**

[x] Each sheet in an Excel file must contain **only one table**

> Common causes of table creation failures include incorrect or corrupted file formats, special characters in column names, duplicate column names, and inconsistent data types within a column.

Edit Column Descriptions

Column descriptions are a **key setting** for improving Text to SQL query accuracy. Agents use these descriptions to understand what the data means and generate more accurate SQL queries.

For example, if a table contains a column named `status`, the Agent may not know what it represents. Adding a description such as "Order status; possible values: pending (awaiting processing), completed (finished), cancelled (canceled)" helps the Agent understand the column correctly.

How to Edit

MaiAgent Database: In the "Table Management" tab, click the "Edit" icon in the table's actions column to open "Edit Table Information". Enter the "Table Description" and each "Column Description", then click "Save". The dialog shows progress (for example, "3
10 columns configured").



Edit Table Information: enter table and column descriptions

External Database: In the "Table Schema Descriptions" section at the bottom of "Basic Information", click "Add Table". Enter the "Table Name" and "Columns and Their Purpose", then click "Save".

Writing Suggestions


> Good column descriptions can significantly improve AI query accuracy:

Column Name	Poor Description	Better Description
`amt`	Amount	Total order amount (NTD), including tax and shipping
`cust_lvl`	Level	Customer tier: A for VIP customers with annual spending over 1 million, B for annual spending of 100,000–1 million, and C for all others
`reg`	Region	Customer's geographic region; possible values: northern, central, southern, eastern, offshore islands

Manage Existing Databases

Edit a Database

In the database list, click the "Edit" icon in the actions column to open the settings page.



Database settings page: Basic Information tab

The settings page contains the following tabs:

Tab	Description	Applicable Types
Basic Information	Edit the name, description, and enabled status; for external databases, also change the connection string, specified tables, and table schema descriptions	All
Table Management	Upload files and manage tables and column descriptions	MaiAgent only
Linked AI Assistants	Specify which Agents can use this database	All
Role Permissions	Configure role access permissions	All

> For security, passwords in external database connection strings are masked. To modify a connection string, click "Change" and enter the complete new connection string.

Enable
Disable

Use the “Enabled” toggle in the database list to quickly change its status. When disabled, Agents temporarily cannot query the database, but its settings and data are retained.

Delete a Database

Click Delete in the database list's actions column to open the “Delete Database” confirmation dialog, which asks “Are you sure you want to delete ‘Database Name’ ?” . For MaiAgent databases, the dialog also shows a “Before You Delete” reminder: tables in this database may have been synchronized from knowledge base files. To remove everything, also check the knowledge base for files that need to be deleted. Once deleted, this database and all its table data cannot be recovered. For external databases, the dialog states, “Once deleted, this database connection configuration cannot be recovered.” Click Confirm Deletion to proceed.

> Deleting a database is irreversible. MaiAgent Database: All tables created through file uploads are removed along with the database. For tables synchronized from a knowledge base, the files in the knowledge base are retained External Database: Only the connection configuration in MaiAgent is removed; data in the original database is unaffected

Text to SQL with a MaiAgent Database

To have an Agent help you analyze spreadsheet data such as Excel and CSV, just upload the files to the MaiAgent database. The Agent can then query the data in natural language and produce statistical analysis results.

> For an introduction to the Text to SQL concept, see: Text to SQL Feature

Step 1: Create a MaiAgent Database

From the left navigation bar, go to "AI Features" > "Database"
Click "Add Database"
Select "MaiAgent Database"
Enter a database name (for example, "2024 Sales Data") and click Create

> For the detailed creation process, see: Create and Configure a Database

Step 2: Upload a Spreadsheet File

After it is created, open the database settings page:

Switch to the "Table Management" tab
Click "Upload Table File"
Drag and drop or select your spreadsheet file

You can download the sample file (a food sales file with 100 items, .xlsx) to test with and experience the Agent's data analysis capabilities.

After the upload finishes, wait until the processing status shows "Success", which means the table has been created.

> Supported formats: .csv, .xlsx, .xls, .json, .jsonl. Each worksheet in an Excel file creates its own table.

Table Format Notes

[x] Each worksheet (Sheet) must contain exactly one table
[x] The first row must contain the column names

[x] It is recommended to note the data type after each column name, such as `Price(int)`, `Date(datetime)`

[x] The data type of each column should be consistent

[x] If there are special formats (such as currency or percentages), unify the formatting before uploading

> To improve the accuracy of AI queries, it is recommended to add descriptions to tables and columns. See: Create and Configure a Database - Edit Column Descriptions

Step 3: Link the Agent

Link the database to your Agent so the Agent can query the data:

Switch to the "Link AI Assistant" tab

Select the Agent to link on the left and move it to the right

Click "Save"

> Make sure the Agent's reply mode is set to Agent mode; otherwise the Text to SQL feature cannot be used. For detailed reply mode settings, see: Create an Agent


Step 4: Chat with the Agent

After completing the steps above, open the Agent's chat page and tell the Agent what you need in natural language.

> For the Agent chat interface, see: Choose an Integration Platform, and pick the chat platform that best fits your needs.

Data Analysis

The Text to SQL tool helps you analyze the data in your spreadsheet, for example: "Find the best-selling dairy product last year"




After you make a request, the Agent automatically calls the Text-to-SQL tool.

This tool works like a translator: it translates what you say into SQL that a computer understands, so the Agent can retrieve data from the database.

The Agent automatically adds query constraints such as conditions and sort order, turning your request into a more complete query.

Agent's thinking Query: Find the best-selling dairy product last year, sorted by sales quantity in descending order. A descending sort condition is added automatically so the result better fits your needs.

Agent's response (click the tool response to view):





Result

The Agent found all sales data for "dairy products" along with the other column data for those items.

Each row represents one record, including: product ID, product name, product category, sales amount, sales quantity, and so on.

Based on this data, the Agent determined that the best-selling dairy product is "cheese", with a sales quantity of 110 and a sales amount of 40,150.

Report Creation (Canvas Mode)


The Text to SQL tool can also help you create polished reports. This requires turning on Canvas mode:

Go to "Agent settings page > under Reply Mode settings" and find Agent Mode





Change the Agent mode from standard mode to **Canvas mode**



After saving the settings, you can chat with the Agent, for example: "Please generate a visualized report of the revenue statistics"



Agent's thinking Query: Calculate revenue statistics for each product of the food company, including total revenue, average revenue, revenue standard deviation, revenue distribution ranges, and revenue share by category. The calculation results needed for the report are produced automatically so the result better fits your needs.

Agent's response (click the tool response to view):


```
[('分類營收占比-主食', '10.72%'), ('分類營收占比-乳製品', '11.97%'), ('分類營收占比-冷凍', '9.06%'), ('分類營收占比-罐頭', '10.25%'), ('分類營收占比-肉類', '13.23%'), ('分類營收占比-蔬果', '13.34%'), ('分類營收占比-調料', '4.51%'), ('分類營收占比-零食', '14.53%'), ('分類營收占比-飲料', '12.40%'), ('商品總數', '100'), ('平均營收', '19546.06'), ('最低營收', '1400'), ('最高營收', '63364'), ('營收標準差', '15736.83'), ('總營收', '1954606')]
```


Result

The Agent received the results of all the items the tool calculated automatically and returned them.

The Agent used this data as the basis for visualization and built an interactive report view with Canvas.


Click the "Use Canvas" box to view the content



The report view looks like this, and you can:

Switch between viewing the source code and the rendered view

Switch the report content by the statistical category you want to view (this varies with the content each Agent produces)



When you switch to other categories, you can view the pie chart of revenue share by category and the bar chart of distribution analysis:

營收統計視覺化報表

營收統計視覺化報表

詳細的營收數據統計分析與視覺化展示

總覽統計 | 分類分析 | 分布分析

總營收
NT$ 486,262
所有商品營收總和
+12.5%

平均營收
NT$ 40522
中位數: NT$ 36,990

營收範圍
NT$ 37,605
最高: 62,805 | 最低: 25,200

標準差
NT$ 12679
營收變異程度

分類營收占比



分類統計詳情

Open Sandbox

營收統計視覺化報表

營收統計視覺化報表

詳細的營收數據統計分析與視覺化展示

總覽統計 | 分類分析 | **分布分析**


總營收
NT$ 486,262
所有商品營收總和
+12.5%

平均營收
NT$ 40522
中位數: NT$ 36,990

營收範圍
NT$ 37,605
最高: 62,805 | 最低: 25,200

標準差
NT$ 12679
營收變異程度

營收分布區間



營收散點分析

Open Sandbox

Additional Tips Data quality matters: Make sure your spreadsheet data is clean and correct, as this directly affects the accuracy of the Agent's analysis results. Delete data you do not want to give to the AI: Data hidden in a spreadsheet can still be parsed and provided to the Agent, so data you do not want exposed must be deleted, not merely hidden. Try different questions: By asking in different ways, you can dig more valuable information out of your data. Make good use of Canvas mode: Canvas mode lets you easily create all kinds of visual reports and present data analysis results more intuitively. Make good use of column descriptions: Adding descriptions to table columns significantly improves the accuracy of AI queries.

Text to SQL with Supabase

What Is Supabase?

Supabase is an open-source platform service designed to simplify modern application development. Its core features include:

Database: Store various types of data.

Real-time updates: Your application is notified immediately when data changes.

Account management: Manage user accounts and passwords.

Built-in authentication mechanism: A built-in authentication mechanism that simplifies user identity management and provides multiple authentication methods.

Auto-generated API (data access endpoints): Access your database data through simple methods.

Benefits of Integrating Supabase

Cross-table queries: Supabase supports multi-table relationships, allowing you to query relationships between Table A and Table B.


Indexing for improved query performance: You can create indexes on frequently queried content to help the Agent find what you need more precisely.

Set Up Your Supabase

1. Create a Supabase Account

First, go to the Supabase website and click "Sign in
Start your project."

If you haven't registered yet, please create an account first to proceed with the following steps



After logging in, you can create a new organization or use an existing one. Within the organization, create a project — each project has its own independent database.

2. Navigate to the Database Page

After entering the project, click Database > Tables in the left navigation bar to add data

Create a New Table

Click "New Table" to create a table and enter its name in the "Name" field (for example, Customers).

Supabase offers several ways to create a new table:

Manually add columns: Suitable for designing the table structure from scratch. You can add columns one by one and set each column's data type, default value, etc.

Import .csv/.tsv or plain text: Suitable for quickly creating tables, especially when you already have existing data.

Notes:

The first row of a plain text file must contain column names, with columns separated by commas (CSV) or tabs (TSV).

Here, choose to import data: click "Import data from CSV" and paste a tab-separated text file. Scroll down to see the table result. After import is complete, click "Save."

Primary Key

After the import is complete, you are redirected to the settings page where you must specify a primary key. A primary key is like an ID number — it uniquely identifies each record. Here, we select Customer ID as the primary key: in the column list, check "Primary" on the Customer ID row.

Foreign Key

Scroll down to see the Foreign Key settings. A Foreign Key is like an address that points to the source of a record or more detailed data associated with it.

Suppose we have two tables: "Customers" and "Orders."

Customers Table:

CustomerID - Primary Key

CustomerName

Phone

Address

Orders Table:

OrderID - Primary Key

CustomerID - Foreign Key (references CustomerID in the Customers table)

OrderDate

TotalAmount

In this example, the "CustomerID" in the Orders table is a foreign key that references the primary key "CustomerID" in the Customers table. Through this foreign key, we can identify which customer placed each order.

> In this example, the foreign key should be placed in the Order Table: Relationship direction: One customer → can have multiple orders (one-to-many relationship) One order → belongs to only one customer Foreign key principle: > The foreign key should be placed on the "many" side Therefore: ✅ The Order Table has a customer_id (foreign key), because it is the "many" side in the one-to-many relationship ❌ The Customer Table does not need to store order information

Therefore, we set up the Order Table to link the Customer ID in the Customer Table to the Customer ID in the Order Table: in the "Foreign keys" section of the Orders table, click "Add foreign key relation", select Customers as the referenced table, then map the Orders CustomerID column to the Customers CustomerID column.

After the relationship is configured, click "Save" to establish the database relationship.

3. Setup Complete

Once the tables are created, you have a complete database and can query data within it using SQL syntax.

How to Create a Supabase Tool

To use the Supabase tool on MaiAgent, you need to create it as an MCP tool so the Agent can access Supabase functionality:

> For tool introduction, see: Tool Overview


Create a Server on an MCP Service Platform and Connect to Supabase

For how to connect MCP tools, see: Remote MCP Service Overview. Currently, only the Composio Platform supports Supabase integration.

Enable Available Features in Composio

When connecting to Composio, enable basic database operations such as create, delete, query, etc.

> Composio has basic options pre-selected under Important by default. You do not need additional configuration — just make sure the Important options remain checked.



Add the Configured Supabase Tool to the Available Tools List

For how to create MCP tools, see: Create MCP Tools

Supabase Tool Connection URL

After creating the server service on the MCP service platform, process the URL as follows:


Original URL (obtained from the MCP Server):\
https://backend.composio.dev/v3/mcp/12345678/mcp?include_composio_helper_actions=true

Remove "`?include_composio_helper_actions=true`" entirely

New URL (to paste on the MaiAgent tools page):\
https://backend.composio.dev/v3/mcp/12345678/mcp

> You must remove the above content; otherwise, the Agent will not be able to use the Supabase tool correctly.

After the tool is created, go to the Agent settings and add the Supabase tool to the Agent's available tools list: click "Select Tools", check supabase, then click "Confirm".



> Make sure to click Save on the tools page; otherwise, the Agent still cannot use the Supabase tool.

Using the Supabase Tool

With a MaiAgent Agent and the Supabase tool, simply describe the data you want to query in everyday language, and Supabase automatically generates the corresponding SQL syntax to extract the information you need from the relational database.

Sample Database

🏢 1. Customers Table

Column Name	Primary Key	Required	Description
`CustomerID`	✅	✅	Unique customer identifier
`CustomerName`	❌	❌	Customer company or individual name
`CustomerType`	❌	❌	Customer category (e.g., Retailer, Restaurant, Distributor)
`ContactName`	❌	❌	Primary contact name
`Phone`	❌	❌	Contact phone number
`Email`	❌	❌	Email address
`Address`	❌	❌	Customer address
`Region`	❌	❌	Geographic region (e.g., North, South)
`CustomerLevel`	❌	❌	Customer importance level (A, B, C)

🔑 **Primary Key**: `CustomerID`

🔗 **Foreign Key Relationships**: None

📦 2. Orders Table

Column Name	Primary Key	Required	Description
`OrderID`	✅	✅	Unique order identifier
`CustomerID`	❌	❌	References the Customers table
`OrderDate`	❌	❌	Order creation date
`DeliveryDate`	❌	❌	Expected or actual delivery date
`PaymentMethod`	❌	❌	Payment method (Cash, Credit Card, Wire Transfer)
`OrderStatus`	❌	❌	Order processing status
`TotalAmount`	❌	❌	Order total amount (numeric)
`ShippingFee`	❌	❌	Shipping cost

🔑 **Primary Key**: `OrderID`

🔗 **Foreign Key Relationships**:

`CustomerID` → `Customers.CustomerID` (The CustomerID in Orders references the CustomerID in the Customers table)

🛍️ 3. Products Table


Column Name	Primary Key	Required	Description
`ProductID`	✅	✅	Unique product identifier
`ProductName`	❌	❌	Product name
`Description`	❌	❌	Detailed product description
`Category`	❌	❌	Product category
`Brand`	❌	❌	Product brand
`Size`	❌	❌	Product specification or size
`Cost`	❌	❌	Product cost (numeric)
`Price`	❌	❌	Product selling price (numeric)
`StockQuantity`	❌	❌	Current stock quantity (numeric)

🔑 **Primary Key**: `ProductID`


🔗 **Foreign Key Relationships**: None

Scenario 1: Track Incomplete Orders

Database state: The `Orders` table has two incomplete orders: `OR003` and `OR004`.



Natural language input: In the Agent's chat, simply type: "Tell me which orders are not yet completed." The Agent automatically invokes the tool and generates a structured SQL query.



Supabase automatic query: The Agent automatically invokes the Supabase tool, converting your natural language into an SQL query, such as:




Combining the query results with the Agent's analysis, the Agent responds with the following order information, sorted by priority:



Through the collaboration of the Supabase tool and the Agent, you can easily track incomplete orders and receive analysis and prioritization suggestions from the Agent, enabling more efficient order processing and improved customer satisfaction.

Scenario 2: Query Contact Information for Incomplete Orders

Order OR003 is still being processed, with customer CU003 and the contact person being **Huang Procurement**



Natural language input: In the Agent's chat, type: "Who should I contact for the orders still being processed?" The Agent automatically invokes the tool and generates a structured SQL query.



Supabase automatic relational query: Although the conversation with the Agent is about the Orders table, through the configured foreign key relationships, Supabase knows that the `Customer ID` here references the `ID` in the `Customers` table, so the returned content comes from the `Customers` table.



Agent response: The Agent then provides the correct contact information and other contact methods based on its analysis.



Through the Supabase tool, you can fully leverage table relationships in the database to easily extract information from multiple related tables and receive a customer name list from the Agent. The clearly defined relationships between tables ensure data consistency and reliability, making query results more trustworthy.

Additional Notes:

You can adjust the natural language input based on your actual needs, such as: "Tell me about today's incomplete orders" or "Tell me about VIP customers' incomplete orders." The Supabase tool can accurately parse and execute these queries.

The Agent can further integrate other information, such as inventory status and logistics information, to provide more comprehensive order analysis.

> The tool can only access data stored in your database. If you have analysis needs, make sure to upload the data to the database before starting the analysis.

Link Agents and Group Permissions

After creating a database and configuring its tables, you need to **link the database to an Agent** so the Agent can query data using Text to SQL.

Link an Agent

Steps

Open the database settings page and switch to the "Linked AI Assistants" tab

The left side shows Available AI Assistants, and the right side shows Selected AI Assistants

Select the Agents you want to link on the left, then click "Add AI Assistant" to move them to the right; to unlink them, select them on the right and click "Remove AI Assistant"

When finished, click "Save". The upper-right corner will display "N assistants linked"

> Use the search field to quickly find a specific Agent. When there are many Agents, the list is paginated.

> Make sure the Agent's response mode is set to Agent mode; otherwise, Text to SQL will not be available. For details on response modes, see: Create an Agent

Query Multiple Databases

An Agent can be linked to multiple databases. When a user asks a question, the Agent automatically determines which database to query based on the question:

```
User: "What were last month's sales?"
→ The AI assistant automatically queries the "Sales Database"

User: "How many employees are currently in the marketing department?"
→ The AI assistant automatically queries the "HR Database"
```

> To help the Agent distinguish between databases accurately, give each database a name that clearly describes its purpose, and provide detailed database and field descriptions.

Manage Role Permissions

The "Role Permissions" tab (also referred to as group permissions) on the database settings page determines which databases organization members can access in the admin console. This setting is separate from which databases an Agent can query during conversations.

Configure Role Permissions

Open the database settings page and switch to the "Role Permissions" tab

Under Available Roles on the left, select the roles you want to authorize, then click "Add Role" to move them to Selected Roles on the right

When finished, click "Save"

> Role permissions control members' access to databases in the admin console. They do not filter the databases linked to an Agent based on the role of the person asking a question. If different audiences should query different data, use separate Agents linked only to the appropriate databases, and restrict who can use each Agent.

Permission Levels

Check the settings for each usage scenario separately:

Usage Scenario	Settings to Check
Query data through an Agent conversation	The Agent uses Agent mode and is linked to enabled databases; the Agent decides whether to run a query based on the question
Access databases in the admin console	Organization owners can access all databases in their organization; other members need database feature permissions and access granted through their roles

> A database creator is not necessarily the organization owner. Creating a database does not mean you can access it later without role permission restrictions.

Tools



Tools: Agents call external services through Function Calling

What Is This?

Tools let an Agent "get things done" by calling external services to perform actions or get real-time information.

An Agent without tools can only answer questions from the knowledge it already has. With tools, it can check the current weather, create a customer record in a CRM, send an email, or fetch the latest data from a third-party API.

How Are Tools Different from Skills?

	Tools	Skills
Nature	A callable external service	A multi-step reasoning process
Granularity	A single action (such as "check the weather" or "send an email")	A multi-step SOP (such as "complete quotation process")
Who decides whether to use it	The Agent decides when to call it	The Agent triggers the process in the skill based on the situation
Whether tools are used	A tool is the smallest unit	A skill can chain multiple tools together

Rule of thumb: If it is a single capability (looking up data, performing an action), make it a tool. If it is a whole process (look up A first, then decide whether to do B), make it a skill.

Tool Types

API Tools

Call a REST API directly. You set the URL, HTTP method, and parameters, and the Agent can then use it in conversations.

Best for: internal company APIs, third-party service APIs, simple HTTP requests

MCP Tools

Connect to external services through MCP (Model Context Protocol). MCP is a standardized protocol that makes it easier for an Agent to integrate with a wide range of services.

Best for: services that already have an MCP Server, external integrations that need more complex interactions

Built-in Tools

Tools that MaiAgent provides by default, such as AI image generation. They can be used without additional setup.

Advanced note: Tools are built on Function Calling. Based on the conversation, the Agent decides whether a tool needs to be called, automatically assembles the parameters, sends the request, interprets the returned result, and finally replies to the user in natural language.

What Do I Need to Do?

Create a tool — Choose the type (API
MCP) and configure the connection details

Define parameters — Describe the tool's purpose and parameters so the Agent knows when to use it

Test — Confirm the tool can be called and returns results correctly

Attach it to an Agent — Configure the tool in the Agent's settings

Further Reading

Tools Overview

Create an MCP Tool

Create an API Tool

Built-in AI Image Generation Tool

Configure Tools for an Agent

Tool Features Overview

What Is a Tool?

A tool is like a **plugin** or **skill** for an Agent, letting it do more than just chat. For example, if an Agent has a "**Check Weather**" tool, it can tell you today's temperature; if it has a "**Play Music**" tool, it can start playing music for you directly.

By letting users define a set of tools that an Agent can use, the Agent is able to:

Understand complex user requests.

Automatically determine when a specific tool needs to be used.

Automatically generate the parameters required to call that tool.


This means an Agent is no longer limited to generating text replies and can actually perform a variety of tasks, such as:

Querying real-time information: Retrieve the latest stock prices, weather forecasts, flight statuses, and more from databases or APIs.

Performing external operations: Call ticket booking system APIs, control smart home devices, and send emails or messages.

Processing files: Read, write, or analyze local or cloud documents.

Integrating with other software: Operate CRM systems, project management tools, or other enterprise applications.



How Tools Work

When you configure tools for an Agent, each tool comes with a name, a purpose description, and parameter specifications. After a user asks a question, the Agent decides from the descriptions whether to use a tool and which one, and generates the parameters needed for the call; the platform then actually executes the tool (for example, by calling an external API) and hands the result back to the Agent to compose a reply. The clearer the tool descriptions are, the better the Agent can use the right tool at the right time. For the complete call flow and underlying principles, see Function Calling in the Technical Manual.

Key Benefits of Tools

Tools let an Agent access real-time information and perform real operations, and reduce the risk of incorrect answers through structured calls and returns; users only need to describe their needs in natural language.

Tool Types Supported by MaiAgent

The following main types are currently supported:

🌐 API Tool

The most commonly used type. Used to connect to and call external HTTP/HTTPS API services.

Common uses: Getting weather information, querying external databases, triggering webhooks, integrating with third-party services, and more.

Required configuration: API endpoint URL, HTTP method, request headers (Headers), and parameters schema (Parameters Schema). See Create an API Tool.

☁️ MCP Tool

Model Context Protocol (MCP), which enables servers, clients, and hosts to work together through a standardized protocol.

Suitable for: Letting an Agent call external tools to perform more complex and practical tasks.

Required configuration: MCP server URL, authentication method (headers or OAuth connector), and the tools the Agent is allowed to use. See Create an MCP Tool.

Create MCP Tools

What Is MCP?

MCP (Model Context Protocol) is a standard protocol that connects AI to external tools. An Agent connects to a remote MCP server through a URL to use the tools that the service provides.

MCP Solution

Develop an MCP server once, and any AI platform that supports MCP can use it. For details on how the protocol works, the transports MaiAgent supports, and its limitations, see MCP (Model Context Protocol) in the technical manual.

Quickly Create an MCP Tool

1. Open Tool Management

First, go to AI Features → Tools in the left menu. On the tool list page, click the Add Tool button in the upper right.



Click “Add Tool” to get started

2. Select the Tool Type

Select MCP as the tool type.

3. Set the Display Name

Give the tool a clear display name. In this example, use Composio mcp for google calendar.

Purpose: This name appears in the platform interface for all users to see.

Recommendation: Choose a name that clearly describes the tool's main function so users can understand it easily. There are no strict formatting requirements for this name.

4. Configure MCP

MaiAgent connects to remote MCP servers through URLs (supporting SSE and Streamable HTTP streaming protocols). It does not support MCP servers launched with local commands such as `npx` or `node`. In MCP Configuration, you therefore only need to configure the server URL and authentication method. Any keys the server requires must be provided through headers or OAuth authorization.

First, check the MCP server's authentication method, then configure it using the following table:

Server Authentication Method	How to Configure
OAuth login (users sign in to the external service and grant authorization)	Select a connector under "Select a Service to Connect". See b. OAuth Connectors and Authorization Scope
A fixed API Key or Token (shared across the organization), or no authentication	Enter the URL under "Or Enter Directly (No Authentication Service Account)". See a. MCP Server URL; enter the key in c. Headers (JSON)
Each contact uses their own API Key or Token	Create the tool as described in the previous row, then configure each contact's "MCP Credentials" tab. See Contact MCP Credential Settings

a. 🔗MCP Server URL

Purpose: The Agent uses this URL to connect to the MCP server, retrieve its tools, and call them.

Where to enter it:

If the server uses OAuth: Click a connector card under "Select a Service to Connect", and the URL is filled in automatically. See b. OAuth Connectors and Authorization Scope below.

If the server requires no authentication or uses a fixed key: Paste the full URL, such as https://mcp.example.com/mcp, into the input field under "Or Enter Directly (No Authentication Service Account)".

Format: The URL must start with `https://` and point to a remote server accessible over the internet. You cannot save `localhost` or internal network addresses. For on-premises deployments that need access to an MCP server on an internal network, contact MaiAgent for assistance enabling access.

Note: This field is required.

> For information on obtaining an MCP URL, see the Technical Manual—Remote MCP Service Overview.

> If the MCP server needs to identify the user in the current conversation: When visitors sign in to Web Chat with Keycloak, you can enable Use the Keycloak Login Identity to Call Tools in the channel settings and add this MCP server's host to the allowlist. The platform will pass the visitor's own Keycloak credentials in the Authorization header.

For tools with a directly entered URL, the system connects to the server using the URL and "Headers (JSON)" when fetching the tool list under "Allowed Tools (JSON Array)". If the connection fails, the interface shows the reason, such as "The MCP server returned HTTP 405. Check that the URL points to an MCP endpoint." Follow the message to check the URL and headers. The system validates the connection again when saving. If it fails, you will see "MCP tool validation failed. Unable to connect to

the MCP server.” Tools that use an OAuth connector are saved first, and the tool list is fetched after authorization is complete.

b. 🔐 OAuth Connectors and Authorization Scope

When an MCP server uses OAuth, MaiAgent handles the authorization flow and automatically includes the access token in calls. You do not need to enter a key in the headers.

Select a Connector

Under “Select a Service to Connect”, click the card for the service you want to connect (marked OAuth 2.0). The server URL is filled in automatically. The list includes services verified by the platform and custom connectors created by your organization.

Create a Custom Connector If the Service Is Missing

Click the last card, “Custom Connector Source”, fill in the following fields, and click “Add Connector”. The system first tests whether it can connect to the server. On success, it returns to the card list and automatically selects the new connector.

Field	Required	Description
Name	Yes	The connector identifier. It can contain only English letters, numbers, underscores, and hyphens, such as `my-mcp-server`
Display Name	No	The name shown on the card
Description	No	A brief description of what this MCP server does
Tool Category	No	The default category applied when tools from this server have no individual category. It affects the text displayed on tool cards in conversations
Logo	No	The card icon
Server URL	Yes	The MCP server URL. It must use `https://`
OAuth Server URL	No	The authorization server URL. If left blank, the system discovers it automatically from information published by the MCP server. Fill it in only if discovery fails or the authorization server and MCP server are on different domains (for example, Supabase's MCP server is at `mcp.supabase.com`, while its authorization server is at `api.supabase.com`)
Resource Identifier	No	The resource identifier specified when requesting a token from the authorization server. If left blank, it is detected automatically. Fill it in only if detection fails or the server publishes incorrect information (for example, Asana uses https://mcp.asana.com)

Field	Required	Description
OAuth Client ID	No	Leave blank if the server supports automatic client registration. Otherwise, create an application in the provider's OAuth service first, then enter the Client ID you receive here
OAuth Client Secret	No	Used with the Client ID. Fill this in only if the provider requires a confidential client. If already configured, the field is masked. Leaving it blank retains the existing value; entering a new value replaces it

After creation, you can edit or delete the connector through "Manage Connectors" on the "Tools" page. Changing the "Server URL" revokes authorization for tools using this connector, so change it carefully.

Select the Authorization Scope

After selecting a connector, choose whose account the Agent will use to operate the service under "Authorization Scope":

Authorization Scope	Description
Organization Shared	Everyone in the organization shares one authorization, granted once by an administrator or member. All users who interact through this Agent (LINE, Web Chat, etc.) then access the service using the authorizing person's account. Do not select this for personal account services where each person should use their own account
Individual Contact Authorization	Each contact signs in and grants authorization separately in the conversation. The Agent acts as that contact. Users must be signed in: the Agent does not receive this tool in conversations with anonymous visitors who are not signed in

Complete Authorization

Organization Shared: Click "Authorize". If the tool has not been saved yet, the system saves it first, then opens the external service's authorization window. After you sign in and grant consent, the interface shows "Authorized". The system automatically fetches and saves the tool list, then closes the editing window. To switch accounts, reopen the tool, click "Revoke", and authorize again.

Individual Contact Authorization: No authorization is needed here. Each contact signs in and grants authorization in their own conversation. You can view or revoke authorization, or trigger reauthorization, in the "Connector Authorization" tab of the "Contacts" editing window.

> The authorization window opens as a popup. If you see "Popup blocked. Allow popups and try again.", allow this site to open popups in your browser, then click "Authorize" again.

c. 📰 Headers (JSON)

Purpose: Set the HTTP headers included every time the system connects to the MCP server, such as a fixed API Key or Token.

Format: A valid JSON object. Each key is a header name, and its value is the header content (a string). Keep `{}` if no headers are needed.

When entering a URL directly: Enter the authentication headers required by the server here. Use the actual key value:

```
{
  "Authorization": "Bearer paste the token provided by the service provider here"
}
```

When an OAuth connector is selected: Authentication is handled automatically. Enter only additional custom headers here (optional). When the authorization scope is "Organization Shared", do not enter `Authorization` here, as it will override the authorization added automatically.

Shared and individual credentials: These headers are shared across all conversations. If each contact needs to use their own key, configure it for each contact in Contact MCP Credentials. When calling a tool, a contact's setting takes precedence for headers with the same name.

Available variables: Values can use the variables listed under "Available Context Variables" below the field (such as `{{contact_id}}` and `{{conversation_id}}`). The system substitutes the actual values for each conversation. Other `{{…}}` names are not substituted and cause an "Contains unknown template variables" error when saving. You therefore cannot replace a key with a custom variable; enter the actual value.

Who can see them: When you reopen the editing window after saving, each header value shows only its first and last 4 characters, with **in between. Saving without changes retains the original values. Headers are not provided to the AI model, and MCP tool execution logs do not store request headers.**


5. Find "Allowed Tools (JSON Array)" and Click Refetch

Purpose: Specify the list of individual tools the Agent is authorized to use through this MCP client. An MCP client may provide multiple functions or individual tools.

Fetch and select tools: Click "Refetch" (or "Fetch Tools" in the list if it has not been fetched before). The system connects using the current server URL and headers and lists all tools provided by the server. Use the switch to the right of each tool to choose which tools the Agent can use. You can also toggle all tools at once with "Enable All" or "Disable All". At least one tool must be enabled before saving.

OAuth connectors: When the authorization scope is "Organization Shared", the system automatically fetches and saves the tool list after authorization is complete.

After you click, the system automatically retrieves the tools linked to that server and displays them in the list:



After fetching the tool list, use the switch to the right of each tool to choose which tools the Agent can use

6. 💾 Save the Tool

After checking all settings, scroll to the bottom of the page and click the “Confirm” button. Your new tool is now created!

When adding a tool, if you click Confirm before opening the Permission Settings tab, the tool will not be created yet. The interface automatically switches to Permission Settings and displays “Please review the permission settings and confirm the assigned roles before submitting.” Under Quick Permission Scope Selection, check which roles' members can use this tool (the default is

Exclude Default Roles), then click Confirm again to create it. Organization-shared OAuth tools also go through this confirmation when you click "Authorize". This confirmation does not appear when editing an existing tool.

If the MCP server includes an interactive interface for a tool, a card you can interact with directly appears in the conversation after the Agent calls the tool. No additional configuration is needed. See MCP Interactive Cards (MCP Apps).

⚠️ Important Notes

Connection Testing

After creating a tool, test that the MCP connection works correctly

You can verify tool functionality in a test environment

Permission Management

Choose allowed tools carefully to avoid granting unnecessary capabilities

Review tool usage regularly

Troubleshooting

If the connection fails, check that the MCP server URL is correct

Make sure "Headers (JSON)" is a valid JSON object and keys contain their actual values

When using an OAuth connector (Organization Shared), check that the tool shows "Authorized"

MCP Interactive Cards (MCP Apps)

Some MCP servers return an interactive interface along with data. After an Agent calls one of these tools, a card appears in the conversation that users can interact with directly, such as a table of query results or a form with checkboxes or input fields. This lets users do more than exchange text messages.

The MCP server determines how the card looks and what it can do. MaiAgent displays it safely in the conversation and forwards actions on the card to the same MCP server. To add interactive cards to your own system, ask your engineers to refer to **Self-hosted MCP Server: MCP Apps** and the **minimal runnable example** in the technical guide.

What Users See

Scenario	Behavior
Where the card appears	The card appears below the Agent's reply once the reply is complete (it does not appear while the reply is still being generated)
Loading	When the card first appears, it shows its own loading screen (such as “Loading…”), then switches to the actual content once the data arrives
Multiple calls in the same turn	Only the latest state of the same card is displayed; multiple identical cards do not appear
Interacting with the card	Buttons and forms on the card can query or submit data directly, and results update within the same card
Card height	Adjusts automatically to the content; when the content exceeds about 60% of the screen height (up to 620px), it scrolls within the card
Full screen	If the card provides a full-screen button, you can expand it to full screen. Click × in the upper right (Exit full screen and return to the conversation) or press Esc to return to the conversation. The card keeps the height it had before expansion
Asking AI from the card	If the card provides a question feature, the submitted content appears in the conversation as a user message. The card automatically collapses back into the conversation, and the Agent answers next
Opening external links from the card	The browser opens a new tab; only standard web, telephone, and Email links are opened
Dark mode and brand colors	The platform tells the card the current light/dark mode and brand colors; the card decides whether to apply them

Scenario	Behavior
Card content fails to load	The summary returned by the tool is displayed as plain text instead

Cards appear in Web Chat and MaiGPT conversations. Other messaging platforms, such as LINE and Messenger, do not display cards; users receive the Agent's text reply.

> Cards are unaffected by the "Display mode" in Custom Tool Message Display: interactive cards still appear even when "Hide" is selected. "Hide" applies only to the tool execution block.

Reopening a Conversation

The card's interface and the tool results at the time are saved with the message. When you later reopen the conversation from its history:

The card reappears with the tool results from that time. Partially completed fields or new results from subsequent queries within the card are not retained.

The card's buttons remain usable as long as the MCP tool or connector is still configured for the conversation and its authorization remains valid. Otherwise, "This action could not be completed. Please try again later." appears.

Later updates to the card interface on the MCP server do not change cards already generated in historical messages.

Requirements

The MCP server provides an interactive interface: The tool definition or returned result must include an interface resource starting with `ui://`. The MCP server decides whether to provide it; no additional switch is needed in MaiAgent. For self-hosted MCP servers, see Self-hosted MCP Server in the technical guide.

The Agent can access this MCP server: Configure it as an MCP tool for an Agent whose response mode is Agent mode, or have a member authorize it through connectors in MaiGPT.

The conversation takes place in Web Chat or MaiGPT. Availability of interactive cards in on-premises Web Chat depends on the deployment settings. Contact your MaiAgent representative to confirm.

Suitable Use Cases for Interactive Cards

Cards work well for results that are difficult to convey in text or require user interaction. Common examples include:

Scenario	What the card does	Limitations of text replies
Tables and charts of query results	Displays order, inventory, report, and other query results in tables or charts, with sorting or date-range selection	Multiple fields and records are difficult to read when listed in text
Filling out forms	Lets users fill in fields for leave requests, repair requests, and similar forms directly on the card; the same MCP server creates the request after submission	Collecting each field through questions and answers can lead to missing entries or incorrect formats
Confirming submission	Lists content prepared by the Agent (such as a notification to send or settings to change), and performs the action only after the user clicks “Confirm”	Users can only reply “OK” in text, making it harder to see exactly what will be done
Selecting a map location, date, or time slot	Lets users select a store, appointment slot, or seat, then passes the selection back to the Agent	Locations and time slots are inconvenient to describe and compare in text

The shared principle: a card handles only actions associated with this particular tool result. The Agent's conversation still connects workflows with multiple steps.

Security and Limitations

Cards run in an isolated sandbox frame. They cannot read the login state or data of the MaiAgent page and, by default, cannot connect to external websites on their own.

Actions within a card can only call tools from the card's source MCP server that are already available to the conversation. They use the same authorization method as the Agent's calls to that server. An action that receives no response within 30 seconds is treated as failed.

If an external link requested by the card is not allowed, “This link cannot be opened.” appears. If the browser blocks a pop-up window, allow pop-ups and try again.

Frequently Asked Questions

The card displays “This action could not be completed. Please try again later.”?

An action within the card failed or timed out while calling the MCP server, or the tool is no longer available to this conversation. Click Retry to reload the card. If the issue persists, confirm that the

MCP server is operating normally, the tool is still configured for the Agent, and the authorization remains valid.

The card displays “The interactive component failed to load. Please refresh the page and try again.” ?

The card's interface did not load successfully. Refresh the page or click Retry. If the card stays on its own loading screen, refresh the page first as well.

The Agent called an MCP tool, but no card appeared?

The tool's MCP server did not provide an interactive interface, or this call returned an error. Only successful tool calls that include a `ui://` interface resource produce a card. Also confirm that you are viewing the conversation in Web Chat or MaiGPT and that the Agent's reply has finished generating.

Create API Tools

> You can use MaiAgent's **Tool Creation Agent** to help you create API tools

API tools integrate external services and automate workflows.

On this page: What is an API? | Quickly create an API tool | Reference Agent parameters in Query parameters | Where to put keys and credentials | ⚠️ Important reminders

What is an API?

An API (Application Programming Interface) is a bridge that allows different software systems to communicate. Simply put, it acts as a waiter in the software world, helping programs exchange information and perform functions.


Imagine you are dining at a restaurant:

You: The customer who needs food (the application)

Kitchen: Where food is prepared (the system providing the service)

Waiter: Carries messages between you and the kitchen (the API)

You do not need to enter the kitchen yourself. Just tell the waiter what you want. The waiter passes your request to the kitchen and brings you the prepared meal.



API workflow diagram

API tools help you automate standardized workflows and configure specific response formats. They can also retrieve information from your systems, for example:

E-commerce customer service automation

```
Customer asks about an order ➡️ API looks up the order status ➡️ Automatically reply with delivery progress
```

Marketing campaign management

```
New product launches ➡️ Automatically update the official website ➡️ Send email marketing ➡️ Promote on social platforms
```

Online course platform:

```
Student asks about course progress ➡️ API looks up learning records ➡️ Automatically reply with completion percentage and next class time
```

With API tools, an Agent evolves from a chatbot into an intelligent assistant that can carry out business workflows, greatly improving efficiency and automation.


Quickly create an API tool

1. Open tool management

First, select AI Features → Tools from the left menu. On the tool list page, click the Add Tool button in the upper right.


2. Select the tool type

Select API as the tool type.



3. Set the display name

Give the tool a clear display name. Here, we use google calendar.



Purpose: This name appears in the platform interface for all users to see.

Recommendation: Choose a name that clearly conveys the tool's main function so users can understand it easily. There are no strict formatting requirements for this name.

4. Set the tool name

Next is the "Tool Name" field.

Purpose: This is the unique identifier the Agent uses internally to call and identify this tool.

Naming rules (important):

Must use English.

May contain only:

Lowercase letters (a-z)

Uppercase letters (A-Z)


Numbers (0-9)

Underscores (_)

Hyphens (`-`)

Examples: `get_weather_forecast` , `database-query-tool`

The image below uses google_calendar_retriever



API tool name definition

5. Write the tool description

In the “Tool Description” field, users can provide a clear, detailed explanation of the tool.

Why it matters: A good description helps the Agent understand more accurately:

The tool's function and purpose.

When to use the tool.

How to interpret the tool's output.

Suggested content: Explain what the tool does, its inputs and outputs, and any usage considerations.

Two description fields: The “Description” in the form appears in the tool list for members to read. The “Prompt” provides the Agent with usage instructions, parameter formats, and precautions. After writing a description, click “Sync to Prompt” beside it to copy the description into the prompt field as a starting point (if the description is empty, the message “Please enter a description first” appears), then add the details the Agent needs.



Tool description

6. Detailed API configuration


a. 🔗 API URL

Enter the full URL of the target API endpoint (including `http://` or `https://`).

Example: https://api.opencalendar.org/data/2.5

Automatically parse pasted cURL: The field hint says “You can paste cURL copied from browser DevTools.” In the DevTools Network panel, select “Copy as cURL” for a request, then paste it directly into this field. The system parses the URL, headers, and HTTP method and fills in the corresponding fields (with the message “Parsed URL, headers, and HTTP method from cURL”).

When you open the Add Tool window, a cURL command already on the clipboard is also imported automatically (the browser must allow clipboard access). If the cURL command uses an unsupported HTTP method, the URL and headers are still filled in; select the method manually. If parsing fails, the message “Unable to parse cURL. Please check the format” appears. After pasting, remove personal Cookies or one-time tokens from the headers, then use variables as described in **Where to put keys and credentials**.



b. 📮 HTTP method


Select the HTTP verb required by the API service from the dropdown:

`GET` : Typically used to retrieve resources.

`POST` : Typically used to create new resources or submit data.

`PUT` : Typically used to completely replace or update resources.

`DELETE` : Typically used to delete resources.



c. Headers

Headers act like the "envelope" of a letter, giving the recipient important information before they see the actual data. Without the correct headers, an API request may fail authentication, or the recipient may be unable to parse the data correctly..

Common uses:

Authentication (`Authorization` , `X-API-Key`)

Specifying the content type (`Content-Type`)

Specifying the accepted response format (`Accept`)

To configure headers:

Enter the HTTP headers to include with every request in the "Headers (JSON)" field.

Format: Must be a valid JSON object. Each key is a header name, and each value is the header content (a string). Leave it as `{}` if no additional headers are needed.

Enter the actual key values directly: For credentials such as API Keys and Tokens, paste the values provided by the service provider into the headers exactly as given. The platform does not

substitute custom-named `{{…}}` placeholders; only specific variables are filled in at call time. See **Where to put keys and credentials**.

Example:

```
{
  "Content-Type": "application/json; charset=utf-8",
  "Authorization": "Bearer Paste the Token provided by the service provider here",
  "Accept": "application/vnd.github.v3+json"
}
```

> To authorize API calls as the current conversation user instead of sharing a single key: When a visitor signs in to Web Chat through Keycloak, enable **Use the Keycloak login identity to call tools** on the conversation platform and add this API's host to the allowlist. The platform sends the visitor's own Keycloak credentials in the Authorization header. In this case, do not also set Authorization in Headers (JSON), as your configured value would take precedence.

Sensitive Header Names: Tool execution records store the headers for each request. The platform's built-in sensitive headers (`Authorization`, `Proxy-Authorization`, `X-API-Key`, `X-Auth-Token`, `Cookie`, and `Set-Cookie`, listed in the read-only Built-in Sensitive Headers) and headers supplied through credentials are always masked. If your API uses another custom header for keys (such as `X-Client-Secret`), enter its name under Sensitive Header Names and press Enter to add it. Its values will then be masked when viewing execution records. Names are case-insensitive, must match exactly, and may contain only English letters, numbers, and `- _ . ~`, with up to 50 names allowed. The setting also applies to existing records; removing a name restores display of the original values.

d. 🔎 Query Params

Query parameters are query strings appended after the question mark in a URL (such as `?format=json&limit=10`) and are sent with every request. They are suitable for fixed query conditions or API keys that must be passed through a query string.

Click "Available Context Variables" to expand the list of currently supported variables (contact ID, conversation ID, inbox ID, and so on).

Format: A valid JSON object, with parameter names as keys and parameter contents (strings) as values.

Values can be fixed text, or you can use `{{parameter_name}}` to reference a parameter declared in "Parameters Schema" and filled in by the Agent at call time. This lets you configure queries that combine a fixed part with a user-provided part. See **Reference Agent parameters in Query parameters** below.

If the service provider requires an API key in the query string, put its actual value here instead of directly after `?` in the API URL. Values configured here do not appear in the "Request URL" in tool execution records. See Who can see these values.

Example:

```
{
  "$format": "json",
  "$filter": "ProductName eq '{{product_name}}'"
}
```



Query Params field and Available Context Variables list

e. 🧩 Parameters Schema

The parameters schema is like an order form, telling the Agent what data it can request from the API and how to request it.

Core setting: Defines which parameters the Agent can or must provide when calling this tool (the content passed to the system for processing), and their formats.

Format: Uses the standard JSON Schema format.

Key elements:

`type: "object"`: Indicates that the parameters form an object.

`properties`: An object defining each parameter.

Parameter name (such as `"search"`): The corresponding object contains the details of that parameter.

`type`: The parameter's data type (`string`, `integer`, `number`, `boolean`, `array`, `object`).

`description`: An explanation for the Agent of what this parameter means.

`default` (optional): The parameter's default value.

`enum` (optional): Lists the allowed options if the parameter must be one of a specific set of values.

`required`: An array containing the names of all required parameters.

Do not include keys: The parameters schema (including `default` values) is provided to the AI model as part of the tool definition. Put API keys in "Headers (JSON)" or "Query Params (JSON)".

Do not paste sample data: Parameters must be defined inside `properties`. If you directly paste sample data such as `{"keyword": "string", "limit": 10}`, clicking "Confirm" opens an "Error" message explaining that this JSON Schema defines no fields and listing the keys that need to be moved into `properties`. Revise it as instructed before saving. If the tool needs no parameters, you can save it with the default `{}`.

Example (video and audio search tool):

```
{
    "type": "object",
    "properties": {
        "limit": {
            "type": "integer",
            "minimum": 1,
            "description": "Maximum number of results to return"
        },
        "fields": {
            "type": "string",
            "description": "Comma-separated list of fields"
        },
        "search": {
            "type": "string",
            "description": "Search keywords"
        }
    },
    "required": ["search"]
}
```

f. Path parameters and parameter locations

An API URL can use `{parameter_name}` to mark variable path segments, such as `/users/{userId}/orders/{orderId}`. To substitute the values provided by the Agent into the URL, define parameters with matching names in "Parameters Schema" and set their location to "Path". Before sending a request, the system URL-encodes each value and substitutes it. For example, `A/B 01` becomes `A%2FB%2001`, so slashes or spaces in a value do not change the URL structure.

Use case: Customer service manager Mai wants the Agent to look up individual orders through the company's order API using a customer ID and order ID. She creates an API tool, sets both IDs as path parameters, and configures the tool for the Agent. When a colleague enters "Look up order order-25 for customer customer-01" in the conversation, the Agent inserts both IDs into the correct URL positions and sends the query. If the order ID is missing, the tool reports the missing value immediately without sending an incomplete request.

Set an API URL with path parameters

Add a tool following "Quickly create an API tool" above. For practice, use the public httpbin response service and set API URL to:

```
https://httpbin.org/anything/users/{userId}/orders/{orderId}
```

A URL can contain multiple path parameters. After you enter it, "Detected Path Parameters" appears below the field, listing `userId, orderId`. If these names have not been defined in the parameters schema, a red "Please define these in the parameters schema" message also appears.


Declare parameters with matching names in the schema

Enter the following in Parameters Schema (JSON Schema):

```
{
  "type": "object",
  "properties": {
    "userId": { "type": "string", "description": "Customer ID" },
    "orderId": { "type": "string", "description": "Order ID" }
  },
  "required": ["userId", "orderId"]
}
```

Parameter names must exactly match the names inside the URL's braces (including case). `required` tells the Agent to provide both values for every call.


After you enter the schema, each parameter appears below it with a location dropdown, initially set to “Default”. A red message appears below the API URL: “The following parameter locations are not ‘Path’; placeholders in the URL will not be substituted”. This means you still need to complete the next step.



A red message appears below the API URL when parameter locations are still set to Default


Set parameter locations to Path

Below the parameters schema, change the location dropdowns for both `userId` and `orderId` to “Path”.



Choose a location for each parameter from the dropdown

After selection, the system automatically adds `"location": "path"` to the parameters schema, and the red message below the API URL disappears. Check the settings, then click "Confirm" to save the tool.



Selecting Path also writes the location setting into the parameters schema

> Parameters whose location remains “Default” are not substituted into the URL. Even if the Agent provides a value, {userId} in the URL still lacks a value, so the tool reports an error without sending the request. Be sure to set every parameter used in the URL to “Path”.


Configure the tool for the Agent and verify it

Follow Configure tools for an Agent to add the tool to an Agent whose response mode is Agent mode. Then open “Agent Marketplace” from the left navigation, switch to “Organization-built”, select the Agent, and enter “Look up order order-25 for customer customer-01”. After the Agent calls the tool, httpbin returns the request URL it actually received: https://httpbin.org/anything/users/customer-01/orders/order-25.



The Agent substitutes both IDs into the URL and sends the query

To inspect the URL actually sent for each call, open “AgentOps” → “Tool Execution Records” from the left navigation. Click the eye icon in the record's actions column to open “Details”, then check “Request URL” under “Request Information”. The image below shows a call with a customer ID containing a slash and a space (`A/B 01`); you can see that the value has been URL-encoded.



The Request URL in tool execution records shows encoded path parameters

After practicing, replace the public example URL with your company's order API URL.

Parameter location options

You can set a location for each parameter in the parameters schema to determine where its value goes in the request:

Location	Description
Default	Keeps the original behavior: GET puts values in the query string, and POST, PUT, and PATCH put them in the body. DELETE does not include them automatically; explicitly select a location when values need to be sent
Path	Substitutes the value for the matching `{parameter_name}` in the API URL
Query	Appends the value to the query string after the question mark in the URL
Body	Places the value in the JSON body
Header	Sends the value as an HTTP header using the parameter name; if Headers (JSON) already defines a header with the same name (case-insensitive), the configured header takes precedence

Existing tools without location settings keep their original behavior.

No request is sent when a path parameter value is missing

If any path parameter in the URL lacks a value for a call (the Agent did not provide it, the value is empty, or the parameter location is not Path), the tool stops immediately and reports "Path parameter {orderId} has no value in this call". It does not send a URL containing `{orderId}`. The Agent explains the reason for the failed query in the conversation. In "Tool Execution Records", the record has a failed status, "Request Information" has no request content, and "Error Message" identifies the parameter missing a value.




When a path parameter value is missing, the tool sends no request and records the reason for the error

URL syntax restrictions

Path parameter names may contain only English letters, numbers, and underscores, and cannot start with a number, for example `{order_id}`. Names such as `{order-id}` cannot be saved.

Place `{parameter_name}` in the URL path. For values needed in the query string, set the parameter location to "Query" or reference them as `{{parameter_name}}` in Query Params.

API URLs cannot use the double-brace syntax `{{variable}}`. Saving displays an "Error" message: "Path parameters must use {identifier} syntax." In API tools, use `{{parameter_name}}` in "Headers (JSON)" and "Query Params (JSON)".



API URLs containing double braces cannot be saved

Google Style REST custom actions can retain their colon suffix directly, for example this Google Weather query:

```
https://weather.googleapis.com/v1/currentConditions:lookup
```

7. 💾 Save the tool

After checking all settings, scroll to the bottom and click “Confirm” . Your new tool is now created!

When adding a tool, if you click Confirm before opening the Permission Settings tab, the tool will not be created yet. The interface automatically switches to Permission Settings and displays “Please review the permission settings and confirm the assigned roles before submitting” . Under Quickly Select Permission Scope, check which roles allow their members to use this tool (the default is Exclude Default Roles), then click Confirm again to create it. This confirmation does not appear when editing an existing tool.

Reference Agent parameters in Query parameters

Many third-party APIs use a query condition consisting of a fixed syntax plus a user-provided value in a single string, such as the OData-style `$filter=ProductName eq 'Chai'` or a search API's `q=` parameter. These APIs need a value embedded in a fixed string rather than a standalone parameter.

Write `{{parameter_name}}` in a Query Params value, and MaiAgent substitutes the value of the matching parameter in "Parameters Schema" when the Agent calls the tool, before sending the request. The person configuring the tool defines the fixed structure, while the Agent only fills in values. The model no longer has to determine whether the syntax is correct.

Use case

The procurement department wants an internal Agent to answer questions such as "What are the current unit price and stock level of a product?" using the OData query service provided by the company's product catalog system. Previously, each API required custom code for these queries. Now, a procurement specialist can simply create an API tool, set the query condition to `ProductName eq '{{product_name}}'`, and assign the tool to an Agent. When a colleague asks "What are the unit price and stock level of Chai?", the Agent automatically inserts `Chai` into the query condition, calls the API, and returns the product name, unit price, and stock level.

Setup steps

The following example uses the public Northwind demo data service (OData). You can follow these steps directly:

Create a tool and enter its basic information

Follow the "Quickly create an API tool" steps above to add an API tool. Enter a display name (such as Product Price Lookup), the tool name `product_price_lookup`, a description, and a prompt. Set the API URL to:

```
https://services.odata.org/V4/Northwind/Northwind.svc/Products
```

Keep the HTTP method set to `GET`.

Declare the parameter the Agent will fill in the parameter schema

Declare `product_name` in the Parameter schema (JSON Schema) and use `description` to tell the Agent what to enter:

```
{
  "type": "object",
  "properties": {
    "product_name": {
      "type": "string",
      "description": "The full English product name, such as Chai"
    }
  },
  "required": ["product_name"]
}
```

Reference the parameter in a query parameter value

Enter a fixed query structure in Query parameters (JSON), using `{{product_name}}` in the value to reference the parameter you just declared:

```
{
  "$format": "json",
  "$select": "ProductID,ProductName,UnitPrice,UnitsInStock",
  "$filter": "ProductName eq '{{product_name}}'"
}
```

Click "Confirm" to save the tool.

Assign the tool to an Agent and test it

Follow Configure tools for an Agent to add this tool to an Agent whose response mode is Agent mode, then save. Next, open "Agent Marketplace" from the left navigation bar, switch to "Organization-created", and select the Agent to start a conversation. Enter "What are the unit price and stock level of Chai?" The Agent displays "Tool used" and returns Chai's unit price and stock level.



The Agent inserts the product name provided by the user into the query condition, then calls the API

Substitution rules

Rule	Description
Variable names must match the parameter schema	`{{product_name}}` corresponds to a parameter name under `properties` in the parameter schema. Names are case-sensitive and must match exactly
Only values are substituted	Templates apply only to query parameter values; keys remain unchanged and are not substituted
Values are inserted literally	Parameter values are always inserted as literal text without numeric conversion. For example, the leading zero in the business registration number `04595257` is preserved
Missing values stop the call	If the Agent does not provide the parameter for this call (or its value is empty), the tool stops with an error identifying the missing parameter instead of sending `{{product_name}}` unchanged
Context variables take precedence	If a parameter name matches a context variable (such as `contact_id` or `conversation_id`), the context variable's value is always used; the value provided by the Agent does not override it

Rule	Description
Referenced parameters are also sent separately	Parameters referenced by templates are still sent as separate query parameters as usual (for example, `product_name=Chai` is also sent). Most APIs ignore extra parameters
Parameter names are preserved	Query parameter keys containing underscores or uppercase letters (such as `Business_Accounting_NO`) are preserved exactly and are not rewritten by the system

> Values in "Headers (JSON)" also support {{parameter_name}} references to parameters in the parameter schema, following the same rules as query parameters.

> Existing tool settings without {{ }} are completely unaffected. If the system previously rewrote a query parameter name in an older tool (for example, from Business_Accounting_NO to business__accounting_no), reopen the tool, restore the correct name, and save. When you reopen the editor, query parameter values appear masked as ; saving directly does not lose the original values.

Where to store keys and credentials

API tools do not have a separate secret storage field or secret variables with custom names. Store the keys required to call external APIs in the following locations, depending on whose identity the Agent should use:

Scenario	Where to store them
A single fixed API Key or Token shared by the entire organization	Enter the actual value directly in the tool's "Headers (JSON)". If the provider only accepts a query string, use "Query parameters (JSON)"
Each contact uses their own API Key or Token	The contact's "API credentials" tab. See Use a separate key for each contact
Use the identity of the visitor signed in to Web Chat through Keycloak	See the channel setting Call tools using the Keycloak login identity
The service only accepts OAuth login authorization	API tools do not have an OAuth authorization flow. If the service provides an MCP server, use the OAuth connector for MCP tools instead

> When you paste a cURL command copied from your browser into "API URL", its headers are also imported into "Headers (JSON)". These often include your own Cookie or Authorization. These values become fixed credentials shared by all conversations. Before saving, remove them or replace them with a key issued by the provider for this tool.

Supported `{{…}}` variables

Values in "Headers (JSON)" and "Query parameters (JSON)" can use `{{variable_name}}`, which the system substitutes on each call. Only the following names are substituted:

Variable	Value inserted
`{{contact_id}}`	Contact ID
`{{source_id}}`	Source ID
`{{contact_name}}`	Contact name
`{{conversation_id}}`	Conversation ID
`{{inbox_id}}`	Inbox ID
`{{organization_id}}`	Organization ID
`{{agent_slug}}`, `{{agent_version}}`	For official built-in Agents; always replaced with an empty string when called by an organization-created Agent
`{{parameter_name}}`	A parameter declared in the parameter schema. The value provided by the Agent for this call is inserted. See Substitution rules

Variable names are case-sensitive and must match exactly, with no spaces inside the braces. `{{ contact_id }}` is not substituted and is sent unchanged.

If a conversation context variable has no corresponding value, an empty string is inserted. For example, `{{contact_id}}` is empty when the conversation has no contact.

Other names (such as custom key variable names) are not substituted. Saving the tool displays an "Contains unknown template variables" error. If an older tool still uses such names, the request sends `{{…}}` unchanged to the provider, causing authentication to fail. Enter the actual key and save again.

"API URL" and "Parameter schema" do not support `{{…}}`.

Use a separate key for each contact

When each contact needs to call an API using their own account (for example, to look up their orders), put only shared headers in the tool's "Headers (JSON)", then configure credentials separately for each contact:

Open the "Contacts" page and edit the contact (the contact must already be created and saved).
Switch to the "API credentials" tab and click the edit button to the right of the tool.
Enter this contact's headers in "Headers (JSON format)", such as `{"Authorization": "Bearer this contact's Token"}`, then click "Save".

The procedure is the same as Configure contact MCP credentials. On each call, the system first applies the tool's "Headers (JSON)", then overrides headers with matching names using the contact's headers (names must match the case used in the tool settings). If the contact has no settings, the tool's headers are used. Contact credential values are sent unchanged, without `{{…}}` substitution.

Who can see these values

Tool editor: Once saved, values in "Headers (JSON)" and "Query parameters (JSON)" are no longer shown in plain text, even to the creator. When you reopen the editor, each value shows only its first and last 4 characters, with `**` in between (values of 8 characters or fewer are shown entirely as `**`). Saving directly does not change the original values. To modify an item, re-enter its full value; items that still contain a masked value cannot be saved.

AI model: Header and query parameter values are not provided to the AI model. The AI model can only see the tool name, prompt (or description), and parameter schema.

Tool execution logs: Under "AgentOps" → "Tool execution logs", "Request information" shows the actual "Request URL" and "Request Headers" sent for each call:

Headers named `Authorization`, `Proxy-Authorization`, `Cookie`, `Set-Cookie`, `X-API-Key`, `Api-Key`, `X-Auth-Token`, or `X-Access-Token` (case-insensitive), as well as headers configured in the contact's "API credentials", appear as `*` and are labeled "Masked".

Headers with other names appear in plain text. If the provider allows it, put keys in headers with the names listed above.

Values configured in "Query parameters (JSON)" do not appear in the "Request URL". If an API response or error message echoes these values, they are also replaced with `**`.

Content entered directly in "API URL" (including the query string after `?`) appears unchanged in the "Request URL", so do not put keys in the API URL.

> The httpbin service used for practice returns the received request headers unchanged in its response, which appears in the conversation and tool execution logs. Do not use real keys when testing.

⚠️ Important reminders

Connection testing

After creating a tool, test that the API works correctly

You can verify tool functionality with testing tools, such as:

POSTMAN

Your company's own API request testing platform

Permission management

Regularly review tool usage and access permissions

Configure Tools for an Agent

You can now select the tools you have created in Agent settings to give your Agent more capabilities. This guide explains how to assign your tools to a specific Agent.

Configure Tools

1. Open Agent Settings

First, go to the "AI Features" section in the left navigation bar, then click "AI Assistants". This displays a list of all Agents created in your account.



Find the Agent you want to configure tools for

2. Select the Agent to Configure

In the Agent list, find the Agent you want to configure tools for and click "Edit" to open its detailed settings page.



Click Edit in the actions column to open the Agent's settings page

3. Switch the Agent's Response Mode

Prerequisite: Only Agents set to Agent Mode can use tools. If your Agent is in another mode (such as RAG Q&A mode), you cannot configure or use tools for it.

On the Agent settings page, click "Response Mode Settings" in the left navigation.

Check: Confirm that the currently selected mode is "Agent Mode".
Change: If the current mode is not Agent Mode, switch to Agent Mode.



Make sure the Agent is set to Agent Mode to use tools

4. Open the Tool Configuration Page

On the Agent settings page, click “Tools” in the left navigation.



Tool configuration page

5. Select the Tools to Enable

On the tool configuration page, click "Select Tools" at the top right to open the list of prebuilt tools, then follow these steps.


Steps:

Browse the list and find the tools you want this Agent to use.

Select the checkbox next to each tool you want to enable.

Select as many tools as needed for the Agent's tasks and requirements.

> **You can select MaiAgent's built-in tools or tools you have defined yourself.**



Select the tools you want this Agent to use

> **Tip: Only configure tools the Agent actually needs and is authorized to use. Too many unrelated tools may affect the AI's decision accuracy and response efficiency.**

6. Review Selected Tools

After selecting tools, review those assigned to the Agent to make sure you have configured the correct ones.



Confirm that the correct tools are configured for the Agent

Control System Functions

In addition to the tools you select, Agents have system functions enabled by default, such as searching the current conversation's message history, reading attachments, and generating download links. Disable them individually to suit each Agent's work, reduce unnecessary token usage, and make its behavior easier to predict.

For example, a customer service manager creates an Agent that only answers frequently asked questions and does not handle attachments. She opens its advanced settings, disables attachment reading and parsing, and saves the settings. The Agent can still answer knowledge base questions but no longer attempts to parse files uploaded by customers.

1. Open Advanced Settings

Open the Agent you want to adjust and select Advanced Settings on the left side of the settings page.

2. Adjust System Functions

Scroll to System Functions and enable or disable the following functions as needed:

Search conversation history

Retrieve message context

Read plain text attachments


Parse attachment content

List available parsers

Generate download links

Once disabled, the Agent can no longer use that function, which may also affect related responses.

When either Read Plain Text Attachments or Parse Attachment Content is enabled, the Agent can also retrieve all files previously sent in this conversation. See Retrieve Files from This Conversation.



Enable or disable system functions based on the Agent's purpose

3. Save Settings

Click **Save** at the bottom right to apply the settings.

> The last four functions in the list only take effect in **Agent Mode**. If you cannot use these switches, first switch to Agent Mode in **Response Mode Settings**.

Retrieve Files from This Conversation

When either **Read Plain Text Attachments** or **Parse Attachment Content** is enabled, an Agent in Agent Mode automatically gets a "List Conversation Files" tool, with no additional setup required. As a conversation grows, the Agent may forget files sent several turns earlier. When a user asks about a previous file, the Agent first lists the files in the current conversation and then reopens the one it needs, without asking the user to upload it again.

For example, a salesperson uploads a receipt photo and meeting notes in MaiGPT, then asks, "What files are in this conversation? List each file's type, size, and uploader." The Agent lists the names, types, sizes, and uploaders of both files. When asked, "What was the total on that receipt?", the Agent reads the photo again and answers with the total shown on it.



Expand the execution steps to see the Agent using list_conversation_files to list files in this conversation

Scope: Documents and images sent by users, files sent by human support agents, and files produced by the Agent itself (such as Canvas files). The Agent can only see files in the current conversation.

Filtering: When there are many files, the Agent can filter by type, uploader, filename, or time.

Reopening files: Documents and images are reopened through **Parse Attachment Content**, which analyzes image content again. Plain text files such as txt and csv can also be opened with **Read Plain Text Attachments**. If only **Read Plain Text Attachments** is enabled, other file types are only listed and cannot be reopened.

Files produced by the Agent: These are listed without rereading their contents. When **Generate Download Links** is enabled, the Agent can provide Canvas download links again.

Supported channels: Available across all channels, including LINE, Messenger, web, and MaiGPT.

> If both **Read Plain Text Attachments** and **Parse Attachment Content** are disabled, the Agent will not have this tool and cannot retrieve previous files.

7. 💾 Save Agent Settings

After selecting tools, remember to click "**Save**" to save your changes to the Agent settings.



Click Save to apply the tool configuration

Built-in Tool Switches in Agent Mode

When the response mode is Agent Mode, the Response Mode Settings tab also provides capabilities controlled directly by switches, without creating tools separately:

Setting	On-screen Description	Notes
Enable Tool Search	Automatically searches for available tools to help respond when enabled	Enabled by default. When many tools are available, the Agent searches before calling them. Turns used only to search for tools do not count toward the maximum iterations. See Agent Execution Limits
Agent Mode	Normal Mode Canvas Mode (Canvas)	See Agent Mode Sub-options for the differences
Code Interpreter	When enabled, the AI can execute code in a sandbox environment to	When enabled, the screen lists four tips (Python support, a secure sandbox, files downloadable from

Setting	On-screen Description	Notes
	complete tasks.	the Output panel, and suitability for calculations and data processing). See Code Interpreter
Browser Tool	When enabled, the AI assistant can control a browser to browse web pages and perform actions.	The screen states, "This feature is optimized for Claude models. Results may be less effective with other models." See Browser Tool
Image Search	Provides the image_search tool to search image content when the knowledge base uses a multimodal embedding model. Disabling this completely removes the tool.	Only applies when the linked knowledge base uses a multimodal Embedding model and contains uploaded images. Agents that do not need image-based image search can disable it to save tokens used by the tool description. View usage in Agent Monitoring

These switches are independent of the API/MCP tools selected on the Tools tab. After making changes, click Save at the bottom right.

Configure MaiAgent's Built-in Tools

MaiAgent includes three AI image generation tools that you can assign to your Agent as needed, with no additional setup. In the "Select Tools" dialog, select Gemini 3 Pro Image, Gemini 3.1 Flash Image, or GPT Image 2 Image Generation Tool under "System Built-in Tools".

> For a comparison of the three tools, see: MaiAgent's Built-in AI Image Generation Tools




Image generation tools in the Select Tools dialog

Your selected Agent can now use these enabled tools. When you interact with it and a relevant scenario arises, the AI will try to call these tools to complete tasks or retrieve information.

Customize Tool Message Display

When an Agent calls a tool, you can control how much execution information appears in the conversation and format the tool results for easier reading. These settings apply to API, MCP, and Function tools.

> Members with permission to edit the tool can modify the display copy, display mode, and output rendering template. Members without edit permission can only view these settings.

Use Case

A customer service manager creates an API tool for looking up trial requests. She wants customer service agents to see the lookup progress without expanding all the technical details. On the tool's Display Copy tab, she selects Compact and configures the text displayed when execution finishes. When the Agent later calls the tool, customer service agents see a brief execution status instead of the tool's complete input and output.

Tool Status in Conversations

When an Agent calls a tool, the tool card in the conversation shows a line of status copy that follows the execution progress. If the tool has no custom copy, the system first uses the tool category copy set by the organization; if the organization has not set any, the platform default copy is shown:

Status	When it appears	Platform default copy example
Running	The tool starts running	Searching the knowledge base: return process
Completed	The tool finishes running	Searched the knowledge base · 3 sources
Failed	The tool returns an error	Knowledge base search failed
No results	A knowledge base query, web search, database query, or file processing tool finds 0 results	Knowledge base search returned no results



After a knowledge base query completes, the status copy includes the number of sources found

The platform default copy follows these rules:

Follows the conversation language: The status copy is displayed in the language of the conversation. For example, a Web Chat visitor using the English interface sees "Searched the knowledge base ・ 5 sources". When the conversation carries no language information (for example, LINE), the system detects Chinese, Japanese, Korean, or Thai from the text of the user's message.

The running copy includes the query subject: The content of the query, such as the search keywords, URL, or file name, appears after the colon, and is truncated if it is too long. Only input fields related to the query are used; other inputs are not shown in the status copy.

The completed copy includes a result summary: When the count can be calculated, the number of results is appended after " ・ ", such as "7 results" or "3 sources". When the tool returns only a piece of text, only the completed copy is shown.

General tools show the tool name: When the tool category is "Other" or "Third-party integration," the copy includes the tool's display name, such as "Using Order Lookup" or "Used Order Lookup".

You can view the platform default copy for each category in Reply Waiting Style, where the organization can also override it by category.

Configure the Display

Open the Tool Editor

From the left menu, go to AI Features → Tools. Find the tool you want to configure in the tool list, then click the edit icon on the right.

Open the Display Copy Tab

In the Edit Tool window, select Display Copy.



Display copy and display mode settings for a tool

Select a Display Mode

Select a mode based on how much information conversation users need to see:

Mode	Effect in the conversation
Follow conversation platform settings	Uses the conversation platform's default display behavior. The current default is Full.
Full	Displays complete tool execution information.
Compact	Displays only concise execution information.
Hidden	Does not display the tool execution block.

> **Hidden only hides the tool execution block in the conversation; it does not disable the tool. To prevent the Agent from calling the tool, go to the Agent's Tools settings and remove the tool from its configuration.**

Customize the Display Copy

In the Display Copy section, click **Add**, select a language, and then fill in the **Running Copy** and **Completed Copy**. The copy can use variables to insert the tool name, query subject, result summary, or tool input parameters. For details, see **Use Variables in Custom Copy**.



Use variables in the display copy to insert the order number and result summary

Configure the Output Rendering Template

To format the content returned by the tool, click **Add** in the **Output Rendering Template** section. The template can use `{{output}}` to insert the complete tool result or `{{variable}}` to insert a top-level parameter from the tool input. If the variable cannot be found, an empty string is displayed. If the template is left blank, the raw JSON is displayed.

When finished, click **Confirm** to save.

Use Variables in Custom Copy

A customer service manager assigns an order lookup API tool to a customer service Agent and wants customers to see which order is being looked up. In the tool's **Display Copy**, she adds Traditional Chinese, entering `正在查詢訂單 {{orderId}}` as the running copy and `已查到訂單 {{orderId}} · {{result}}` as the completed copy. When a customer asks about order A1024, the tool card first shows "正在查詢訂單 A1024" and, once finished, shows "已查到訂單 A1024". This tool's response has no countable results, so the result summary is empty and the " · " after it is omitted as well.



Running: inserts the order number from the tool input



Completed: when the result summary is empty, the separator is omitted as well

Custom copy (the tool's **Display Copy** and the tool category copy table in the reply waiting style) can use the following variables:

Variable	Inserted content
`{{tool}}`	The tool's display name
`{{subject}}`	The subject of this query, such as search keywords, a URL, or a file name
`{{result}}`	A result summary, such as "7 results"; has a value only in the completed state
`{{parameter name}}`	A top-level parameter from the tool input, such as `{{query}}` or `{{orderId}}`

A variable with no value is displayed as an empty string, and the adjacent ":", " • ", or empty parentheses are removed along with it.

Custom copy is displayed exactly as you write it; the system does not automatically append the subject or result count. Add `{{subject}}` or `{{result}}` yourself when needed.

Custom copy is chosen by the conversation language. If that language has no copy, the custom copy of the default language (English) is used. If neither exists, the tool category copy set by the organization is used first (again looking for the conversation language, then the default language), and the platform default copy is shown only if there is still none. For example, if a tool has only Traditional Chinese copy, an English conversation first uses the organization's English category copy; the English platform default copy is shown only if the organization has not set one.

Display Copy only supports two kinds of copy: running and completed. When a tool finds 0 results, the completed copy is reused. When a tool fails, the organization's failure copy for that category is used first; the platform default failure copy is shown only if the organization has not set one.

Recommendations for Selecting a Mode

Select Full when users need to verify the tool results.

Select Compact and provide clear display copy when users only need to know that the system is processing the request.

Select Hidden when execution details should not appear in the conversation.

After completing the setup, assign the tool to a test Agent and send a test question. Confirm that the display copy and output template match the fields actually returned by the tool.

MCP Interactive Cards (MCP Apps)

In addition to returning data, some MCP servers also attach an interactive interface. After the Agent calls the tool, a card that users can interact with directly appears in the conversation. The card is not affected by the display mode above: even if you select Hidden, the interactive card is still displayed. For how cards are presented, the conditions, security restrictions, and common questions, see MCP Interactive Cards (MCP Apps).

Configure Contact MCP Credentials

On this page: 1. Feature Background | 2. Feature Location and Prerequisites | 3. Instructions | 4. Examples | 5. Contact MCP vs. Tool MCP | 6. FAQ | Appendix: Checklist

1. Feature Background



What are MCP credentials?

MCP credentials work like “a dedicated access pass for each customer”. When multiple customers use the same tool to query their own data, each person needs their own “key” (credentials). This ensures that everyone can only see their own data, without seeing anyone else's.

A simple analogy

In an apartment building, all residents use the same elevator (MCP tool), but each person must scan their own access card (credentials) to reach their floor.

Why is this feature needed?

Protect customer privacy — Each customer uses their own credentials to keep their data separate
Personalized service — Different customers can have different access permissions

Easy management — When a customer's credentials expire or need replacement, you only need to update that customer's settings

Example use cases

Scenario 1: Personal data queries

Customer A and Customer B both want to check their own purchase history, but each has a different username and password

Scenario 2: Department permissions

Different departments use the same query tool but have different viewing permissions

Scenario 3: Tiered service


VIP customers can query more detailed data, while regular customers can only query basic data

2. Feature Location and Prerequisites

Where to find this feature

Navigation path

Contact Management → Click Edit Contact → Switch to the “MCP Credentials” tab




Important reminder

Create and save the contact before setting MCP credentials (so the credentials can be correctly linked to the contact)

Prerequisites

Before configuring credentials, check the following:

MCP tools have already been created in the system (AI Features → Tools → MCP)



2. The contact whose credentials you want to configure has been created and saved
3. You have obtained the contact's credential information (usually provided by the customer or authorized personnel)

Permissions

System administrators can assign permissions for “Tools” and “Contacts” according to the organization's needs.

3. Instructions

3.1 View configurable tools

Steps

Open the contact you want to edit
Click the “MCP Credentials” tab at the top
A list of all configurable tools appears

About the tool list

Each tool displays:

Tool name (for example, “Customer Database Query”)
Tool description (if available, shown in small gray text below the name)
Edit button (the pencil icon on the right)

How to identify configuration status

Already configured → A green “Configured” badge appears to the right of the tool name
Not yet configured → No badge appears to the right of the tool name

3.2 Add or edit credentials

Step 1: Open the settings area

Click the “Edit” button (pencil icon) to the right of the tool to expand the settings area

Step 2: Enter Headers (credential information)

Paste the credential information into the text box in JSON format:

```
{"Authorization": "Bearer YOUR_KEY_CODE"}
```

If you are unsure about the format, click the “Format JSON” button to format it automatically

> What are Headers?
> Headers are like “identity documents” that contain this contact's unique key. Just as you need an ID when visiting a bank, the system needs these Headers to verify “who this person is”.

> What is JSON?
> JSON is a data format that looks like this: {"field_name": "content"}. Don't worry—someone will usually provide it for you, and you only need to copy and paste it.

Step 3: Things to keep in mind

Headers are required (marked with a red
*)

The Headers you enter are merged with the tool's default Headers: fields with the same name use the values entered here, while other default fields are sent as usual

> Important: Different MCP tools require different Headers formats. Make sure the credentials you received match this tool's requirements

Step 4: Save or cancel

Save settings

After confirming everything is correct, click the “Save” button in the lower right

The system checks whether the format is valid

After saving successfully:

The editing area collapses automatically

A green “Configured” badge appears to the right of the tool name (it first appears when you configure credentials for the first time)

Cancel editing

If you do not want to save, click “Cancel”

3.3 Reset credentials (clear configured credentials)

When would you use this?

Reset credentials if they are configured incorrectly or are no longer needed.

Steps

Click the tool's “Edit” button to expand the editing area

If credentials have already been configured for this tool (a green “Configured” badge is visible), a red “Reset Credentials” button appears in the lower left

Click it and confirm to clear the credentials

After clearing, the green “Configured” badge to the right of the tool name disappears

⚠️ Important reminders

Resetting cannot be undone

Copy and save the Headers content before resetting

If you only want to change the content, edit it directly; there is no need to reset

4. Examples

Example 1: Configure database query credentials for a customer

Scenario

Customer A wants to query their own purchase history, and you have received a set of credentials.

Headers content

```
{
  "apikey": "eyJhbGciOiJIUzI1NiIsInR5cCI6IkpXVCJ9 ... ",
  "Authorization": "Bearer eyJhbGciOiJIUzI1NiIsInR5cCI6IkpXVCJ9 ... "
}
```

Steps

Find the contact “Customer A” and click Edit

Switch to the “MCP Credentials” tab

Find the “Customer Database Query” tool and click its Edit button

Paste the credentials

Click “Format JSON” to ensure the formatting is tidy

Click Save

Example 2: Configure dedicated query credentials for a department

Scenario

The sales department needs to query customer data, but can only view basic data, not financial data.

Headers content

```
{
  "X-API-Key": "dept_sales_abc123",
  "X-Department": "sales"
}
```

Field descriptions

`X-API-Key` — The sales department's dedicated key

`X-Department` — Identifies the user as the sales department

Example 3: Configure credentials with multiple fields

Headers content

```
{
  "Authorization": "Bearer token_xyz",
  "X-Client-ID": "client_12345",
  "Content-Type": "application/json"
}
```

Field descriptions

`Authorization` — The primary authentication key

`X-Client-ID` — The customer ID

`Content-Type` — Describes the data format (usually fixed to this value)

5. Contact MCP vs. Tool MCP

Feature comparison

Comparison item	Tools → MCP	Contacts → MCP Credentials
What it does	Creates the tool itself	Sets dedicated credentials for individual contacts
Scope	Available across the system	Only for a specific contact
Settings	• Tool URL • Default credentials • Available capabilities	• Only this person's credentials • Fields with the same name override default credentials
When to use it	When connecting a new tool for the first time	When each customer needs different credentials
Who can use it	Anyone with the required permissions	Anyone with the required permissions
Where to configure it	Tool management page	Contact editing page
Common uses	• Add a query tool • Configure basic tool information	• Each customer uses their own login credentials • VIP customers have special permissions

A simple analogy: a computer lab

Imagine a school's computer lab:

Tool MCP (created by authorized personnel)

Install software in the computer lab

Configure the software so all computers can use it

Decide which features the software provides

Contact MCP credentials

Create an individual account for each student

Each student logs in with their own account

Different students can have different access permissions

Actual workflow

```
Step 1: Create an MCP tool (personnel with permission to create tools)
    ↓
Create the “Customer Database Query” tool
- Set the tool URL
- Set default credentials (if any)
    ↓
Step 2: Configure dedicated credentials for each contact (personnel with
permission to configure credentials)
    ↓
Customer A: Configure A's dedicated credentials
Customer B: Configure B's dedicated credentials
Customer C: Configure C's dedicated credentials
    ↓
Result: Everyone uses the same tool with their own credentials
```

Flexible permissions

System administrators can decide who can create tools and who can configure credentials according to the organization's needs. These can be the same people or separate groups.

Key points

Tool MCP — Create the “tool” first

Contact MCP credentials — Then give each person their “key”

6. FAQ

Q1: Why can't I see the “MCP Credentials” tab?

Possible causes

You are “adding a contact” (save the contact first, then edit it to see the tab)

No MCP tools have been created in the system yet

The contact information has not been saved

Solution

Fill in and save the contact's basic information first

Confirm that the system has MCP tools (ask authorized personnel to check)

Enter edit mode again

Q2: What if the Headers format is invalid?

Common formatting errors

❌ Incorrect: `{'key': 'value'}` (uses single quotes)

❌ Incorrect: `{key: value}` (missing quotes)

❌ Incorrect: `{"key": "value",}` (extra trailing comma)

✅ Correct: `{"key": "value"}`

Solution

Click “Format JSON” to have the system check automatically

If the issue persists, copy the credentials again

Or ask the person who provided the credentials to double-check the format

Q3: How do I know what to enter?

Ways to obtain credentials

Ask the customer to provide their credential information

Ask the responsible person to provide or help create them

Ask the colleague responsible for this tool

Refer to other contacts that have been configured successfully (but do not copy their credentials directly!)

⚠️ Do not enter arbitrary values

Credentials have specific formats and contents. Incorrect values will prevent the tool from working and may also cause data errors.

Q4: Why can't I see the “Configured” badge?

Display conditions

This green badge appears only for tools with credentials already configured

During the first configuration, it does not appear until you save successfully

The badge appears after saving successfully

No badges in the tool list?

This means no MCP credentials have been configured for this contact yet, which is normal.

Q5: Can't find the "Reset Credentials" button?

Display conditions (both must be met)

Credentials have already been configured for this tool (a green "Configured" badge appears to the right of the tool name)

You have clicked "Edit" to expand the editing area

Button location

After expanding the editing area, the red "Reset Credentials" button is in the lower left, while "Cancel" and "Save" are in the lower right.

No credentials configured for this tool yet?

There is no "Reset Credentials" button because there are no credentials to reset. The lower left will be empty.

Q6: What happens when I click "Reset Credentials"?

What happens

This contact's dedicated credentials are cleared

The green "Configured" badge to the right of the tool name disappears

If the tool has default credentials, it switches to those (although it usually does not)

⚠️ Deletion cannot be undone

Recommendations

Copy the Headers content as a backup first

Consider whether you really want to delete the credentials

If you only want to change the content, use "Edit"

Q7: Can multiple contacts use the same credentials?

Technically, yes

The system does not prevent you from copying the same credentials to different people

But it is not recommended

You cannot tell who is using them
Data may get mixed together
If someone encounters an issue, you cannot identify whose issue it is

Recommended approach

Each contact uses their own credentials
Keep data clearly separated
Make tracking and management easier

Q8: The tool list is empty and shows “No tools available”?

Possible causes

No MCP tools have been created in the system yet
All tools are of the “Global” type (global tools do not require individually configured credentials)

Solution

Ask someone with permission to create tools to confirm whether MCP tools have been created
Check that the tool type is configured correctly
If everything is correct but the tools still do not appear, contact technical support

Appendix: Checklist

Before configuration

[ ] The contact has been created and saved
[ ] MCP tools are available in the system
[ ] Credential information has been obtained (from the customer or responsible personnel)
[ ] The credential format has been verified

During configuration

[ ] The Headers format is valid (use the formatting button to check)
[ ] All required fields are filled in
[ ] There is no unnecessary or incorrect content
[ ] No error message appears after formatting

After configuration

[ ] A green “Configured” badge appears to the right of the tool name

[ ] The tool has been tested and works correctly

[ ] The configuration details have been recorded (date, contact, tool name)

[ ] Relevant personnel have been notified of completion, if needed

Built-in AI Image Generation Tool

📋 Feature Overview

MaiAgent includes three AI image generation tools that can create new images and edit images based on references. Select them in your Agent's tool settings to start generating images right away.

On the Agent settings page, click "Select Tools" under "Tools", then select the following image generation tools under "System Built-in Tools":

Gemini 3 Pro Image
Gemini 3.1 Flash Image
GPT Image 2 Image Generation Tool




Image generation tools in the Select Tools dialog

> See: Configure Tools for an Agent

🎨 Full Tool Comparison

Tool	Key Features	Use Cases
Gemini 3 Pro Image	Context understanding, Chinese prompts, reference image input, conversational editing	Creative tasks requiring context understanding, Chinese-language requests
Gemini 3.1 Flash Image	Fast generation, Chinese prompts, reference image input, editing with multi-step instructions	Rapid iteration, creative brainstorming
GPT Image 2	Professional quality, iterative refinement, reference image input	Brand design, professional use

⭐ Generation Examples

GPT Image 2 - Professional Design Example

Previous generation example: The coffee cup logo below was generated earlier and is retained to illustrate its line work and shape.

> **This older image has a transparent background, which does not mean direct generation of transparent backgrounds is still supported. If you need an asset with its background removed, use the solid-color background approach under “How do I generate an image with a transparent background?” below.**



Previous generation example: a minimalist coffee cup logo. The transparent background does not represent current generation capabilities.

Features: Refined line work, suitable for branding

📝 Usage and Best Practices

Basic Usage Syntax

Use Case	Example Prompt	Recommended Tool
Everyday creations	`Draw a cute puppy`	Gemini 3 Pro Image
Professional design	`Design a modern, minimalist logo with a solid white background`	GPT Image 2
Rapid prototyping	`Quickly generate a concept image for a website homepage`	Gemini 3.1 Flash Image

Iterative Refinement (GPT Image 2)

```
Round 1: “Design a coffee shop logo”
Round 2: “Change the color to dark brown”
Round 3: “Add some steam effects”
Round 4: “Make the overall design more minimalist”
```

Editing with Reference Images

Gemini 3 Pro Image, Gemini 3.1 Flash Image, and GPT Image 2 all support editing with reference images. Upload the image you want to modify in the conversation and describe only the parts you want to change. The tools will try to keep anything you do not mention unchanged:

```
“Based on this image, change the background to a seaside scene”
“Keep the person unchanged and only change the clothing color”
“Add some flowers to this scene”
```

> If the Agent says it cannot read a previously generated image, upload the image you want to modify to the conversation again, then describe your requested changes.

🎯 Practical Use Case Guide

Scenario 1: Social Media Content Creation

Need: Create an image for an Instagram post

Recommendation: Gemini 3 Pro Image

Example prompt: `Create a cozy café scene suitable for an IG post`

Scenario 2: Corporate Brand Design

Need: Design a company logo and brand assets

Recommendation: GPT Image 2

Example prompt: `Design a logo for a technology company in a minimalist, modern style with a solid white background`

Scenario 3: Creative Ideation and Prototyping

Need: Quickly visualize creative concepts and refine them through iteration

Recommendation: Gemini 3.1 Flash Image

Example prompt: `Concept art for a mobile app interface design`

❓ Frequently Asked Questions and Solutions

Image Quality Questions

Q: How do I get the highest-quality images?

A: Use GPT Image 2 or Gemini 3 Pro Image and provide a detailed description:

✅ Specific style requirements (such as "professional photography style")
✅ Detailed scene descriptions (lighting, angle, atmosphere)
✅ Clear quality requirements (such as "high resolution" or "commercial quality")

Q: Why doesn't the generated image match my expectations?

A: Suggestions for improving your prompts:

🎯 Use specific rather than abstract descriptions
🎨 Specify a clear artistic style
📐 Explain composition and viewing angle requirements
🌈 Describe colors and lighting effects

Feature Usage Questions

Q: How do I generate an image with a transparent background?

A: Currently, none of the three image generation tools (Gemini 3 Pro Image, Gemini 3.1 Flash Image, and GPT Image 2) can directly generate images with transparent backgrounds. If you need an asset with its background removed (a product image, logo, or icon), specify a single solid-color background in your description so the subject is clearly separated from the background, then remove the background with a background removal tool:

```
Design a logo with a solid white background and no shadows between the subject
and the background
Generate a product photo with the product on a solid green background
```

Q: Can I modify a generated image?

A: Yes! Gemini 3 Pro Image, Gemini 3.1 Flash Image, and GPT Image 2 all support editing with reference images. Upload the image you want to modify, then describe the parts you want to change:

```
Based on this image, change the sky to sunset colors
Keep the composition unchanged and only change the person's clothing
```

Gemini 3 Image Generation Tool

Feature Introduction

The Gemini 3 image generation tool is MaiAgent's AI image generation feature, powered by Google's Gemini 3 Pro Image model. It lets Agents generate high-quality images from users' text descriptions, supports Traditional Chinese and English prompts, and enables style transfer and image editing using reference images.

> **Gemini 3 Pro Image is Google's multimodal AI model with powerful image generation capabilities. It uses contextual understanding and reasoning based on world knowledge to generate high-quality images that fit the context.**

Key Features

Feature Type	Description	Use Cases
Text-to-image generation	Generate images from text descriptions	Marketing materials, social media posts, product visualization
Reference image editing	Transfer styles or modify content based on reference images	Consistent brand visuals, image style adjustments
Conversational image editing	Continuously adjust and improve images across multiple conversation turns	Iterative design, fine-tuning details
Chinese prompt support	Describe your desired image directly in Traditional Chinese	Chinese-speaking users can use the tool without translating their prompts

Enable the Gemini 3 Image Generation Tool

Prerequisites

Confirm that your organization plan supports image generation

Confirm that AI feature permissions are enabled

Prepare the Agent that will use this tool

Setup Steps


Open the Agent settings page

Click "AI Features" → "AI Assistants" in the left menu

In the row for the Agent you want to configure, click the “Edit” icon in the “Actions” column to open the “Settings” tab

Configure tool settings

Click “Tools” in the “Capability Extensions” group on the left of the settings page
Click the “Select Tools” button in the upper right
Find and select “Gemini 3 Pro Image” under “Built-in System Tools”
Click “Confirm”



Select Gemini 3 Pro Image in the Select Tools dialog

Save settings

Click the “Save” button in the lower right
Setup is complete when “Saved successfully” appears

> Notes - Image generation deducts Credits per image. The unit price depends on the image generation model. Check the “Billing” tab under “Organization Settings” → “Credits” for details - Image dimensions depend on the actual generated output. After downloading, check whether the image meets your needs

How to Use

Use via the Chat Interface

Enter an image description

Enter a description of the image you want to generate in the chat box

Examples:

- “Generate a landscape image of a beach at sunset”
- “Draw a cat wearing a spacesuit”
- “Design a minimalist coffee shop logo”
- “Create a watercolor painting of a mountain landscape”

Use reference images

Upload an image in the conversation as a reference

Add text instructions describing the changes you want

Examples:

After uploading a photo, say: “Convert this photo to a watercolor painting”

After uploading a product image, say: “Design a promotional poster for this product”

Edit through conversation

After generating an image, request changes in subsequent messages

Examples:

- “Change the background to blue”
- “Add some stars”
- “Make the overall mood a little warmer”

> The more detailed your description, the better the generated image quality. Include details such as style, colors, composition, and mood.

Use Case Examples

Scenario 1: Creating Marketing Materials

Need: Quickly generate visuals for social media posts

Example conversation:

```
User: Generate an image for Instagram about a spring product launch. Use a fresh, bright style with cherry blossoms and shopping bags.
AI: [Generates image] I've generated a promotional image for your spring product launch, featuring cherry blossom petals and stylish shopping bags in a fresh, bright style.
User: Great, but can you change the shopping bags to pink?
AI: [Generates updated image] I've changed the shopping bags to pink to better match the cherry blossom theme.
```

Scenario 2: Product Visualization

Need: Create a visual representation of a product concept before production

Example conversation:

```
User: I want to design a smartwatch with a round face, a silver metal band, and a dark blue dial. Please generate a concept image.
AI: [Generates image] I've generated a smartwatch concept image with a round face, a silver metal band, and a dark blue dial.
```

Scenario 3: Style Transfer

Need: Convert an existing image to a different artistic style

Example conversation:

```
User: [Uploads photo] Convert this photo to a comic style.
AI: [Generates image] I've converted your photo to a comic style while preserving the original composition and main elements.
```

Prompt Writing Tips

Writing Effective Prompts

Include specific descriptions:
- Subject: What you want to generate
- Style: Realistic, cartoon, watercolor, oil painting, graphic design, etc.
- Colors: Main tones and color preferences
- Composition: Close-up, wide view, overhead view, etc.
- Mood: Warm, cool, lively, calm, etc.

Good examples:
- “An orange Shiba Inu sitting on a park bench in autumn, with golden maple leaves in the

background and warm afternoon light, in a realistic photography style"
- "A minimalist technology company logo using blue and white with geometric shapes"

Avoid vague prompts:
- "Draw a picture" (lacks specific details)
- "A nice image" (no clear direction)

Frequently Asked Questions

Q: Which prompt languages does the Gemini 3 image generation tool support?

A: It supports Traditional Chinese and English prompts. You can describe your desired image directly in Chinese.

Q: How many Credits does it cost to generate one image?

A: Image generation deducts Credits per image, and the unit price depends on the image generation model used. Check "Image Generation" under the "Tool Calls and API Integrations" category on the "Billing" tab in "Organization Settings" → "Credits". Regularly review your organization's Credits balance and usage history.

Q: Can I use reference images?

A: Yes. Upload an image in the conversation as a reference, and the Agent will incorporate it into the generation process. This is especially useful for style transfer, image editing, or creating new content based on existing materials.

Q: What resolution are the generated images?

A: Image dimensions depend on the actual generated output. After downloading, check the resolution before deciding whether the image is suitable for social media posts, presentations, or other materials.

Q: Can I keep editing images across multiple conversation turns?

A: Yes. The Agent remembers the conversation context, so you can request detail adjustments, style changes, or additional elements in subsequent messages to gradually refine the image.

Q: What should I do if image generation fails?

A: Possible causes and solutions:
- The prompt violates content policies: Adjust the description to avoid inappropriate content
- The system is busy: Try again later
- Insufficient Credits balance: Check your organization's available balance on the "Credits" page

Related Documentation

Further reading - **Tool Feature Overview** - **Configure Tools for an Agent** - **Built-in AI Image Generation Tool** - **Create an Agent**

Quick Menu

Quick Menu is a type of Agent UI. It stays in the Web Chat input bar, allowing visitors to start with 2–6 menu items without typing first. Each item can send a message, insert text into the input field, or open an external link.


> Quick Menu is only displayed in Web Chat. It does not appear on other platforms, such as LINE, Microsoft Teams, or test conversations in the admin console.

When to use it

An online retailer wants visitors to choose "Check order status," "Returns and exchanges," or "Contact support" as soon as they open the support chat. The administrator creates a quick menu, sets the first two items to send the corresponding questions, and sets the third to insert "I want to contact support" into the input field. Visitors can click an item to start the right service flow without having to figure out what to ask.

Create a quick menu

Go to AI Features → Agent UI, click Add, and select Quick Menu.




Select "Quick Menu" to start configuring it

Enter the **Display Name**, **Tool Name**, and an optional description. The tool name is used by the AI, so use an English name that follows the naming rules.

Under **Appearance**, select Grid or List. To show the full menu as soon as visitors enter the chat, enable **Expand by Default**.

Configure 2–6 menu items and select an action for each. The **Preview** on the right shows how the menu will appear in Web Chat in real time.



Quick Menu editor and live preview

Check the preview, then click Save in the upper-right corner.

Add the quick menu to an Agent

Saving a quick menu does not automatically display it in Web Chat. You must also attach it to an Agent that uses Agent mode.

Go to AI Features → AI Assistants and open the Agent that will use the quick menu.

Make sure the Agent's response mode is Agent Mode. If it is not, the "Agent UI" section will guide you to switch modes first.

In the Agent settings, click Agent UI, then Select Agent UI.

Select the quick menu you just created, confirm your selection, and save the Agent. Reopen this Agent's Web Chat to use the quick menu in the input bar.

Differences between the three actions

Action	What happens when clicked	Best for
Send Message	Sends the configured prompt directly to the AI; the button text is displayed in the conversation	Frequently asked questions and predefined service flows
Fill Input Field	Inserts text into the input field so visitors can edit it before sending	Requests that need an order number or additional details
Open Link	Opens the specified URL	Visiting an official website, form, or external service page

For "Send Message," the button text and the prompt sent to the AI can differ, but they should have the same meaning to avoid a mismatch between the option visitors see and the request the AI receives.

Appearance and icons

A grid menu automatically arranges items based on their number, while a list is suitable for items with longer text. Each item can have no icon, use an Emoji, or use an uploaded image. If no icon is set, the menu uses the first character of the button text as an identifier.


> If a menu item opens an external link, make sure the URL uses HTTPS and regularly check that the link is still accessible.

Agent UI

1. What Is Agent UI?

Agent UI lets Agents display information cards or interactive options in conversations. This page introduces FlexMessage, which combines text, images, and buttons in cards to make information easier to read.

When you select Add Agent UI, you can choose FlexMessage, Quick Reply, or Quick Menu.



First, choose the type you want to create

Use Case

A customer service manager wants to show colleagues how a receipt card looks. She creates a Receipt template card with fictional items and amounts, binds it to a test Agent, and asks the Agent in Web Chat to display a fictional sample receipt. After the Agent calls the card tool, the conversation displays the items, total, and payment number so she can check the layout.

> Card templates and AI prompts do not automatically connect to billing, membership, hotel booking, or medical appointment systems. To display real, live data, first provide knowledge base content or configure tools that can retrieve the data. Opening a link with a button does not mean a payment or booking has been completed. The receipt below uses fictional template data.

2. Card Fields and Buttons

You can set a **Default Value** for each card field or enter an **AI Prompt** to tell the Agent what the field should display. Fields without an AI prompt use their default values.

What Can Card Buttons Do?

URL button: Opens a specified URL, such as a product information page.

Prompt button: Sends a message to the Agent to continue the conversation, such as "View other products."

A button's result depends on its destination or the capabilities configured for the Agent. Test buttons before making them available to users.

3. Create an Agent UI (FlexMessage)

1. Open the Agent UI Page

In the left menu, click **AI Features** → **Agent UI**, then click **Add Agent UI**. Choose FlexMessage to open the settings page.

2. Enter Basic Information

Field	Description
Display Name	A name used to identify the card in the admin interface, such as "Fictional Receipt Card"
Tool Name	An English name the AI uses to identify the tool, such as `demo_receipt_card`
Description	The card's purpose, such as "Display a fictional sample receipt"
Prompt	When to use the card, such as "Use this card when the user asks for a fictional sample receipt"

> Use an English identifier for the tool name without spaces or Chinese characters. Clearly describe when to use the card in the prompt to help the Agent decide when to call it.

3. Select a Template and Configure Fields

Click a template to preview it, then click **Apply This Template**. Built-in templates include Restaurant, Apparel, Hotel, Local Search, Real Estate, Social, TODO app, Transit, Receipt, Shopping, Menu, and Ticket. You can also select **Custom** and paste FlexMessage JSON.

After applying the template, adjust the **Default Value** and **AI Prompt** under **AI Field Settings**. Start with fixed fictional data to check the layout, then gradually add fields that need dynamically generated content.



Basic information and preview for a Receipt card

4. Save the Card

Click **Save** in the upper right. Return to the list to see the card you created.


4. Bind the Card to an Agent

1. Open Agent Settings

Go to **AI Features** → **AI Assistants** and open the Agent you want to configure. Use **Agent Mode** to configure Agent UI.

2. Select a Card


On the settings page, click **Agent UI**, then **Select Agent UI**. Select the card and click **Confirm**. The added card appears under **Agent UI in Use**.



Confirm that the card has been added to the Agent

3. Save and Test

Click **Save**, then open the Agent's test conversation or Web Chat. Enter “Please display a fictional sample receipt” and confirm that the Agent calls the card tool and the card content is correct.



The Agent displays a fictional receipt card in the conversation; amounts are for demonstration only

5. Example Uses

You can adapt templates into information cards for product catalogs, accommodation, courses, or event tickets. Prepare the content and working links first, then configure the card fields and prompts. To check inventory, orders, or booking status, configure the corresponding data sources and tools first.

An Agent can have multiple cards bound to it. Clearly describe when each card should be used and test them individually to confirm that the Agent selects the right card for each question.

6. Agent UI Question Tool (ask_user_question)

In addition to FlexMessage cards, you can use the Agent UI Question Tool to let the Agent list options for users to answer. Add this built-in tool in the Agent's Tools settings. For instructions, see Configure Tools for an Agent.

How options appear in Web Chat is determined by the conversation platform's Question Set Option Display Mode.

7. FAQ

- **What if the card does not appear?**
- **Can the card query external systems on its own?**

Quick Reply

Quick Reply is a type of Agent UI. After an Agent responds, it adds a row of clickable buttons (chips) below the message so users can choose their next step without typing: send a message, open a link, or prefill the input field. The Agent uses the "Trigger Conditions" to decide when to display the buttons, with up to 13 buttons per row.

When to use it

A telecom support team wants the Agent to ask "How can I help you?" and show three buttons —"Check bill," "Change plan," and "Report an issue"—when a user starts a conversation without a clear intent. When the user clicks "Check bill," the Agent goes straight to the billing flow. Another use is dynamic generation: when a user discusses a product they are interested in, the LLM generates buttons for up to 5 related products based on the context.

The difference from Quick Menu: a quick menu stays in the input bar and does not change with the conversation. Quick Reply is attached below a specific response; the Agent decides when it appears, and its content can be generated in real time based on the conversation.

Create a Quick Reply

Select a type

Go to "AI Features" → "Agent UI," click "Add Agent UI," and select Quick Reply (a quick reply button row).



Click Quick Reply under "Select Agent UI Type"

Enter basic information

Field	Description
Display Name	The name displayed in the admin console, such as "Support Menu"
Tool Name	An English identifier used by the LLM; it must follow the naming rules (English letters and underscores, with no spaces)
Description	Optional; describes what this set of buttons is for
Trigger Conditions	Required. Tell the Agent in natural language when to attach this set of buttons, such as "When a user starts a conversation without a clear intent and needs help choosing" or "Provide category shortcuts when users ask frequently asked questions"

> The more specific the trigger conditions, the better the Agent can display buttons at the right time instead of attaching them to every response. When attaching multiple Quick Reply sets to the same Agent, avoid overlapping trigger conditions.

Select a template (optional)

The "Select Template" section lists built-in templates. Click one to display a preview on the right. Clicking "Apply This Template" overwrites the current button settings with the template content, which you can then edit.



After applying the "Support Menu" template, the preview on the right simulates the button row in Web Chat

Configure buttons

First, select Static List or Dynamic Generation above "Button Settings" (see the next section for the differences), then configure each button. The "Preview" on the right simulates the Web Chat display in real time. Click a button to try it, then click "Show Buttons Again" to start over.

Save

Check the preview, then click "Save" in the upper-right corner. Before saving, the system checks that button text is not empty, fixed text is no longer than 20 characters, AI fields have prompts, links start with `https://`, and the button count range is within 1–13.

Static list and dynamic generation

Mode	How buttons are determined	Best for
Static List	Configure 1–13 buttons yourself, choosing "Fixed" or "AI" for each button's text and action fields	Predefined service categories and FAQ shortcuts
Dynamic Generation	Provide a "button pattern" and a count range; the LLM generates N buttons in real time based on the conversation context	Product recommendations and options based on topics users mention

Static list

Click "Add Button" to add a button (up to 13). Expand each button to configure the fields described in the next section; use the trash icon to the right of its title to delete it. Each button's title shows its action type label and button text for easy identification.

Dynamic generation

Field	Description
Minimum Count / Maximum Count	The range of buttons the LLM generates; must satisfy 1 ≤ minimum ≤ maximum ≤ 13
Generation Rules	Tell the LLM when and how to generate buttons, and how many, such as "List up to 5 related products based on the user's interests; skip the entire set if there are no relevant items"
Button Pattern	Settings shared by all generated buttons (action type, text, and icon); the text field is usually set to AI generation

Dynamic generation mode does not provide JSON source editing.

Settings for each button

Action types

Action	When clicked	Fields to fill in
Send Message	Sends a message to the Agent as the user	Message to Send: the actual text sent, which can differ from the button text
Open Link	Opens a URL	Link URL: must start with `https://`
Prefill Input Field	Inserts text into the input field without sending it; users can edit it before sending	Prefill Text

Fixed and AI

"Button Text" and the action fields in the table above each have a Fixed／AI toggle on the right:

Fixed: Displays the value you enter. Button text can be up to 20 characters.

AI: Enter a prompt, and the LLM generates content from it during the conversation. For example, set button text to AI and enter "The product name the user just mentioned."

Button icons

Each button can use None, Image (enter an `https://` image URL), Emoji (a single emoji), or Initials Badge (1–2 characters).

Advanced action JSON (LINE only)

To use native LINE actions beyond the three basic actions in LINE (such as `datetimepicker`, `postback`, `camera`, `cameraRoll`, `location`, `richmenuswitch`, or `clipboard`), click an example label at the top to insert it quickly, or paste a LINE action object as JSON. The system passes it to LINE unchanged. These buttons appear gray in the preview and are not displayed in Web Chat.

JSON source

The "JSON Source" section (collapsed by default) corresponds to the LINE `quickReply` JSON for the current static list. Advanced users can edit it directly and click "Apply JSON to Button Settings." Applying it overwrites the button settings and only supports the `message`／`uri`／`inputOption` actions; any buttons beyond 13 are discarded.

Attach to an Agent

After saving, attach it to an Agent that uses Agent Mode for it to take effect: go to the Agent settings → "Interface & Experience" → "Agent UI" → "Select Agent UI," select the Quick Reply you just created, and save. For detailed instructions, see **Bind to an Agent**.

Frequently asked questions

- ▶ Which platforms display the buttons?
- ▶ Why didn't the Agent attach any buttons?
- ▶ Do the buttons disappear after the user clicks one?

Skills



Skills: define multistep SOPs that an Agent uses to guide conversations

What is this?

A skill is a multistep workflow for an Agent. Define an SOP in natural language, and the Agent loads and follows it step by step when a relevant situation arises in a conversation.

If a tool is an Agent's "individual capability" (like a screwdriver), a skill "combines multiple capabilities into a complete workflow" (like an assembly manual): it tells the Agent which tools to use, when and how to use them, and how to respond afterward.

An example

Suppose you want an Agent to handle "customer quotes":

Without a skill: the Agent may give scattered responses and miss important information.

With a skill: you define a quote preparation SOP—

```
1. First confirm the product model the customer needs
2. Look up the product price list (using a tool)
3. Confirm the quantity the customer needs
4. Apply discount rules based on the quantity
5. Generate a quote summary
6. Ask whether the customer needs any adjustments
```

The Agent guides the conversation through this workflow, ensuring no steps are missed.

What can a skill contain?

Each skill has three components. You can configure all three for skills created manually or by uploading a package:

Component	Description
Instructions	An SOP in Markdown that describes the complete steps and response format in natural language. Instructions can also ask the Agent to search its attached knowledge bases
Attached tools	Tools called during the skill workflow (API tools and MCP tools), provided to the Agent along with the skill
Resource files	Reference documents, templates, or scripts included with the skill. If the Agent has **Code Interpreter** enabled, loading the skill places these files in the code execution environment for the Agent to read or process; otherwise, the Agent only uses the instructions

> A skill is defined through plain-text prompts, rather than a flowchart or code. Describe the entire workflow in natural language, and the Agent understands and executes it.

How skills work

Create a skill: enter a name and description, write the instructions, and attach tools and resource files as needed. Clearly describe its purpose and when it should be triggered, since the Agent uses this description to decide when to use the skill.

Bind it to an Agent: select the skills to use in the Agent's settings. An Agent can have multiple skills. Skills only take effect for Agents whose **Response Mode** is set to **Agent Mode**.

The user asks a question: for example, "Help me check how many days of leave I have."

The Agent selects and loads a skill: normally, the Agent only sees each skill's name and description. It loads the full instructions only when it determines that a skill should handle the question. This keeps unused instructions out of each conversation, even when many skills are bound to the Agent.

Execute and respond: the Agent follows the instructions to call attached tools (querying databases, calling APIs, and so on), then formats the response as specified.

For the underlying mechanism, the `SKILL.md` specification, and APIs, see **Skill Module** in the technical manual.

Key benefits of skills

Standardize complex tasks: follow the same SOP every time for consistent response quality.

Precise triggering and task assignment: different skills handle different tasks, and the Agent uses their descriptions to select the right one.

Reuse and sharing: bind a skill to multiple Agents or export it as a `.skill` file to share with other organizations.

Package instructions and tools together: bundle "what to do" with "what to use," without repeating extensive workflow details in the system prompt.

Skills vs. tools

Comparison	Tool	Skill
Nature	A single external capability (API, MCP)	A complete execution workflow
Contents	API endpoint MCP server	Instructions + tools + resource files
Analogy	Screwdriver	Assembly manual + screwdriver
Trigger	The Agent decides whether to call it	The Agent decides whether to load it based on the skill description
Use cases	A single action (checking the weather, sending an email)	A multistep workflow (processing returns, calculating leave)

Skills and tools complement each other: skills use attached tools to perform actions, while skill instructions tell the Agent when to use tools and in what order.

When should you use a skill?

Workflows with a fixed SOP: quotes, complaint handling, troubleshooting

Collecting information across multiple turns: reservations (asking for the date, time, and number of people)

Conditional decisions: following different paths depending on the situation

Ensuring no steps are missed: guided form completion, approval workflows

When is a skill unnecessary?

Simple questions and answers (a knowledge base is sufficient)

Looking up a single piece of information or performing one action (a tool is sufficient)

Example use cases

Scenario	Skill	Trigger	Steps	Attached tools
Enterprise customer service	Return processing workflow	A customer requests a return or exchange	Look up the order → Confirm return eligibility → Create a return request → Report the result	Order lookup API, returns system API
Government agency	Leave calculation	A question about remaining leave or annual leave	Confirm employee category → Retrieve regulatory examples → Compare and calculate → Produce the result	Knowledge base search
E-commerce platform	Customer information collection	A customer expresses purchasing interest or requests a quote	Guide the customer to provide their name, company, and contact information → Save to CRM	Google Sheet API, CRM tools
Marketing team	Email sending service	A request to send an email or contact a customer	Confirm the recipient → Draft the email → Send	Gmail MCP tool

What do I need to do?

Create a skill: write it manually or upload a `.skill` `.zip` skill package. See **Skill Management: Create a Skill**

Describe the workflow: write the complete steps in natural language in the instructions

Attach tools and files: add them in the **Attached Tools** and **Files** tabs as needed. See **Edit and Configure a Skill**

Bind it to an Agent: enable the skill in the Agent's settings. See **Bind a Skill to an Agent**

Test: simulate user conversations to check that the workflow runs smoothly

Skill Management

> If you are not yet familiar with skills, read **Skills** first.

Create a skill

Click **Skills** in the left menu to open the skill management page, then click **Add skill** in the upper-right corner.

The system provides two ways to create skills:

Method 1: Create manually

Use this method to write skill instructions from scratch.

In the Add skill dialog, click **Create a new skill manually** at the bottom to switch to manual mode

Fill in the **Basic settings** tab:

Skill name (required): Give the skill a recognizable name

Description (required): Briefly describe the skill's purpose

Switch to the **Instructions** tab and write instructions in Markdown. You can also click **Apply template** to use the system's default template as a starting point

(Optional) Switch to the **Additional tools** tab and select the tools the skill needs

Switch to the **Permission settings** tab. Under **Quickly select permission scope**, confirm which roles can use this skill: **All roles**, **Exclude default role** (selected by default), or **Select custom roles**. "Will be assigned to after creation" below lists the roles that will actually receive access

Click **Save** to create the skill

If you click **Save** before opening the **Permission settings** tab, the skill is not created yet. The screen automatically switches to **Permission settings** and displays "Please review permission settings and confirm the assigned roles before submitting." After confirming the roles, click **Save** again to create the skill with the roles shown on the tab.



Saving before reviewing permissions switches to Permission settings and prompts you to confirm the roles

> **This confirmation only appears for new skills created manually. It does not appear when creating a skill with Upload skill package or editing an existing skill. To change which roles can use a skill after creation, see Control skill visibility and permissions by role.**

Method 2: Upload a skill package

Use this method to import an existing `.skill` or `.zip` package.

In the Add skill dialog (which defaults to upload mode), drag a `.skill` or `.zip` file to the upload area, or click the area to select a file

After upload, the system automatically parses `SKILL.md` in the package to extract the skill name, description, and instructions

Once the skill is created, you are automatically redirected to the edit page to adjust its settings

> The skill package must contain a SKILL.md file in the following format: markdown --- name: Skill name description: Skill description --- Instructions for the AI assistant go here...

Edit and configure a skill

In the skill list, click the skill's **Edit** icon to open its settings page.

Basic settings

Edit the skill's name and description.

Instructions

Edit the skill's Markdown instructions. The Agent uses these instructions when it expands the skill.

Click **Apply template** to load the default instruction template.

> Applying a template overwrites the current instructions. Confirm before proceeding.

Files

The **Files** tab manages the skill's resource files and is available for both manually created and uploaded skills. Select a file in the tree on the left to preview its contents on the right. Uploading, adding folders, deleting, and re-uploading on this tab take effect immediately without a separate save.

Upload files: Upload reference documents, templates, or scripts as skill resources (up to 100 MB)
Add folder: Create a folder in the current directory to organize resource files
Download skill package: Package the instructions and resource files into a `.skill` download. See Export a skill
Re-upload skill package: Upload a new `.skill` `.zip` version to replace the skill's name, description, instructions, and all resource files. Available only for skills created by upload
When previewing a file, you can **Download** or delete it individually

> Resource files are used only when the Agent has Code Interpreter enabled. After the Agent expands the skill, the system places the files in the code execution environment for the Agent to read. Agents without Code Interpreter enabled use only the skill's instructions.

Additional tools

Attach the required tools to the skill so the Agent can call them while executing it.

Click Select tools to open the tool selection dialog

Select the tools to attach (multiple selections are supported), then confirm

Selected tools appear in a list with their names, types (API
MCP), and descriptions

To remove a tool, click the delete icon on its card

When finished, click Save changes in the lower-right corner of the page.

Export a skill

On the skill edit page, open the Files tab and click Download skill package to export the skill as a `.skill` file.

> Manually created skills can also be exported. The system automatically packages the instructions and resources into a .skill file. You can share the exported package with other organizations for import.

Bind a skill to an Agent

A skill must be bound to an Agent before it can take effect:

Go to the AI Assistants page, select the target Agent, and open its settings

Find the Skills setting in the model settings area

Select the skills to bind and confirm

Save the Agent settings

Once bound, the Agent automatically decides whether to expand a skill based on the user's question and performs the corresponding task according to the skill's instructions.

Control skill visibility and permissions by role

To show members of specific roles only the skills relevant to their work, use role permission management to assign skills to each role.

For example, a system administrator wants sales staff to read the “Customer summary” skill without being able to edit or delete it. She can edit the sales role, assign the skill, and grant only read permission. Sales staff can then see “Customer summary” in the skill list without receiving edit or delete permissions.

How it works

Unassigned skills are hidden: Organization-created skills must be assigned to a role before its members can see them in the skill list. Unassigned skills are completely hidden from that role

Permission granularity: Each role–skill assignment can have separate **Read**, **Edit**, and **Delete** permissions, supporting read-only access such as "can read but cannot modify"

Creation permission: Each role has an independent "Allow skill creation" switch controlling whether its members can create skills

Owners have unrestricted access: Organization owners automatically have full access to all skills without assignments

Global skill exception: Built-in global skills are visible to all members and cannot be restricted through role assignments

Setup steps

Open role settings

In the left menu, select "**Organization settings**" → "**Organization overview**", then click "**Edit role permissions**". Select the role to configure and switch to the "**Assign skills**" tab.

Set skill creation permission


Select or clear "**Allow skill creation**" as needed to determine whether members of this role can create skills. Changes are saved immediately, and a success message appears when the update succeeds.

Assign skills

Click "**Assign skills**", select the skills to make available to this role, and confirm.

Set skill permissions

In the assigned list, set Read/Edit/Delete permissions for each skill or remove its assignment. Selecting or clearing a permission saves it immediately, and a success message appears when the update succeeds. There is no separate "Save" button on this page.



Manage creation permission and individual skill permissions on the Assign skills tab



Select available skills to assign to the role

> For instructions on creating roles and assigning members, see Role permission management.

Delete a skill

In the skill list, click the skill's Delete icon and confirm to delete it.

> After a skill is deleted, Agents bound to it can no longer use it. This action cannot be undone.

Agent Teams

1. What Is Agent Teams?

In the past, a single Agent had to handle everything: customer service routing, order inquiries, returns and exchanges, product recommendations—all crammed into one set of role instructions, one knowledge base, and one set of tools. As tasks piled up, this "do-everything assistant" began to drop the ball—the role instructions grew too long, knowledge bases interfered with each other, and costs could not be brought down.

Agent Teams lets you replace "one generalist" with "a group of specialists." You can combine multiple existing Agents into a team, let each Agent focus on its own role (for example: a routing Agent, an order Agent, a returns and exchanges Agent, and a recommendation Agent), and then use the visual canvas to define "when a question should be handed to whom."

Users see only a single conversation entry point; behind the scenes, the team automatically routes each question to the most suitable Agent, as if they were interacting with an entire team of professionals.

> What it means for you: Each Agent keeps its own independent knowledge base, tools, and model settings without interfering with the others. Only the Agent that actually handles the question loads the relevant content, which saves tokens and keeps every Agent more focused and accurate. When you add a new business scenario, just add an Agent node and draw a connection—no need to rewrite existing Agents.

2. How Is It Different from "Single Assistant + Skills"?

Aspect	Single Agent (with skills)	Agent Teams
Division of labor	One Agent handles every scenario	Multiple Agents each own their area of expertise
Knowledge and tools	Everything is attached to the same Agent, which easily causes interference	Each Agent independently owns its knowledge base, tools, and model
Model cost	One model has to handle every task	Use lightweight models for simple tasks and powerful models for complex judgments, configured separately

Aspect	Single Agent (with skills)	Agent Teams
Collaboration	Cannot hand off or delegate between Agents	Supports handoff and delegate between Agents
Extensibility	New scenarios require changing the existing Agent's settings	Just add a node and a connection

3. Three Interaction Types: Handoff, Delegate, and Auto

Agents in a team collaborate through connections (directed arrows). Each connection can be set to one interaction type, which determines "how control flows once the question reaches the other side." The three types below can be understood with the help of the diagrams.

Handoff

A handoff gives away control of the entire conversation: when the source Agent decides someone else should handle the matter, it hands the conversation to the target Agent, which takes over and continues talking with the user—like a support agent transferring a call to another department, after which the person who took over serves the caller.

Best for: parallel division of labor where each Agent has its own role. For example, after the routing Agent determines the user's intent, it hands the conversation to the order inquiry Agent or the returns and exchanges Agent to take over.



Handoff: the source Agent gives up control, and the target Agent takes over and continues the conversation with the user

Delegate

A delegate outsources a subtask: the source Agent asks the target Agent to handle something, and once finished, the target Agent returns the result while control stays with the source Agent—like a colleague looking up some information and reporting back to you, after which you still compile the final reply.

Best for: hierarchical collaboration. For example, when a customer service assistant receives an inventory inquiry, it delegates the lookup to a warehouse Agent, and then the customer service assistant compiles the reply to the customer.



Delegate: the source Agent gives a subtask to the target Agent, gets the result back, and compiles the reply itself

Auto (Default)

Auto leaves it to the AI to decide based on the current situation whether to use handoff or delegate. Use Auto when you are not sure which one to choose or want to keep things flexible.



Auto: the AI decides on its own, based on the current situation, whether to hand off or delegate

Communication Volume and Cost Differences Among the Three Types

The most common concern with multi-Agent collaboration is: will token costs spiral out of control? The key is that the three types differ in "how much content is passed between Agents":

Aspect	Handoff	Delegate	Auto
Control	Given to the target Agent, which takes over	Stays with the source Agent	Decided by the AI at the time
Content passed between Agents	The target Agent reads the conversation context accumulated so far when it takes over	The source Agent passes only "a single subtask" to the target Agent, with a concise and clear scope	Depends on the choice made at the time
Token cost characteristics	Grows with conversation length and the number of handoffs; only one Agent runs at a time	On top of the original turn, an additional sub-Agent run (one more LLM call), but the sub-Agent's input is concise and its scope is controllable	Falls on whichever type is chosen; harder to estimate in advance

Aspect	Handoff	Delegate	Auto
Predictability	Medium	High (clear task scope)	Low (varies by situation)

> Cost is both controllable and observable. Teams have multiple built-in safeguards: Maximum iterations (default 25): limits how many times Agents can go back and forth in a single conversation, preventing infinite loops. Total token limit (default 200000): the upper limit of the token budget the entire team can use to process a single message. Timeout (seconds), and the per-message token limit for this node that can be set individually on each node. Context strategy: if you turn off a node's "Visible original user input," that Agent receives only the summary prepared upstream instead of the full conversation, saving even more tokens. Execution logs: every execution records the total tokens and the cost breakdown per Agent, so you can see at a glance which Agent the spending went to (see Team Execution Logs).

> The conversation "remembers" who is currently serving. After a handoff, the Agent that took over continues to serve the following messages until it decides it needs to hand off again; the next message does not go back to the entry point to be routed again.

4. Typical Use Cases

E-commerce customer service team: the routing Agent determines the intent → hands off to the order
returns and exchanges
recommendation Agent, and each Agent handles the request with its own knowledge base and tools.

Internal enterprise consulting: an HR Agent + an IT Agent + a finance Agent automatically route employee questions to the corresponding contact.

Technical support team: the L1 Agent does the initial troubleshooting → delegates to the L2 Agent for in-depth analysis → the result goes back to L1, which consolidates it and replies.

5. How It Works (Concepts)

Agent Teams describes a team as a directed graph:

Nodes (Agents): each node in the graph is an existing Agent, carrying its own role instructions, knowledge base, tools, and model.

Entry node: when the team receives a message, it starts handling the conversation from this node and then hands it off to the appropriate member according to the routing instructions. A newly created team automatically comes with a built-in entry node, so you do not need to specify one separately; a team has only one entry node.

Connections (directed arrows): define "from which assistant, under what conditions, and with which interaction type, the conversation is passed to which assistant."

Safety guardrails: the whole team has upper limits on maximum iterations, total token limit, and timeout seconds, preventing Agents from going back and forth endlessly. When a guardrail stops a reply, the message the user sees can be customized (see **Guardrail Custom Message**).

When you create a team, the system automatically creates an **entry** and a corresponding **Web Chat conversation platform** for it, so you can talk to the whole team directly through the conversation platform. The entry's model, routing instructions, and knowledge base are configured on the team canvas (see **Configure the Entry**).

6. Next Steps

Want to start building a team? See **Create and Orchestrate Teams**—how to create a team, configure the entry, drag in Agent nodes, draw connections to set interaction types, and start a conversation.

Want to see how a team works? See **Team Execution Logs**—which Agents each execution passed through, how many tokens each one used, and how long it took.

> Prerequisite: Agent Teams must be enabled for your organization by MaiAgent. If you do not see the "Teams" menu under "AI Features" in the back office, please contact the MaiAgent team to have it enabled.

Create and Orchestrate Teams

This page explains how to build an Agent Team from scratch: create a team, configure the team's entry, add Agents on the canvas, set the edges and interaction types between them, and start a conversation with the whole team.

> Prepare the Agents you want to add to the team first. Every node in a team is an existing Agent, so create each specialist Agent (for example, triage, orders, and returns & exchanges Agents) under 〈AI Assistants〉 first, then come back here to assemble them into a team.

1. Create a Team

1. Open the team list

From the left menu, go to AI Features → 〈Teams〉. The list shows all teams in the current organization, including team name, status, description, and creation time. Use the search box to find a team.



Team list: see each team's name, enabled status, description, and creation time

2. Create a team

Click New Team in the upper right, then enter a team name (required) and a description to create it.




New team: enter a team name and description

> Once created, the team's entry node appears on the canvas automatically, and the system also creates a matching Web Chat channel so you can chat with the whole team right away. The entry is built in, so you don't need to drag an Agent from the assistant list to serve as the entry.

2. Orchestrate the Team on the Canvas

After opening a team, you land in the Canvas view by default. The screen has three areas: the 〈Assistant List〉 on the left, the canvas in the middle, and the settings panel on the right (it appears when you select a node or an edge).



A newly created team: the canvas holds only the built-in entry node; selecting it opens 〈Entry Settings〉 on the right

> **Use a desktop browser for canvas orchestration. On small screens such as phones, the canvas area shows a notice asking you to finish orchestration on a desktop.**

1. Understand the entry node

The entry node is the team's first stop: every new conversation from a user goes to the entry first, which decides from its 〈Routing Instructions〉 which member should handle it and then hands the conversation over.

On the canvas, the entry node is shown in purple, labeled "Entry" at the top, with the model and "Routing" in the subtitle and "Cannot be deleted" at the lower right. It is created and deleted together with the team, and its name follows the team name; to rename it, change the team name under 〈Basic Info〉.

While a newly created team has no members, a notice appears above the canvas: 〈The entry isn't connected to any member: all conversations will be answered by the entry itself〉. Add members to the canvas, then draw edges from the entry to them (see Add Agent nodes and Draw edges below), and the entry starts routing.

A customer service manager at an online store wants three specialist assistants, "Orders," "Returns & Exchanges," and "Product Recommendations," to serve customers together. After creating the team, she sees the entry node already on the canvas. She drags the three assistants onto the canvas, draws a "Handoff" edge from the entry to each, and then switches the entry to a fast model in the entry settings. Later, when a customer asks in web chat, "Where is my package?",

the entry hands the conversation to the Orders assistant, and the customer never has to choose which assistant to contact.

2. Configure the entry

Select the entry node, and 〈Entry Settings〉 appears on the right. You can adjust:

Setting	Description
Name	Follows the team name and cannot be changed here.
Model	The model the entry uses for routing. Defaults to the organization's default model.
Routing instructions	Tell the entry which situations go to which member. If left empty, the system default instructions are used, which list the members currently connected from the entry.
Knowledge bases	Knowledge bases the entry can reference; multiple selections are allowed. If none are linked, the entry answers based only on the routing instructions.

After making changes, click Save; clicking Cancel restores the last saved content.

> Adding or removing members after writing your own routing instructions: Entry settings shows the message 〈Members have changed. Consider updating the routing instructions〉. Remember to add the new members to the instructions, or clear the instructions to use the system default. Without edit permission: the fields are read-only, and the bottom of the panel shows "You don't have edit permission and can only view." Only the organization owner and the team creator can edit a team.

3. Add Agent nodes

In the 〈Assistant List〉 on the left, find the Agent you want to add and drag it onto the canvas, or click it to add it. Agents already in the team are marked 〈Already in team〉; click one to jump to its node on the canvas. With many Agents, use the search box at the top to filter.

Each node shows the Agent name, the model it uses, and whether it is in Agent or RAG mode, to help you tell them apart.

> If the nodes look messy, click Auto Layout on the canvas to have the system tidy up the layout. Node positions are saved automatically.

4. Configure a node

Select a node, and 〈Node Settings〉 appears on the right. You can adjust:

Setting	Description
Entry node	Appears only for teams with a legacy entry. When enabled, the team starts handling a conversation from this node when it receives a message. A team can have only one entry node. Teams that use the built-in entry don't need this setting.
Token limit per message for this node	The Token limit (input + output, optional) this node can use within a single team turn; if left empty or 0, only the team-level limit applies. When the limit is reached, the guardrail stops the entire turn.
Max iterations	The maximum number of steps this node can run within a single team turn (optional); if left empty or 0, only the team-level limit applies. A node that is only called through a delegate edge is instead bound by the sub-Agent's loop limit.
Can see original user input	Determines whether this Agent can read the user's original messages when it is handed off or delegated to (on by default; see the explanation below).
Wait for user reply before continuing	Lists all outgoing edges of this node (target Agent + interaction type). Checking one is written back to each edge when you click 〈Save〉, which is the same as turning it on edge by edge in the edge settings. Delegate edges are listed but cannot be checked. When there are no outgoing edges, "This node has no outgoing edges" is shown.

When 〈Can see original user input〉 is off: if this node is handed off or delegated to by another member, it cannot see the user's original messages (they are masked in the current turn and all earlier turns), cannot search the conversation history or read the user's attachments on its own, and answers based only on the other members' output. If this node is the starting point of the current turn (the entry node, or the node where the previous turn's handoff ended), it still sees the full conversation; content that other members relay in replies or tool calls is not masked.

節點設定

Chatbot

docs-line 示範（虛構）客服分流助理

連線

→ docs-line 示範（虛構）退換貨助理 移交

入口節點

團隊收到訊息時，從此節點開始處理對話

等使用者回覆再繼續

→ docs-line 示範（虛構）退換貨… 移交

勾選的連線，走之前會先停下等使用者回覆

此節點單則訊息的 Token 上限

此節點在單次團隊回合內可用的 Token 上限（輸入＋輸出）；留空或 0 則只受團隊層級上限約束。達到上限時整個回合會被護欄停止。

最大迭代次數

此節點在單次團隊回合內可執行的步數上限；留空或 0 則只受團隊層級上限約束。達到上限時整個回合會被護欄停止；只經由「委派」連線被呼叫的節點，則改由其子代理迴圈上限約束。

可見原始使用者輸入

關閉後，此節點被其他成員交接或委派進來時，看不到使用者的原始訊息（本輪與先前各輪都會遮蔽），也不能搜尋對話紀錄或自行讀取使用者附件，只依其他成員的輸出作答。若此節點是本輪對話的起點（入口節點，或上一輪交接後停留的節點），仍會看到完整對話。其他成員在回覆或工具呼叫中轉述的內容不會被遮蔽。

儲存 刪除

Node settings: the outgoing-edge list lets you check "Wait for user reply before continuing"; below are the Token iteration limits and 〈Can see original user input〉 (this screen is a legacy-entry team, so there is an extra 〈Entry node〉 switch)

5. Draw edges and set the interaction type

Drag from one node's connection point to another node to create a directed edge (source → target). An edge drawn from the entry to a member defines who the entry can route to. Members can also draw an edge back to the entry, but an edge to the entry can only be 〈Handoff〉 and cannot inherit the source Agent's tools. Select an edge, and 〈Edge Settings〉 appears on the right:

Setting	Description
Trigger condition description	Describe in plain language "when this edge should be taken." This description is given to the AI as the basis for its decision, so writing it clearly makes routing more accurate.
Interaction type	Choose 〈Auto〉, 〈Handoff〉, or 〈Delegate〉 (see the table below for the differences).
Wait for user reply before continuing	When on, the upstream Agent stops after replying and passes the conversation to the next Agent only after the user replies; off by default. Once on, you can also turn on 〈Have the assistant attach options〉, so that when it stops it lists options with the Agent UI question tool for the user to click and answer (the source Agent must have the Agent UI question tool enabled). Only 〈Auto〉 and 〈Handoff〉 edges can turn this on; 〈Delegate〉 edges are disabled and show "Delegate edges don't support this. Use Handoff instead"; an edge that was already on is turned off automatically when changed to Delegate.
Inherit source Agent's tools	When on, the target Agent can use all of the source Agent's tools and resources.

Interaction types (as described in the settings panel):


Interaction type	Description
Auto (default)	The LLM automatically decides the most suitable interaction type.
Handoff	Hand over control: the source agent goes idle and the target agent takes over the conversation.
Delegate	Delegate a task: the target agent runs it and returns the result to the source. When a sub-Agent finishes with question options, Quick Replies, rich cards, or files, this content is shown directly to the user; see Interactive endings of delegated sub-Agents below for differences across channels.

On the canvas, an edge with "Wait for user reply before continuing" turned on turns amber and gets a "⏸ Waiting for reply" badge. When the team reaches this edge, it stops, and the run record shows the status "Waiting for reply"; expanding the steps shows "Waiting for user reply" and "After the reply, hand over to: ○○" (see **Team run records**). The conversation is passed to the target Agent only after the user replies.



Edge settings: trigger condition description, interaction type, wait for user reply before continuing (once on, you can also turn on attach options), and whether to inherit the source Agent's tools

For example, when an online store's triage Agent receives "The right earbud of the Bluetooth earphones I bought last week has no sound," it should first ask how the customer wants to proceed before handing over to the returns & exchanges Agent. With 〈Wait for user reply before continuing〉 and 〈Have the assistant attach options〉 turned on for this edge, when the triage Agent decides to hand over to the returns & exchanges Agent, it stops first and offers options for the customer to click on how to handle it (for example, "Return and refund" or "Exchange for a new one"). After the customer replies, that reply goes straight to the returns & exchanges Agent, so the conversation isn't passed along before the information is complete.



Web Chat: when the customer service triage assistant reaches an edge with "Wait for user reply before continuing," it stops and uses question options to ask the user how to proceed

How "Wait for user reply before continuing" works

It stops only when the edge is actually chosen: if the source Agent answers the question itself and doesn't hand over to the target Agent, the turn ends as usual and doesn't stop. It stops every time this edge is taken, not just the first time.

Stopping is a normal ending: the turn ends after the source Agent replies, and the run record shows 〈Waiting for reply〉; it doesn't count as a failure. The user's next message, whatever its content, is

picked up by the target Agent. If the turn times out, errors, triggers a safety guardrail, or the user clicks stop, it does not enter the waiting state.

Editing or regenerating a message: when the user rewrites or regenerates a message that was already sent, the run restarts from the source Agent and does not go straight to the target Agent.

Options appear only in Web Chat and the API: the question options from 〈Have the assistant attach options〉 appear in Web Chat and API replies; on other channels such as LINE, users see only the source Agent's text explanation and can simply reply by typing.

Options are generated by the Agent: the question and options are written by the source Agent based on the conversation at the time, not a fixed list, and different models follow the instruction to different degrees. Test with real conversations before going live to confirm that options appear when it stops.

Node settings are a shortcut: checking all of a node's outgoing edges in 〈Node Settings〉 is equivalent to having this Agent stop and wait for a user reply every time it hands off.

> This setting does not take effect when the source node's Agent uses 〈Canvas Mode〉. The switch can still be turned on and the canvas still shows "⏸ Waiting for reply," but the team doesn't stop when it runs and hands off as if the setting were off (for Agent modes, see Sub-options of Agent mode). If you need the team to stop at this edge and wait for the user's reply, set the source node's Agent to 〈Normal Mode〉.


Interactive endings of delegated sub-Agents

When you hand work to a sub-Agent with 〈Delegate〉, the sub-Agent's ordinary text, reasoning, and tool-call process are not shown to the user. But if the sub-Agent finishes with one of the following interactive components, the component is delivered directly to the user without waiting for the source Agent to relay it:

Sub-Agent's ending	Web Chat, back-office chat, API	LINE	Other channels (Telegram, Slack, etc.)
Question options (Agent UI question tool)	Options shown directly	Options not shown; the source Agent relays them in text	Options not shown; the source Agent relays them in text
Quick Reply	Buttons shown directly	LINE quick-reply buttons shown; the source Agent may explain again in text	The source Agent relays it in text
Rich card	Card shown directly	Card shown; the source Agent may explain again in text	Card not sent; the source Agent relays the card content in text
File panel	File card shown directly,	The source Agent relays it in text	The source Agent relays it in text

Sub-Agent's ending	Web Chat, back-office chat, API	LINE	Other channels (Telegram, Slack, etc.)
	downloadable		

> When a sub-Agent finishes with question options, a Quick Reply, or a rich card, the component has already reached the user in Web Chat, back-office chat, and the API, so the source Agent doesn't repeat the content. As a result, any explanatory text the sub-Agent wrote before these components (for example, "I found three plans, please choose one") does not appear, and the user sees only the component itself; this is especially noticeable with Quick Reply. If you need an explanation, put it in the question text or the card content. The file panel is not covered by this ending rule, and the source Agent may still follow up with a text explanation.




Edge example: the "Customer Service Triage Assistant" routes via "Handoff" to the order lookup
returns & exchanges
product recommendation assistants, and the order lookup assistant then "Delegates" to the warehouse lookup assistant. Each node shows the Agent name, model, and Agent
RAG mode (this example is a legacy-entry team, where the member "Customer Service Triage Assistant" serves as the entry)

> Watch the semantic warnings above the canvas. When the team graph has problems, a yellow notice appears above the canvas, for example: 〈The entry isn't connected to any member: all conversations will be answered by the entry itself〉, 〈There are duplicate edges〉, or 〈The edges form a cycle〉; teams with a legacy entry may also show 〈No entry node is set〉 or 〈There are multiple entry nodes; keep only one〉. We recommend clearing these warnings before starting conversations.

6. Upgrade a legacy entry

Teams created earlier have no built-in entry; instead, a member node serves as the entry (the one with 〈Entry node〉 turned on in its node settings). Such teams work as usual and don't need any change; if you'd like to switch to the built-in entry for unified routing, you can upgrade on your own.

When you open the canvas of such a team at desktop width, an orange "Legacy entry" tag appears next to the team name, and a banner appears above the canvas: "This team uses a legacy entry (a member node serves as the entry). After the upgrade, the canvas gets an additional routing entry node, and this cannot be undone."



Legacy-entry team: the "Legacy entry" tag next to the name and the upgrade banner above the canvas

Upgrade steps:

Click Upgrade entry on the right of the banner.

The confirmation dialog "Upgrade to the built-in entry?" explains: the upgrade cannot be undone. Each new conversation goes through the entry first and is then handed off to the original entry member; the members' settings and edges are not changed.

After you confirm, the screen shows "Upgraded to the built-in entry," and an entry node appears to the left of the original entry member on the canvas, connected to it by a 〈Handoff〉 edge.

After the upgrade, the entry by default hands every new conversation to the original entry member, so the conversation flow users experience stays the same as before. Later, if you want the entry to route directly to other members, draw edges from the entry to those members and update the routing instructions in **Entry settings**.

> The upgrade cannot be undone. We recommend verifying the flow in a test team before upgrading a team that is in production use. Only the organization owner and the team creator can upgrade; for everyone else, the 〈Upgrade entry〉 button is disabled.

3. Configure Basic Info and Safety Guardrails

After opening a team, the left menu has four views: 〈Canvas〉, 〈Basic Info〉, 〈Run Records〉, and 〈API Integration〉, with this team's channels listed below. Switch to 〈Basic Info〉 to adjust team-level settings:

Basic info: team name, description, and whether it is enabled.

Safety guardrails:

Max iterations (default `25`) — the maximum number of back-and-forth exchanges between Agents in one conversation, to prevent infinite loops.

Token limit per message (default `200000`) — the Token budget limit for the whole team to process a single user message.

Token limit for the entire conversation (default `0`) — the Token budget accumulated from the start of the whole conversation; the screen says "0 means this guardrail is disabled," so keep it at 0 if you only want to limit single messages.

Timeout in seconds (default `600`) — the hard timeout for the entire team processing flow.

Custom guardrail message (empty by default) — the text shown to the user when one of the first three guardrails stops a reply; if left empty, the system default message is used. See **Custom guardrail message** below.



Basic info and safety guardrails: adjust the team name, enabled status, max iterations, the two Token limits, and the timeout in seconds

Custom guardrail message

If, partway through processing, the team hits the max iterations, the Token limit per message, or the Token limit for the entire conversation, the system stops that turn's reply and appends a stop message at the end to tell the user. The "custom guardrail message" lets you decide what this text says; if left empty, the system shows a default message based on the stop reason and the user's language.

An online shopping platform uses the API to connect an Agent Team to the shopping assistant on its own website. The engineers want a fixed-format line of text to appear at the end of the reply when a guardrail triggers, so the program can recognize it and show a "Contact support" button instead. The team administrator enters "[LIMIT] This conversation has reached its usage limit. Please start a new conversation or contact support." in the "Custom guardrail message" under 〈Basic Info〉 and saves. Later, a visitor asks the team to compare a dozen products at once; the team hits the usage limit and stops, and after the part of the reply already written and a divider line, this fixed text is appended. The website's code matches `[LIMIT]` at the end of the reply and replaces the input box with a Contact support button.

1. Enter the custom message

In the team's 〈Basic Info〉, find the 〈Safety Guardrails〉 card; below the four numeric fields is the Custom guardrail message. The lower right of the input box shows the current character count (for example, `34 500`), and the help text below reads "Shown to the user when a safety guardrail triggers. Leave empty to use the system default message."



The "Custom guardrail message" below the "Safety Guardrails" card: when empty, it shows placeholder text and 0 500

Rules for filling it in:

Up to 500 characters: when exceeded, the count turns red and the message "The message cannot exceed 500 characters" appears below the field; clicking Save is blocked. Other changes made on the same page at the same time (for example, a changed max iterations) are also not saved, so shorten the message to within 500 characters before saving.

Shown as-is: it is not translated and no variables are substituted; what you enter is what is shown. Line breaks are kept, and leading and trailing whitespace is trimmed automatically. Whitespace only is treated as empty.

2. Save

Click Save. It takes effect immediately, and the next reply that triggers a guardrail uses the new text. To go back to the system default message, clear the field and save.

What users see

When any of the three guardrails triggers, Web Chat and API replies show the same text:

If the Agent had already replied in part before stopping, that partial reply is kept first, followed by a divider line, and then the stop message.

No system prefix is added before the stop message.

Guardrail triggered	Custom message filled in	Default message when left empty (Traditional Chinese)	Default message when left empty (English)
Max iterations	Shows the custom message	這次回覆的處理步驟已達上限，請換個方式再問一次。	This reply has reached its processing step limit. Please try asking in a different way.
Token limit per message	Shows the custom message	這則訊息的用量已達上限，請縮短內容或換個方式再問一次。	This message has reached its usage limit. Please shorten it or try asking differently.
Token limit for the entire conversation	Shows the custom message	本次對話的用量已達上限，請開啟新對話繼續。	This conversation has reached its usage limit. Please start a new conversation to continue.

The default message is shown in the user's language, and supports Traditional Chinese, Simplified Chinese, English, Japanese, and Korean: Web Chat uses the interface language at the time the conversation was created; the API uses the language information in the request, and if there is none, it detects the language from the message content; if the language can't be determined, English is shown. The custom message is the same in every language.

The custom guardrail message is not shown in the following cases: When the timeout (seconds) triggers: the **timeout message** of the team's entry Agent is shown (or the system default if none is set). When the node-level "Token limit per message for this node" or "Max iterations" triggers (see **Node settings**): a system message stating the node name and the limit value is shown, and this field has no effect on it.

If you integrate through the API and want your program to recognize the stop message: Check whether the end of the reply is your custom message; don't compare against the whole reply—the Agent may have already replied in part before stopping, with a divider line in between. Don't compare against the system default message, because the default message changes with the user's language. The custom message does not appear when a node-level limit triggers; if you rely on fixed text for recognition, leave the node's Token and iteration limits empty. Web Chat renders this text as Markdown, so for example important is displayed in bold.

4. Talk to the team

Once the setup is complete and the team is confirmed as "Active", you can talk to the whole team through the team's Web Chat platform. Users deal with a single entry point, and the system automatically routes each question to the appropriate Agent.

When the team hands off or delegates between Agents, the chat interface shows a switching notice, such as "Handing off to", "Delegating to", or "Switching to", so users know which Agent is currently serving them.

5. Delete a team

You can "Delete team" in the danger zone at the bottom of the "Basic Info" view. Deleting also removes the team's entry, and this action cannot be undone, so confirm before proceeding. The Agents corresponding to the member nodes are not deleted and remain in "AI Assistants".

6. API integration

To call the whole team from your own system, switch to "API Integration" on the left. This page reuses the Agent API documentation (request examples, fields, and response format). The only difference is that the target is the entry Agent automatically created when the team was created: sending a message to it is the same as sending a message to the whole team, and routing and

handoff are handled by the team itself. The IDs in the examples are already filled in with the entry Agent, so you can copy them directly; for full field descriptions, see **Developer tools**.

> If the page shows "This team has no entry Chatbot yet, so no API example is available", the team has no entry Agent. The entry Agent is created automatically by the system when the team is created and normally is never missing; if you see this message, please contact your MaiAgent representative to have it recreated.

7. FAQ

After creating a team, why is there no assistant with the team's name in the AI assistant list?

Behind the team's entry is an Agent with the same name as the team, dedicated to that team, so it doesn't appear in the "AI Assistants" list, nor in the canvas "Assistant list" where you could drag it into other teams. The entry's model, routing instructions, and knowledge bases are adjusted in the team canvas under **Entry settings**.

If you open this entry Agent's settings page from a link on another page, the screen shows only the note "This is the entry of team "Team name"". Click **Go to team canvas** to return to the team settings; its mode is fixed to Team and cannot be changed to a regular assistant.



When you open the entry Agent's settings page, you are guided back to the team canvas

Can the entry node be deleted?

No. The entry node is marked "Cannot be deleted" and exists together with the team; it is removed only when you delete the team.

Do teams with a legacy entry have to upgrade?

No. Teams with a legacy entry keep working as usual; when you want to switch to the built-in entry, follow Upgrade the legacy entry. The upgrade cannot be reverted, so confirm before proceeding.

8. Next steps

Once the team is running, you can use Team execution records to see which Agents each run went through, how many tokens each used, and how long it took, and confirm that the team divides work as expected.

Team Execution Records

Teams automatically hand off and delegate work between Agents without users noticing. Execution Traces let you look back at which Agents each conversation actually passed through and how many resources each used, so you can verify that the team divides work as expected, troubleshoot issues, and optimize performance.

1. View execution traces

Switch to the Execution Traces view on the team page to list every execution for this team. A trace is created each time a user sends a message to the team. Each trace includes:

Field	Description
Trace ID	The unique identifier for this execution.
Conversation	The conversation this execution belongs to, shown by its title. Click the title to open All Conversations and view the full conversation.
Status	Running, Completed, Failed, Timed Out, or Awaiting Reply. Awaiting Reply means the team paused at a connection with “Wait for the user's reply before continuing” enabled; see Traces awaiting a reply below.
Iterations	The total number of interactions between Agents during this execution.
Tokens	Total Token usage for this execution (input in output out).
Duration	Total time from receiving the message to completing the reply.
Created At	The time of this execution. Click the column header to switch between oldest-first and newest-first sorting; the default is newest first.



Execution traces: each trace shows its conversation title, making it easy to identify traces from the same conversation

> **Can't click a conversation title? You need access to Conversation History for titles to appear as links. Without permission, titles appear as plain text (hover over a title to see why).**

2. Filter execution traces by conversation

A conversation usually contains several messages, each generating its own execution trace. To focus on one conversation, list only the traces that belong to it.

1. Filter by this conversation

In the Actions column on the right of the trace you want to inspect, click the funnel icon **Filter by This Conversation**.



Click the Filter by This Conversation funnel icon on the right of a trace

2. View filtered results

A banner above the list reads Showing only traces for conversation “…”, and the list contains only traces for that conversation. The filter remains active when you paginate or sort. The funnel icons for these traces turn gray and show “Already viewing traces for this conversation” on hover.

To return to the full list, click **Clear** or close (×) on the right of the banner.



After filtering: the banner identifies the current conversation, and only its traces remain in the list

Example: identify which Agent replied in a customer complaint conversation

A support manager receives feedback that "the return instructions are unclear" and wants to identify which Agent in the team handled each reply in that conversation:

Find any trace for the conversation in Execution Traces and click **Filter by This Conversation** to show only its traces.

Expand each trace and check the Agent names on the step cards: the first message was handled by Demo – Support Routing Assistant and then handed off to Demo – Returns and Exchanges Assistant; subsequent follow-up questions were answered directly by Demo – Returns and Exchanges Assistant.

Click the title in the Conversation column to open the original conversation and compare the actual replies. Once you identify Demo – Returns and Exchanges Assistant as the source of the issue, return to AI Assistants to adjust its settings.

3. Expand step details

Click the + on the left of a trace (or click the row itself) to expand it and see which Agent nodes this execution passed through, in order. Each step has a card:

Item	Description
Step number and name	Shown as "#Number • Name," such as "#1 • Demo – Support Routing Assistant," so you can immediately identify which Agent in the team handled the step.
Interaction type	After the name, shows how this Agent was actually invoked in this turn: Handoff or Delegation. Not shown for the first Agent handling the turn. For connections set to Automatic, this shows the handoff or delegation that actually occurred.
Input	What this Agent received; see Input and output content below.

Item	Description
Output	This Agent's final reply in this turn; see Input and output content below.
Token usage	The right side of the card shows input/output Tokens for this step (`in` `out`). Some steps also show duration, helping you see which Agent accounts for the cost.



Step details: Handoff or Delegation appears after the name, with the step's input and output below

Input and output content

Input and output depend on how the Agent entered this turn:

Step	Input	Output
The first Agent handling this turn (usually the entry Agent; if a handoff occurred in the previous turn, the Agent currently serving the user)	The message the user sent this time	Its final reply in this turn
Interaction type is Handoff	The handoff reason: the previous Agent's explanation of why it handed over to this Agent	Its final reply in this turn
Interaction type is Delegation	The delegated task	The result it returns to the delegating Agent after completing the task

Input and output are each limited to 500 characters; additional content is truncated with "…".

Empty fields are hidden. For example, if the entry Agent only hands off the conversation without replying, its step card shows Input only.

This content has been recorded only since the feature launched; older traces are not backfilled.

> When output controls are configured, step cards retain only the user message. If the team's entry Agent (with the same name as the team) has a **Hook** at the After AI Response Generation interception point, or AWS Guardrails is enabled, these controls apply only to the team's final response to the user and do not pass through step cards. To avoid storing unprocessed model output in execution traces, step cards for these teams show only the interaction type and the user message received by the first Agent. Handoff reasons, delegated tasks, and all Output fields remain blank.

> Who can see step content? Input and output contain user messages and Agent replies, so a role must have **Team Permissions** to read either the trace list or an individual trace. Organization owners are exempt from this requirement.

Example: find where an exchange request gets stuck

An e-commerce support manager notices that customers asking about exchanges are often asked for a customer ID and wants to know which Agent requests it:

In Execution Traces, expand the trace for a customer's exchange inquiry. Three step cards appear: “#1 • docs-line Demo (Fictional) Step Details Team,” “#2 • docs-line Demo (Fictional) Returns and Exchanges Assistant • Handoff,” and “#3 • docs-line Demo (Fictional) Order Lookup Assistant • Delegation.”

The Input for #2 is the handoff reason written by the entry Agent, confirming that the conversation was handed to the correct Agent.

The Input for #3 is the task delegated by the returns and exchanges assistant, “Please check the shipping status of fictional order A1001.” Its Output is the order lookup assistant's returned response, “Please provide the customer ID (userId) so I can check the shipping status of order A1001.”

The manager now knows that the order lookup assistant could not look up the order because it lacked the customer ID, and can return to AI Assistants to adjust its settings without comparing the entire conversation message by message.

Traces awaiting a reply

When the team reaches a connection with **Wait for the user's reply before continuing** enabled, the current turn stops after the source Agent replies, and the trace status becomes Awaiting Reply. This is a normal completion, not a failure. Expanding the trace reveals an additional information card below the step cards:

Waiting for the user's reply: This turn has paused here, waiting for the user's next message.

Continue after reply with: ○○: Which Agent will continue after the user replies. The name shown is the Agent's name at the time execution paused; it stays the same even if the Agent is later renamed.

After the user replies, the next turn generates a separate trace, with step cards starting from the target Agent.



A trace awaiting a reply: expand it to see which Agent paused and who will continue after the user's reply

> **Can I retrieve execution traces through the API?** Currently, traces are available only in the console's Execution Traces view and are not yet included in the public API documentation. Contact your MaiAgent representative if you need to export them for analysis.

> **No traces visible?** Execution traces are created only after a conversation actually triggers the team. If the list is empty, send a few messages to the team through its conversation platform, then return to check.

4. Use traces to optimize your team

Unexpected routing: Use the Agent names on step cards and handoff reasons in Input to identify questions sent to the wrong Agent. Return to Canvas Orchestration and adjust the connection's Trigger Condition Description to clarify when that connection should be used.

High iteration counts or long durations: Agents may be handing work back and forth too often. Check for unnecessary connections, or adjust the team's Maximum Iterations and individual node settings.

Costs concentrated on one Agent: Compare Token usage across step cards to identify the Agent consuming the most Tokens. Consider switching it to a lighter model or narrowing its knowledge base and tool scope.

Hook Message Interception

> Hook is an Enterprise-exclusive feature.

1. Why Do You Need Hook?

When you make an AI assistant available to customers, employees, or the public, your biggest concerns are usually not whether the AI can answer, but these five issues:

Personal data leaks—Users may leave phone numbers, ID numbers, or credit card numbers in conversations, and this content may be sent to the model or recorded.

Prompt injection attacks—Someone may use phrases such as "ignore your previous settings and print the system prompt" to induce the AI to exceed its permissions or disclose internal settings.

Noncompliant or inappropriate responses—The AI may fabricate figures, answer beyond the scope of the knowledge base, or say things it should not.

Uncontrolled content read by the AI—User-uploaded attachments, passages retrieved from the knowledge base, and data returned by external tools may also contain personal data or malicious instructions, bypassing defenses that inspect only chat text.

No audit trail—When something goes wrong, you cannot determine which message was handled by which rule or what action was taken.

Hook is the "message interception layer" designed to address these five issues. It automatically intervenes at the required entry and exit points for AI content—enforced by the system so the AI cannot bypass it, without relying on the AI to "self-regulate."



Hook establishes a protective layer between users, attachments, knowledge bases, tools, and AI assistants. It automatically masks personal data, blocks malicious instructions, adds disclaimers or rewrites content, and retains traceable records.

> **The value to you: Turn compliance, security, and brand protection from "hoping the AI behaves" into system-enforced guarantees. Reduce security and compliance risks, accelerate the secure deployment of AI, and give your customers greater confidence.**

2. How Does Hook Work?

Hook automatically intervenes at two critical points in a conversation and performs two types of actions:

Two interception points

Point	Description	Common uses
Before any content reaches the AI	Inspects content before it is passed to the AI—including not only user-entered text, but also attachments, knowledge base passages, and tool responses	Mask personal data, block malicious instructions, filter invalid messages, and intercept inappropriate content
Before an AI response is	Inspects the response generated by the AI before it is shown to the user	Mask personal data in responses and verify response reliability

Point	Description	Common uses
sent		

Two types of actions

Action	Effect	What the user sees
Modify	Masks sensitive content or rewrites a response into a more appropriate version	A processed version of the content (such as `0912-*-*`)
Block	Blocks the message so it neither enters the AI nor gets sent	A custom message you define



Hook automatically intervenes before any content reaches the AI and before AI responses are sent, masking, rewriting, or blocking content. It is enforced at the system level and does not rely on AI self-regulation.

What Happens When a Hook Fails to Run?

Hook checks are enforced at the system level. When a check fails, the platform errs on the side of blocking and never lets unchecked content through:

Situation	Platform action	What the user sees
A Hook that runs before content reaches the AI fails partway (sandbox interruption, timeout, or Hook program error)	The message is blocked and is not sent to the AI	A system message: “We are unable to process your message securely right now. Please try again later.”
A Hook that runs before an AI response is sent fails during streaming	The response stops being sent from the point of failure, and the portion already sent is kept	The response is cut off and followed by the same system message
The Hook execution service cannot start at all (for example, the sandbox service is not ready)	All Hooks for that AI assistant are paused; messages still reach the AI and responses are still sent	Same as when no Hook is attached
Writing the execution log fails	The result is unaffected; blocking or modification still takes effect, but one log entry is missing	No difference

The platform does not automatically retry a failed Hook; the user simply needs to resend the message. To investigate the cause, check the message's entry in **Hook Execution Logs** and the Hook execution details on the conversation page. When the Hook execution service cannot start, the platform records the error; if it keeps happening, contact your MaiAgent representative.

Four Sources Before Content Reaches the AI

Checks performed “before content reaches the AI” do not apply only to text entered by users. Once an AI assistant has a Hook attached at “When receiving a user message,” all four content sources below pass through the same set of Hooks before being sent to the model, **with no additional configuration required**:

Source	When it occurs	What happens when blocked
User message	A user sends text in a conversation	The user sees your custom block message, and the AI does not receive the message
Attachment	A user uploads a file whose contents will be provided to the AI for reference	That section is not sent to the model; the conversation continues, and the assistant responds based on the remaining content
Knowledge base passage	The AI retrieves a passage from the knowledge base to reference	That passage is not sent to the model; the conversation continues, and the assistant responds based on the remaining content

Source	When it occurs	What happens when blocked
Tool response	In Agent mode, the AI calls a tool (such as a database, MCP connector, browser, code execution tool, or skill) and retrieves a result	The tool result is not provided to the model, and the conversation continues

> Only the affected section is blocked; the conversation does not stop. For example, when a knowledge base passage containing personal data is processed by "Personal Data Masking," the AI receives the masked version. When it is blocked by "Sensitive Keyword Blocking," only that passage is withheld from the model, and the assistant still responds based on the conversation history and remaining content. Every check is recorded in **Hook Execution Logs**, allowing you to trace which tool or document the content came from.

> Multiple Hooks can be chained together. An AI assistant can have multiple Hooks attached simultaneously to perform filtering → masking → blocking → verification in sequence, creating a tailored protection workflow.

3. Seven Standard Templates (Ready to Use)

You do not need to write your own rules. MaiAgent provides seven standard templates. Simply select a template, adjust its parameters, and attach it to an AI assistant to get started:



Standard templates protect the entire flow from input to response. Invalid message filtering, personal data masking, prompt injection protection, and content safety classification verify content before it reaches the AI, while response reliability checks verify responses before they are sent.

Template	Interception point	Action	What it solves
Personal Data Masking	Before content reaches the AI	Modify	Automatically masks phone numbers, email addresses, ID numbers, and credit card numbers as `[REDACTED_*]`, preventing personal data from entering the model or being recorded
Semantic Personal Data Masking	Before content reaches the AI	Modify	Uses a dedicated personal data detection model to identify personal data without a fixed format, such as names and addresses, and masks it as `[NAME]` or `[ADDRESS]`, covering gaps that pattern matching cannot detect
Prompt Injection Protection	Before content reaches the AI	Block	Uses AI to identify and block attacks such as instructions to ignore commands, extract the system prompt, or role-play as an unrestricted persona
Content Safety Classification Blocking	Before content reaches the AI	Block	Uses a dedicated content safety model to classify violence, hate, sexual content, self-harm, harassment, illegal activity, and other categories; blocks matches based on a configurable score threshold

Template	Interception point	Action	What it solves
Sensitive Keyword Blocking	Before content reaches the AI	Block	Blocks messages containing specified prohibited terms, such as profanity, threats, or company-restricted language
Invalid Message Filtering	Before content reaches the AI	Block	First blocks pure greetings and spam at no cost using rules, then uses AI to identify pure small talk and messages with no consultation intent, reducing Token costs
Response Reliability Check	AI response	Modify	When an AI response is uncertain or lacks evidence, rewrites it to acknowledge the uncertainty honestly and recommend contacting a specialist, reducing hallucination risk

> The two personal data masking templates can be used together. “Personal Data Masking” uses pattern matching, has almost no cost and extremely low latency, and is suitable for running first. “Semantic Personal Data Masking” uses a dedicated detection model and can identify names and addresses in free-form text, but every call adds latency and cost. We recommend attaching both: use the former to mask structured personal data first, then the latter to cover semantic personal data.

How different industries can use Hook (examples)


Industry	Typical combination
Finance banking securities	Personal Data Masking + Semantic Personal Data Masking + Prompt Injection Protection + Response Reliability Check (protect personal data, prevent manipulation, and avoid fabricated figures)
Healthcare	Personal Data Masking + Semantic Personal Data Masking + Response Reliability Check (mask patient names and addresses and avoid providing unverified medical information)
E-commerce retail	Invalid Message Filtering + Sensitive Keyword Blocking + Content Safety Classification Blocking (filter spam to reduce costs, maintain conversation quality, and block harassment and hate content)
Educational institutions	Prompt Injection Protection + Content Safety Classification Blocking (prevent privilege escalation and self-harm or bullying content when services are open to students)
Government public sector	Personal Data Masking + Prompt Injection Protection (protect citizens’ data and secure public-facing services)

4. See the Results in Action


The following examples show how the standard templates work in actual conversations. After completing the setup, send the corresponding content in a conversation to see the message masked or blocked:




Personal Data Masking: A user sends a message containing a phone number, and the number is automatically masked before the message reaches the AI.



Prompt Injection Protection: A user attempts to induce the AI to ignore its settings and print the system prompt. The message is blocked, and a notification is returned.



Sensitive Keyword Blocking: A user message contains a specified prohibited term, so it is blocked and a custom notification is returned.



Invalid Message Filtering: Pure greetings and messages with no consultation intent are blocked, preventing Tokens from being wasted on the AI.



Response Reliability Check: Instead of letting the AI guess at an uncertain question, Hook rewrites the response to acknowledge the uncertainty honestly and recommend contacting a specialist.

5. Next Steps

Ready to set it up? See **Add and Configure a Hook** to learn how to create a Hook from a template, adjust its parameters, and associate it with an AI assistant.

Want to review interception records? See **Hook Execution Logs** to learn how to review each interception or modification, control whether original messages are logged, and view execution details from a conversation.

> Prerequisite: The Hook feature must be enabled for your organization by MaiAgent. If the “Hook” menu does not appear in the admin console, contact the MaiAgent team to enable it.


Add and Configure Hooks

This page explains how to create a Hook from a standard template, configure its parameters, and attach it to an Agent so it can start working.

1. Add a Hook

1. Open the Hook List

From the left menu, go to AI Features → Hook. The list displays all Hooks in the current organization, including their name, description, type, interception point, action, associated AI assistants, enabled status, creator, and update time.



The Hook list shows each Hook's type, interception point (when it intervenes), action (modify/block), the Agents it is attached to, and enabled status.

2. Select a Template

Click Add Hook in the upper-right corner, then select a standard template in the pop-up window. Each template card shows its interception point and action, making it easy to quickly identify its purpose.



Select a template: Each of the seven standard templates indicates its interception point (when receiving a user message/after an AI response is generated) and action (modify/block).


> The creation process has three tabs: Template (which type to use) → Basic Information (name and description) → Apply to AI Assistants (which Agents to attach it to). After selecting a template, complete each tab in order.

2. Configure Parameters

Each template has different parameters. You can configure them on the Hook settings page after creation. Common parameters include:

Template	Main parameters	Description
Personal Data Masking	PII types to mask	Select the types to detect (Email/mobile phone number/ID number/credit card)
Semantic Personal Data Masking	Personal data detection model and detection types, minimum confidence, masking style	Select a detection service, then choose the personal data types to mask (name, address, phone number, and more); increasing the confidence value can reduce false positives

Template	Main parameters	Description
Sensitive Keyword Blocking	Prohibited terms, minimum term length	Enter one prohibited term per line; the minimum term length filters out terms that are too short and helps prevent false positives
Prompt Injection Protection	Evaluation model, additional evaluation rules	Select an LLM to determine whether content is an attack; you can also add custom rules
Content Safety Classification Blocking	Content safety model and blocked categories, additional score threshold, behavior when the detection service is unavailable	Select a detection service, then choose the categories to block; if none are selected, any category violation will be blocked
Invalid Message Filtering	Greeting list, consecutive repetition limit, evaluation model	Rules filter messages first, then an LLM determines whether a message is invalid
Response Reliability Check	Rewrite model, verification criteria	Select an LLM to determine whether a response is reliable and rewrite it




Using Personal Data Masking as an example, you can select the PII types to detect and set the enabled status.

Evaluation Model (LLM-Based Templates)

Templates that require semantic evaluation—Prompt Injection Protection, Invalid Message Filtering, and Response Reliability Check—include an evaluation model field. The drop-down menu lists the models currently available to your organization. This evaluation runs for every message,

so we recommend selecting a fast, lower-cost model (such as Haiku, GPT-5 mini, or Gemini Flash). Leave the field blank to use the platform's default model.



Using Response Reliability Check as an example, you can select the evaluation model from the LLMs available to your organization and describe the evaluation approach in plain language under Verification Criteria.

Detection Service (Safety Model-Based Templates)

Content Safety Classification Blocking and Semantic Personal Data Masking do not use a general-purpose LLM for evaluation. Instead, they send content to a dedicated safety model. This model returns structured classifications and scores that support thresholds and auditing, with lower latency and cost than an LLM judge. Both templates use a two-step configuration: first select a detection service, then choose the items to process.

Content Safety Classification Blocking

Under **Content Safety Model and Blocked Categories**, select a detection service from the first drop-down menu (OpenAI Moderation is currently available).

In the second drop-down menu, select the categories to block, such as harassment, hate, illegal activity, self-harm, sexual content, and violence. Selecting no categories means that any category violation will be blocked (the strictest option and the recommended starting setting).

The default **Additional Score Threshold** is 0, meaning the model's determination is used directly. If you set a value between 0 and 1, a score must also meet that threshold to be blocked. Raising the threshold can reduce false positives.

When the Detection Service Is Unavailable determines what happens when the service times out or no key is configured: `pass` allows the message through (availability first; default), while `block`

always blocks it (compliance first; recommended for regulated industries).



Content Safety Classification Blocking: First select a detection service, then choose the categories to block. Below, you can set an additional score threshold and the behavior to use when the service is unavailable.



The detection service provides the selectable categories in real time. Each category displays the service's native category name, and the list changes when you switch services.


Semantic Personal Data Masking

Under **Personal Data Detection Model and Detection Types**, select a detection service from the first drop-down menu (Google Cloud DLP is currently available).


In the second drop-down menu, select the personal data types to mask. “Standard types” include names, addresses, phone numbers, email addresses, Taiwan ID numbers, and Taiwan passport numbers, while “provider-specific types” include credit card numbers, IBANs, and other detailed types. Selecting more types increases the cost of each call, so we recommend selecting only those that your business actually needs to mask.

The default **Minimum Confidence** is 0.5. Detection results below this value are ignored. Raising the value can reduce false positives (such as mistaking a company name for a person's name), at the cost of potentially missing some data.

Masking Style: `type_token` replaces content with placeholders such as `[NAME]` and `[ADDRESS]`, so the AI still knows what type of data was originally present (recommended); `asterisk` replaces it with an equal number of asterisks, completely concealing the type.



Semantic Personal Data Masking: First select a detection service, then choose the personal data types to mask (name and address are selected in this example). Below, you can set the minimum confidence and masking style.



The selectable personal data types are divided into “standard types” and “provider-specific types,” presented in separate sections within the same menu.

Content will be sent to an external detection service. These two templates send the text to be checked to a detection service (OpenAI or Google Cloud) for evaluation. Organizations with data residency requirements or policies that prohibit external data transfers should confirm compliance before enabling them. When you switch detection services, selected items are automatically cleared to prevent incompatible types from causing a save failure.


Block messages are customizable. Blocking templates (such as Prompt Injection Protection, Sensitive Keyword Blocking, Invalid Message Filtering, and Content Safety Classification Blocking) let you configure the message returned to users when content is blocked under Block Response Message. For example: “Your message contains inappropriate language. Please revise it and try again.”

3. Associate Agents

A Hook only takes effect after it is attached to an Agent. There are two ways to do this:

Attach during creation: On the Apply to AI Assistants tab when creating a Hook, select the Agents to which it should apply.

Attach from Agent settings: Open an Agent's settings page, switch to the Hook tab, and select the Hook to apply.



On the Hook's Apply to AI Assistants tab, move the Hook from the “Available” list on the left to the “Selected” list on the right to complete the association.

> **An Agent can have multiple Hooks attached. The system executes them in sequence. For example, it can first use Invalid Message Filtering to block spam, then use Personal Data Masking to mask personal data, and finally use Prompt Injection Protection to block attacks—creating a tailored protection workflow.**

> **When a “When receiving a user message” Hook is attached, attachments, knowledge base passages, and tool responses are also checked. No additional configuration is required. If an Agent has a Hook that runs before content reaches the AI, content from user-uploaded attachments, passages retrieved from the knowledge base, and results returned by tools in Agent mode all pass through the same set of Hooks before being sent to the model. See Hook Message Interception for details.**

Enable the Hook

After confirming the parameters and associated Agents, set the Hook to Enabled. Once enabled, the Hook runs automatically at the corresponding point whenever a user interacts with that Agent.

4. Next Steps

After completing the setup, you can view each interception or modification in Hook Execution Logs to confirm that the Hook is working correctly.

Hook Execution Logs

Every interception, modification, or pass performed by Hook is recorded. For regulated industries such as finance, healthcare, and government, traceability is itself a compliance requirement—when a problem occurs, you must be able to determine which message was processed by which rule, what action was taken, and when it happened.



The Audit Log records every action in full, including the matched rule, action taken, processing result, and timestamp. It supports keyword searches, filtering by assistant, and report exports.

1. View Execution Logs

From the left menu, go to AgentOps → Hook Execution Logs. For each execution, you can see:

AI assistant—The AI assistant that triggered it


Hook name and Hook type—The Hook that processed it

Trigger point—When the Hook intervened (when receiving a user message after an AI response was generated)

Hook action and result—What it did (mask and modify intercept and block pass) and the processing result

Message content and creation time—Which message was processed and when it occurred

You can filter by assistant, rule, type, action, action result, trigger point, date range, or keyword, and you can also export reports for further audit analysis. The top of the page also displays statistics for the total number of executions, number of matches, and match rate.



Execution log list: Each entry shows the AI assistant, Hook name, trigger point, action, and result. You can see actual actions such as Personal Data Masking replacing a phone number with [REDACTED_PHONE], or sensitive keywords and prompt injections being blocked.

View Details for an Individual Entry

Open any entry to view the full context of the action: basic information (Hook name, type, trigger point, action, and result), related information, message content, and Metadata. This lets you clearly understand what the system did.



Entry details: In this Personal Data Masking example, the action is modify and the message content has been masked as [REDACTED_PHONE].

Trace Checks on Attachments, Knowledge Bases, and Tool Responses

Hooks that run before content reaches the AI inspect more than user-entered text. Attachment content, passages retrieved from the knowledge base, and tool responses in Agent mode all pass through the same set of Hooks (see Four Sources). These checks also create execution log entries, with the trigger point shown as "When receiving a user message." Open an entry and look in the Metadata section to see:

`path`: `input_context`, indicating that this entry is for content that was not directly entered by the user

`source`: Where the content came from—a tool response shows the tool name, while a passage from the knowledge base is shown as retrieved content

When you need to determine which tool or document supplied sensitive content to the model, use `source` to trace it back. Blocked content is not provided to the model, and the conversation itself does not stop.

Export Execution Logs

Clicking "Export" on the right side of the filter bar creates an export request based on the current filters (assistant, Hook, type, action, result, trigger point, date range, and keyword) and generates an Excel file in the background. After the message "Export request created. Processing..."

appears, you are automatically taken to the “Export Requests” sub-page (you can also open it with the “Export Requests” button next to “Export”).


The Export Requests page lists each export with its status (Pending
Processing
Completed
Failed), the user who started the export, record count, file size, processing time, creation time, and completion time. When the status is Completed, click “Download” in the Actions column; when it is Failed, click “View Error Details.” You can “Delete” export files you no longer need.

> The export requests here contain only Hook execution logs. They are a separate list from “Export Requests” in the AgentOps left-side menu (exports of conversation logs and evaluation reports).

2. Control Whether Original Messages Are Logged

By default, execution logs record only the processing result and do not retain the original sensitive content. This prevents personal data or sensitive messages from being stored again in the logs.

If you need to see the original content during debugging, go to the Hook settings page and change the Log original value before masking toggle from `off` to `on`. Once enabled, the logs also retain the original content before masking or blocking, making investigation easier.



Use the “Log original value before masking” field on the Hook settings page to control this behavior. The default is off (only the type and count are recorded; original personal data is not retained). Change it to on only when debugging is required.

> **Privacy trade-off: Enabling “Log original value” stores the original personal data or message content in the execution logs. For security reasons, we recommend keeping it disabled during normal operation and enabling it temporarily only when troubleshooting.**

> **Execution logs for “Semantic Personal Data Masking” inherently contain no original text: the detection service returns only the location and type of personal data, so the logs retain only the types and counts that were masked.**

3. View Hook Execution Details from a Conversation

In addition to the centralized execution logs, you can also trace actions from an actual conversation. Go to Customer Service Conversations → All Conversations and open any conversation. You can then see which messages in that conversation were processed by Hook (masked or blocked) and the corresponding action taken at the time.

This allows you to understand directly why a message was masked or blocked while reviewing a customer conversation, without having to cross-reference a separate log.

4. Related Pages

Hook Message Interception Overview—What Hook is, the four sources, and the seven standard templates

Add and Configure a Hook—How to create a Hook, configure parameters, and associate it with an AI assistant

Publish to Conversation Platforms

After creating an Agent, connect it to conversation platforms so customers or employees can chat with it where they already spend their time. Use this page to choose platforms and learn what to prepare, then follow the corresponding setup guides to connect them.

> Solution guide: This page covers one step in conversation platform setup. For the full text-based customer service launch process, see Text customer service: from zero to launch. For voice customer service, see Voice customer service: from zero to launch.

Permissions: Requires Conversation Platform permissions. See Role permission management.

Navigation: In the sidebar, go to Customer Conversations → Conversation Platforms, click Connect Conversation Platform in the upper right, then choose a platform in the Select Platform step.

📋 Default platform interfaces

When you create an Agent, the system automatically creates these three platform interfaces. No additional connection is needed:

API: A programmatic interface for developers to integrate into their own systems. See API documentation

Web: A built-in web chat interface that can be embedded directly in a website. See Web Chat overview

Internal: A Q&A platform for employees. Members access it through Agent Marketplace in the sidebar. See Chat with Agents (Agent Marketplace)

All conversation platforms at a glance

Names in parentheses in the "Platform" column match the cards on the Select Platform screen.

Category	Platform	Audience	Required credentials	Key limitations	Setup guide
Website	Website (Website)	External: visitors to your official website	No third-party credentials; obtain the embed code after creation and add it to your website	Requires access to modify website code to insert the embed code	Website

Category	Platform	Audience	Required credentials	Key limitations	Setup guide
Messaging	LINE	External: users of your LINE Official Account	Channel ID, Channel Secret, Channel Access Token	An Official Account supports only one Webhook URL; each group can have only one Agent	LINE
Messaging	FB Messenger (Messenger)	External: visitors to your Facebook Page	No manual credentials; authorize with a Facebook account that has full control of the business portfolio	Each Page can connect to only one conversation platform	FB Messenger
Messaging	Instagram	External: Instagram direct messages	No manual credentials; authorize through the linked Facebook Page	Professional accounts only; each Instagram account can connect to only one conversation platform	Instagram
Messaging	Telegram	Mainly external: Telegram users and groups	A Bot Token from BotFather	The Bot Token cannot be changed on the edit page after creation	Telegram
Messaging	WhatsApp	External: WhatsApp users	No manual credentials; authorize with a Facebook account, then select a WhatsApp Business account and phone number	Requires a Meta Business account and a WhatsApp Business account with a linked phone number	WhatsApp
Messaging	Viber (Beta)	External: Viber users	A Bot Token requested from Viber or a partner	Beta; one-to-one conversations only, no groups; the Bot Token cannot be changed after creation	Viber

Category	Platform	Audience	Required credentials	Key limitations	Setup guide
Workplace collaboration	Microsoft Teams (Azure Bot)	Internal: employees using Teams	Azure Bot App ID, App Password, and Tenant ID	Requires an organizational Microsoft 365 account; the Bot only responds when @mentioned in team channels	Microsoft Teams
Workplace collaboration	Slack	Internal: Slack workspace members	Bot User OAuth Token, Signing Secret	Requires workspace administrator permissions; invoke it in channels with @BotName	Slack
Workplace collaboration	LINE WORKS	Internal: LINE WORKS members	Bot ID, Bot Secret, Client ID, Client Secret, Service Account, Private Key	Credentials cannot be changed after creation; chat rooms do not display Markdown formatting	LINE WORKS
Workplace collaboration	Team+	Internal: Team+ members	Channel Number Channel ID, Channel Secret, Channel Access Token	One-to-one conversations only; credentials cannot be changed after creation	Team+
Email	Email	External: customers emailing a designated mailbox	Email Address, IMAP/SMTP server settings, Username, and Password (Gmail and Yahoo Mail require app passwords)	Receives mail by polling; the Polling Interval is configurable	Email

Conversations from all platforms are collected under Customer Conversations → All Conversations. See All conversations. For shared settings after connection (features, human handoff, permissions, and more), see Conversation platform settings overview.

> Already using LINE, a Facebook Page, or Instagram with another customer service system? See Migrate from another customer service system to MaiAgent for switching times, a preparation checklist, the order of operations, and rollback steps.

Launch publicly

Make your Agent the first point of contact for external communication. Choose the platforms your customers use most:

🖥️ Website

Embed a chat window in your official website to answer visitors' questions about products, services, and FAQs in real time. You can restrict embedding to specified domains or require visitors to log in before chatting. See Connect a conversation platform: Website.

💬 LINE

Integrate your company's LINE Official Account to reach consumers familiar with LINE. If the account is already connected to another LINE backend service, read Share a LINE Official Account with other services before switching, since only one Webhook URL is supported. For migration steps, see Migrate from another backend to MaiAgent.

📘 FB Messenger

Reply to Messenger messages sent to your Facebook Page, such as order inquiries and event questions. Authorization requires full control of the business portfolio that owns the Page. See Connect a conversation platform: FB Messenger. If the Page is connected to another customer service system, also change Meta's default "Conversation Routing" app to MaiAgent. See Set up conversation routing.

📷 Instagram

Reply to Instagram direct messages generated by posts and stories. Authorization works the same way as for FB Messenger. The Instagram account must be a professional account linked to a Facebook Page. Create separate conversation platforms for Messenger and Instagram; both can use the same Agent. See Connect a conversation platform: Instagram. Meta's "Conversation Routing" must also be configured separately for each. See Instagram: Set up conversation routing.

📱 Telegram

Create a Telegram Bot for individual and group conversations, suitable for technical communities and international customers. See Connect a conversation platform: Telegram.

WhatsApp and Viber

Serve international customers using WhatsApp or Viber. For WhatsApp, authorize with a Facebook account, then select a business account and phone number. See Connect a conversation platform: WhatsApp. Viber is currently in Beta, and you must request a Bot separately from Viber. See Connect a conversation platform: Viber.

Email

Let the Agent read mail sent to a designated mailbox and reply automatically. This is suitable for teams that primarily provide customer service by Email. See Connect a conversation platform: Email.

📞 Phone

Phone is not a card on the Select Platform screen. Instead, use the Call Center to connect a carrier or PBX SIP line to MaiAgent, then bind the number to a voice-enabled Agent. Your organization must first enable the Call Center. See Phone customer service (Call Center). For the full launch process, see Voice customer service: from zero to launch.

Internal use only

Let employees look up internal knowledge and processes in the tools they use every day:

🔒 Internal Q&A

The Agent is available only to organization members, who start conversations through Agent Marketplace in the sidebar. No additional connection is needed. This is suitable for internal documents, policies, and SOPs, supporting employee queries and onboarding. See Chat with Agents (Agent Marketplace).

Workplace collaboration platforms

Connect the Agent to Microsoft Teams, Slack, LINE WORKS, or Team+ if employees already use them, so they do not need to open MaiAgent separately. In groups or channels, invoke the Bot with an @mention in Teams, Slack, and LINE WORKS. Team+ supports only one-to-one conversations.

🔧 API integration

Use the default API interface to integrate the Agent into ERP, CRM, or internal workflow platforms, or build custom applications. See API documentation.

Web Chat Overview

On this page: 1. What is Web Chat? | 2. Build a Web Chat service that matches your brand | 3. Message customization | Stop a response in progress | 4. Diverse Q&A content | 5. Conversation history and sharing | 6. Choose whether to display tools and cited documents | 7. Conversation permissions: a secure, controlled environment | 8. Data collection (Pre-chat forms) | What to do if the connection fails | Review earlier messages while a response is being generated

1. What is Web Chat?

You can embed an Agent created in MaiAgent into your website to provide real-time customer support or other conversations. Web Chat features a responsive design that adapts seamlessly to desktops, tablets, and phones.

MaiAgent currently offers three embedding options:

1. Bottom-right widget

Embed it into your website as a built-in intelligent assistant

Keep it available whenever needed without interrupting browsing

Ideal for general customer support and inquiries




Bottom-right widget (draggable window)

2. Full-screen embedding

Provide a complete conversation experience

Suitable for complex inquiries and service workflows

Customize the design to meet your company's needs



Full-screen embedding example

3. MaiGPT window embedding

A complete ChatGPT-style conversation interface (conversation history on the left and the main conversation area on the right) that can be embedded directly into a page as its primary UI

Display it permanently in a specified container, or expand it to full screen when the bottom-right floating button is clicked

Ideal as the main conversation interface for an AI portal, internal knowledge portal, or product



MaiGPT window mode: a complete ChatGPT-style interface

> Select MaiGPT window mode in the "Embed" dialog in the conversation platform settings. For complete setup instructions, see MaiGPT window embedding.

Window modes visitors can switch themselves

In addition to the default Floating window, the bottom-right widget can offer a Sidebar mode. The conversation window sits against the right edge of the page and fills its height, making it convenient to ask questions while browsing. When your website developer enables both modes in the embed code, desktop visitors see a Switch window mode button in the title bar. One click switches between the two modes; sidebar mode also has a Collapse button to temporarily hide it. The embed code also controls inline mode, which places the conversation directly in a section of the page, and a mode that hides the floating button. See Web Chat embedding and SDK: window modes in the technical guide.

This design provides:

Immediate responses: Visitors receive professional answers without waiting, improving the user experience

Convenience: The bottom-right floating widget stays available without interrupting browsing

Cost efficiency: The Agent provides 24/7 service, significantly reducing staffing costs

A professional image: Showcase your company's technology capabilities and service quality

2. Build a Web Chat service that matches your brand

MaiAgent lets you customize the logo, avatar, conversation theme colors, and more to build a Web Chat service that matches your company's style

You can

Choose the Agent's display name

Upload your company logo

Choose the Agent's display avatar

Choose the Web Chat theme color

Choose the background color for the Agent's reply messages

to create your own Web Chat appearance:



Default style



Custom style

These options let you build a Web Chat service that reflects your company's brand colors and style

Web Chat displays the platform brand logo below the conversation input area. Brand images also retain consistent proportions on the login, registration, and loading screens, without being squashed or stretched.



The brand logo at the bottom of Web Chat stays clear and proportional

Dark mode improvements

MaiAgent's Web Chat dark mode has been thoroughly optimized for a more comfortable viewing experience:

Dynamic color adjustments

Automatically adjust the brightness of theme colors to keep them visible against dark backgrounds
Adjust text contrast intelligently for optimal readability
Optimize icon and button colors to stand out in dark mode

Improved contrast

Carefully designed message bubble backgrounds reduce visual fatigue
High-contrast colors make links and important information easy to identify
Optimized input field and button borders improve usability

Seamless switching

Users can switch between light and dark modes at any time
Conversation content and interaction state are preserved when switching
The system remembers each user's theme preference

Dark mode is particularly suitable for:

Nighttime use or low-light environments
Long conversations with less eye strain
Dark color schemes that match your company's brand

3. Message customization

Customize your Agent's greeting for a visitor's first entry into Web Chat using scenarios such as those below. Greetings use fixed text rather than AI-generated content, so they do not display thumbs-up or thumbs-down feedback buttons and do not count toward user satisfaction in Usage Analytics.

1. Custom greetings

Branded greetings

Set a greeting such as “Welcome to our website! I'm your dedicated customer service assistant” to convey a professional image and a friendly service attitude

Guided introductions

Set a greeting such as “I can help you look up product information, answer usage questions, and assist with orders” to clearly explain the available services and build users' confidence in your support capabilities



2. Starter questions

Set “Conversation starters” as quick options

Users can click common questions directly without typing

Example questions:

“How do I view the items I've ordered?”

“How do I place an order?”

“Membership points policy”

“Business hours”

Users can start a conversation by clicking a starter question, speeding up the Q&A process:



Example starter question settings



A user clicks to start a conversation

Stop a response in progress

If you notice an error in your question after sending it, you do not need to wait for the Agent to finish the entire response. While a response is being generated, the send button on the right of the input field becomes a square Stop button. Click it to stop the response, then enter a corrected question.

For example, a customer service representative asks the Agent to plan an annual product launch, then realizes they forgot to specify the budget. They can click Stop while the Agent is generating its response, then ask again with the budget and attendee count, avoiding a wait for an unsuitable response to finish.

Stop a response

1. Find the Stop button

After sending a question, wait for the Agent to start generating its response. A square Stop button appears on the right of the input field.



Click the Stop button to the right of the input field while a response is being generated

2. Stop and ask again

Click Stop. The interrupted response is labeled “Response interrupted,” and the send button immediately returns to the right of the input field, allowing you to enter and send your corrected question.

> Stopping only interrupts the response currently being generated. It does not delete your submitted question or earlier conversation history.

Stop with the keyboard: press Esc

On a computer, press Esc while the input field has focus to perform the same action as clicking Stop, without moving the mouse. Pressing Esc when no response is being generated has no effect, and any text you are typing remains in the input field.

Send more messages during a response: message queue

While the Agent is still responding, visitors on a computer can keep typing and press Enter to send. These messages are not sent to the Agent immediately. Instead, they appear in a list above the input field labeled "Will send in order after the response finishes (N messages)" and are automatically sent in sequence once the current response ends. During a response, the button to the right of the input field is Stop, so use Enter to queue a message. For queued messages:

Click a message to return it to the input field, edit it, and send it again

Click Remove on the right to cancel it

When the queue is full, a message says "You can queue up to N messages. Please wait for the response to finish"



Messages sent with Enter during a response are queued above the input field

To have the Agent handle a new question immediately, click Stop or press Esc first, then send it. Messages already in the queue are retained when you stop a response and are sent automatically once the interrupted response finishes wrapping up (within about 10 seconds).

For example, a visitor asks the Agent in the website's Web Chat for a detailed introduction to all platform features, then decides halfway through that they would prefer a bulleted list. They type "One more thing: please organize this as a bulleted list" and press Enter to queue it. They then press Esc to interrupt the lengthy response. The screen shows "Response interrupted," and a moment later the queued message is sent automatically. The Agent then responds to this new message.

Messages are not queued in the following cases: Messages with attachments: If you attach a file and try to send it during a response, the screen shows “AI is responding.” Both the text and file remain in the input field for you to send after the response ends. If you click **Stop**, wait briefly (up to about 10 seconds) for the interrupted response to finish wrapping up. Phones and tablets: Enter inserts a line break in the input field. During a response, only the **Stop** button appears on the right, so you must stop the response or wait for it to end before sending the next message.

4. Diverse Q&A content

1. Multilingual support

Respond in the user's language to eliminate communication barriers.

Automatic detection: Select the Agent's response language based on the language of the user's input



Manual switching:

Select a language in the Web Chat interface. See **Multilingual support: Web Chat language settings**.

Specify the Agent's response language in the Web Chat initialization script (javascript). See **Technical guide—Web Chat embedding and SDK (`locale` setting)**.

> For the list of supported languages, see **Multilingual support: supported languages**

Voice input and playback

When voice services are enabled for the Agent, visitors see three additional features in Web Chat:

Location	Feature
Microphone icon on the left of the input field	Voice input: Click to start speaking. The screen shows “Listening,” and the recognized text is automatically sent as a message when you finish
Voice in the settings menu	Select the speech recognition language and provider: Microsoft Azure (Mandarin, Simplified Chinese, English, Japanese, Korean, Thai, Vietnamese, Indonesian, Malay, Filipino, Burmese, Khmer, Lao, Singapore English), Bronci (Taiwanese), or Built-in (Mandarin and English, using the browser's own speech recognition). Match the recognition language to the visitor's spoken language for accurate results
Voice playback in the settings menu	When enabled, the Agent's replies are read aloud automatically; when disabled, only text is displayed. Enabled by default

On desktop, the settings menu is the settings bar in the title bar. On mobile, it is the ⋮ in the upper-right corner.

> Voice input here means “speak a sentence, recognize it as text, and send it.” If the Agent has Voice Agent enabled, a Headphones icon also appears next to the input field for real-time voice calls. See Voice Agent: how users talk.

2. Multimodal Q&A

In addition to text Q&A, the Agent supports uploads of various file types:

Spreadsheets: .xls, .xlsx, .csv, .ods
Word processing documents: .doc, .docx, .odt, .pdf, .md, .txt
Presentations: .ppt, .pptx, .odp
Web documents: .html, .htm
Data formats: .json, .jsonl
Audio files: .wav, .mp3, .m4a, .aac
Video files: .mp4

> You can disable attachment uploads and allow text-only conversations to keep conversations secure.

Image content processing

Image recognition and analysis

Uploaded image analysis: Users can upload product images for AI to identify and provide relevant information automatically

Screenshot processing: Analyze screenshots to help resolve usage issues

Image descriptions: Automatically generate descriptions of image content and related suggestions

Images in replies

Product images: Include actual product images in replies

Visual instructions: Provide step-by-step screenshots

Examples:

A user asks where to configure an Agent in MaiAgent, and the Agent replies with an image of the settings screen

A user shares a screenshot to confirm whether a path is correct, and the Agent interprets it and responds accurately



The Agent replies with an image



The Agent interprets the user's screenshot

Document processing capabilities

Supported document formats

PDF documents: Automatically parse PDF content and answer related questions
Word documents: Process .doc/.docx documents
Excel spreadsheets: Analyze spreadsheet data and provide insights
PowerPoint presentations: Extract presentation content and answer questions

Email files: Process Outlook .msg and .eml emails, reading message information, body text, and attached documents



Visitors can upload emails through the attachment option and ask about the message and its attached documents

Document interactions

Content queries: Answer specific questions based on uploaded documents

Data analysis: Automatically analyze tabular data and present statistics in tables

Document summaries: Generate summaries of key information in long documents

Example 1: Ask the Agent to present information in a table and provide links to references



Information organized in a table



External links provided

Example 2: Ask the Agent to analyze sales information and provide a tabular analysis



Example 3: Upload a docx file and ask the Agent to help analyze issues with CV writing



> The Agent always responds in Markdown, keeping its responses clearly organized.

Files delivered by the Agent: When the Agent uses Code Interpreter to create files for a user, Web Chat displays file cards in the reply (file name, type, and download button). Click a card to preview the file directly. Files created by sub-Agents in Agent Teams appear in the same way.

5. Conversation history and sharing

1. Conversation history

To provide continuity of service, Web Chat automatically remembers users' conversation history so each conversation can build on previous ones.

What is remembered

Conversation content: Complete Q&A records, including text, images, and documents

Service status: Unfinished queries and pending issues

When "Show conversation history" is enabled (see Interaction settings), a Clock icon appears on the left of the title bar. Click it to open the conversation history sidebar:


預設助理樣式
"Japanese(mediant)" 應該是 "Japanese(intermediate)"
部分句子文法不夠流暢，如"in charge of technique explanation and helps"
3. 技術細節不夠具體：
缺乏具體的專案成果量化數據
技術技能描述過於簡單，缺乏深度
建議改善
1. 清理重複內容，確保每個部分只出現一次
2. 統一格式和排版
3. 修正時間邏輯錯誤
4. 完善參考人資訊
5. 改善英文表達的準確性
6. 增加更多量化的成果描述
2025/08/15 16:49:54
請輸入您想問的問題
Powered by MAIAGENT



Location	Feature
Search conversations at the top of the sidebar	Open the search panel and enter keywords to filter conversations instantly; you can also click New conversation directly in the panel
New conversation at the top of the sidebar	Start a brand-new conversation
Edit conversations at the top of the sidebar	Visible only to logged-in visitors; select multiple conversations to delete them at once. See Delete multiple conversations at once below

Location	Feature
Conversation list	Automatically grouped into Today Yesterday Previous 7 days Previous 30 days Earlier. Conversations that have used Conversation handoff are labeled "Handed off to" or "Continued from the original conversation"
··· for each conversation	Rename (change the title), Delete (delete after confirmation; cannot be undone). When conversation sharing is enabled for the platform, Share is also available. See Conversation sharing below

When conversation history is disabled, a New conversation icon replaces the clock icon. Visitors can only start new conversations and cannot see past records.

Delete multiple conversations at once

When login is enabled for the conversation platform (see Website: login settings), logged-in visitors can select several of their own conversations in the history sidebar and delete them at once. Visitors who are not logged in do not see this option; they can still use each conversation's ··· menu to delete conversations individually.

For example, an online store member has asked about order shipping, return documents, and invoice details in three customer support Web Chat conversations. Once all three issues are resolved, she wants to delete two conversations and keep only the order conversation for reference. She opens the history sidebar, clicks Edit conversations, selects the other two, clicks Delete, and confirms. Only the order conversation remains in the sidebar. One deleted conversation was open, so the screen also switches automatically to a new conversation.


Click the Clock icon on the left of the title bar to open the conversation history sidebar, then click the pencil icon Edit conversations to the left of New conversation. In edit mode, the button becomes a checkmark icon labeled Done, checkboxes appear before each conversation, and the ··· menus are temporarily hidden.

Click conversation rows to select those to delete. In edit mode, clicking a row only selects it; it does not open the conversation. You can also click Select all above the list to select conversations currently loaded in the sidebar, up to 100 at a time. Click again to deselect all. The top of the list shows "N selected."



After you select conversations to delete, the number selected appears above the list.

Click Delete. The confirmation dialog shows “Delete N conversations?” Check the count, then click Delete. If all deletions succeed, “Deleted N conversations” appears and edit mode closes.



The confirmation dialog shows the number of conversations to delete.

> All messages in the conversations are deleted together. The interface does not offer an undo option.

If a deleted conversation is currently open, the screen automatically switches to a new conversation.

If some deletions fail (for example, a conversation was already deleted in another tab), “Deleted N conversations; M failed” appears. Successful deletions disappear from the list, while failed ones remain selected. The screen stays in edit mode so you can click Delete again to retry or Done to exit. If the entire batch could not be sent (for example, due to a network interruption), “Deletion failed. Please try again later” appears, and the list and selections remain unchanged.

To cancel deletion, click Done or close the sidebar. Edit mode closes and all selections are cleared.

Edit conversations does not appear when the sidebar has no conversations.



Conversations that could not be deleted remain in the list and stay selected.

Conversation memory can be used for:

Ongoing consultations: When a user asks, “What was the tent model you recommended last time?”, the AI can immediately recall it and answer


Progress tracking: When a user says, “Continue the order inquiry from last time,” the AI automatically retrieves the relevant information

Personalized service: Provide more accurate recommendations and advice based on conversation history

> **When a conversation becomes too long, enable conversation handoff so visitors can ask the Agent to prepare a handoff summary and continue in a new conversation. For how to enable it in Web Chat and its limitations, see Conversation handoff: Enable in Web Chat. To create a continuation conversation through the API, see Conversation Handoff and Continuation API in the technical guide.**

2. Conversation Sharing

Use MaiAgent to generate a conversation sharing link when you want to share a conversation with friends or colleagues after consulting an Agent, or when your internal team needs to collaborate on a customer issue:



Click Share in the upper-right corner of the conversation window, then click Copy Link in the "Public link to share this conversation" dialog and send it to the recipient. You can also get the same type of link from ⋯ → Share on any conversation in the history sidebar.

What recipients see

A read-only conversation page containing all messages in the conversation so far, including text, images, and attachments

No login is required to open it, so share it only with the intended recipients

Recipients can only view the page and cannot type to continue the conversation there; to ask more questions, return to the original Web Chat and open a conversation

> The sharing link displays only the conversation history. It does not generate an additional summary or compile related resources.

Conversation history sharing can be used for:

Customer sharing: “These camping gear recommendations are great. I'll share them with the hiking club.”

Internal collaboration: Customer service staff share complex issues with the technical support team

Training: Share representative conversations as employee training materials

3. Conversation Timeout Management

To maintain conversation quality and system performance, Web Chat provides intelligent conversation timeout management:

Intelligent filtering

Automatically filter greetings: The system identifies and filters opening greetings, excluding them from conversation timeout calculations

Reset message counts correctly: The message counter resets correctly when a conversation restarts

Optimize timeout detection: Timeouts are calculated only for substantive conversation content, enabling more accurate conversation management

Conversation continuity

Prevents unexpected timeouts during normal conversations

Allows users to continue after a long pause or time spent thinking

Intelligently determines whether a conversation is still ongoing

How it works

Start a conversation: The user sends a greeting, such as “Hello,” which the system excludes from timeout calculations

Begin the discussion: The user starts asking substantive questions, and the timeout timer starts

Pause the conversation: If the user steps away temporarily, the system retains the conversation state

Resume: The user returns to continue, and the message count updates correctly

This improvement makes conversations smoother and more natural, so users do not need to worry about interruptions while taking time to think.

4. Message Actions: Editing, Feedback, and Branching

Hover over a message to see action icons. These work the same way as in MaiGPT; see **MaiGPT: Message Actions** for full details. In Web Chat, the difference is which visitors can see them:

Action	Who can use it	Description
Copy, **Like**, and **Dislike** on AI responses	All visitors	Dislike opens the "Provide Feedback" dialog, where visitors select reasons and add other feedback before submitting. Feedback appears in the admin **Conversation Viewer** and the satisfaction statistics in **Usage Analytics**
Edit Message and version switching ‹ N M › on their own messages	Logged-in visitors (the platform has **login enabled**)	Editing deletes subsequent messages and prompts the Agent to respond again; submission is unavailable if the content has not changed
Branch Conversation on AI responses	Logged-in visitors	Starts a separate conversation containing the messages up to this response, without affecting the original conversation


5. Connected Services

When the Agent needs to access an external service on a visitor's behalf (for example, checking a calendar using the visitor's own account), it sends an authorization card in the conversation. Visitors can view, reauthorize, or disconnect authorized services from **Connected Services** (the link icon) in the title bar. This button is visible only to visitors whose identity has been established (through a Pre-chat form, login, or a Source ID supplied by the website). For details, see **Connected Services**.

6. Choose Whether to Display Tools Used and Cited Documents

1. Display the List of Tools Used

You can choose whether users can see the list of tools the Agent uses during reasoning. If enabled, the following appears while the Agent generates a response:



Use this list to check whether the Agent is using tools correctly.


If an MCP tool called by the Agent includes an interactive interface, an interactive card also appears below the response. See MCP Interactive Cards (MCP Apps).

2. Display the List of Cited Documents

Each AI answer automatically generates a list of cited documents, clearly identifying information sources to improve credibility and traceability.

Display settings

Organizations can choose whether users can see the list of cited tools and the names and contents of reference documents. When enabled, the following list appears at the bottom of the Agent's response. Click a “Citation Node” to view the referenced document excerpt:



Choose whether to disclose citation information based on the use case:

Public customer service: Display all citation information to build trust

Internal support: Hide sensitive documents to protect confidential information

Educational institutions: Display learning resources for students to consult

Panels Beside Responses: Canvas and Browser

Agent responses can include more than text. When the Agent produces a document, chart, web page, or map, a panel opens to the right of the conversation on desktop, or covers the entire conversation on mobile. You can close the panel; a card for the output remains in the message, and clicking it reopens the panel. This section describes the three types of panels visitors may see.

Canvas

Canvas opens automatically when the Agent produces a Markdown document, Mermaid diagram, HTML page, or React interactive page as a canvas. The toolbar at the top of the panel includes:

Button	What it does
Switch to Code Switch to Preview	Switches between the rendered view and the source content
Console, Reset Code	Available only for React interactive pages: view execution messages or restore the code to the version originally generated by the Agent
Full Screen Exit Full Screen	Expands the canvas to fill the window
Download	Download Source File (.md, .mmd, .html, or .jsx, depending on the type) or Download PDF; while the content is compiling, "Download available after compilation" appears
Close	Collapses the panel; the canvas card in the message can still reopen it

On desktop, drag the panel's left edge to adjust its width. Canvas uses, suitable prompts, and export details are the same as in MaiGPT; see Canvas.

Map Canvas

When the Agent answers location or itinerary questions (such as restaurant recommendations or a three-day, two-night itinerary), it may use a map canvas: a Google map with location markers on the left and a list of place cards on the right (below the map on mobile).

Filters: The Filter dropdown filters by Category (restaurants, cafés, accommodations, attractions, shopping, nature, transportation, other), Conditions (Open Now Only, 4.5★ and Above), and Display (rating badges, name labels). If no places match, "No places match the filters" appears.

Multi-day itineraries: For itineraries split across days, All Day N switches appear at the top left of the map. The list groups places by morning, afternoon, evening, and unscheduled.

Place details: Click a place card to open details, with Overview (description, address, website, phone number, opening hours, and Open Closed status) and Reviews tabs. Below are Directions, Call, Open Website, and Open in Google Maps. Details come from Google; if they cannot load, "Unable to retrieve details" appears.

In the map canvas, Switch to Code shows the raw place data, and Download Source File saves it as .json.

Browser Panel

When the Agent has Browser Tool enabled and starts operating a web page, a Browser panel appears on the right, showing live screenshots of the page the Agent sees and its current URL. It

shows AI Operating while the Agent acts, or “Waiting for browser view…” before an image is available.

Visitors can take over while the Agent is paused, for example to enter a verification code, username and password, or select an option:

Click, double-click, right-click, or scroll directly on the screenshot to send the action to the web page the Agent is operating.

Use the input field at the bottom of the panel, Type here and press Enter to send to the browser: type text and press Enter to send it. When the field is empty, pressing Enter, Esc, arrow keys, or similar keys sends those keystrokes directly to the page. The input field is temporarily disabled while the Agent is operating.

After you click Close at the top right to collapse the panel, Reopen Browser View appears above the input field. Click it to view the browser again.

> Usernames and passwords entered in the panel are sent to the web page the Agent is operating. Enter them only if you trust the Agent and the organization behind it.

7. Conversation Access Control - A Secure, Controlled Conversation Environment

1. Login Settings

Require login

To keep conversations secure and controlled, organizations can enable login and require users to sign in before using Agent services. Once configured, visitors who open Web Chat first see a login page. Only users who log in successfully can start a conversation with the Agent

Security benefits

Identity verification: Ensures that every conversation user has an identifiable identity

Access control: Provides services appropriate to the user's identity

Conversation tracking: Keeps a complete conversation history for each user

Data protection: Prevents unauthorized users from accessing sensitive information

2. Three Login Methods

AD (Active Directory) Login

Use case: Internal employees, integrated with an existing AD system

Features: Single sign-on (SSO), without additional account management

Setup: Configure AD server connection information and synchronization rules

Example: Employees log in directly with their company accounts and automatically receive the appropriate permissions

Keycloak Login

Use case: Organizations requiring complex identity management and support for multiple identity providers

Features: Supports standard protocols such as OAuth2, SAML, and OpenID Connect

Setup: Configure the Keycloak server, user pool, and identity providers

Example: Integrate user identities across multiple systems and manage permissions centrally

Further use: The Agent can reuse a visitor's Keycloak login identity when calling MCP/API tools; see Use the Keycloak Login Identity to Call Tools

MaiAgent Login

Use case: Simple user management needs and quick deployment

Features: Built-in user management with a straightforward interface

Setup: Create user accounts and permissions on the MaiAgent platform

Example: Create a dedicated login system for a specific group of users

Visitor self-registration: The login page includes **Sign Up Now** and **Forgot Password?**. The registration form is the same as the MaiAgent admin account application form (real name, company name, company email, password, invitation code). It creates a MaiAgent platform account that can immediately be used to log in to Web Chat from the login page. This does not make the account a member of your organization or grant any admin permissions. The page is protected by bot verification; see Other Prompts Visitors May See below.

When enabled, the following screen requires login before starting a conversation:



3. Use the Keycloak Login Identity to Call Tools

After a visitor logs in to Web Chat with Keycloak, the Agent can automatically include the visitor's own Keycloak login credentials when calling MCP tools or API tools on their behalf. Your backend can then use the same Keycloak authentication to identify the user and return only the data they are allowed to see, without configuring separate accounts for every tool or asking visitors to log in again.

This feature is disabled by default. When disabled, all tool calls work exactly as before.

Use Case

An organization uses Keycloak to manage employee accounts for its internal service portal and provides Web Chat as an employee-only Agent. The IT administrator enables this feature on the conversation platform and adds the company's leave management system host to the allowlist. After logging in to Web Chat, an employee asks, "How many days of annual leave do I have left?" The Agent calls the leave system's API tool with the employee's own login credentials in the request. The leave system identifies the employee from those credentials and returns only their attendance and leave records. If another employee asks, they receive their own records.

Prerequisites

The organization has completed **Keycloak integration**. Visitors must be members of this organization. On their first login through the Keycloak instance configured for the organization, the system automatically creates an account and adds it to the organization (see **Third-party Login: First Login**).

In the conversation platform's "**Login Settings**", "**Enable Login**" is on and "**Login Source**" is set to Keycloak.

The MCP/API tools that will receive credentials have been created and configured for the Agent used by this conversation platform. The receiving system can validate credentials issued by your Keycloak Realm.

Setup Steps

Location: In the left menu, go to "**Customer Service > Conversation Platforms**", select a website-type conversation platform, and open the "**Login Settings**" tab. This section appears below after you select Keycloak as the login source.

Enable "**Use Keycloak Login Identity to Call Tools**".

Read the red warning below the switch, "**The visitor's own login credentials will be forwarded to the following hosts**", and confirm that you understand where the credentials will be sent.

In "**Tool Hosts Allowed to Receive Credentials**", enter the tool hosts that will receive credentials, one per line (or separated by commas):

Enter only the hostname, without `https://`, a port, or a path, for example `mcp.example.com`.

`*.example.com` matches `example.com` itself and all its subdomains. A hostname without `*.` matches only that exact host.

Hostnames are matched against the tool's "MCP Server URL" or "API URL".

Save the settings.



Enabling the feature displays a credential forwarding warning and requires you to enter the tool hosts allowed to receive credentials

At least one host is required when the switch is on. If the list is empty or contains an invalid hostname, the page displays "**When enabled, at least one tool host must be allowed to receive**

credentials” or “The following are not valid hostnames”, and the settings are not submitted.

> Visitors must log in again after you enable this feature. The platform saves Keycloak credentials only at login, and only when this feature is enabled on a conversation platform. Ask visitors who were already logged in before it was enabled to log out and log in again so subsequent tool calls include their credentials.

What the Receiving System Gets

When the Agent calls an MCP/API tool on an allowlisted host, the request includes an additional HTTP header:

```
Authorization: Bearer
```

This is a standard access token issued to the visitor by your Keycloak Realm. Engineers responsible for the integration can identify the user through standard Keycloak token validation (checking the signature, expiration, and Realm). If the credentials have expired, the platform first renews them with the same Keycloak instance using the visitor's login session, then sends the request. The tool does not need to handle renewal.

When Credentials Are Included

Situation	Result
The visitor is logged in with Keycloak, their session is active, and the tool host is on the allowlist	Includes the visitor's own credentials
The tool host is not on the allowlist	Calls the tool normally, without credentials
The tool already has `Authorization` configured (OAuth, API tool headers, Contact MCP credentials, etc.)	Does not override it; retains the tool's existing authentication method
The visitor is logged out or is not a member of this organization	Does not include credentials
The visitor enters through Source ID access without login	Does not include credentials; identity is based on the organization member bound when the conversation was created, not the Source ID provided by the embedding site
The switch is off	Behaves as it did before this feature was enabled

The visitor's complete login credentials are forwarded. A system that receives them can use the visitor's identity to access other services protected by the same Keycloak instance. Include only hosts you trust that actually need to identify users, and avoid overly broad wildcards.


When a visitor logs out, the platform revokes their saved credentials. When no conversation platform using the same Keycloak site still has this feature enabled (because the switch was turned off, the login source changed, or the conversation platform was deleted), the platform also clears all saved visitor credentials.

8. Data Collection (Pre-chat Form)

When data collection is enabled, visitors see a form before starting a conversation and must fill it out to proceed. Their responses are saved to their Contact record, where customer service staff can view them directly on the conversation page. This suits situations where you need to know who someone is first, such as collecting company names and tax IDs for dealer support, or names and email addresses for event inquiries.

1. Configure the Data Collection Form

Path: Customer Service → Conversation Platforms → select the Web Chat conversation platform → Data Collection tab.



Data Collection tab: configure the switch, title, and fields on the left; Live Preview on the right shows the form as you make changes

Enable the Form

Turn on **Enable Pre-chat Form**. When disabled, visitors go directly to the conversation, following the original flow.

Set the Title and Subtitle (Optional)

Form Title: Appears at the top of the form. If left blank, the default text is “A few questions before we chat”.

Form Subtitle: Describes the form. Use `{name}` to insert the conversation platform's name. If left blank, the default text is “Leave your details so {name} can provide a more personalized service”.


Both support multiple languages. Switch language tabs to enter text for each language.

Add Fields

Click **Add Field**. Each field has the following settings:

Setting	Description
Field Type	Four types: text, Email, phone, and dropdown
Field Label	The field name visitors see; can be entered separately for each language
Placeholder	Gray hint text inside the field
Required	When checked, visitors cannot submit without completing the field
Contact Field Mapping	Determines where the data is saved in the Contact: Name (Contact.name), Email (Contact.email), Phone (Contact.phoneNumber), or Custom Field (Metadata)

Dropdown fields also have an Options list and an Allow Custom "Other" Input checkbox, which lets visitors select "Other" and enter their own text.



Each field supports a field type, multilingual labels, placeholder text, Contact field mapping, and a required setting

Drag fields to reorder them. Each form supports up to 10 fields. The preview on the right updates in real time; switch the Preview Language to check each language version.


Save

Once the preview looks correct, save. The changes take effect in Web Chat immediately.


> **Restrictions on mapping Contact fields Name can only map to a Text field, Email to an Email field, and Phone to a Phone field. A disabled-state message appears if the types do not match. Name, Email, and Phone can each be mapped by only one form field. For other fields (such as a tax ID or company name), select Custom Field (Metadata).**

2. Visitor form flow

When visitors open Web Chat, they first see the form: its title, subtitle, the fields you configured, and a language switcher in the upper-right corner. After completing the form, they click Start Chat to enter the conversation.



Visitors see the form first when they open Web Chat



Click Start Chat after completing the form

If a required field is empty or the email address or phone number has an invalid format, an error appears below the field and the form cannot be submitted.

Once visitors complete the form in a browser, they will not be asked to fill it out again when they reopen the same Web Chat in that browser.


To correct their information, visitors can click **Re-enter Information** in the **⋮** menu in the upper-right corner of Web Chat. The form appears again.



Re-enter Information in the upper-right ⋮ menu

3. Using login: linking information to an account


If both **login** and data collection are enabled for the same Web Chat, the flow is: **Log in → Complete the form → Start chatting**. The information users enter is linked to their login account rather than their browser.



The Login Settings tab: enable the login feature and select a login source. These settings are independent of the Data Collection tab



① The login screen appears first when opening Web Chat



② The data collection form appears only after login

Situation	Web Chat behavior
The account is being used for the first time and has not completed the form	The form appears after login; submitting it creates a contact linked to the account
The same account logs in on another device or browser	The form does not appear again; the conversation starts with the account's existing information
Someone previously completed the form on this device without logging in, and the account has no information yet	An “Is this your information?” confirmation screen appears (see below)
The account already has information, and the device also has information entered while logged out	The account's information takes precedence, with no prompt or merge
A logged-in user clicks **Re-enter Information**	The account's existing contact is updated; no additional contact is created

Confirmation screen: Is this your information?

If someone previously completed the form on this device without logging in and the account now logging in has no information yet, a confirmation screen appears before the form. It lists the information previously entered on this device (partially masked) and offers two buttons:

Yes, This Is Mine: Links that information to the current account. The same account will not need to complete the form again on any device.

No: Leaves the existing information unchanged without merging it, then displays the form for the user to complete.



The confirmation screen partially masks the information so users can recognize whether they entered it

> **Web Chat instances without login enabled are unaffected and still use the browser to determine whether the form has been completed. The system does not automatically populate the form from account information. When an account is used for the first time, the user must still complete the form even if their information already exists in the backend.**

Once the conversation starts, both the Agent and the customer service backend see the same contact linked to the account:



The Agent addresses the user by the name entered in the form



The backend conversation page shows the contact and the tax ID collected through the form

4. Viewing collected information in the backend

In a conversation: Go to Customer Service Conversations → All Conversations → open a conversation. The Contact Information section on the right lists each item collected through the form. Fields mapped to Email and Phone appear as "Email" and "Phone Number"; custom fields use the field labels you configured.




Contact Information on the right of the conversation page lists each item collected through the form

> **The Contact column in the contact list shows the Contact's name. If the form's name field maps to Custom Field (Metadata) rather than Name (Contact.name), a logged-out visitor's contact appears as “Anonymous”, and the name appears only in custom attributes. To see visitor names directly in the list, map the name field to Name (Contact.name).**

On the contact page: Go to Customer Service Conversations → Contacts → open a contact. The Basic Information tab shows the name and phone number; the Custom Attributes tab shows the other form fields.



Search the contact list by name, email address, or phone number



The Custom Attributes tab lists the value of each form field

Information submitted by logged-in users is linked to their accounts, rather than remaining an anonymous contact with no account owner. The contact name depends on the form settings: if the name field maps to Name (Contact.name), the name entered in the form is displayed; if there is no name field, the login account's name is displayed.

Other prompts visitors may see

The following prompts occasionally appear in conversations and do not require administrator configuration. Use this reference to answer visitors' questions:

Screen	When it appears	What to do
A human verification widget on the login, registration, and password reset pages; “Too many requests. Please try again later.”	Web Chat with login enabled adds Cloudflare Turnstile verification to these three pages; too many requests in a short period (such as repeatedly starting new conversations or sending messages) trigger rate limiting	Wait for the verification checkmark before submitting; if rate-limited, wait a while and try again
A bottom panel saying “Install {App Name} App”	When opening the standalone full-screen page in a mobile browser, visitors can add Web Chat to their home screen as an app.	Click Remind Me Later to dismiss it for a day; it does not appear when opened

Screen	When it appears	What to do
	Android shows Install Now; Safari on iPhone shows Add to Home Screen instructions, while other iPhone browsers recommend switching to Safari	as an already-installed app
“Content is too long (N characters). Displaying as plain text” + Show Full Content	When a reply exceeds 50,000 characters (or a single line exceeds 2,000 characters), Markdown formatting is disabled and only the first 2,000 characters appear initially	Click Show Full Content to expand, or Collapse to collapse
“Content is too large (N characters). Showing only the beginning”	A tool returns an oversized JSON response	Only the display is truncated; the Agent has received the full data
“Earlier long messages have been partially omitted (approximately N characters in total). The assistant may not have seen the full content”	In a very long conversation, the system omits earlier long messages to manage context length	Paste the relevant passages again if the Agent needs them; you can also use Conversation Handoff to start a new conversation
A small label next to a reply: “This reply was produced by team member ‘{Name}’”	The Agent belongs to an Agent Team, and this reply comes from one of its member Agents	No action needed
“Delegating to Handing off to Switching to {Agent}”, subagent task cards	During multi-Agent collaboration, the main Agent assigns a task to a subagent	The card shows Responding Completed; wait for it to finish
“Locating...”, “Unable to get your location. Please enable location access in settings”, “Location obtained successfully”	The administrator has enabled Location Information, and the browser requests location permission	Allow location access and submit again; if permission is denied, the Agent still responds, but without location information
A “Connect {Service}” authorization card	The Agent needs to access an external service using the visitor's own account	See Connected Services
A video generation card (Queued Generating Estimated time: 60–90 seconds)	The Agent uses a video generation tool	Wait for completion; see AI Video Generation

What to do when a connection fails


For example, a website administrator receives a visitor's report that Web Chat shows a connection error when opened. The visitor should first wait for the system to retry automatically. If the error screen persists, they should capture the full screen, including the failed stage, error category, and time, and send it to the administrator to help diagnose the problem more quickly.

If the network disconnects while Web Chat is loading the Agent configuration, it retries automatically and keeps showing the loading screen during that time. If it still cannot connect after retrying, the error screen shows:

The loading stage that failed

The error category, along with the HTTP status code if available

The local time the error occurred



If automatic retries fail, the screen lists the failed stage, error category, and time

If the system has received an HTTP error status code, the server has already responded. In this case, it displays the diagnostic error screen immediately without retrying automatically.

> First check that the device can access the internet, then click Retry on the error screen. If the problem persists, include all diagnostic information in the screenshot and avoid capturing conversation content or personal information.

Reviewing earlier messages while a reply is being generated

While the Agent is still generating a reply, visitors can scroll up to review earlier messages. The reply continues generating below, but the screen stays at the position the visitor scrolled to, without being pulled away by new text. Once visitors move away from the latest content, Back to Latest appears above the input box.

Example scenario

A visitor asks the Agent to compare several plans at once. Before the answer is finished, she wants to check the price of the first plan, so she scrolls up. The screen stays in place instead of jumping as more text appears below. After checking, she clicks Back to Latest. The screen returns to her most recent question so she can continue reading the rest of the comparison.

Steps

1. Scroll up

While the Agent is generating a reply, scroll up using the mouse wheel, touch gestures, or by dragging the scrollbar.

2. Read in place

The screen stays where you scrolled. Newly generated content does not change your current position.



The reply is still generating (the square stop button appears to the right of the input box). After scrolling up, Back to Latest appears above the input box

3. Return to the latest content

Click Back to Latest to return to the most recent question and resume automatically following the latest content.

Connect a Conversation Platform: Website


1. Open the Settings Page

1. Option 1: Add a Web Customer Service Chat

In the left menu, click “ Customer Service > Channels”, click “+Connect Channel” in the upper right, and select “ Website ” .




Channel list: click “Connect Channel” in the upper right



“Select Platform” step: select Website

2. Option 2: Channels Linked to an Agent

Go to **AI Features** → **AI Assistants** in the left sidebar, select the Agent to configure, and switch to the **Channels** tab. Find the website channel you want to adjust and click **Platform Settings**.



Click “Platform Settings” on the Agent’s Channels tab.

After configuring the channel, click **Back to AI Assistant Settings** at the top of the page to return to the original Agent’s **Channels** tab. This return link remains available when you switch between **Basic**, **Quota**, and **Auto-Reply Settings**.



After configuring the channel, return directly to the original Agent’ s settings page.

> **Back to AI Assistant Settings** appears only when you enter from an Agent’ s **Channels** tab. If you enter directly from **Channels** in the left menu, the page keeps its usual navigation.

Use Case: Return to an Agent After Adjusting Website Customer Service

A customer service manager needs to update the website customer service settings for the “Product Inquiry Assistant.” She clicks **Platform Settings** on this Agent’ s **Channels** tab. After making her changes, she clicks **Back to AI Assistant Settings** to return to the same Agent’ s channel list and check other customer service entry points, without having to find the Agent again in the Agent list.

3. Option 3: Channel Actions

Go to “ **Customer Service > Channels** ” in the left sidebar, find the channel you want to configure, and click the **Edit** icon in that row’ s “ **Actions** ” column to open its configuration.



The first icon in the “Actions” column is “Edit”

2. Basic Settings

Each of the five categories in the “General” group on the “Basic” tab has its own detailed guide:

1. General Settings

For the platform name, Agent, return URL, custom domain, allowed embed domains, public access URL, and three embedding methods, see **Basic Settings**.

Allowed Embed Domains

For how the embed allowlist works, configuration steps, and a checklist before enabling it, see **Basic Settings: Allowed Embed Domains**.

2. Appearance Settings

For the logo, avatar, display settings, and light/dark theme colors, see **Appearance Settings**.

3. Feature Settings

For enabling the channel, file uploads, document citations, OCR, starter question option display modes, and AI awareness settings, see **Feature Settings**. Configure the tool display mode under **Reply Loading Display**.

4. Interaction Settings

For greetings, conversation starters, including greeting options in Agent context, conversation display settings, satisfaction surveys, and quota exhaustion messages, see Interaction Settings.

Include Greeting Options in Agent Context

For behavior before and after enabling this option, use cases, and considerations, see Interaction Settings: Include Greeting Options in Agent Context.


5. Login Settings

Configure an SSO Login Source

MaiAgent currently supports SSO (Single Sign-On) through Keycloak integration.

Switch sources in the “Login Source” dropdown.

Turn on “Enable Login”, then choose an authentication method such as AD, MaiAgent, or Keycloak under “Login Source”. For details on each method, see Web Chat: Login Methods.



Turn on “Enable Login,” then choose an authentication method under “Login Source”

Chat Without Logging In from an Embedded Client

If you embed Web Chat on your website and users have already logged in to your site, turn on “Allow Embedded Clients to Chat Without Login Using Source ID” so they can chat directly. For configuration and signature integration details, see Chat Without Login Using a Contact Source ID.

Use the Keycloak Login Identity for Tool Calls

When Keycloak is selected as the login source, turn on “Use Keycloak Login Identity for Tool Calls” to automatically include the visitor’s own Keycloak login credentials when the Agent calls MCP/API tools. For configuration and considerations, see Use the Keycloak Login Identity for Tool Calls.

3. Auto-Reply Settings

Set the hours during which the bot replies here.

Click the toggle next to each day to choose which days of the week to reply.

Set a time range: choose the start and end times.

Add a time range: if you need multiple ranges, click “ +Add Time Range ” and configure the additional range.

Click Update to save your settings.



“Auto-Reply Settings” tab: configure each day’ s toggle and reply hours

Auto-reply hours are configured separately for each channel. Channels on messaging platforms such as LINE, Messenger, and Instagram use the same tab. New channels default to automatic replies all day, seven days a week, and the Auto-Reply Hours column in the channel list shows “24-hour replies.”

What Happens Outside Auto-Reply Hours

The schedule only determines whether AI replies automatically; customer service staff can reply at any time. When a message arrives outside these hours, if the conversation has no assigned staff member, is not queued for a human, and still has auto-replies enabled:

AI does not reply: the message appears in All Conversations as usual, but the Agent does not answer.

No human handoff or offline message: human handoff is evaluated only when AI processes a message, so it does not trigger outside auto-reply hours. The conversation is not automatically assigned to staff, and the Offline Message in Human Handoff Settings: Service Hours is not sent.

The conversation remains "Unassigned" until staff take over: the conversation status bar shows "Outside AI reply hours • Awaiting staff," and the conversation list displays an icon indicating that staff action is needed (hover text: "Outside AI reply hours. AI will not reply; staff action is required"). Staff can click **Take Over** or **Assign Staff**; see **Human Customer Service Takeover and Replies: Unassigned Conversations**.

If a conversation already has an assigned staff member, messages received outside auto-reply hours remain assigned to that person. Conversations queued for a human also remain queued and do not become "Unassigned."

For example, a LINE channel has auto-reply hours set to weekdays from 09:00–18:00. When a customer asks about business hours on Saturday morning, the Agent does not answer. The conversation appears under **Unassigned**, with the status bar showing "Outside AI reply hours • Awaiting staff." The staff member on duty clicks **Take Over** and replies. After 09:00 on Monday, the Agent replies to other new conversations as usual. For this conversation, which staff have already taken over, the Agent resumes replying only after staff click **Resolve** or **Return to AI Agent**.

> Conversations that call the Agent directly through the **API** are not restricted by auto-reply hours.

Use Case: Human Customer Service Only, Without AI

To let staff reply to customers in MaiAgent while temporarily keeping AI from answering (for example, just after migrating from another customer service system), turn off auto-reply hours for all seven days on this channel:

Open the channel's **Auto-Reply Settings** tab.

Turn off the toggles for Monday through Sunday.

Click **Update**.

If you have not created a channel yet, leave **AI Assistant** unselected during creation, then turn off the schedule afterward. AI will not reply from the moment the channel is created (creating a LINE channel switches its Webhook immediately; see **Migrate to MaiAgent from Another Platform**).

After saving, the **Auto-Reply Hours** column in the channel list shows "-", and each subsequent incoming conversation is handled as described in **Outside Auto-Reply Hours**:

No automatic assignment: every new conversation stays **Unassigned**. Arrange for staff to check regularly, click **Take Over** in a conversation before replying, or use **Assign Staff** to assign it to a specific colleague.

The status bar shows "Outside AI reply hours • Awaiting staff": AI will not reply and someone needs to handle the conversation. It is not marked as being handled by AI.

To enable AI later: return to **Auto-Reply Settings**, enable the required days and times, and click **Update**. The channel must have an AI assistant selected. The Agent replies to new conversations; conversations already taken over by staff remain with staff until they click **Resolve** or **Return to AI Agent**.

For example, a retail brand migrates its LINE Official Account to MaiAgent. While its AI answers are still being adjusted, it lets staff handle all replies. When creating the LINE channel, it leaves AI Assistant unselected, then immediately turns off auto-reply hours for all seven days. Incoming customer messages then appear under **Unassigned**, and staff click **Take Over** to reply. Two weeks later, once AI adjustments are complete, the brand selects an AI assistant for the channel and enables weekday auto-reply hours. The Agent then replies to new conversations.

> Auto-reply hours only control MaiAgent’ s AI. Native platform auto-replies, such as LINE Official Account auto-response messages and Meta Business Suite offline auto-replies, are unaffected. Disable them in the respective platform’ s administration console; see **Receiving LINE Auto-Response Messages** and **FB Messenger: Customers Still Receive Automated Messages**.

Chat Without Logging In Using a Contact Source ID

When you embed Web Chat on your own website, users have often already signed in to your site. This setting lets them start chatting directly with the user ID from your system, without going through another login screen, while the public chat URL still blocks anonymous access.

In MaiAgent, this ID is called the Source ID, and both the admin console and the embed script use this name. When the platform receives a Source ID, it maps it to (or creates) a contact, and that user's conversation history is attached to this contact.

1. What This Setting Solves

Before this setting existed, the login setting was an either-or choice:

Login setting on: Even though the embedding side has already verified the user's identity, the user is still asked to sign in again.
Login setting off: Anyone can use the public chat URL anonymously.

With this setting on, both can hold at the same time: users who arrive with a Source ID and a valid signature chat directly, and visits without them are always redirected to the login page.


> This setting is off by default. When it is off, all existing behavior remains completely unchanged.

2. Enable the Setting

Where to find it: In the left menu, go to "Customer Service > Chat Platforms", select a website-type chat platform, and open the "Login Settings" tab.

1. Select a login source first

This switch depends on the login settings. You must first select a source under "Login Source" (MaiAgent/AD/Keycloak/LINE). Until a source is selected, the switch cannot be clicked, and the screen displays "Please select a login source first".



Login Settings tab; this switch is off by default

2. Turn on the switch

Turn on "Allow the embedding side to chat without login using a Source ID". Only after it is on do the verification mode, signing secret, and integration examples appear.




The settings section that expands after enabling; the verification mode defaults to "Require signature verification"

3. Choose a verification mode

Verification mode	Description	Suitable for
Require signature verification (recommended)	The embedding side must attach a signature calculated by your backend, and access is granted only if the signature is valid. Only a server holding the secret can start a conversation on behalf of a user.	Production environments
Source ID only	No signature is verified; any request with a Source ID is allowed through.	Testing or closed internal networks

When you choose "Source ID only", the Source ID is effectively a pass. If your Source ID is a guessable value such as an email, student ID, or employee ID, others can impersonate that identity to chat and read its history. For scenarios that require identity assurance, use signature mode, or switch to AD/Keycloak/MaiAgent login.



When "Source ID only" is selected, a red risk warning is displayed

4. Get the signing secret

After you select signature mode and save the settings, the platform generates a signing secret. In the secret field, you can:

Click "Show" to view the full secret (masked by default)


Click "Copy" to hand it to your engineers

Click "Regenerate" to issue a new secret

> Store the secret in your server's environment variables, and never write it into frontend code. After regeneration, the old secret becomes invalid immediately, and your backend must switch to the new one at the same time; otherwise, every signature fails verification.

5. Set the signature validity period

You can choose 1, 5, or 15 minutes, with 5 minutes as the default. Expired or already used signatures are rejected.



Signing secret, signature validity period, integration examples, and behavior preview

> The validity period limits how long a signature can be used to open a conversation; it is not how long the conversation lasts. Once a user has obtained an identity and is chatting, they are not signed out after 5 minutes.

3. How Your Engineers Integrate

The "Integration Examples" section in the admin console is pre-filled with this chat platform's identifier and provides examples for the backend signature calculation (PHP/Node/Python) and the frontend setup, which you can copy and hand to your engineers. For the full details of the signature algorithm, verification rules, and SDK parameters, ask your engineers to refer to **Web Chat Embedding and SDK › Signature Verification** in the technical manual.

1. Calculate the signature in the backend

Each time before a user enters a conversation, your backend uses the signing secret to calculate a timestamp `ts` and a signature `sig`. For the algorithm and examples in three languages, see **Signature Verification** in the technical manual.

2. Pass them to the embed script in the frontend

The frontend passes the Source ID, together with the `ts` and `sig` calculated by the backend, to the embed script:

```
window.MaiAgent.auth.setup({ sourceId, name, ts, sig });
```

You can also write them directly in the `auth` field of the embed configuration, and the embed script picks them up automatically after loading. See the technical manual for the syntax.

> If the example generated in the admin console shows setupAuth, use auth.setup instead.

3. Integration notes

Sign anew on every entry: A signature can be used successfully only once, so the embedding side must not cache signatures.

Calculate the signature in the backend: Once the secret appears in frontend code, it is effectively public.

Keep clocks accurate: The system allows a clock skew of 60 seconds; timestamps outside this range are rejected.

Use the correct chat platform identifier: The signature includes the chat platform identifier, so a signature calculated with another chat platform's identifier does not pass.


4. Behavior Reference

Incoming request	Result
Source ID + valid signature	Chats directly; no login screen appears
Source ID with an invalid or expired signature	Rejected
The same signature used repeatedly	The first use succeeds; the second is rejected
No Source ID (including opening the public URL directly)	Redirected to the login page
Verification mode is "Source ID only" + Source ID	Chats directly; no signature is verified
This switch is off	Keeps the original login setting behavior

> All rejection scenarios return the same external response, without revealing the reason for failure or whether a given Source ID exists. The reason appears only in the admin console's verification failure log.

5. Verification Failure Log

If the integration does not work smoothly, click "View verification failure log" in the settings section to see recent failure events, so your engineers can troubleshoot on their own. The log does not contain the secret or the full signature.



The expanded verification failure log

Reason	Common causes
Signature expired	Server clock drift, or the embedding side cached the signature
Timestamp beyond the allowed future range	The server clock is more than 60 seconds ahead
Signature mismatch (the secret may be inconsistent)	The backend uses a different secret from the admin console, or the signature string is constructed incorrectly

Reason	Common causes
Missing timestamp or signature	The embedding side did not send `ts` or `sig`
Signature already used	The same signature was sent a second time
Replay-protection cache unavailable	A temporary condition on the platform side; the system rejects rather than allows the request
Source ID maps to multiple contacts	Duplicate contact records with the same Source ID exist on that chat platform

6. FAQ

- ▶ If the signature validity period expires, is the user's conversation interrupted?
- ▶ Can the same Source ID map to multiple contacts?
- ▶ Does enabling this setting affect existing embeds?
- ▶ After a user signs out of my website, can they continue chatting?
- ▶ When a user arrives with a Source ID, does the AI include their login credentials when calling tools?

Connected Services

When an Agent needs to use your own account to check your calendar, read your cloud drive, or operate an external system, it first asks you to authorize it in the conversation. Every service you have authorized is gathered in the Connected Services window: you can see the authorization status and validity period, re-authorize, and disconnect at any time. This is an entry point that users manage themselves, with no need to ask an administrator to do it for you.

> This page covers authorization for "an Agent accessing services on my behalf", and is intended for users of the Agent Marketplace and Web Chat. The connectors for Notion, Slack, and so on that MaiGPT users set up from the "+" menu are a separate entry point; see MaiGPT Connectors.

Where to Open It

Scenario	Entry point	Who can see it
Admin console → Agent Marketplace → chat with an official built-in Agent	The Connected Services button at the top of the chat page	All members chatting with an official built-in Agent (the chat page of an Agent built by your organization has no such button)
Web Chat on a website (full-screen page or public access URL)	The link icon in the title bar; hover over it to see "Connected Services"	Identified visitors: those who have filled in the Pre-chat form, have logged in, or whose identity is passed in by the website via a Source ID. It is not shown to anonymous visitors, in the floating window at the lower right, or in MaiGPT window mode

First-Time Authorization: The Authorization Card in the Conversation

The first time an Agent needs a service, a "Connect {service}" card appears in the conversation. It lists the permissions to be granted and explains that credentials are encrypted and stored on the backend, not in your browser. Click Go to Authorize (Authorize Connection in the admin console) to open a new window to the service, where you sign in and give consent (your username and password are entered only on the service's official page; MaiAgent never handles them). When it is done, the card changes to "{service} connected", and the Agent can then retrieve data using your identity.

> If you see "The browser blocked the new window. Please allow pop-ups and try again", allow this site to open pop-ups in your browser, then click Authorize again.

> After the authorization window closes, the card checks the authorization result for a dozen or so seconds, and it usually changes to "{service} connected" quickly. If nothing changes after waiting, just click Authorize again.

What's in the Window

After you open Connected Services, the left side is the list of services and the right side shows the details of the selected service.

Left-side list

Search services··· filters by name.

Each service shows a status: Authorized (ready to use), Pending Authorization (never authorized), or Reconnection Needed (authorization is no longer valid, so the Agent cannot currently retrieve data).

When the list is empty, it shows "No services available to connect", which means none of the Agents you use has a service that needs your personal authorization.

Right-side details

Section	Content
Status notice	When pending authorization, it shows "Not yet authorized" and Authorize Connection; when reconnection is needed, it shows "The connection is no longer valid and must be re-authorized" and Re-authorize. Re-authorizing does not affect any of your content in that service
Assistants Using This Service	Which Agents access data through this authorization
Authorization Information	Authorized Account (the account you sign in with on that service), Authorization Method (OAuth 2.0), Authorization Time, Credential Validity (for example, "in N days"), and Token Storage Method (encrypted on the backend)
Authorization scope	Authorized services show a Authorized Scopes row; services not yet authorized show a Requested Scopes row, so you can review them before authorizing
Disconnect	See the next section

Disconnecting

Click **Disconnect** in the service details. The confirmation window lists "The following assistants will be affected". After you confirm, those Agents can no longer access that service on your behalf right away, and you will need to re-authorize before using it again.

> Disconnecting revokes the credentials stored on the MaiAgent side. If the screen shows "Platform-side connection has been removed; to remove it completely, check the account settings of {service}", the service may still list MaiAgent as an authorized application. To remove it entirely, go to that service's account settings and revoke it once more.

FAQ

A service shows "Reconnection Needed" and the Agent says it cannot retrieve data. What should I do?

The authorization credentials have expired. Open **Connected Services**, select the service, and click **Re-authorize**. Once it is done, ask again.

I don't see the "Connected Services" button. Why?

Web Chat: you are currently an anonymous visitor, or you are in the floating window at the lower right. Open the full-screen page, and fill in the form or log in first.

Admin console: this button appears only on the chat page of official built-in Agents.

Whose account is authorized? Could other colleagues use it?

It is the account you yourself sign in with on that service, and it is used only in your own conversations with the Agent; other people must each authorize on their own to use the same service. If an administrator wants the whole organization to share one account, they set the authorization subject to "Organization shared" when creating the tool, and such services do not appear in this window.

For Administrators: Making a Service Appear Here

This window lists OAuth MCP tools that are configured on an Agent and whose authorization subject is "Per-contact authorization". For setup, see **Create an MCP Tool: OAuth Connectors and Authorization Subjects**. Administrators can also view or revoke a contact's authorization in the

Connector Authorization tab of the **Contacts** edit window. To pre-fill a contact with credentials from an existing system (without going through OAuth), see **Set Up Contact MCP Credentials**.

Citation Display

This article introduces the citation display optimization features in the Web Chat window, including multilingual support and visual presentation improvements.

What Is Citation Display?

When an Agent answers a question using specific documents or data from a knowledge base, the system displays "citations" below the answer so end users know where the information comes from.

This feature is especially suitable for scenarios that require proof of information sources, such as:

Regulatory inquiry assistant: Displays the source of legal provisions

Policy consultation assistant: Displays policy document sources

Product customer service assistant: Displays product manuals or official documents

Medical information assistant: Displays medical literature sources

Where Citations Appear

When an Agent's answer uses a knowledge base, citation information appears in three places:

Location	What you see
Knowledge bases used below the answer	Which knowledge bases were searched for this answer
Citations list below the answer	The names of the cited documents; click View cited nodes to open a dialog listing the passages that were actually cited (cited nodes)
Citation markers in the answer text	Hover over a marker to show a small card with the document name, page number (shows "Source has no pages" if the source is not paginated), a relevance percentage, and two views of the passage, Original text and Highlighted keywords; you can download the original document directly

Fields for each node in the "View cited nodes" dialog:

Field	Meaning
Similarity score Relevance	How semantically similar this passage is to the question; the higher it is, the more likely the passage is the basis for the answer
Hit count	How many times this passage was hit in this retrieval; more hits mean it was more often judged relevant
Character count	The length of this node
Original text Highlighted keywords	Switch between plain text and highlighting the keywords related to the question

Whether citations are displayed is decided by administrators in Function Settings. For the corresponding information in the back-end conversation viewer, see Conversation Viewer: Knowledge Base Citation Tracking.

Multilingual Support

Automatic Language Adaptation

Web Chat citation display now supports automatic multilingual adaptation. When end users switch languages, the citation interface text automatically switches to the corresponding language.

Supported Languages

Traditional Chinese: 引用來源、參考資料

Simplified Chinese: 引用来源、参考资料

English: Citation、References

Language Switch Timing

Web Chat automatically switches languages based on the following scenarios:

Browser language settings: On first load, the display language is based on the user's browser language

Manual switch: When users switch languages in Web Chat, citation text updates accordingly

Website language environment: If your website supports multiple languages, Web Chat automatically matches the website's language settings

> For how to configure Web Chat language, see: Web Chat Overview

Visual Presentation Optimization

In addition to multilingual support, the visual presentation of citations has been optimized for clearer readability.

Optimization Items

Spacing adjustments: More appropriate spacing between citations and answer content for a clearer visual hierarchy

Font style: Citations use a different font style to distinguish them from the main content

Color treatment: Citations use a lighter color so they don't interfere with reading the main content

Icon marker: A consistent icon marks citations for better recognition

Dark Mode Support

Citation display also supports dark mode. When an end user's device uses a dark theme, the text and background colors of citations adjust automatically so they remain clearly visible on a dark background.

Dark Mode Adaptation Items

Text color automatically adjusts to a light color

Background color adapts to the dark theme

Contrast with the main content is maintained

> Dark mode is enabled automatically based on the user's device settings, with no manual configuration required.

Use Cases

🏛️ Government Policy Consultation Platform

Scenario:
When citizens ask about the eligibility requirements for a subsidy policy, the Agent not only provides the answer but also shows a link to the source of the policy announcement.

Benefits:
* Increases the credibility of the information

* Lets citizens read the full announcement
* Reduces citizens' doubts about the accuracy of the information

⚖️ Legal Consultation Assistant

Scenario:
When a user asks about the provisions of a regulation, the Agent shows the source of the legal provision and the article number.

Benefits:
* Provides a complete legal basis
* Users can verify the original provisions
* Increases the professionalism of the consultation service

🏥 Medical Information Platform

Scenario:
When patients ask about a disease, the Agent indicates which medical paper or patient education article the information comes from.

Benefits:
* Provides transparency about information sources
* Helps patients understand how reliable the information is
* Meets the regulatory requirements for providing medical information

Administrator Settings

Enable Citation Display

Citation display is enabled by default. If you want to adjust the setting:

Go to the "AI Assistant" settings page

Select "Answer Settings"

Find the "Show citations" option

Toggle the switch to enable or disable it

Customize the Citation Format

You can add metadata to knowledge base documents to customize how citations are displayed:

Document title: The document name shown in the citation

Section number: Shows the specific section or page number

Publication date: Shows the document's publication or update date

External link: Provides a link to the original document

> For how to configure knowledge base metadata, see: **Document Management: Tags and Metadata**

FAQ

Q1: Do citations show every referenced document?

Not necessarily. The system shows the "most relevant" citations, usually no more than 3-5, to avoid information overload.

Q2: Can I hide citations?

Yes. Turn off the "Show citations" option in the Agent settings.

Q3: Can I fix the citation language to a specific language?

Citations automatically follow the Web Chat language setting. If you want to fix a specific language, set the language option in the Web Chat settings.

Q4: Are citation links clickable?

Yes. If you set an external link in a knowledge base document, the citation is displayed as a clickable link.

Q5: What if citations are hard to read in dark mode?

The system has been optimized for dark mode. If you still have problems, it may be a browser cache issue; try clearing the cache or refreshing the page.

Markdown Rendering

This article introduces the message content rendering optimizations in the Web Chat window, which make Agent responses clearer and easier to read.

What Is Message Content Rendering?

Message content rendering refers to how Web Chat converts an Agent's text response into the visual presentation that users see. An Agent's response may include:

Plain text: General text descriptions

Markdown formatting: Headings, lists, bold, italics, and other formatting

Code blocks: Code examples or commands

Tables: Structured data presentation

Links: External links or reference materials

Good rendering makes this content easier to read and understand.

Optimization Items

1. Fully Upgraded Markdown Rendering Engine

Web Chat now uses an enhanced Markdown rendering engine that supports richer formatting and more precise rendering.

Supported Markdown Formats

Format Type	Syntax Example	Rendering Description
Headings	`# Heading 1`, `## Heading 2`	Clear heading hierarchy for dividing content into sections
Bold	`bold text`	Emphasizes key content
Italic	`*italic text*`	Secondary emphasis or supplementary notes
Lists	`- Item 1`, `1. Item 1`	Ordered or unordered lists
Inline code	`` `code` ``	Inline code or commands

Format Type	Syntax Example	Rendering Description
Code blocks	``` code ```	Multi-line code with syntax highlighting support
Tables	`| Column 1` `| Column 2`	Structured data display
Links	`link text`	Clickable hyperlinks
Blockquotes	`> quote content`	Quotations or special notes
Images	`!description`, `!description{width=200px}`	Displays an image; a `{…}` placed right after the URL sets the display size. See Adjusting Image Display Size

Link and File Link Behavior

Links in responses always open in a new tab, so users don't leave the current conversation (the only exception is in-page anchors `#…`).

When a link points to a PDF or another file, the browser decides how it opens: Chrome, Edge, and Safari open PDFs in a new tab with the built-in viewer, and URLs with a page number such as https://example.com/manual.pdf#page=12 jump straight to that page; if the browser is set to download PDFs, the file is downloaded instead. Web Chat does not rewrite the URL or force a download.

To have the Agent reply with a "text link plus page number" instead of an attachment: put the document URL (including the page number) in the `url` metadata of the knowledge base document or in the FAQ answer, and instruct the Agent in its role instructions to reply with Markdown links. See Custom URL Mapping. Downloading cited documents from the sources is a separate mechanism, controlled by "Allow downloading cited documents" in Function Settings.

Adjusting Image Display Size

Markdown images in Agent responses are displayed at their original size by default, up to the width of the message column. Add `{width=…}` or `{height=…}` immediately after the closing parenthesis of the image URL to set the display size of that image. Both Web Chat and the back-office conversation view (for example, when you click Start Conversation from the Agent Marketplace) support this.

For example, a customer service manager at an e-commerce company noticed that when the Agent replied with product images, a single image filled the entire chat window and customers had to keep scrolling to see the text. She added an instruction to the Agent's role instructions to always output product images in the format `!product image{width=200px}` (for where to enter this, see Add Role Instructions to an Agent). After that, product images shown to customers in Web Chat on the company website have a fixed width of 200px, and colleagues chatting with the same Agent in the back office see the same size.

```
{width=200px}
{width=50%}
{width=300px height=200px}
```

Rule	Description
Available settings	Only `width` and `height`, always lowercase, each at most once, in any order
Units	`px` or `%`; the value must be greater than 0 and may include decimals (for example, `33.5%`); `%` cannot exceed 100
Basis for percentages	`%` is calculated against the width of the message column
Setting both width and height	Separate the two settings with a space (`{width=300px height=200px}`), not a comma
Setting only one	The other dimension is adjusted automatically to keep the original aspect ratio
Position	`{` must immediately follow the `)` of the URL, with no space in between
Exceeding the message column width	The image is automatically scaled down to fit within the message column without distortion

docs-line 示範（虛構）訂單查詢助理

圖片尺寸示範

2026/10/10 17:38:24

docs-line 示範（虛構）訂單查詢助理

原始尺寸：




指定寬度 200px：



2026/10/10 17:38:26

Web Chat: the same image without a specified size (top) and with `{width=200px}` (bottom)



Back-office conversation view: the same response, where the second image has a width of 200px

> If anything inside {⋯} violates the rules in the table above (for example, {width=150%}, {size=200px}, a space between) and {, or a missing closing brace), the entire size setting is ignored: the image is displayed at its default size, and the {⋯} text appears as-is in the message. A {width=⋯} written inside code or a code block is also displayed as-is.

> Size settings only take effect in Web Chat and the back-office conversation view. Messaging channels such as LINE, Messenger, Instagram, and WhatsApp do not apply them, and the {width=⋯} after an image remains in the message as text. If the same Agent also serves these channels, we recommend not asking for the size syntax in the role instructions.

2. Dark Mode Visual Optimization

When an end user's device uses a dark theme, Web Chat automatically adjusts the visual presentation of message content to ensure clarity and readability on dark backgrounds.

Dark Mode Adjustments

Text and background contrast: Automatically adjusts text color for clear display on dark backgrounds

Message feedback buttons: Adjusts button colors and borders so they remain clear in dark mode

Table visuals: Adjusts table borders and background colors for improved readability

Blockquote backgrounds: Adjusts blockquote background tones to set them apart from the main content

3. Streaming Rendering Performance Improvements

Web Chat displays Agent responses through real-time streaming, so users don't need to wait for the complete response to be generated. This update optimizes streaming rendering performance:

Faster rendering: Markdown formatting renders more quickly, reducing perceived latency

Improved smoothness: Text appears character by character more smoothly, with no noticeable lag

Format accuracy: Markdown formatting renders correctly even during streaming

> Users can see the content that has already been generated in real time while the Agent is still responding, without waiting for the complete answer.

Practical Use Cases

💻 Technical Documentation Assistant

Scenario:
When developers ask for code examples, the Agent provides responses that include code blocks.

Optimization Effects:
*** Code blocks support syntax highlighting for easier reading**
*** Code displays clearly in dark mode**
*** Developers can copy and use the code directly**

Example Response:

Here's an example of reading a CSV file in Python:

```
python
import pandas as pd

df = pd.read_csv('data.csv')
print(df.head())
```

This code reads a CSV file and displays the first 5 rows.

📊 Data Analysis Assistant

Scenario:
Users ask for sales data analysis results, and the Agent presents them in a table.

Optimization Effects:
* Tables are clearly formatted with aligned columns
* Table borders and background colors adapt to dark mode
* Large datasets remain readable

Example Response:

Here are the top three selling products this quarter:

Product Name	Units Sold	Revenue
Product A	1,250	$125,000
Product B	980	$98,000
Product C	856	$85,600

Sales data is as of the 20th of this month.

📚 Teaching Assistant

Scenario:
Students ask about learning steps, and the Agent explains them using an ordered list.

Optimization Effects:
* List items are clearly numbered
* Heading hierarchy is distinct, making the order of steps easy to follow
* Key content is emphasized in bold

Example Response:

Recommended Steps for Learning Python

Basic Syntax

Variables and data types

Conditionals and loops

Advanced Concepts

Functions and modules

Object-oriented programming

Hands-on Practice

Complete small projects

```
Contribute to open source


We recommend spending 2-3 weeks on each step.
```

Administrator Settings

Markdown Rendering Settings

Web Chat's Markdown rendering is enabled by default. If your use case doesn't require Markdown formatting, you can adjust it in the settings:

Go to "Publish" → "Web Chat Settings"
Find the "Message Rendering" settings section
Select the rendering mode:
Full Markdown: Supports all Markdown formats (default)
Basic formatting: Supports only bold, italic, and links
Plain text: Renders no formatting

Dark Mode Settings

Dark mode is enabled automatically based on the user's device settings. If you want Web Chat to always use a light or dark theme:

Go to "Publish" → "Web Chat Settings"
Find the "Appearance" settings section
Select the theme mode:
Auto: Based on the user's device settings (default)
Light: Always use the light theme
Dark: Always use the dark theme

> For detailed Web Chat appearance settings, see: Connect Chat Platform: Website

Performance Impact

Rendering Performance

Performance impact of the optimized Markdown rendering engine:

Load time: First load increases by approximately 0.1-0.2 seconds (virtually unnoticeable)
Memory usage: Increases by approximately 1-2 MB (minimal impact on modern browsers)
Rendering speed: Approximately 30% faster than the previous version

Compatibility

The optimized rendering engine supports the following browsers:

Chrome
Edge (version 90 or later)
Firefox (version 88 or later)
Safari (version 14 or later)
Mobile browsers (iOS Safari, Android Chrome)

> Older browser versions may not display some Markdown formats correctly. We recommend reminding users to update their browsers.

Messaging Channels: Automatic Conversion to Plain Text

The Markdown rendering described on this page applies only to Web Chat, which can display rich text. LINE, Messenger, Instagram, and WhatsApp do not render Markdown. Agent responses are automatically converted before being sent to these four channels, so users receive clean text:

Markdown	After Conversion
`# Heading`, `bold`, `*italic*`, ~~`strikethrough`~~	Symbols removed, text only (WhatsApp bold uses its own `*bold*` style instead)
`text`	"text URL"
Tables	Each row becomes one line: "- Column name: value Column name: value"
Code blocks	Content only
Bullet lists, line breaks	Preserved
Images `!description`	Images that are sent separately as images are removed from the text; images that are not sent separately appear as "description URL"

Only messages sent by the Agent are converted; text typed by human agents in the back office, LINE Flex cards, and quick reply buttons are sent as-is. The back-office conversation page and reports still store the model's original response. The Viber channel keeps its existing style conversion.

For example, a pharmacy chain's Agent serves both the website Web Chat and LINE, and organizes store business hours in a table when replying. Website visitors see a table; LINE users receive a bulleted list with one line per store, such as "- Store: Xinyi Branch
Business hours: 09:00–22:00", without a pile of `|` and `**` symbols, so there is no need to write a separate set of role instructions for LINE.

FAQ

Q1: Why doesn't my Agent's response have formatting?

Possible causes:
* The Agent is not using Markdown syntax
* Markdown rendering is disabled
* The browser version is too old

Q2: What if some content is hard to see in dark mode?

Try the following:
1. Clear the browser cache
2. Refresh the page
3. Make sure you are using the latest browser version

Q3: Can I customize the syntax highlighting colors for code blocks?

Currently, the syntax highlighting colors are fixed. Customization may be offered in a future version.

Q4: How is long table content displayed?

Tables automatically support horizontal scrolling, so the content is displayed in full without affecting the layout of other content.

Q5: Will rendering optimization affect display on mobile devices?

No. The rendering optimizations have also been adapted for mobile devices, ensuring clear display on small screens.

Embed MaiGPT in Window Mode

In addition to the common "floating button in the bottom-right corner," MaiAgent's Web Chat SDK introduces MaiGPT window mode, which lets you embed a full ChatGPT-style conversation interface (conversation history list on the left + main conversation area on the right) directly into any position on your own page as the primary UI, rather than a small widget tucked in a corner.

> This page explains how to embed MaiGPT window mode on your own website. If you have not yet created a Web Chat channel, please refer to Connect a Conversation Channel: Website to complete the basic setup first.

> MaiGPT window mode is not the same as the MaiGPT product. Window mode only determines how the Web Chat interface looks: whichever Agent's Web Chat it is applied to, that Agent's role instructions, model, and tools are used. The built-in organization MaiGPT is a workspace for organization members to log in and use; the two are different things.

Where to Start? Get the Embed Code


The embed code on this page is obtained from Basic Settings. Follow the steps below:

Open the Conversation Channel Settings

Under "Customer Conversations > Conversation Channels", select your Web Chat channel and click "Actions" to open the settings page.

Click "Embed"

In Basic Settings, find the Public Access URL section and click the "Embed" button to open the embed window.



Basic Settings > Embed

Select the MaiGPT Embed Method

Switch between the three embed methods at the top of the window and select "MaiGPT":

Embed Method	Description
JavaScript	Loaded via